

**United States Department of the Interior
National Park Service**

For NPS use only

**National Register of Historic Places
Inventory—Nomination Form**

received

date entered

See instructions in *How to Complete National Register Forms*
Type all entries—complete applicable sections

1. Name

historic PORT NORFOLK HISTORIC DISTRICT (VHLC File #124-51)

and/or common N/A

2. Location

Roughly bounded on the N by Bayview Blvd.; on the E by
street & number rear property lines of the E side of Chataqua Ave.; N/A not for publication
on the S by SCL RR tracks and Hartford St.; and on the W by Douglas Ave. and Hull Creek.
city, town Portsmouth N/A vicinity of

state Virginia code 51 county (in city) code 740

3. Classification

Category	Ownership	Status	Present Use
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input type="checkbox"/> building(s)	<input type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial
<input type="checkbox"/> structure	<input checked="" type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government
	<input type="checkbox"/> being considered	<input checked="" type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial
	<u>N/A</u>	<input type="checkbox"/> no	<input type="checkbox"/> military
			<input type="checkbox"/> museum
			<input type="checkbox"/> park
			<input checked="" type="checkbox"/> private residence
			<input checked="" type="checkbox"/> religious
			<input type="checkbox"/> scientific
			<input type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property

name Multiple Ownership

street & number N/A

city, town N/A N/A vicinity of state N/A

5. Location of Legal Description

courthouse, registry of deeds, etc. Portsmouth City Hall

street & number N/A

city, town Portsmouth state Virginia 23704

6. Representation in Existing Surveys

Portsmouth Planning Office Port Norfolk
title Survey

has this property been determined eligible? yes no

date 1982, 1983 federal state county local

depository for survey records Virginia Historic Landmarks Commission, 221 Governor Street

city, town Richmond state Virginia 23219

7. Description

Condition		Check one	Check one	
<input type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input checked="" type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site	
<input checked="" type="checkbox"/> good	<input type="checkbox"/> ruins	<input type="checkbox"/> altered	<input type="checkbox"/> moved	date <u>N/A</u>
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed			

Describe the present and original (if known) physical appearance

SUMMARY DESCRIPTION

Port Norfolk Historic District is a distinct early suburban neighborhood which encompasses approximately thirty city blocks located in the northern region of the city of Portsmouth. It is roughly bounded by the Elizabeth River to the north, industrial land east of Chautauqua Avenue and north of the Seaboard Coast Line Railroad to the east, Hartford Street between Broad Street and Douglas Avenue to the south, and Hull Creek and Douglas Avenue to the west. A typical grid pattern of streets divides the neighborhood into rectangular city blocks of approximately 600' by 300'. Each block is further divided into approximately twentyfive buildings lots, each lot facing the north-south extending streets that constitute the main thoroughfares within the district. These seventy foot-wide streets are named (from east to west): Chautauqua Avenue, Maryland Avenue, Broad Street, Mount Vernon Avenue, Florida Avenue, Douglas Avenue, and Hamilton Avenue. The secondary or east-west extending streets have very few building lots facing them. These fifty-foot wide streets include (from south to north): Hartford Street, Woodrow Street, Cleveland Street, Detroit Street, Wesley Street, Bruce Place, Rolfe Terrace, and Adriatic Street. At the northern boundary of the district, Bayview Boulevard extends east-west along the Elizabeth River with building lots facing north toward the street and river. The district contains an impressive collection of residential architecture, mostly dating from 1890-1910, which conveys the nostalgic image of a well-preserved turn-of-the-century community with a remarkably cohesive architectural fabric.

ARCHITECTURAL ANALYSIS

Compatible in design, scale, and fabric, the residences of Port Norfolk present a variety of building styles prevalent at the turn of the century and into the 20th century. Queen Anne, Bungalow, and American Four Square architectural styles are well represented in the domestic architecture of the district. Most of the building stock is typical of middle-class residential housing of the period (213 and 331 Broad Street), however there are a number of impressive Queen Anne-style dwellings in the district that are more reflective of upper-middle-class fashion and tastes. The most prominent houses of this type are found along Bayview Boulevard (2701, 2713, 2801, 2813, 2901 Bayview Boulevard). These dwellings are mostly frame two-and-a-half-story structures that feature an interplay of various roof lines, gables, and turrets with conical roofs. A diversity of texture is achieved by the use of exterior wall shingles and slate roof tiles that are cut and arranged in decorative patterns. Each house also has a one-story porch with either Victorian period features such as spindle friezes, turned posts, and decorative sawnwork, or with classical-inspired features such as Tuscan columns and pediments. Many other Queen Anne-style houses or modified variants of the style are found in blocks nearest the river where real estate was most desirable, namely, the 100 block of Florida Avenue (108 and 146 Florida Avenue), the 100 block of Mount Vernon Avenue (140 and 149 Mount Vernon Avenue), the 100-500 blocks of Broad Street (158, 202, 500, and 559 Broad Street), and the 100 block of Maryland Avenue (107, 127 and 160 Maryland Avenue). A curious feature of many district houses (630 Broad Street, 301 and 401 Florida Avenue, 301 and 532 Maryland Avenue, 500 Broad Street, 146 Florida Avenue, 2701 Bayview Boulevard) is the metal roof cresting that extends along roof ridges and gables. Reminiscent of Oriental architecture, the cresting appears serpent-like in character and was probably

(See Continuation Sheet #1)

8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input checked="" type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input type="checkbox"/> other (specify)

Specific dates 1890-1940 **Builder/Architect** N/A

Statement of Significance (in one paragraph)

STATEMENT OF SIGNIFICANCE

Port Norfolk, an architecturally cohesive turn-of-the-century planned suburb of Portsmouth, Virginia, has associations with historic developments in the region dating from the mid-18th century. The fabric of the neighborhood is in excellent condition with outstanding examples of middle- and upper-middle-class housing typical of the period. Domestic styles range from elaborate and well-preserved Queen Anne examples to the popular Bungalow of the first quarter of the 20th century. The site of Port Norfolk served successively as the rich glebe holdings of Portsmouth Parish and Trinity Church, later as a strategic landing point in the British capture of Portsmouth and Norfolk in the Revolution, and finally as a successful 19th-century farm. Beginning in 1890 with the formation of the Port Norfolk Land Company, and continuing to ca. 1920, the planned community provided healthful and attractive housing for employees of the expanding railroad and shipping facilities that adjoined it. Port Norfolk is exemplary of the widespread efforts in the late 19th and early 20th centuries to accommodate the growing demand for housing in an uncrowded neighborhood as well as to provide for the commercial, recreation and religious needs of its residents.

HISTORICAL BACKGROUND

The land on which Port Norfolk is located was occupied by colonial settlers as early as the late 17th century. In 1734 Port Norfolk and adjoining Pinner's Point, as well as most of present-day Portsmouth, were acquired by Col. William Crawford. Twenty years later, he laid out the town of Portsmouth into eighty lots. A parcel of that tract was set aside for Trinity Church (built 1761), the parish church of Portsmouth Parish, and one year later the parish vestry purchased from Colonel Crawford 175 acres encompassing Port Norfolk for their glebe lands. Glebe lands in 18th-century colonial Virginia were used to support the minister and his family as well as to meet other needs of the parish. The frame dwelling built shortly after 1762, which served as the glebe residence, stood facing the Elizabeth River at the corner of present Mount Vernon Avenue and Bayview Boulevard. Occupying these glebe lands were the first four rectors of Portsmouth Parish--Rev. Charles Smith (1762-1773), Rev. John Braidford (1772-1776), Rev. Arthur Emerson (1785-1801), and Rev. George Young (1801-1811). Mr. Emerson established the earliest school in the Portsmouth area, a glebe mission school, located just south of the proposed Port Norfolk Historic District in the 1800 block of Mount Vernon Avenue. According to the Rt. Reverend C. Charles Vache, historian of Trinity Church, it is likely that the glebe dwellings were abandoned shortly after 1811 and subsequently torn down.

The glebe lands also played a significant role in the Revolution in the Tidewater area of Virginia. It was in this area that British forces landed in 1779 in preparation for their capture of Portsmouth and then Norfolk. Apparently the glebe property was not occupied at that particular time, the Rev. Braidford having left to serve as a chaplain to the American forces.

9. Major Bibliographical References

(See Continuation Sheet #3)

- Butt, Marshall W. Portsmouth Under Four Flags, 1752-1970. Portsmouth, Va.: Messenger Printing Co., Inc., 1970.
- Cram, Ralph Adams. Impressions of Japanese Architecture and the Allied Arts. Boston: Marshall Jones Co., 1905.

10. Geographical Data

Acreeage of nominated property 160 acres

Quadrangle name Norfolk South, Va.

Quadrangle scale 1:24000

UTM References

A	1 8	3 8 1 1 1 0	4 0 7 9 2 8 0	B	1 8	3 8 1 2 0 0	4 0 7 8 9 5 0
	Zone	Easting	Northing		Zone	Easting	Northing
C	1 8	3 8 1 1 6 0	4 0 7 8 2 1 0	D	1 8	3 8 0 9 1 0	4 0 7 8 0 5 0
E	1 8	3 8 0 5 5 0	4 0 7 8 0 2 0	F	1 8	3 8 0 3 2 0	4 0 7 8 8 5 0
G	1 8	3 8 0 4 6 0	4 0 7 9 2 4 0	H			

Verbal boundary description and justification The district is roughly bounded on the N by Bayview Blvd.; on the E by a line ext. from the SW (cor.) of Bayview Blvd. and Chautauqua Ave. S to N property line (Npl) of 156 Chautauqua, thence E to NE cor. of 153 Chautauqua (vacant lot), then S along rear pls of 153-515 Chautauqua, then W to W side of Chautauqua

List all states and counties for properties overlapping state or county boundaries(See Continuation Sheet #4)

state	N/A	code	county	N/A	code
state	N/A	code	county	N/A	code

11. Form Prepared By

(See Continuation Sheet #4)

(1)

name/tit Virginia Historic Landmarks Commission Staff

organization Virginia Historic Landmarks Commission date August 1983

street & number 221 Governor Street telephone (804) 786-3144

city or town Richmond state Virginia 23219

12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national state local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature

H. Bryan Mitchell, Executive Director

title Virginia Historic Landmarks Commission

date AUG 16 1983

For NPS use only

I hereby certify that this property is included in the National Register

date

Keeper of the National Register

Attest:

date

Chief of Registration

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory--Nomination Form**

PORT NORFOLK HISTORIC DISTRICT, PORTSMOUTH, VA

For NPS use only
received
date entered

Continuation sheet #1

Item number 7

Page 1

7. DESCRIPTION--Architectural Analysis

inspired by the architectural treatise Impressions of Japanese Architecture written by the noted architect Ralph Adams Cram and published in 1905. The simple, two-story frame house is by far the most representative example of residential architecture in Port Norfolk. This vernacular house type usually has its gable end oriented to the street and features a three-bay facade, sometimes with a bay window, and an asymmetrically positioned door. A front porch with turned posts and turned balustrade is a popular feature that is found on nearly every house in the district.

Bungalows and modified variants of the style dating from the 1920s are also popular and are found throughout the district. They are 1½-story houses characterized by sweeping gable or hipped roofs with wide overhanging eaves, shed or hipped-roof dormers, and one-story porches with tapering square columns on brick pedestals (325 Hamilton Avenue, 149 Broad Street, 440 Maryland Avenue).

Another building type represented in the district's early 20th-century residential architecture is the American Four Square house with its typical square mass of two stories with a hipped roof, hipped or shed dormer, and asymmetrically positioned entrance in a two-bay facade (226 Broad Street, 401 Florida Avenue, 300 Douglas Avenue). The style proved popular with residents of Port Norfolk who built many variations on the American Four Square design.

Houses built between 1930-1950 are often frame or brick single-story, cottage-like residences exhibiting a variety of vernacular architectural features, however just as many residences denote eclectic styles. Some examples are more representative of period architecture of the mid-20th century than others. In particular those houses exhibiting vestiges of the Colonial Revival (230 Broad Street).

Single-family housing is predominant throughout Port Norfolk; however, there are a few multi-family housing units in the district. A few early 20th-century examples are seen on Mount Vernon Avenue (332, 105, 449-41 Mount Vernon Avenue). Dating from the 1920s and 1930s, these apartment buildings are two- or three-story brick structures with a single central entrance flanked by projecting porch towers of several stories.

Each porch has two tall brick columns surmounted by tapering square wood columns on the topmost floor. A common flat roof extends across both porch towers and the entrance bay. These apartment buildings are classic examples of what was a new phenomenon in housing of the early 20th century.

A small commercial area in the center of the district is located at the intersection of Broad and Detroit streets. Mostly small businesses serving the needs of Port Norfolk residents, they include a few turn-of-the-century and early 20th-century brick and frame commercial vernacular structures (400 Broad Street) and an abandoned service station.

Considering the size of the district and the number of buildings it contains, there are relatively few modern intrusions in Port Norfolk. The incompatible structures that do exist are usually tract or ranch houses which usually differ in scale, rhythm, and building material with the predominant turn-of-the-century and early 20th-century architecture.

(See Continuation Sheet #2)

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

PORT NORFOLK HISTORIC DISTRICT, PORTSMOUTH, VA

For NPS use only
received
date entered

Continuation sheet #2

Item number 7, 8

Page 2, 1

7. DESCRIPTION--Architectural Analysis

Practically all the earlier buildings of Fort Norfolk are set back from the street a set number of feet, creating a strictly regulated cadence of facades. The streets are also lined with concrete walkways and curbs as well as rows of mature shade trees which add a picturesque quality to the streetscape of this proud residential neighborhood.

DE

8. SIGNIFICANCE--Historical Background

As a result of the Confiscation Act of 1802, all Episcopal churches in Virginia were forced to give up their glebe lands; however, due to numerous legal challenges to the Assembly's act, it was not until 1815 that the Portsmouth glebe lands were auctioned and the proceeds assigned to the local overseers of the poor. The subsequent owners including John Thompson, grandfather of a later mayor of Portsmouth, farmed the 175-acre tract throughout most of the 19th century.

With the extensive development of the railroads and resulting increase in shipping and manufacturing in the Norfolk/Portsmouth area by the late 19th century, the Norfolk Land Company was founded by a group of Northern investors who purchased the 175-acre parcel in 1890. Gen. K.H.K. Douglass, Confederate veteran and later adjutant general of the state of Maryland, served as the company's first president. The company, whose name is a combination of "Portsmouth" and "Norfolk," proceeded to lay off the subdivision into house lots of approximately 40' by 140'. In the late 19th century, a number of planned suburban neighborhoods capitalized on the growing demand for housing away from unhealthy and crowded cities. Promotional material of the day commended the "fresh, wholesome air," and the "splendid view of the harbor."² Port Norfolk's simple grid street plan was similar to that of most of the Ghent neighborhood in Norfolk (NRHP 1980) with the most sought-after building lots being of somewhat larger dimensions and on the water. However, Port Norfolk differed from Ghent in that the great majority of residents were laborers in the rail, shipping, and manufacturing centers that bordered the neighborhood on the east and south leading to the dock area. The railroad track over which was hauled thousands of tons of southwest Virginia coal still forms the southeastern boundary of the district.

Also stimulating the successful growth of Port Norfolk and giving its residents access to the downtown was the horse-drawn streetcar line installed along Mount Vernon Avenue in 1895. Conversely, construction of a fishing pier with a pavilion on the waterfront at the corner of Bayview and Chataqua and of the Chesapeake Hotel, served to attract visitors to the community from nearby Portsmouth and Norfolk. The beach became popular for swimming and fishing, and the pavilion and hotel became social centers. Most of the housing standing in Port Norfolk was built between 1890 and 1920. A school --Port Norfolk Graded School (no longer standing), and three churches--Port Norfolk Baptist, Wesley Methodist, and St. Stephen's Episcopal (now Port Norfolk Pentecostal Assembly)--all date from Port Norfolk's heyday. An examination of city directories for 1920 reveals that Port Norfolk had its own railway depot, railway express office, (in the 600 block of Broad Street) pharmacy, bakery, and grocery store. Playgrounds for Negro and white children were located in the 600 block of Broad Street and the 800 block of Mount Vernon Avenue, respectively.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

PORT NORFOLK HISTORIC DISTRICT, PORTSMOUTH, VA

For NPS use only
received
date entered

Continuation sheet #3

Item number 8, 9

Page 2, 1

8. SIGNIFICANCE--Historical Background

In 1918 the Port Norfolk neighborhood was annexed to the city of Portsmouth under the name of "Washington Ward."⁴ At the time of annexation Port Norfolk remained a high-density, primarily white neighborhood containing a mixture of large and small dwellings. Most of the houses, both large and modest, had porches to avail themselves of the "fresh air" off the harbor. City directories of the period indicate a large number of residents were employed by the railroads as conductors, superintendents, and yard masters, or in the factories as electricians, mechanics, and clerks.

Port Norfolk since World War I has remained an architecturally cohesive community with a strong sense of neighborhood identity. In the 1970s, the Port Norfolk Civic League was formed to prevent speculative developers from converting single-family dwellings into multi-family apartments. There is considerable local interest in preserving the neighborhood as evidenced by the recent designation, with neighborhood support, of Port Norfolk as an historic district under the historic district code of the city of Portsmouth.

LC/MTP

¹C. Charles Vache, A History of Trinity Church - Portsmouth Parish: 1761/62-1961-62. (Portsmouth, Va.: Trinity Church, 1962), p. 24.

²Promotional Sheet on Port Norfolk, 1890, Virginia Historic Landmarks Commission Archives, Richmond, Va., and the Portsmouth Naval Shipyard Museum, Portsmouth, Va.

³Map of Port Norfolk. M.W. Mason, Port Norfolk Land Company, Map Book 4, p. 71. (1890)

⁴City of Portsmouth Annexation Map, Department of City Planning, City of Portsmouth, n.d.

9. MAJOR BIBLIOGRAPHICAL REFERENCES

"Ghent Historic District, Norfolk, Va.," National Register of Historic Places Nomination Form, July 1980.

Hill Directory Company. Incorporated Norfolk and Portsmouth, Virginia City Directory. 1920-21. Richmond: Hill Directory Company, 1921.

Port Norfolk Neighborhood Study. Portsmouth: Office of City Planning, 1981.

Richmond, Va. Virginia Historic Landmarks Commission Archives. Norfolk City Files, Port Norfolk (124-51). Tony Germanotta, "Port Norfolk--Old Rail Community."

Portsmouth: Virginian Pilot/Ledger-Star, 1980; Promotional sheet on Port Norfolk 1890 (also available at Portsmouth Naval Shipyard Museum, Portsmouth, Va.).

(See Continuation Sheet #4)

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

PORT NORFOLK HISTORIC DISTRICT, PORTSMOUTH, VA

For NPS use only
received
date entered

Continuation sheet #4

Item number 9, 10

Page 2, 1

9. MAJOR BIBLIOGRAPHICAL REFERENCES

- Smith, Fay and Champion, William. Our Church - Then and Now (A History of Broad Street Methodist Church in Portsmouth, Virginia, 1897-1947). Portsmouth: Printcraft Press Inc., 1947.
- Stewart, Col. William H. History of Norfolk County. Chicago: Biographical Publishing Company, 1902.
- Vache, C. Charles. A History of Trinity Church Portsmouth Parish. Portsmouth: Trinity Church, 1962.
- Wentz, R.W. Jr. A Pictorial History of Portsmouth. Virginia Beach, Va.: Donning Co. Publishers, Inc., 1975.

Maps:

- Map of Port Norfolk, M.W. Mason, Port Norfolk Land Company. Map Book 4, p. 71. #328. (Portsmouth Engineering Department, Portsmouth, Va. 23704)
- Map of Portsmouth Showing Annexation History. Portsmouth: Department of City Planning, n.d.

10. GEOGRAPHICAL DATA--Verbal Boundary Description & Boundary Justification

then S to S pl of 546 Chautauqua, then W to SW cor. of 546, then S to N side of Woodrow St.; on the S by a line ext. from latter pt. W to W side of Maryland Ave.; thence S to RR tracks and S pl of playground, then W to W side of Broad St., the S to N side of Hartford St., then W to SW pl of 3009 Hartford; and on the W by a line ext. from latter pt. N along alley to NW pl of 630 Douglas Ave., then NE to SW cor. of 611 Douglas, then N along SE pl of 611 to NE cor. of same, then W to SE cor. of 2905 Woodrow, then N to N side of Woodrow, then E to W side of Florida Ave., then N to S pl of 530 Florida, then W to E side of Douglas (ext.), then N to N side of Detroit St., then W to E side of Hull's Creek, then N along creek to Bayview Blvd. Boundary Justification: The boundaries of the Port Norfolk Historic District have been drawn to coincide insofar as possible with the original bounds of the 1890 development of the Port Norfolk Land Company. (See Map #3). The northern boundary follows the Western Branch of the Elizabeth River; the eastern boundary has been drawn to exclude the area devoted exclusively to industry; the southern boundary has been drawn to exclude 1950s housing and the land devoted to heavy commercial use; the western boundary follows the banks of the creek that empties into the Western Branch. The portion of the original Port Norfolk subdivision that lies south of the Seaboard Coast Line right-of-way, no longer retains its architectural integrity and has been replaced with post-World-War-II housing and heavy commercial land use. Fringe areas of the original subdivision have been excluded because of the high percentage of noncontributing structures.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, Virginia

For NPS use only
received
date entered

Continuation sheet # 5

Item number 7

Page 3

DESCRIPTION -- Inventory (arranged alphabetically by the name of the street)

ADRIATIC STREET

2900 Block

124-51-1 2919: wood frame (vinyl siding); 2 stories; gable roof (composition); 3 bays. Detached house. Builders vernacular. 1910.

BAYVIEW BOULEVARD

2500 Block

NC 2501: wood frame (vinyl siding); 2 stories; gable roof (composition); 3 bays. Apartment building. Contemporary. 1983. (Castle Development Corp.) * Noncontributing structure.

124-51-2 2509: wood frame (aluminum siding); 2½ stories; gable roof (asbestos shingles); 3 bays. Detached house. Colonial Revival. 1941.

124-51-3 2513: wood frame (weatherboard, cedershakes-second floor); 2 stories; gable roof (asbestos shingles); 1 shed dormer; 2 bays; 1-story, 1-bay porch with square wood columns on brick piers. Detached house. Bungalow. 1924.

124-51-4 2517: wood frame (weatherboard); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with shed roof and wrought iron posts. Detached house. Vernacular. 1918.

124-51-5 2521: wood frame (aluminum siding); 2 stories; gable roof (asbestos shingles); 3 bays. Detached house. Vernacular. 1941.

NC 2525: brick (stretcher); 1 story; gable roof (composition); 5 bays. Detached house. Contemporary. 1963. * Noncontributing structure.

2600 Block

124-51-6 2601: wood frame (aluminum siding); 2 stories; gable roof (composition); 1 shed dormer; 3 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters. Detached house. Bungalow. 1915.

NC 2609: brick (stretcher bond); 1 story; gable roof (composition); 4 bays. Detached house. 1959. * Noncontributing structure.


124-51-7 2621: Brick (American); 3 bays; 2½ stories; hipped with gables roof (slate); 1-story, 3-bay porch with hipped roof; enclosed. Detached house. Vernacular. 1910.

124-51-8 2625: brick (7-course); 4 bays; 2½ stories; hipped roof (slate alternately imbricated); 1-story, 3-bay porch with Doric columns and wrought iron railing. Detached. subdivided house. Vernacular. 1913. (See Contin. Sheet #6)

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, Virginia



Continuation sheet # 6

Item number 7

Page 4

DESCRIPTION -- Inventory (continued)

BAYVIEW BOULEVARD (continued)

2700 Block

- 124-51-9 2701: brick (American); 2½ stories; hipped roof (slate alternately imbricated); 1 gable dormer; 3 bays; 1-story, 1-bay porch with Doric columns supporting hipped roof; wrought iron railing. Detached house. Queen Anne. 1914. Metal cresting on roof.
- 124-51-10 2709: wood frame (asbestos shingle); 2 stories; gable roof (asbestos shingles); 2 bays; 1-story, 2-bay porch with square posts. Detached house. Vernacular. 1900.
- 124-51-11 2713: wood frame (weatherboard; cedar shakes); 2½ stories; gable roof (asbestos shingles); 2 bays; 1-story, 9-bay porch extends on three sides, turned posts and balusters; decorative sawnwork; hipped roof. Detached house. Queen Anne. 1895.
- 124-51-12 2725: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays. Detached house. Colonial Revival. 1941.

2800 Block

- 124-51-13 2801: wood frame (weatherboard); 2½ stories; hipped roof (composition); 1 hippea dormer; 2 bays; 1-story, 1-bay porch with Doric columns and turned balusters. Detached house. Queen Anne. 1899.
- 124-51-14 2813: wood frame (cedar shakes; painted); 2½ stories; hipped roof (asbestos shingles); 1 hipped dormer; 3 bays; 1-story, 5-bay porch with bracketed turned posts; turned balusters; hipped roof. Detached house. Queen Anne. 1896.
- 124-51-15 2821: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays; 1-story, 1-bay front stoop with plain square posts. Detached house. Vernacular. 1950.

2900 Block

- NC 2915: brick (American); 4 stories; flat roof (not visible); balconies; 3 bays. Apartment building. Contemporary. 1964. * Noncontributing structure.
- 124-51-16 2901: wood frame (aluminum siding); 2½ stories; gable roof (slate, alternately imbricated); 3 bays; 1-story, 7-bay porch with slender Doric columns; turned balusters. Detached house. Queen Anne. 1905.
- 124-51-17 2917: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 2 bays; 1-story, 2-bay porch screened; decorative square posts; bracketed cornice. Detached house. Vernacular. 1905.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Port Norfolk Historic Distric, Portsmouth, Virginia

7

7

Continuation sheet

Item number

Page

5

DESCRIPTION -- Inventory (continued)

BAYVIEW BOULEVARD (continued)

2900 Block

124-51-18 2925: wood frame (aluminum siding); 2 stories; gambrel roof (slate); 4 bays; 1-story, 1-bay stoop with broken pediment on panelled posts. Detached house. Vernacular. 1928.

300 Block

124-51-19 3009: wood frame (asbestos shingles); 2½ stories; gable roof (asbestos shingles); 3 bays; 2-story, 3-bay porch with shed roof, plain square posts, plain railing second story. Commercial (marina). Vernacular. 1925. Cully's boats.

124-51-20 3001: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 1 gable dormer; 2 bays; 1-story, 1-bay porch with tapering wood columns on brick piers. Detached house. Bungalow. 1925.

124-51-21 3013: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 1 shed dormer; 3 bays; 1-story, 3-bay porch with tapering square columns on brick piers. Detached house. Bungalow. 1925.

124-51-22 3019: wood frame (asbestos shingle); 1 story; gable roof (composition); 3 bays; 1-story, 2-bay porch with brick piers supporting wooden posts. Detached house. Vernacular. 1928.

BROAD STREET

100 Block

NC 100-102: brick (stretcher); 1 story; hipped roof (composition); 2 bays; 1-story, 1-bay to each side porch with wrought iron posts. Detached house. Ranch. 1970s. * Noncontributing structure.

124-51-23 101: brick (American); 1 story; gable roof (composition); 3 bays. Detached house. Pre-ranch style. 1950.

NC 104: brick (stretcher); 1 story; hipped roof (composition); 2 bays. Detached house. Ranch style. Approximately 1976. *Noncontributing structure.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk Historic District, Portsmouth, Virginia
Continuation sheet # 8 Item number 7

For NPS use only
received
date entered

Page 6

DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)


100 Block

- NC 106: brick (stretcher); 1 story; hipped roof (composition); 3 bays. Detached house. Ranch style house. Approximately 1975. * Noncontributing structure.
- NC 108-110: brick (stretcher); 1 story; hipped roof (composition); 3 bays. Detached house. Ranch style. 1974. * Noncontributing structure.
- 124-51-24 109: wood frame (asbestos shingle); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with round posts with dowel railing. Detached house. Vernacular. 1910.
- 124-51-25 117: wood frame (weatherboard); 2½ stories; gable roof (slate); 3 bays; 1-story, 3-bay porch with round posts; dowel railing extends on 2 sides; supported by Doric columns, turned balusters. Detached house. Vernacular. 1910.
- 124-51-26 119: wood frame (aluminum siding); 1½ stories; hipped roof (asbestos shingles painted silver); 3 gable dormers; 3 bays; 1-story, 2-bay porch with brick posts; turned balusters. Detached house. Vernacular. 1900.
- 124-51-27 123: wood frame (weatherboard); 2½ stories; hipped with gable roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with Doric columns; turned balusters. Detached house. Vernacular. 1910.
- 124-51-28 126: wood frame (vinyl siding); 2 stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with turned posts; turned balusters. Detached house. Vernacular. 1900.
- 124-51-29 130: wood frame (vinyl siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with slender Doric columns. Detached house. Vernacular. 1915.
- 124-51-30 134: wood frame (asbestos siding); 2 stories; gable roof (composition); 1 gable dormer; 2 bays; 1-story, 3-bay porch with square posts. Detached house. Ranch style. 1948.
- 124-51-31 137: wood frame (weatherboard); 2½ stories; gable roof (composition); 4 bays; 2-story, 2-bay porch with square tapered wooden posts and cedar shake railing. Detached house. Vernacular. 1915.
- 124-51-32 138: wood frame (vinyl siding); 2½ stories; hipped roof (composition); 3 bays; 1-story, 3-bay porch with squared posts; bracketed cornice. Detached house. Vernacular. 1900.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk Historic District, Portsmouth, Virginia



Continuation sheet

9

Item number 7

Page 7

DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

100 Block

- 124-51-33 146: wood frame (asbestos siding); 2½ stories; gable roof (slate, alternately imbricated); 2 bays; 1-story, 3-bay porch with shed roof; small pediment on porch; turned posts, turned balusters. Detached house. Vernacular. 1900.
- 124-51-34 141: brick (American); 1½ stories; gable roof (composition); 3 hipped dormers; 5 bays. Detached house. Contemporary. 1953.
- 124-51-35 150: wood frame (vinyl siding); 2½ stories; gable roof (slate alternately imbricated); 3 bays; 1-story, 3-bay porch with shed roof; small pediment with decorative shingles. Detached house. Vernacular. 1900.
- 124-51-36 149: wood frame (aluminum first floor, cedar shakes top floor); 1½ stories; gable roof (composition); 1 shed dormer; 3 bays; 1-story, 3-bay porch with squared posts on brick piers. Detached house. Bungalow. 1927.
- 124-51-37 153: brick (American); 2 stories; gable roof (composition); 2 bays; 1-story, 2-bay porch with squared posts on brick piers. Detached house. Vernacular. 1940.
- 124-51-38 154: wood frame (vinyl siding); 2 stories; gable roof (slate); 3 bays; 1-story, 3-bay porch with turned posts, turned balusters, hipped roof, and scroll brackets. Detached house. Vernacular. 1900.
- 124-51-39 157: wood frame (vinyl siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with Doric columns supporting hipped roof. Detached house. Queen Anne. 1900.
- 40 159: wood frame (asbestos shingle); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with slender Doric columns supporting hipped roof. Detached house. Vernacular. 1900.
- 40 161: wood frame (weatherboard); 2½ stories; hipped roof (asbestos shingles); 1 hipped dormer; 3 bays; 1-story, 3-bay porch; screened. Detached house. Queen Anne. 1900.
- NC 162: brick (stretcher); 1 story; hipped roof (composition); 2 bays. Detached house. Contemporary. 1963. *Noncontributing structure.
- 124-51-42 158: wood frame (weatherboard); 2½ stories; gable roof (slate alternately imbricated pattern); 2 bays; 1-story, 3-bay porch with Doric columns. Detached house. Queen Anne. 1900.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, Virginia

For NPS use only
received
date entered

Continuation sheet

10

Item number

7

Page

8

DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

100 Block

124-51-43

166: wood frame (vinyl siding); 2½ stories; hipped roof (slate alternately imbricated); 3 bays; 1-story, 4-bay porch with hipped roof; square wooden posts; turned posts. Detached house. Vernacular. 1900.

200 Block

-44

201: brick (American); 1½ stories; gambrel roof (composition); 3 bays; 1-story, 3-bay porch with tapered square posts on brick piers. Detached house. 1939.

-45

202: wood frame (weatherboard); 2 stories; cross gable roof (composition); 3 bays; 2-story, 5-bay recessed porch with slender turned posts. Detached house. Queen Anne. 1895.

-46

205: wood frame (weatherboard); 2½ stories; hipped roof (slate, alternately imbricated); 1 hipped dormer; 2 bays; 1-story, 3-bay porch with Doric columns; turned balusters. Detached house converted into two. Vernacular. 1910.

-47

210: wood frame (weatherboard); 2½ stories; gable roof (slate; alternately imbricated); 2 bays; 1-story, 4-bay porch on front and wrapped around both corners, turned posts with brackets. Detached house. (front pediment on porch). Queen Anne. 1900. Turret with wooden shingles.

-48

211: wood frame (asbestos shingle); 2½ stories; hipped roof (composition); 3 bays; 1-story, 6-bay porch with square posts with brackets; plain balusters. Detached house. Vernacular. 1910.

-49

214: wood frame (weatherboard); 2½ stories; hipped roof (composition); 1 gable (clipped) dormer; 5 bays; 1-story, 4-bay porch with paired square posts. Detached house. Vernacular. 1920.

-50

218: wood frame (aluminum first floor; wood shingle); 2½ stories; gable roof (slate); 1 flat bungalow style dormer; 3 bays; 1-story, 2-bay porch with square wood posts on brick piers. Detached house. Vernacular. No date.

-51

219: wood frame (weatherboard); gable roof (composition); 3 bays; 2½ stories; 1-story, 3-bay porch with slender Doric Columns supporting shed roof. Detached house. Vernacular. 1890.

124-51-52

223: wood frame (asbestos shingles); gable roof (slate); 2½ stories; 3 bays; 1-story enclosed porch. Detached house. Vernacular. 1900.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, Virginia

Continuation sheet


11

Item number

7

Page

9



DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

200 Block

- 124-51-53 226: woodframe (vinyl siding); 2½ stories; hipped roof (slate alternately imbricated); 1 slate roof hipped dormer; 2 bays; 1-story, 4-bay porch with tapering wood posts on brick piers. Detached house. Vernacular. 1922.
- 54 230: brick (irregular); 2½ stories; gambrel roof (composition); 5 bays; front stoop. Detached house. Dutch Colonial. 1930.
- 55 231: wood frame (aluminum siding); 2½ stories; gable roof (asbestos shingles); 3 bays; 1-story, 2-bay porch with Doric columns and plain balusters; balustrade on deck. Detached house. Vernacular. 1895.
- 56 237: wood frame (asbestos shingles); 2½ stories; hipped roof (slate, alternately imbricated); 2 bays; 2-story, 1-bay porch with giant order square columns on brick piers, screened. Apartment building. Vernacular. 1920.
- 57 238: wood frame (asbestos siding); 2½ stories; gable (cross) roof (asbestos shingles); 3 bays; 1-story, 3-bay porch with squared post on brick piers supporting hipped roof. Detached house. Vernacular. 1910.
- 58 241: wood frame (asbestos shingles); 2½ stories; hipped roof (slate); 2 bays; 2-story, 1-bay porch with giant order square columns on brick piers. Apartment building. Vernacular. 1920.
- 59 244: wood frame (aluminum siding); 2 stories; gambrel roof (slate); 3 gable dormers; 4 bays. Detached house. Colonial Revival. 1939.
- 60 245: wood frame (weatherboard); 2½ stories; gable roof (asbestos shingles); 3 gable dormers; 3 bays; 1 center-bay front stoop with pediment supported by Doric columns. Detached house. Colonial Revival. 1940.
- 61 250: wood frame (vinyl siding); 2½ stories; hipped roof (slate, alternately imbricated); 1 hipped dormer; 2 bays; 1-story, 3-bay porch which extends on two sides; tapering wood columns on brick piers. Detached house. Vernacular. 1910.
- 62 251: brick (American); 2½ stories; gable roof (slate); 1 shed dormer; 2 bays; 1-story, 2-bay porch supported by columns (paired in north bay). Detached house. Bungalow style. 1925.
- NC 254: brick (stretcher); 1 story; gable roof (composition); 2 bays. Detached house. Contemporary. 1955. *Noncontributing structure.
- 124-51-63 258: wood frame (vinyl siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with slender Doric posts. Detached house. 1910.

**United States Department of the Interior
National Park Service**


**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 12

Item number 7

Page 10



DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

200 Block

124-51-64 259: brick (American); 3 stories; flat roof (not visible); 3 bays; 3-story, 1-bay porches (2) with brick piers. Apartment building. 1920.

300 Block

-65 301: wood frame (asbestos shingle); 2½ stories; gable roof (standing seam metal); 3 bays. Detached house. Vernacular. 1900.

-66 305: brick (American); 1½ stories; gable roof (composition); 2 bays; 1-story, 1-bay porch with wrought-iron posts and railing. Detached house. Pre-ranch style. 1943.

-67 309: wood frame (asbestos shingle); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with slender Doric columns. Detached house. Vernacular. 1910.

-68 315: wood frame (weatherboard, first floor; cedar shakes- second floor); 2½ stories; gable roof (slate); 1 shed dormer; 2 bays; 1-story, 2-bay porch paired square columns on brick piers. Detached house. Vernacular. 1912.

-69 317: wood frame (asbestos shingle); 2½ stories; hipped roof (composition); 1 hipped dormer; 4 bays; 1-story, 4-bay porch with extension on 2 sides; Doric columns supporting hipped roof. Detached house. Vernacular. 1910.

-70 318: brick (stretcher); 2 stories; gable roof (slate); 7 bays; Church. Gothic Revival. 1914. (Wesley Methodist Church).

-71 322: wood frame (asbestos shingle, upperhalf, wood shingles, lower half); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with slender turned posts supporting hipped roof: dentils. Detached house. Vernacular. 1900.

-72 329: wood frame (weatherboard); 2½ stories; gable (cross) roof (composition); 3 bays; 1-story, 2-bay porch which extends on two sides; paired Doric columns. Detached house. Vernacular. Late-19th century.

-73 331: wood frame (weatherboard); 2 stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with turned posts, brackets, turned balusters. Detached house. Vernacular. 1900.

124-51-74 334: brick (stretcher); 1½ stories; hipped roof (standing seam metal); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with square tapering columns on brick piers. Detached house. Bungalow. 1930.

**United States Department of the Interior
National Park Service**

For NPS use only
received
date entered

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic Distric, Portsmouth, Virginia

Continuation sheet 13

Item number 7

Page 11

DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

300 Block

124-51-75 335: wood frame (weatherboard); 2½ stories; mansard roof (slate); 1 gable dormer; 3 bays; 1-story, 3-bay porch with slender square supporting hipped roof. Detached House. Vernacular. 1900.

-76 339: wood frame (weatherboard); 2 stories; gable roof (composition); 2 bays; 1-story, 3-bay porch with Doric columns and turned balusters. Detached house. Vernacular. 1910.

-77 340-46: brick (decorative details); 1 story; flat roof (not visible); 10 bays. Commercial (restaurant). Contemporary. 1941.

-78 343: wood frame (asbestos shingle); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with slender Doric columns. Detached house. Vernacular. 1900.

-79 347: wood frame (weatherboard); 2½ stories; hipped roof (composition); 2 hipped dormers; 3 bays; 2-story, 3-bay on first story, 1 bay on second story porch with giant order Doric columns with pediment. Detached house. Georgian Revival. 1900.

-80 348: wood frame (wood shingle); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with Doric columns. Detached house. Vernacular. 1940.

NC 352-56: concrete block; 1 story; flat roof (not visible); Gas station. 1961.
* Noncontributing structure.

124-51-81 353-55: brick (stretcher); 2 stories; flat roof (not visible); 5 bays. Commercial (store). Vernacular commercial. 1927.

-82 357: wood frame (asbestos shingle); 2½ stories; hipped roof (slate, alternately imbricated); 1 gable dormer; 5 bays. Commercial (store). 1906.

400 Block

-83 400: brick (flemish); 2 stories; flat roof (not visible); 6 bays; 1-story, 6-bay porch (second floor) supported by Tuscan columns. Commercial (store). Commercial. 1922. (Lee's Hot Dogs)

124-51-84 404: wood frame (asbestos shingles); 2 stories; gable roof (composition) 3 bays. 2-story, 3-bay porch with Doric columns; turned balusters. Detached house. Vernacular. 1900.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk Historic District, Portsmouth, Virginia
Continuation sheet ¹⁴ Item number 7

Page 12

DESCRIPTION -- Inventroy (continued)

BROAD STREET (continued)

400 Block

124-51-85

401-17: brick (5-course American); 1 story; gable roof (slate); 3 bays. Church. Colonial Revival. 1960. (Port Norfolk Baptist Church).

-86

421: wood frame (weatherboard); 2½ stories; hipped roof (asbestos shingles); 1 hipped dormer; 3 bays; 2 porches, 2 stories; 1-bay on each porch with brick piers. Apartment building. Vernacular. 1926.

-87

425: wood frame (weatherboard); 2½ stories; hipped roof (slate, alternately imbricated); 3 bays; 1-story, 3-bay porch with Doric columns. Detached house. Vernacular. 1910.

NC

429: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 2 bays; 1-story glassed in porch. Detached house. Ranch. 1948. * Non-contributing structure.

-88

432: brick (irregular); 2 stories; flat roof (not visible); 7 bays. Government. Contemporary. Mid-20th century. (City of Portsmouth, Dept. of Parks & Recreation).

-89

433: wood frame (weatherboard); 2½ stories; gable roof (asbestos shingles); 1 shed dormer; 2 bays; 1-story, 2-bay porch with tapering wood columns on brick piers. Detached house. Vernacular. 1928.

-90

441: wood frame (aluminum siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with squared posts on brick piers. Detached house. Bungalow. 1926.

-91

443: wood frame (asbestos shingle); 2½ stories; gable roof (composititon); 3 bays; 1-story, 3-bay porch with turned posts. Detached house. Vernacular. 1910.

-92

444: wood frame (vinyl siding); 2½ stories; gable roof (asbestos shingles); 1-story, 4-bay porch with round posts, wrought iron railing supporting hipped roof. Detached house. Vernacular. 1905.

-93

445-47: wood frame (aluminum siding); 2½ stories; gable roof (standing seam metal); 4 bays; 1-story, 4-bay porch with square columns. Double house. Vernacular. 1910.

124-51-94

449: wood frame (vinyl siding); 2½ stories; gable roof (asbestos shingles); 1 shed dormer; 2 bays; 1-story, 2-bay porch wiht square posts on brick piers. Detached house. Vernacular. 1928.

United States Department of the Interior
National Park Service


National Register of Historic Places
Inventory—Nomination Form

Port Norfolk Historic District, Portsmouth, Virginia

Continuation sheet 15

Item number 7

Page 13



DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

400 Block

124-51-95

453: wood frame (asbestos shingles); 2 stories; hipped roof (standing seam metal); 2 bays; 1-story, 3-bay porch with square posts, turned balusters and hipped roof. Detached house. Vernacular 1910.

-96

457: wood frame (weatherboard); 1½ stories; gable roof (standing seam metal); 1 gable dormer with bungalow brackets; 3 bays; 1-story, 1-bay porch with stucco piers supporting shed roof. Detached house. Bungalow. 1923.

-97

458: wood frame (asbestos shingle); 2½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with south bay screened; slender Doric columns; extends on two sides. Detached house. Vernacular. 1905.

-98

450: wood frame (aluminum siding); 2½ stories; gable roof (composition); 2 bays; 1-story, 3-bay porch with wrought iron supports, shed roof on brick piers. Detached house. Vernacular. 1900.

500 Block

-99

500: wood frame (weatherboard); hipped roof (slate); 2½ stories; 1 gable dormer with roof cresting; 3 bays; 1-story, 4-bay porch extends on two sides; Doric columns; dentil frieze; turned balusters. Detached house. American Four Square roof with P.N. porch with metal roof cresting. 1910.

-100

501-03: wood frame (aluminum siding); 2 stories; gable roof (standing seam metal); 4 bays; 1-story, 3-bay porch with double and triple molded square posts with plain square railing; paired slender square posts supporting hipped roof. Double house. Vernacular. 1910.

-101

505-07: wood frame (weatherboard); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with wrap around porch; slender Doric columns supporting hipped roof. Detached house. Vernacular. 1913.

-102

515: wood frame (weatherboard); 1 story; gable roof (glass fiber tiles); 5 bays. Repair garage. Commercial vernacular. 1937. (McCarty's Wheel Shop).

-103

516: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 3 bays; 2-story, 3-bay porch extends on two sides; Doric columns; turned balusters. Detached house. Vernacular. 1910.

-104

520: wood frame (asbestos shingle); 2½ stories; gable roof (composition); 1-story, 6-bay porch extends on two sides; turned posts; hipped roof. Detached house. Vernacular. 1910.

124-51-105

524: wood frame (asbestos shingle); 2½ stories; gable roof (composition); small front pediment covered with shingles; 2 bays; 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1910.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, Virginia

For NPS use only
received
date entered

Continuation sheet 16 Item number 7 Page 14

DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

500 Block

- 124-51-106 525-27: wood frame (asbestos shingle); 2½ stories; gable roof (standing seam metal); 4 bays; 1-story, 4-bay porch with plain square posts and railing; Double house. Vernacular. 1910.
- 107 528: wood frame (aluminum siding); 2½ stories; gable roof (slate); 3 bays; 1-story 3-bay porch with bracketed posts, turned posts and turned balusters. Detached house. Vernacular. 1906.
- 108 526: wood frame (vinyl siding); 2½ stories; gable roof (composition); 1 shed dormer; 2 bays; 1-story, 2-bay porch with square posts on brick piers supporting hipped roof. Detached house. Vernacular. 1933.
- 109 529: wood frame (weatherboard); 2 stories; flat roof (not visible); 3 bays; 2-story, 3-bay porch with paired square posts on brick piers. Detached house. Vernacular. 1944.
- 110 530: wood frame (aluminum siding); 2½ stories; gable roof (slate); front pediment covered with siding and P.N. windows; 3 bays; 1-story, 3-bay porch with slender turned posts; decorative scroll work; turned balusters. Detached house. Vernacular. 1910.
- NC 533: wood frame (asbestos shingle); 1 story, 3 bays; gable roof (composition); 1-story, 2-bay porch with wrought iron posts. Detached house. Contemporary. 1950.
* Noncontributing structure.
- 111 542: wood frame (asbestos shingle); 2½ stories; gable roof (not visible); pediment on front covered with asbestos shingles; triple window; 5 bays; 2-story, 3-bay porch with square posts on brick piers. Detached house. Vernacular. 1915.
- 112 543: wood frame (aluminum siding); 2½ stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch extends on two sides; slender Doric columns; turned balusters. Detached house. Vernacular. 1900.
- 113 549: wood frame (weatherboard); 2½ stories; hipped roof (slate, alternately imbricated); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with dentils; square posts; paneled frieze. Detached house. American four square. 1914.
- 124-51-114 546: wood frame (asbestos shingle); 2½ stories; gable roof (slate); two story bay at rt. side second floor bay- at left front pediment with decorative shingles; 2 bays; 1-story, 2-bay porch with plain balusters. Detached house. Vernacular. 1910.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, Virginia

Continuation sheet


17

Item number

7

Page

15



DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

500 Block

NC 554-56: brick (stretcher); 2 stories; modified gable roof (composition); 2 bays. Apartment building. Contemporary. 1973. *Noncontributing structure.

124-51-115 558: wood frame (weatherboard); 2½ stories; gable roof (composition); notched shingles on front pediment; 4 bays; 1-story, 2-bay porch with Doric columns. Detached house. Vernacular. 1900.

-116 559: wood frame (aluminum siding); 2½ stories; gable roof (asbestos shingles); 2 bays; 1-story, 2-bay porch extends on two sides; columns on brick piers; plain balusters. Detached house. Vernacular. 1915.

600 Block

NC 600: concrete block; 1 story; flat roof (not visible); 3 bays. Park restrooms. Contemporary. 1966. *Noncontributing structure.

-117 614-16: wood frame (brick texture); 2½ stories; gable roof (standing seam metal); 6 bays; 1-story, 3 bay porch with Doric columns. Double house. Vernacular. Around 1910.

-118 618: wood frame (asbestos shingle); 2½ stories; gable roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with slender turned posts with brackets; turned balusters. Detached house. Vernacular. 1900.

-119 620-22: wood frame (weatherboard); 2½ stories; gable roof (composition); 6 bays; 1-story, 4-bay porch with square posts. Double house. Vernacular. 1900.

-120 624: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with square post on brick piers; plain balusters. Detached house. Vernacular. 1921.

-121 626: wood frame (asbestos shingle); 2 stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with plain square posts. Detached house. Vernacular. 1900.

-122 628: wood frame (asbestos shingle); 2 stories; hipped roof (standing seam metal); 4 bays; 1-story, 3-bay porch with turned balusters and Doric columns. Detached house. Vernacular. 1910.

124-51-123 630: wood frame (asbestos shingle); 2½ stories; hipped roof (slate, alternately imbricated); 3 bays; 1-story, 3-bay porch with turned posts and balusters; decorative sawnwork, metal cresting on roof. Detached house. Vernacular. 1910.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Port Norfolk Historic District, Portsmouth, Virginia
Continuation sheet 18 Item number 7

Page 16

DESCRIPTION -- Inventory (continued)

BROAD STREET (continued)

600 Block

- 124-51-124 634: wood frame (aluminum siding); 1½ stories; gable roof (composition); 6 bays. School (day care center). Vernacular. 1940.
- 124-51-125 600: Playground; 1890. Original site plan (subdivision) 1890 designates this as "Colored Play Ground site" has remained playground since subdivision.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet


19

Item number

7

Page

17



DESCRIPTION -- Inventory (continued)

BRUCE PLACE

100 Block

- 124-51-126 101: wood frame (aluminum siding); 2½ stories; gable roof (composition); 3 bays. Detached house. Vernacular. 1910.
- 124-51-127 102: wood frame (weatherboard); 2½ stories; gable roof (composition); 1 gable dormer with double window; notched wood shingles; 3 bays. Detached house. Vernacular. 1900.
- 128 110: wood frame (aluminum siding); 1½ stories; gable roof (standing seam metal); 3 bays; 1-story; 2-bay arcaded porch. Detached house. Queen Anne. 1900.
- 129 115: wood frame (weatherboard); 3 stories; flat roof (not visible); 5 bays; 2 3-story, 2-bay porches with square posts on second and third stories; brick piers on first story. Plain balusters. Apartment building. Vernacular. 1910.
- NC 117: brick (stretcher); 1 story; gable roof (composition); 4 bays. Detached house. Ranch style. 1962 *Noncontributing structure.
- NC 119: brick (stretcher); 1 story; hipped roof (composition); 4 bays. Detached house. Ranch style. 1962. * Noncontributing structure.
- NC 120: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 4 bays; 1-story, 1-bay porch on side. Detached house. Ranch style. 1952. * Noncontributing structure.
- 130 127: wood frame (vinyl siding); 1½ stories; hipped roof (composition); 1 gable dormer; 3 bays; 1-story, 5-bay porch with Doric columns; hipped roof. Detached house. Vernacular. 1905.

CHAUTAUQUA AVENUE

100 Block

- 131 108: wood frame (asbestos siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1900.
- 124-51-132 114: wood frame (asbestos siding); 2½ stories; hipped roof (composition); 2 gable dormers, one on each side; 2 bays; 1-story, 3-bay porch with Doric columns, turned balusters; hipped roof. Detached house. Vernacular. 1910.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form


Port Norfolk, Historic District, Portsmouth, VA
Continuation sheet

Item number

7

Page

18



DESCRIPTION -- Inventory (continued)

CHAUTAQUA AVENUE (continued)

100 Block

124-51-133 118: wood frame (vinyl siding); 2½ stories; gable roof (composition); 2 bays; 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1905.

-134 124: brick (stretcher); 2 stories; hipped roof (composition); 3 bays. Detached house. Vernacular. 1950.

-135 136: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays. Detached house. Vernacular. 1939.

-136 146: wood frame (asbestos siding); 1½ stories; gable roof (composition); 2 gable dormers; 4 bays. Detached house. Pre-ranch style. 1941.

-137 155: wood frame (asbestos siding); 2½ stories; gable roof (slate); 2 bays. Detached house. Vernacular. 1900.

-138 156: wood frame (asbestos siding); 1½ stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch with square post on brick piers; plain balusters. Detached house. Bungalow. 1920.

-139 159: wood frame (weatherboard); 2½ stories; gable roof (slate); 2 bays; 1-story, 1-bay corner octagonal porch with front pediment over entrance bay; brackets on posts. Detached house. Queen Anne. 1900.

NC 160: brick (stretcher); 1 story; gable roof (composition); 5 bays. Detached house. Ranch style. 1951. *Noncontributing structure.

-140 162: wood frame (weatherboard); 2½ stories; hipped roof (composition); 2 bays; 1-story, 2-bay porch with Doric columns; turned balusters. Detached house. Vernacular. 1900.

200 Block

-141 200: wood frame (aluminum siding); 1½ stories; gable roof (asbestos); 2 gable dormers; 3 bays. Detached house. Vernacular. 1942.

-142 201: wood frame (asbestos siding); 1½ stories; gable roof (composition); 4 bays; 1-story, 2-bay porch with wrought-iron railing and posts. Detached house. 1941.

124-51-143 204: wood frame (aluminum siding); 2½ stories; gable roof (not visible); 3 bays; 1-story, 2-bay screened porch with square posts on brick piers. Detached house. Vernacular. 1900.

**United States Department of the Interior
National Park Service**


**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet

Item number

Page



21

7

19

DESCRIPTION -- Inventory (continued)

CHAUTAQUA AVENUE (continued)

200 Block

124-51-144

205: wood frame (asbestos siding); 1½ stories; gable roof (composition); 4 bays. Detached house. Vernacular. 1941.

-145

208: wood frame (aluminum siding); 2½ stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch with square posts on brick piers. Detached house. Vernacular. 1910.

-146

209: wood frame (asbestos siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with wrought-iron posts. Detached house. Vernacular. 1941.

-147

212: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 1 gable dormer; 2 bays; 1-story, 3-bay porch with Doric columns on brick piers; hipped roof. Detached house. Vernacular. 1900.

-148

215: wood frame (asbestos siding); 1½ stories; gable roof (composition); 4 bays; 1-story, 2-bay porch on side; plain square posts; no balusters. Detached house. Vernacular. 1941.

NC

216-220: brick (stretcher); 1 story; hipped roof (composition); 5 bays. Detached house. Ranch. 1955. * Noncontributing structure.

-149

219: wood frame (asbestos siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with square wood posts. Detached house. Vernacular. 1941.

-150

226: wood frame (asbestos siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 5 bays; 1-story, 3-bay porch extends on side; 2 square posts; 2 Doric columns; plain balusters; hipped roof. Detached house. Vernacular. 1900.

-151

227: wood frame (asbestos siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2 bay porch with square posts on brick piers. Detached house. Vernacular. 1941.

-152

228: wood frame (asbestos siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 4 bays; 1-story, 3 bay porch with Doric columns; plain balusters. Detached house. Vernacular. 1900.

NC

231: wood frame (aluminum siding); 2½ stories; gable roof (composition); 7 bays; Apartment. Contemporary. 1983. * Noncontributing.

124-51-153

232: wood frame (asbestos siding); 2½ stories; gable roof (slate); 4 bays; 1-story, 4-bay porch with slender posts; plain balusters; dentil work on cornice. Vernacular. 1900.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet

22

Item number

7

Page

20

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

CHAUTAUQUA AVENUE (continued)

300 Block

- NC 301: wood frame (weatherboard); 2 stories; gable roof (composition); 7 bays; 2-story, 7-bay porch with iron balusters. Apartment building. Contemporary. 1975. *Noncontributing structure.
- 124-51-154 304: wood frame (aluminum siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with plain square posts. Detached house. Vernacular. 1952.
- 155 308: (asbestos siding); 2½ stories; gable roof (composition); 4 bays; 1-story, 3-bay porch with plain square posts on first story; balustraded deck. Detached house. Vernacular. 1900.
- NC 312: wood frame (vinyl siding); 1 story; hipped roof (composition); 3 bays; 1-story, 1-bay porch with square post. No balusters. Detached house. Vernacular. 1964 *Noncontributing structure.
- 156 313: wood frame (vinyl siding); 1½ stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch enclosed; paired square posts; hipped roof. Detached house. Vernacular. 1932.
- 157 315: wood frame (vinyl siding); 2½ stories; gable roof (slate); 1 shed dormer; 3 bays; 1-story, 3-bay porch screened; brick piers; gable roof. Detached house. Vernacular. 1928.
- 158 318: wood frame (asbestos siding); 2½ stories; gambrel roof (asbestos); 1 hipped dormer; 2 bays. Detached house. Vernacular. 1900.
- 159 319: wood frame (aluminum siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with square posts on brick piers; no balusters. Detached house. Vernacular. 1931.
- 160 320: wood frame (asbestos siding); 2½ stories; gable roof (composition); 3 bays. 1-story, 3-bay porch with shed roof; turned posts; dentils; no balusters. Detached house. Vernacular. 1900.
- 161 321: wood frame (aluminum siding); 1½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1932.
- 124-51-162 322: wood frame (asbestos siding); 2½ stories; hipped roof (slate); 1 shed dormer; 2 bays; 1-story, 3-bay porch with Doric columns; plain baluster. Detached house. Vernacular. 1900.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

For NPS use only
received
date entered

Continuation sheet 23 Item number 7 Page 21

DESCRIPTION -- Inventory (continued)

CHAUTAQUA AVENUE (continued)

200 Block

NC 235: brick (stretcher); 1½ stories; gable roof (composition); 2 gable dormers; 2 bays. Detached house. Vernacular. 1939. * Noncontributing structure.

124-51-163 236: wood frame (asbestos siding); 2½ stories; gable roof (asbestos); 4 bays; 1-story, 3-bay porch with wrought-iron supports. Detached house. Vernacular. 1900.

NC 238: brick (stretcher); 2½ stories; gable roof (composition); 3 bays. Detached house. Contemporary. 1954. * Noncontributing structure.

NC 239: wood frame (shingle); 1 story; gable roof (composition); 3 bays; 1-story, 2-bay porch with plain square posts; no balusters. Detached house. Vernacular. 1952.

-164 240: wood frame (weatherboard); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1931.

-165 243: wood frame (asbestos siding); 1½ stories; gable roof (composition); 3 bays. Detached house. Vernacular. 1941.

-166 246: brick (stretcher); 1½ stories; gable roof (composition); 4 bays. Detached house. Vernacular. 1950.

-167 247: brick (stretcher); 1½ stories; gable roof (asbestos); 3 bays; 2-story, 2½-bay porch - 1st story; square wood posts, no balusters, 2nd story; plain balusters, no roof. Detached house. Vernacular. 1948.

-168 257-59: wood frame (asbestos siding); 2 stories; hipped roof (composition); 6 bays; 2-story, 4-bay porch with slender turned posts; plain balusters; dentils on cornice. Double house. Vernacular. 1900.

-169 251: wood frame (asbestos shingle); 2 stories; hipped roof (composition); 6 bays; 2-story, 4-bay porch with slender turned posts and balusters; dentils on cornice. Detached house. Vernacular. 1910.

300 Block

124-51-170 300: wood frame (vinyl siding); 1½ stories; gable roof (composition); 1 gable dormer; 3 bays; 1-story, 2-bay porch with plain square posts; plain balusters. Detached house. Vernacular. 1952.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

For NPS use only
received
date entered

Continuation sheet 24

Item number 7

Page 22

DESCRIPTION -- Inventory (continued)

CHAUTAUQUA AVENUE (continued)

300 Block

124-51-171

324: wood frame (weatherboard, first floor - wood shingle, 2nd floor); 2½ stories; hipped roof (composition); 1 hipped dormer on front; 3 bays; 1-story, 1-bay porch with north bay which projects from rest of porch; paired columns and piers; hipped roof. Detached house. Vernacular. 1910.

-172

325: wood frame (asbestos siding); 1½ stories; gable roof (composition); 3 bays. 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1932.

-173

326: wood frame (asbestos siding); 2½ stories; gable roof (composition); 2 bays. 1-story, 3-bay porch with paired Doric columns at end; turned balusters on side. Detached house. Vernacular. 1910.

-174

333: wood frame (asbestos siding); 2½ stories; gable roof (composition); 3 bays. 1-story, 2-bay porch with slender posts; no balusters. Detached house. Vernacular. 1909.

-175

337: wood frame (aluminum siding); 1-story; gable roof (composition); 3 bays; 1-story, 3-bay porch; screened. Detached house. Vernacular. 1950.

-176

340: wood frame (shingle); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with Doric columns; turned balusters. Detached house. Vernacular. 1910.

-177

341: wood frame (asbestos siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with wrought-iron supports. Detached house. Vernacular. 1950.

-178

342: wood frame (aluminum siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with plain square posts. Detached house. Contemporary. 1951.

-179

344: wood frame (vinyl siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with square posts on brick piers. Plain balusters. Detached house. Vernacular. 1926.

124-51-180

345: wood frame (shingle); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with plain baluster, hipped roof and turned posts. Detached house. Vernacular. 1900.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

For NPS use only
received
date entered

Continuation sheet

25

Item number

7

Page

23

DESCRIPTION -- Inventory (continued)

CHAUTAUQUA AVENUE (continued)

300 Block

124-51-181 347: wood frame (asbestos siding); 2½ stories; gable roof (standing seam metal); 4 bays; 1-story, 3-bay porch with slender Doric columns; added entrance; plain balusters; hipped roof. Detached house. Vernacular. 1900.

-182 352: wood frame (asbestos siding); 2 stories; gable roof (composition); 2 bays; 1-story, 1-bay porch with paired slender posts supporting hipped roof. Detached house. Vernacular. 1950.

-183 353: wood frame (vinyl siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square wood posts. Detached house. Vernacular. 1900.

-184 357: wood frame (asbestos siding); 2½ stories; hipped roof (composition); 2 bays; 1-story, 3-bay porch extends on side; slender Doric columns; plain balusters. Detached house. Queen Anne. 1900.

-185 358: wood frame (aluminum siding); 2½ stories; hipped roof (standing seam metal); 3 bays; 1-story, 4-bay wrap around porch with Doric columns and wrought-iron baluster, two story turret. Detached house. Vernacular. 1900.

400 Block

-186 403: wood frame (shingle); 2½ stories; cross gable roof (slate); 3 bays. 1-story, 4-bay porch with turned posts; hipped roof; no balusters. Detached house. Modified Queen Anne. 1900.

-187 407: wood frame (aluminum); 1 story; gable roof (composition); 3 bays. Detached house. Ranch. 1952.

-188 408: wood frame (asbestos shingle); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with shed roof; Doric columns; no balusters. Detached house. Vernacular. 1940.

NC 411: brick (stretcher); 1 story; gable roof (composition); 3 bays; 1-story, 1-bay porch with decorative iron posts; no balusters. Detached house. Ranch. 1949. * Noncontributing structure.

124-51-189 414: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer, 3 bays; 1-story, 3-bay porch with slender square posts; plain balusters; hipped roof. Detached house. Vernacular. 1895.

NC 415: wood frame (asbestos shingle); 1 story, gable roof (not visible); 3 bays; 1-story, 1-bay porch with hipped roof; square posts; no balusters. Detached house. Vernacular. 1941. * Noncontributing structure.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Port Norfolk, Historic District, Portsmouth, Va. 7
Continuation sheet 26 Page 24

DESCRIPTION -- Inventory (continued)

CHAUTAUQUA AVENUE (continued)

400 Block

NC 416: brick (stretcher); 1 story; gable roof (not visible); 3 bays; 1-story, 2-bay porch screened; square posts. Detached house. Ranch. 1948. * Noncontributing structure.

124-51-190 420: wood frame (aluminum siding); 2½ stories; gable roof (not visible); 2 bays; 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1895.

124-51-191 421: wood frame (asbestos shingle); 1 story; gable roof (composition); 3 bays; 1-story, 1-bay porch with square posts on brick piers; gable roof. Detached house. Ranch. 1941.

124-51-192 422: wood frame (aluminum siding); 1½ stories; gable roof (composition); 2 bays; 1-story, 1-bay porch with paired square posts; balustrade on deck; with plain balusters. Detached house. Vernacular. 1936.

NC 423: brick (stretcher); 1 story; gable roof (asbestos shingle); 3 bays; 1-story, 2-bay porch with plain square posts. Detached house. Ranch. 1950. * Noncontributing structure.

-193 425: wood frame (weatherboard); 2 stories; gable roof (standing seam metal on porch, roof not visible); 3 bays; 1-story, 2-bay porch with hipped roof; square wood posts on brick piers; plain balusters. Detached house. Bungalow. 1928.

-194 426: wood frame (aluminum siding); gable roof (composition); 3 bays; 1-story, 2-bay porch screened; square posts; no balusters; pediment. Detached house. Vernacular. 1939.

-195 434: wood frame (asbestos shingle); 2½ stories; hipped roof (slate, American foursquare roof alternately imbricated); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with wrought iron posts; no balusters; hipped roof. Detached house. Vernacular. 1910.


-196 436: wood frame (aluminum siding); 1 story; gable roof (composition); 3 bays; 1-story, 2-bay porch screened; square posts. Detached house. Vernacular. 1938.

124-51-197 437: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square posts on brick piers; hipped roof. Detached house. Bungalow. 1915.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA



Continuation sheet 27

Item number 7

Page 25

DESCRIPTION -- Inventory (continued)

CHAUTAUQUA AVENUE (continued)

400 Block

124-51-198 437: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square posts on brick piers; hipped roof. Detached house. Bungalow. 1915.

-199 439: wood frame (aluminum siding); 1 story; gable roof (composition); 3 bays. Detached house. Vernacular. 1941.

NC 440: brick (stretcher); gable roof (asbestos shingles); 1 gable dormer; 1½ stories; 2 bays; 1-story, 1-bay porch screened; shed roof; brick piers. Detached house. Vernacular. 1938. * Noncontributing structure.

-200 441: wood frame (aluminum siding); gable roof (composition); 1 stories; 4 bays. Detached house. Vernacular. 1940. Yard enclosed with white picket fence.

-201 443: wood frame (asbestos shingle); 1 story; gable roof (composition); 3 bays; 1-story, 1-bay porch with paired square posts supporting broken pediment with fan light. Detached house. Vernacular. 1951. Yard enclosed with white picket fence.

-202 445: wood frame (aluminum siding); 2½ stories; gable cross roof (composition) and (standing seam metal on porch); 5 bays; 1-story, 3-bay porch with Doric columns; hipped roof. Detached house. Vernacular. 1916.

-203 458: wood frame (asbestos shingle); 1½ stories; gable roof material, not visible); 3 bays; 1-story, 3-bay porch with plain square posts; no balusters. Detached house. Vernacular. 1912.

500 Block

-204 500: wood frame (asbestos shingle); 2½ stories; gable roof (asbestos shingles, not visible); 3 bays; 1-story, 3-bay porch with bricketed turned posts; hipped roof. Detached house. Vernacular. 1910.

-205 501: wood frame (asbestos shingle); 2 stories; gable roof (standing seam metal); 1-story, 2-bay porch with turned posts; plain balusters; hipped roof. Detached house. Vernacular. 1915.

124-51-206 502: wood frame (aluminum siding); gable roof (composition); 3 bays. 2½ stories. Detached house. Vernacular. 1910.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 28

Item number 7

Page 26

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

CHAUTAUQUA AVENUE (continued)

500 Block

- 124-51-207 504: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch, screened; square posts. Detached house. Vernacular. 1941.
- 200 505: wood frame (aluminum siding); 2 stories; gable roof (composition); 2 bays; 1-story, 2-bay porch with square posts on brick piers; shed roof. Detached house. Vernacular. 1910.
- 209 506: wood frame (asbestos shingle); 1½ stories; gable roof (asbestos shingles, not visible); 2 bays; 1-story, 3-bay porch screened; tapered columns. Detached house. Bungalow. 1920.
- NC 507: wood frame (aluminum siding); 1 story; gable roof (composition); 4 bays. Detached house. Ranch. 1954. * Noncontributing structure.
- 210 508: wood frame (weatherboard); 1 story; gable roof (composition); 3 bays; 1-story, 2-bay porch with shed roof; wrought iron posts. Detached house. Vernacular. 1941.
- 211 509: wood frame (shingle); 2½ stories; gable roof (standing seam metal - porch, roof not visible); 2 bays; 1-story, 2-bay porch with slender posts; hipped roof. Detached house. Vernacular. 1910.
- 212 510: wood frame (asbestos shingle); 1½ stories; gable cross roof (composition); 3 bays; 1-story, 3-bay porch with plain square wooden posts; no balusters. Detached house. Bungalow. 1920.
- NC 511: stone (coursed ashlar); 1 story; gable roof (composition); 3 bays; 1-story, 1-bay porch with plain square posts; no balusters. Detached house. Ranch. 1952. * Noncontributing structure.
- 213 512: wood frame (aluminum siding); 1 story; gable roof (asbestos shingles, not visible); 3 bays. Detached house. Vernacular. 1941.
- NC 513: stone texture siding; 1 story, gable roof (composition); 3 bays. Detached house. Vernacular. Mid-20th century. * Noncontributing structure.
- 124-51-214 514: wood frame (aluminum siding); 1 story; gable roof (standing seam metal); 3 bays; 1-story, 1-bay porch with square posts on brick piers; plain balusters. Detached house. Bungalow. 1920.
- 124-51-215 515: wood frame (asbestos shingle); 1 story; gable roof (composition); 3 bays; 1-story, 2-bay porch screened; partially enclosed. Detached house. Vernacular. 1947.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historic District, Portsmouth, VA

For NPS use only
received
date entered

Continuation sheet 29 Item number 7 Page 27

DESCRIPTION -- Inventory (continued)

CHAUTAUQUA AVENUE (continued)

500 Block

- 124-51-216 518: wood frame (aluminum siding); 1 story; gable roof (asbestos shingles); 5 bays. Detached house. Vernacular. 1938.
- 217 520: wood frame (asbestos shingle); 1 story; gable roof (composition); 3 bays. Detached house. Vernacular. 1942.
- 218 546: wood frame (asbestos shingle); 1 story; gable roof (composition); 3 bays; 1-story, 1-bay porch with slender posts supporting pediment. Detached house. Vernacular. 1956.

CLEVELAND AVENUE

2700 Block

- 124-51-219 2716: concrete block; 1 story, gable roof (composition); 1 bay; 1-story, 3-bay porch; screened, set in corner. Detached house. Vernacular. Mid-20th century. * Noncontributing structure.

DETROIT STREET

2600 Block

- 220 2613: brick (American 5-course); 1 story; gable roof (composition); 3 bays. Commercial (travel agency). Vernacular. 1928. (Trans-Global Precuratois Ltd.).
- 221 2616: wood frame (brick texture); 1 story; gable roof (composition); 3 bays. Vernacular. 1937. Commercial (barber shop).
- 222 2622: brick (stretcher); 2 stories; parapet roof (not visible); 6 bays. Commercial (store). Commercial vernacular. Early 20th century.

2700 Block

- NC 2715-17: brick (American 5-course); 1 story; parapet, flat roof (not visible); 6 bays. Commercial. 1900.
- 124-51-223 2719: brick (stretcher); 1 story; flat roof (not visible); 4 bays. Commercial (store). 1900. * Noncontributing structure.

2800 Block

- 124-51-224 2813: wood frame (asbestos shingle); 2½ stories; gable roof (composition); 2 bays. Detached house. Vernacular. Early 20th centruy.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historic District, Portsmouth, VA

For NPS use only
received
date entered

Continuation sheet 30

Item number 7

Page 28

DESCRIPTION -- Inventory (continued)

DOUGLAS AVENUE

100 Block

124-51-225 101: wood frame (aluminum siding); 2½ stories; gable roof (composition); 1 gable dormer at left front; 4 bays; 1-story, 4-bay porch with hipped roof, fluted round columns, slender Doric columns; no balusters. Detached house. Vernacular. 1910.

-226 107: wood frame (aluminum siding); 1½ stories; gable roof (asbestos); 2 gable dormers; 3 bays. Detached house. Vernacular. 1942.

-227 108: wood frame (wood shingles); 1½ stories; gable roof (asbestos); 1 gable dormer; 3 bays; 1-story, 2-bay porch with square posts; no balusters. Detached house. Vernacular. 1949.

-228 110: wood frame (asbestos siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 4 bays; 1-story, 4-bay porch extends on one side with slender Doric columns; hipped roof. Detached house. Vernacular. 1900.

-229 114-120: Vacant lot.

124-51-230 115: wood frame (aluminum siding); 2½ stories; gable roof (composition); 2 bays; 1-story, 2-bay porch extends on two sides, turned posts and balusters; hipped roof. Detached house. Vernacular. 1910.

NC 117: stucco; 2 stories; hipped roof (composition); 2 bays; 2-story, 2-bay porch (very plain). Detached house. Contemporary. 1950. * Noncontributing structure.

NC 119-27: brick (stretcher); 2 stories; gable roof (composition); 5 bays. Apartment building. Contemporary. 1965. * Noncontributing structure.

NC 122: brick (stretcher); 1 story; hipped roof (composition); 3 bays. Detached house. Ranch. 1978. * Noncontributing structure.

NC 126: brick (stretcher); 1 story; 3 bays; 1-story, 3-bay porch with slender turned posts; no balusters. Detached house. Ranch. 1979. * Noncontributing structure.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Port Norfolk, Historic District, Portsmouth, Va.

Continuation sheet 31

Item number 7

Page 29

DESCRIPTION -- Inventory (continued)

DOUGLAS AVENUE (continued)

100 Block

NC 136-38: brick (stretcher); 1 story; gable roof (composition); 6 bays. Detached house. Ranch. 1948. * Noncontributing structure.

124-51-231 139: stucco; 2½ stories; hipped roof (composition); 1 hipped dormer on front; 4 bays; 1-story, 2-bay porch with paired slender Doric columns on stucco piers; no balusters. Detached house. Vernacular. 1900.

-232 140: wood frame (aluminum siding); 1 story; gable roof (composition); 3 bays. Detached house. Ranch. 1979. * Noncontributing structure.

-233 143: wood frame (aluminum siding); 2½ stories; gable roof (composition); 1 pedimented dormer; 4 bays; 1-story, 3-bay porch with slender Doric columns; no balusters; hipped roof. Detached house. Vernacular. 1900.

-234 155: wood frame (asbestos siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with shed roof supported by wrought iron posts; octagonal turret over south bay. Detached house. Queen Anne. 1910.

-235 163: wood frame (aluminum siding); 1½ stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with square posts and balusters; pedimented roof. Detached house. Vernacular. 1910.

200 Block

-236 201: wood frame (aluminum siding); 1½ stories; gable roof (composition); 2 gable dormers; 3 bays. Detached house. Vernacular. 1948.

-237 205: wood frame (aluminum siding); 1 story; gable roof (composition); 6 bays; enclosed porch. Detached house. Ranch. 1956. * Noncontributing structure.

-238 207-33: brick (stretcher); 1 story; hipped roof (slate); 5 bays (round headed doors and windows; heavy cornice; decorative metal doors). Government (fallout shelter). Colonial Revival. 1925.

-239 235: wood frame (weatherboard); 2½ stories; cross gable roof (composition); 3 bays; 1-story, 5-bay porch with slender, bracketed turned posts; turned balusters; hipped roof. Detached house. Vernacular. 1900.

124-51-240 238: wood frame (wood shingles) 1 1½ stories; gable roof (asbestos shingles); 1 bay. Detached house. Vernacular. Mid-20th century. Garage Apartment.

**United States Department of the Interior
National Park Service**


**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 32

Item number 7

Page 30



DESCRIPTION -- Inventory (continued)

DOUGLAS AVENUE (continued)

200 Block

NC 241: brick (stretcher); 1 story; hipped roof (composition); 6 bays. Detached house. Ranch. 1962. * Noncontributing structure.

124-51-241

247: wood frame (cedar shingles); 2½ story, hipped roof (composition); 1 hipped dormer on front; 4 bays; 1-story, 2-bay porch with paired square posts; plain balusters (south bay screened). Detached house. Vernacular. 1960.

NC

251-53: brick (stretcher); 1 story; gable roof (composition); 6 bays. Apartment building. Ranch. 1968. * Noncontributing structure.

-242

256-58: wood frame (asbestos siding); 2½ stories; gable roof (slate); 4 bays; 1-story, 6-bay porch with turned posts; stick style balusters; shed roof. Double house. Vernacular. 1900.

300 Block

-243

300: brick (stretcher); 2½ stories; gable roof (slate); 1 shed dormer on front with triple window; 1-story, 3-bay porch with square posts on brick piers; hipped roof; plain balusters. Detached house. American Four Square. 1925.

-244

301: wood frame (aluminum siding); 2½ stories; gable roof (asbestos); 3 bays. Detached house. Vernacular. 1940.

-245

305: wood frame (aluminum siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch screened; square posts; plain balustrade on flat roof. Detached house. Vernacular. 1951.

-246

308: brick (stretcher); 2 stories; shed roof; 3 bays; 2-story, 2-bay porch with brick piers; plain balusters. Apartment building. Vernacular. 1920.

-247

309: wood frame (asbestos siding); 1½ stories; gable roof (composition); 4 bays; glass enclosed porch with louvres. Detached house. Vernacular. 1939.

-248

310: wood frame (weatherboard); 2 stories; hipped roof (composition); 3 bays; 2-story, 2-bay porch with slender Doric columns; plain balusters. Detached house. Vernacular. 1910.


124-51-249

312: brick (7-course American); 2½ stories; gable roof (slate); 1 shed dormer on front; 3 bays; 1-story, 3-bay porch screened; square posts on brick piers; hipped roof. Detached house. Vernacular. 1922.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA



Continuation sheet 33

Item number 7

Page 31

DESCRIPTION -- Inventory (continued)

DOUGLAS AVENUE (continued)

300 Block

124-51-250

320-322: wood frame (weatherboard); 2½ stories; gable roof (composition); 3 bays; 2-story, 2-bay porch with plain balusters and square posts. Double house. Vernacular. 1910.

-251

321: wood frame (weatherboard); 2½ stories; hipped roof (slate, imbricated pattern); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with Doric columns, plain balusters. Detached house. Vernacular. 1915.

-252

323: wood frame (weatherboard); 2½ stories; gable roof (slate); 1 shed dormer; 2 bays; 1-story, 3-bay porch extends on side; square posts on brick piers; plain balusters. Detached house. Vernacular. 1922.

-253

334: wood frame (asbestos siding); 1½ stories; gable roof (asbestos); 3 bays. Detached house. Vernacular. 1920.

-254

326: wood frame (aluminum siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 1-side, 2-center bays with flat roof, wood posts on brick piers. Detached house. Vernacular. 1910.

-255

335: wood frame (asbestos siding); 2½ stories; gable roof (slate); 3 bays; 1-story, 4-bay porch with hipped roof; square posts; and plain balusters. Detached house. Vernacular. 1908.

-256

337: wood frame (bricktex); 2½ stories; hipped roof (composition); 1 gable dormer with 1 double hung window; 2 bays; 1-story, 2-bay porch screened with hipped roof; wood posts on brick piers with dentil cornice. Detached house. Vernacular. 1910.

-257

338: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch extends on one side; square tapered posts; brick piers; plain balusters; hipped roof. Detached house. Modified Queen Anne. 1915.

-258

341: wood frame (shingle); 2½ stories; hipped roof (asbestos); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with plain balusters; wood posts on brick piers. Detached house. Vernacular. 1915.

NC

348: brick (stretcher); 1 story; gable roof (asbestos); 3 bays. Ranch. 1946. * Noncontributing structure.

124-51-259

350: wood frame (asbestos); 2½ stories; gable cross roof (composition); 4 bays. Double house. Vernacular. 1910.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 34

Item number 7

Page 32

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

DOUGLAS AVENUE (continued)

300 Block

NC 352: wood frame (shingle); 1 story; gambrel roof (composition); 2 bays. Detached house. Contemporary. 1964. * Noncontributing structure.

NC 358: brick (stretcher); 1 story; gable roof (composition); 6 bays. Detached house. Ranch. 1964. * Noncontributing structure.

124-51-260 359: wood frame (weatherboard, vertical wood siding at bottom, cedar shakes top); 2½ stories; hipped roof (asbestos shingles); 1 gable dormer; 3 bays; 1-story, 4-bay porch with plain square posts; no balusters. Detached house. Vernacular. 1907.

400 Block

-261 401: wood frame (aluminum siding and cedar shakes); 2½ stories; gable roof (composition); front shed dormer; 3 bays; 2-story, 3-bay porch with wood posts on brick piers. Detached house. Vernacular. 1910.

-262 403: brick (stretcher); 1 story; gable roof (composition); 3 bays; 1-story, 1-bay gable roof; plain square posts; no balusters. Vernacular. 1964. * Noncontributing structure.

-263 409: wood frame (bricktex); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with Doric columns, plain balusters. Detached house. Vernacular. 1910.

-264 413: wood frame (aluminum siding); 1½ stories; gable roof (slate); 1 shed dormer on front with triple full-size window and wooden railing; 2 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters. Detached house. Bungalow. 1915.

-265 417: wood frame (shingle); 1½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square columns. Detached house. Vernacular. 1940.

-266 425: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 4-bay porch extends on side, Doric columns; turned balusters. Detached house. Vernacular. 1910.

-267 443: wood frame (aluminum siding); 2½ stories; gable roof (slate-2nd story); 3 bays; 1-story, 3-bay porch with slender Tuscan columns. Detached house. Vernacular. 1915.

124-51-268 451: brick (stretcher); 2½ stories; gambrel roof (asbestos); 4 bays; 1-story, 1-bay porch with Doric columns with broken pediment. Detached house. Dutch Colonial. 1932.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet


35

Item number

7

Page

33



DESCRIPTION -- Inventory (continued)

DOUGLAS AVENUE (continued)

400 Block

124-51-269

459: wood frame (shingle); 2½ stories; gable roof (asbestos); 2 bays; 1-story, 3-bay wrap around porch with Doric columns; no railing. Detached house. Vernacular. 1910.

600 Block

-270

627: wood (aluminum siding) and brick (stretcher); 1 story; gable roof (slate); 3 bays. Detached house. Vernacular. 1948

-271

630: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 1 hipped dormer on front; 3 bays; 1-story, 2-bay porch with square tapered posts; plain balusters. Detached house. Vernacular. 1910.

-272

634: wood frame (aluminum siding); 1½ stories; hipped roof (composition); 1 hipped dormer on front; 3 bays; 1-story, 3-bay porch with tapered square posts; plain balusters. Detached house. Bungalow. 1910.

NC

635: wood frame (asbestos shingle); 1 story; gable roof (composition); 4 bays. Detached house. Ranch style. 1962. *Noncontributing structure.

-273

638: wood frame (aluminum siding); 2 stories; gable roof (slate); 2 bays; 1-story, 2-bay porch with hipped roof; tapered columns; plain balusters; hipped roof. Detached house. Vernacular. 1910.

-274

641: wood frame (weatherboard); 1 story; gable and hipped roof (composition); 4 bays. Detached house. Vernacular. 1915.

-275

642: wood frame (aluminum siding); 1½ stories; gable roof (asbestos); 3 bays; 1-story, 2-bay porch with tapered posts on brick piers; plain balusters. Detached house. Bungalow. 1910.

-276

644: wood frame (aluminum siding); 2 stories; hipped roof (slate); 3 bays; 1-story, 2-bay porch with wrought-iron posts and balusters; hipped roof. Detached house. Vernacular. 1910.

124-51-277

646: wood frame (aluminum shingle); 2½ stories; cross gable roof (composition); 4 bays; 1-story, 3-bay porch with round post; plain square railing; hipped roof; Doric columns; plain balusters. Detached house. Vernacular. 1910.

FLORIDA AVENUE

100 Block

NC

106: brick (stretcher); 1 story; hipped roof (composition); 4 bays. Detached house. Contemporary. 1957. * Noncontributing structure.

(See Continuation Sheet # 36)

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 36

Item number 7

Page 34

For NPS use only

received

date entered

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

100 Block

- 124-51-278 108: wood frame (weatherboard); 2½ stories; gable roof (composition); 1 gable dormer; 3 bays; 1-story, 4-bay porch with turned posts and balusters with scroll brackets. Detached house. Queen Anne. 1900.
- NC 109: brick (stretcher); 1 story; gable roof (composition); 4 bays. Detached house. Ranch. 1954. * Noncontributing structure.
- 279 110: wood frame (shingle and vinyl); 2 stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch with square wood posts on brick piers. Detached house. Vernacular. 1918.
- 280 113: wood frame (aluminum siding); 2½ stories; gable roof (asbestos shingles); 1 gable dormer; 3 bays; 1-story, 1-bay porch. Detached house. Vernacular. 1940.
- 281 115: wood frame (asbestos shingle); 1½ stories; jerkin head roof (asbestos shingles); 3 bays; 1-story, 3-bay porch with wood posts on brick piers. Detached house. Bungalow. 1930.
- 282 118: wood frame (first floor weatherboard, top floors cedar shakes); 2½ stories; gable cross roof (composition); 3 bays; 1-story, 3-bay porch with slender turned posts with brackets; turned balusters; shed roof. Detached house. Vernacular. 1900.
- 283 122: wood frame (shingle); 2½ stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch screened; turned posts, no railing. Detached house. Vernacular. 1910.
- 284 123: wood frame (vinyl siding); 1½ stories; gable roof (asbestos shingles); 1 gable dormer; 3 bays. Detached house. Vernacular. 1938.
- 285 128: brick (stretcher); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square brick posts; no railing. Detached house. Vernacular. 1910.
- 286 134: wood frame (asbestos siding); 2 stories; hipped roof (slate); 3 bays. Detached house. Vernacular. 1900.
- 287 131: wood frame (weatherboard); 2½ stories; hipped roof (composition); 1 hipped dormer; 4 bays; 1-story, 4-bay porch with Doric columns, turned balusters. Detached house. Vernacular. 1910.
- 124-51-288 135: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 4 bays; 1-story, 3-bay porch with Doric columns. Detached house. Vernacular. 1910.

(See Continuation Sheet #37)

United States Department of the Interior
National Park Service


National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 37

Item number 7

Page 35



DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

100 Block

124-51-289

138: wood frame (weatherboard); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square wooden posts; bracketed cornice; turned balusters. Detached house. Vernacular. 1900.

124-51-290

143: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch screened; extended on side; heavy Doric columns; no balusters; hipped roof. Detached house. Vernacular. 1910.

124-51-291

146: wood frame (weatherboard); 2 stories; gable roof (slate); 3 bays; 1-story, 3-bay porch extends on two sides; slender turned post with brackets; turned balusters. Metal cresting on roof. Double house. Vernacular. 1900.

124-51-292

147: (asbestos shingle); 2½ stories; hipped roof (slate); 1 hipped dormer; 4 bays; 1-story, 2-bay porch with plain square posts; partially screened in; no balusters. Detached house. Vernacular. 1910.

NC

148-50: brick (stretcher) 2 stories; flat roof (not visible); 3 bays. Apartment building. Contemporary. 1955. * Noncontributing structure.

-293

149: wood frame (aluminum siding); 1½ stories; gable roof (composition); 1 shed dormer; 2 bays; 1-story, 2-bay porch with square posts on brick piers; plain balusters. Detached house. Vernacular. 1915.

-294

151: wood frame (weatherboard - 1st floor, wood shingles - second floor); 2½ stories; gable roof (slate); 1 shed dormer; 2 bays; 1-story, 2-bay porch with square posts on brick piers; plain balusters. Detached house. Vernacular. 1915.

-295

154: wood frame (asbestos shingle); 2 stories; gable roof (composition); 1 shed dormer; 3 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters; shed roof. Detached house. Vernacular. 1920s.

NC

153: brick (stretcher); 1 story; hipped roof (composition); 5 bays; 1-story, 3-bay porch with wrought iron supports. Detached house. Ranch. 1955. * Noncontributing structure.

124-51-296

158: brick (stretcher); 1½ stories; gable roof (composition); 1 gable dormer; 4 bays; 1-story, 1-bay porch screened; hipped roof. Detached house. Vernacular. 1952.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

For NPS use only
received
date entered

Continuation sheet 38 Item number 7 Page 36

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE -- (continued)

200 Block

124-51-297 200: wood frame (weatherboard); 2 stories; hipped roof (asbestos);
1 gable dormer; 3 bays; 1-story, 3-bay porch with square posts on brick
piers; wrought iron railing. Detached house. Bungalow. 1900.

NC 204: brick (stretcher with aluminum siding on front); 1 story; gable
roof (composition); 3 bays; 1-story, 2-bay porch with square posts; plain
balusters. Detached house. Ranch. Mid-20th century. * Noncontributing
structure.

-298 205: wood frame (asbestos shingles); 2½ stories; gable roof (standing seam
metal); 3 bays; 1-story, 2-bay porch screened; square posts on brick piers;
hipped roof. Detached house. Vernacular. 1900.

-299 207: wood frame (asbestos shingle); 2½ stories; gable roof (standing
seam metal); 3 bays; 1-story, 3-bay porch screened; turned posts and balusters.
Detached house. Vernacular. 1900.

-300 209: wood frame (asbestos shingle); 2½ stories; gable roof (composition);
3 bays; 1-story, 3-bay porch screened; plain square posts with brackets.
Detached house. Vernacular. 1900.

-301 211: wood frame (brick texture); 2½ stories; gable roof (composition);
3 bays, 1-story, 3-bay porch with turned posts with brackets; turned balusters;
shed roof. Detached house. Vernacular. 1900.

-302 213: wood frame (aluminum siding); 2½ stories; gable roof (standing seam
metal); 3 bays; 1-story, 3-bay porch with slender posts with brackets;
plain balusters; shed roof. Detached house. Vernacular. 1900.

-303 215: wood frame (asbestos shingle); 2½ stories; gable roof (composition);
3 bays; 1-story, 2-bay porch with square posts on brick piers; stick-style
railing. Detached house. Vernacular. 1900.

124-51 - 304 217: wood frame (asbestos shingle); 2 stories; gable roof (composition);
3 bays; 1-story, 3-bay porch screened; turned posts; no balusters.
Detached house. Vernacular. 1900.

NC 218: wood frame (upper-shingle); brick (lower brick)
1 story; gable roof (composition); 4 bays. Detached house. Ranch. 1960.
* Noncontributing structure.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 39

Item number 7

Page 37

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

200 Block

NC 220: wood frame (asbestos siding); 1 story; gable roof (composition); 4 bays. Detached house. Ranch. 1960. * Noncontributing structure.

124-51-305 221: wood frame (asbestos shingle); 2 stories; gable roof (not visible); 3 bays; 1-story, 3-bay porch with square posts and plain balusters. Detached house. Vernacular. 1900.

NC 222: wood frame (asbestos siding); 1 story; gable roof (composition); 3 bays; front stoop with center bay; plain square posts. Detached house. Ranch. 1960. * Noncontributing structure.

NC 224: wood frame (upper 1/2, aluminum siding), brick (lower 1/2, stretcher); 1 story; gable roof (composition); 4 bays. Detached house. Ranch. Mid-20th century. * Noncontributing structure.

124-51-306 229: wood frame (asbestos shingle); 2 1/2 stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with Doric columns; no balusters; hipped roof. Detached house. Vernacular. 1900.

-307 233: wood frame (asbestos shingle); 1 1/2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with plain square posts and balusters; hipped roof. Detached house. Vernacular. 1900.

-308 240: wood frame (weatherboard); 2 1/2 stories; hipped roof (slate, imbricated); 3 bays; 1-story, 4-bay porch with Ionic columns; no balusters; extends on both sides. Detached house. Vernacular. 1910.

NC 245: brick (American); 1 story; hipped roof (composition); 4 bays. Detached house. Ranch. 1950s. * Noncontributing structure.

-309 246: wood frame (aluminum siding); 1 1/2 stories; gable roof (composition); 2 gable dormers. 4 bays; 1-story, 1-bay side porch screened; plain square posts. Vernacular. 1940.

124-51-310 249: wood frame (aluminum siding); 1 1/2 stories; cross gable roof (asbestos shingles); 3 bays; 1-story, 2-bay porch with plain square posts; no balusters. Detached house. Vernacular. 1941.

NC 250: wood frame (cedar shakes); 2 1/2 stories; gambrel roof (composition); 2 shed dormers; 3 bays; 1-story, 3-bay porch with plain columns; no balusters. Detached house. Vernacular. 1900. * Noncontributing structure.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historical District, Portsmouth, VA
Continuation sheet ⁴⁰

Item number 7

Page 38

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

200 Block

124-51-311

252: wood frame (shingle); 2 stories; gable roof (asbestos); 2 bays. Detached house. Vernacular. 1900.

-312

259: wood frame (weatherboard); 2½ stories; gable roof (composition); 2 bays; 1-story, 4-bay porch extends on side; Doric columns; turned balusters; hipped roof. Detached house. Vernacular. 1910.

300 Block

NC

300: brick (American); 1 story; gable roof (composition); 5 bays. Detached house. Ranch. 1957. * Noncontributing structure.

-313

301: wood frame (asbestos siding); 2 stories; gable roof (slate); 3 bays; 1-story porch extends on side; turned posts and balusters; hipped roof. Detached house. Vernacular. 1900. Metal cresting on roof.

-314

309: wood frame (shingle); 1½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square posts on brick piers; turned balusters. Detached house. Vernacular. 1915.

-315

310: wood frame (aluminum siding); 1½ stories; gable roof (composition); 2 bays; 1-story, 4-bay porch screened; plain square posts. Detached house. Vernacular. 1940.

-316

314: wood frame (asbestos siding); 2 stories; gable roof (standing seam metal); 2 bays; 1-story, 4-bay porch with square posts and balusters; hipped roof. Detached house. Vernacular. 1907.

-317

315: brick (stretcher); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters; hipped roof. Detached house. Vernacular. 1935.

-318

318: wood frame (aluminum siding); 2½ stories; gable roof (asbestos siding - 2nd floor); 4 bays; 1-story, 4-bay porch with slender turned posts and balusters; hipped roof. Detached house. Vernacular. 1900.

-319

319: wood frame (weatherboard); 2 stories; gambrel roof (asbestos); 5 bays; 1-story, 1-center-bay porch with Doric columns; broken pediment. Detached house. Vernacular. 1925.

124-51-320

320-22: wood frame (asbestos shingles); 2½ stories; gable roof (composition); 4 bays; 1-story, 4-bay porch with slender turned posts with brackets; turned balusters; cornice with dentils; hipped roof. Double house. Queen Anne. 1910.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 41

Item number 7

Page 39

For NPS use only
received
date entered

DESCRIPTION -- Inventroy (continued)

FLORIDA AVENUE (continued)

300 Block

124-51-321

323: wood frame (vinyl siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with Doric columns; turned balusters; hipped roof. Detached house. Vernacular. 1907.

-322

326: brick (9-course American); 1½ stories; hipped roof (asbestos); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters. Detached house. Bungalow. 1930.

NC

325: brick (stretcher); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with plain square posts; screened. Detached house. Ranch. 1949. * Noncontributing structure.

-323

330: wood frame (cedar shakes); 2 stories; gable roof (slate); 2 bays; 1-story, 3-bay porch with slender turned posts with brackets; turned balusters. Detached house. Vernacular. 1910.

-324

332: wood frame (aluminum siding); 2½ stories; gable roof (standing seam metal); 2 bays; 1-story, 3-bay porch with Doric columns; turned balusters; hipped roof. Detached house. Vernacular. 1910.

-325

333-35: wood frame (weatherboard); 2 stories; gable roof (composition); 6 bays; 1-story, 4-bay porch with slender turned posts with brackets; dentil work on cornice; decorative sawn work on pediment. Double house. Vernacular. 1905.

-326

341: wood frame (asbestos siding); 2 stories; gable cross roof (composition); 2 bays; 1-story, 3-bay porch with slender Doric columns, turned balusters; hipped roof. Detached house. Vernacular. 1905.

-327

346: wood frame (aluminum siding); 2½ stories; gable roof (asbestos); 1 shed dormer; 3 bays; 2-story, 2-bay porch with square posts on brick piers; plain balusters. Detached house. Vernacular. 1920.

-328

347: wood frame (wood shakes); 2½ stories; hipped roof (composition); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with wrought-iron supports. Detached house. Vernacular. 1910.

-329

350: brick (stretcher); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with Doric columns on brick piers; turned balusters. Detached house. Vernacular. 1910.

124-51-330

351: wood frame (asbestos siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 4 bays; 1-story, 4-bay porch with square posts; dentils on cornice, no balusters. Detached house. Vernacular. 1910.

(See Continuation Sheet # 42)

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 42

Item number 7

Page 40

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

300 Block

124-51-331

352: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with Doric columns on brick piers; wrought iron balusters; hipped roof. Detached house. Vernacular. 1910.

-332

355: wood frame (weatherboard); 2½ stories; gable roof (slate, alternately imbricated); 4 bays; 1-story, 3-bay porch extends on side; turned posts and balusters; dentils on cornice. Metal cresting on roof; decorative barge boards. Detached house. Vernacular. 1910.

-333

360: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 4-bay porch extends on side; Doric columns; turned balusters; gable over entrance bay. Detached house. Vernacular. 1907. Metal cresting on roof.

-334

357: wood frame (aluminum siding); 1 story; hipped roof (composition); 3 bays; 1-story, 3-bay porch screened; square posts on brick piers. Detached house. Bungalow. 1922.

-335

359: wood frame (weatherboard); 2½ stories; hipped roof (standing seam metal); 2 bays; 1-story, 3-bay porch extends on side; Ionic columns; turned balusters; dentils on cornice. Detached house. Vernacular. 1910.

400 Block

-336

400: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch extends on side; Ionic columns (clustered on center bay) turned balusters; pediment with decorative sawn work over center bay. Detached house. Vernacular. 1915.

-337

401: brick (6-course American); 2½ stories; hipped roof (slate); 1 hipped dormer; 2 bays; 1-story, 5-bay porch extends on side; Doric columns on brick piers; turned balusters. Detached house. Vernacular. 1914. Metal cresting on roof.

-338

405: wood frame (weatherboard); 2½ stories; gable roof (standing seam metal and asbestos); 1 shed dormer; 2 bays; 1-story, 2-bay porch screened; square posts on brick piers; hipped roof and plain balusters. Detached house. Vernacular. 1915.

124-51-339

407-09: wood frame (weatherboard); 2½ stories; hipped roof (standing seam metal and asbestos); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with square posts on brick piers; plain balusters; hipped roof. Detached house. Vernacular. 1915.


**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA
Continuation sheet ⁴³

Item number 7

Page 41



DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

400 Block

- 124-51-340 408: wood frame (vinyl siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 5 bays; 1-story, 3-bay porch screened; square posts on brick piers; plain balusters. Detached house. Vernacular. 1910.
- 341 412: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 1 gable dormer; 3 bays; 1-story, 2-bay porch screened; paired square posts on brick piers; plain balusters. Detached house. Bungalow. 1918.
- 342 413: wood frame (weatherboard); 2½ stories; hipped roof (asbestos shingle); 1 hipped dormer; 2 bays; 2-story, 2-bay porch with square posts on brick piers; plain balusters. Double house. Vernacular. 1915.
- 343 424: wood frame (weatherboard); 2½ stories; gable roof (asbestos shingles); 1 shed dormer; 2 bays; 1-story, 2-bay porch with square posts on brick piers; plain balusters. Detached house. Bungalow, two-story. 1920.
- 344 425: wood frame (aluminum siding); 2½ stories; gable roof (composition); 1 shed dormer; 4 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters. Detached house. Vernacular. 1915. Carport in south bay.
- 345 431: wood frame (wood shakes); 2½ stories; gable roof (composition); 1 shed dormer; 3 bays; 1-story, 3-bay porch with square posts on brick piers; shed roof. Detached house. Vernacular. 1917.
- 346 434: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 gable pedimented dormer; 4 bays; 1-story, 4-bay porch with square posts on brick piers; plain balusters; pediment over south bay; dentils on cornice. Detached house. Vernacular. 1910.
- 347 438: wood frame (weatherboard); 1½ stories; hipped roof (composition); 1 gable dormer; 3 bays; 1-story, 5-bay porch with turned posts, no balusters; Detached house. Vernacular. 1895.
- 348 439: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 1-bay porch with paired Doric columns supporting pediment; no balusters. Detached house. Vernacular. 1915.
- 124-51-349 442: wood frame (cedar shakes); 1½ stories; gable roof (composition); 1 gable dormer; 3 bays; 1-story, 2-bay porch screened; square posts on brick piers; shed roof. Detached house. Bungalow. 1923.

**United States Department of the Interior
National Park Service**


**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 44

Item number 7

Page 42



DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

400 Block

NC 443: wood frame (aluminum siding); 1½ stories; gable roof (composition); 1 gable dormer; 3 bays; 1-story, 1-bay porch with wrought iron posts. Detached house. Ranch. 1949. * Noncontributing structure.

NC 446: brick (American); 1½ stories; gable roof (composition); 3 bays. Detached house. Ranch. 1951. * Noncontributing structure.

124-51-350

447: wood frame (asbestos siding); 2½ stories; 3 bays; 1-story, 2-bay porch with Doric columns; hipped roof. Detached house. Vernacular. 1910.

-351

451: wood frame (weatherboard); 2½ stories; gable roof (composition); 5 bays; 1-story, 5-bay porch extends on 2 sides; Doric columns; hipped roof; no balusters. Double house. Vernacular. 1910.

-352

454: wood frame (aluminum siding); 2½ stories; hipped roof (slate, alternately imbricated); 4 bays; 1-story, 2-bay porch extends on two sides; Doric columns; no balusters. Detached house. Vernacular. 1905. Damaged by fire.

500 Block

-353

500: wood frame (aluminum siding); 2½ stories; hipped roof (asbestos shingles); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with square posts on brick piers; plain balusters. Detached house. Vernacular. 1924.

NC

501: wood frame (asbestos siding); 1 story; gable roof (composition); 3 bays; 1-story, 3-bay porch with wrought-iron posts and railing. Detached house. Ranch. 1949. * Noncontributing structure.

-354

505: wood frame (aluminum siding); 1½ stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch; enclosed. Detached house. Vernacular. 1951.

-355

508: wood frame (asbestos shingle); gable roof (standing seam metal); 2 bays; 1-story, 2-bay porch with turned posts; no balusters; shed roof. Detached house. Vernacular. 1910.

-356

509: wood frame (asbestos siding); 2 stories; hipped roof (composition); 3 bays; 1-story, 2-bay porch screened; square posts; no balusters. Detached house. Vernacular. 1907.

124-51-357

511: wood frame (asbestos siding); 2½ stories; gable roof (standing seam metal); 2 bays; 1-story, 2-bay porch with square posts on brick piers; wrought-iron railing; hipped roof. Detached house. Vernacular. 1910.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk, Portsmouth, VA
Continuation sheet 45

Item number 7

Page 43

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

500 Block

- 124-51-358 512-18: wood frame (weatherboard); 1½ stories; gable roof (composition); 2 hipped dormers; 3 bays; 1-story, 5-bay porch extends on side; square posts; no balusters. Detached house. Bungalow. 1910.
- 359 513: wood frame (wood shakes); 2½ stories; gable roof (slate); 3 bays; 1-story, 3 bay porch with turned posts and balusters. Detached house. Vernacular. 1900.
- NC 515: wood frame (weatherboard); 1 story; gable roof (composition); 1 bay; no porch. Detached house. Vernacular. 1945. * Noncontributing structure.
- 360 529: wood frame (asbestos shingle); 1½ stories; gable roof (composition); 3 bays. Detached house. Vernacular. 1950. * Noncontributing structure.
- 361 530: wood frame (wood shakes); 2 stories; gable roof (slate); 4 bays; front stoop, 1 center bay with Doric columns; broken pediment. Detached house. Vernacular. 1900.
- 362 533: wood frame (vinyl siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 4-bay porch with wrought iron posts, no balusters; hipped roof. Detached house. Vernacular. 1900.
- NC 537: wood frame (aluminum siding); 1½ stories; gable roof (asbestos); 1 gable dormer; 3 bays; 1-story, 2-bay porch with wrought iron post and railing. Detached house. Vernacular. 1950. * Noncontributing structure.
- 124-51-363 543: wood frame (aluminum siding); 1½ stories; gable roof (asbestos); 2 gable dormers; 3 bays. Detached house. Vernacular. 1941.
- 364 547: wood frame (wood shakes); 2½ stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch extends on 2 sides; Doric columns; no balusters. Detached house. Vernacular. 1910.
- 365 551: wood frame (weatherboard); 2½ stories; hipped roof (slate, alternately imbricated); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with Doric columns; wrought iron railing. Detached house. Vernacular. 1915.
- 124-51-366 555: wood frame (cedar shakes); 2½ stories gable roof (not visible); 2 bays; 1-story, 2-bay porch with turned posts and balusters; decorative sawn work. Detached house. Vernacular. 1900.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Portsmouth Historic District, Portsmouth, VA

Continuation sheet 46

Item number 7

Page 44

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

500 Block

124-51-367

559: wood frame (weatherboard); 1½ stories; gable roof (standing seam metal); 1 shed dormer; 3 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters. Detached house. Bungalow. 1923.

600 Block

NC

601: wood frame (asbestos shingle); 1 story; gable roof (composition); 4 bays. Detached house. Vernacular. 1966 * Noncontributing structure.

124-51-368

605: wood frame (asbestos siding); 1½ stories; gable roof (standing seam metal); 2 gable dormers; 3 bays; 1-story, 2-bay porch with square posts. Detached house. Vernacular. 1920.

-369

617: wood frame (aluminum siding); 1 story; gable roof (asbestos); 3 bays; 1-story, 1-bay porch with paired square posts; broken pediment. Detached house. Vernacular. 1922.

-370

623: wood frame (asbestos siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 1-bay porch with gable roof screened; square posts, plain balusters. Detached house. Vernacular. 1910.

-371

627: wood frame (aluminum siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 1-bay porch with square posts; no balusters; Detached house. Vernacular. 1941.

NC

631: wood frame (aluminum siding); 1 story; gable roof (composition); 3 bays; 1-story, 1-bay porch with wrought-iron posts and railing; pediment. Detached house. Vernacular. 1952. * Noncontributing structure.

-372

633: wood frame (weatherboard); 2½ stories; gable roof (standing seam metal); 3 bays; 1-story, 2-bay porch with Doric columns; no balusters; hipped roof. Detached house. Vernacular. 1920.

-373

637: wood frame (weatherboard); 2 stories; hipped roof (standing seam metal); 2 bays; 1-story, 2-bay porch with Doric columns; turned balusters. Detached house. Vernacular. 1910.

124-51-374

639: wood frame (aluminum siding); 2 stories hipped roof (not visible); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with Doric columns; no balusters. Detached house. Vernacular. 1910.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Portsmouth Historic District, Portsmouth, VA
Continuation sheet 47 Item number 7

For NPS use only
received
date entered

Page 45

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

600 Block

124-51-315 641-43: wood frame (weatherboard); 2½ stories; hipped roof (slate, alternately imbricated; standing seam metal); 1 hipped dormer; 4 bays; 1-story, 4-bay porch with Doric columns; turned balusters; standing seam metal shed roof. Double house. Vernacular. 1910.
(See end of inventory for 645)

124-51-376 653: wood frame (asbestos siding); 1 story; gable roof (composition); 3 bays; 1-story, 3-bay porch with Doric columns; turned balusters; hipped roof. Detached house. Vernacular. 1909.

-377 655: wood frame (weatherboard); 1½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters; hipped roof. Detached house. Bungalow. 1929.

-378 657: wood frame (weatherboard); 2½ stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with Doric columns; no balusters; hipped roof. Detached house. Vernacular. 1914.

-379 600: wood frame (weatherboard); 1 story; gable roof (composition); 3 bays. Detached house. Vernacular. 1941.

-380 616: wood frame (weatherboard) and brick (stretcher); 1 story; gable roof (composition); 3 bays. Detached house. Vernacular. 1940.

NC 618: wood frame (aluminum siding); 1 story; hipped roof (composition); 5 bays. Detached house. Ranch. 1951. * Noncontributing structure.

NC 622: wood frame (aluminum siding); 1 story; gable roof (slate); 4 bays. 1-story, 2-bay porch with square posts; pediment. Detached house. Ranch. 1951.
* Noncontributing structure.

-381 624-26: wood frame (aluminum siding); 2½ stories; hipped roof (standing seam metal); 4 bays; 1-story, 4-bay porch with slender Doric columns; iron balusters. Detached house. Vernacular. 1915.

-382 634: wood frame (aluminum siding); 2½ stories; gable roof (slate); 1-story, 3-bay porch with Doric columns; hipped roof; no balusters. Detached house. Vernacular. 1910.

124-51-383 642: Rusticated ashlar. 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with Doric columns; turned balusters. Detached house. Vernacular. 1915.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk, Historic District, Portsmouth, VA
Continuation sheet 48

Item number 7

Page 46

DESCRIPTION -- Inventory (continued)

FLORIDA AVENUE (continued)

600 Block

124-51-384

652: wood frame (weatherboard); 1½ stories; gable roof (composition); 1 shed dormer; 3 bays; 1-story, 3-bay porch with square wood posts on brick piers; plain balusters. Detached house. Bungalow. 1918.

-385

656: wood frame (aluminum siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch extends on two sides; square posts on brick piers; plain balusters. Detached house. Vernacular. 1900.

HAMILTON AVENUE

300 Block

-386

325: wood frame (weatherboard); 1½ stories; hipped roof (composition); 1 hipped dormer, 3 bays; 1-story, 3-bay porch with square wood posts on brick piers. Detached house. Bungalow. 1929.

NC

309: brick (stretcher); 1 story; gable roof (composition); 8 bays. Detached house. Ranch. 1953. * Noncontributing structure.

NC

332: brick (stretcher); 1 story; hipped roof (composition); 4 bays; Detached house. Ranch. 1955. * Noncontributing structure.

-387

333: wood frame (asbestos siding); 2½ stories; hipped roof (asbestos); 1 hipped dormer; 2 bays; 1-story, 1-bay porch with gable roof on brick piers; plain square posts; screened in. Detached house. 1910.

-388

335: wood frame (wood shingle); 1½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with plain square posts. Detached house. Vernacular. 1920.

-389

336: wood frame (asbestos siding); 2½ stories; hipped roof (standing seam metal); 3 bays; 1-story, 1-bay porch with square posts, broken pediment. Detached house. Vernacular. 1900.

-390

343: wood frame (shingle) 1½ stories; gable roof (composition); 1 gable dormer; 3 bays; 1-story, 3-bay porch with square posts. Detached house. Vernacular. 1926.

124-51-391

344: wood frame (aluminum siding); 2 stories; gambrel roof (asbestos); 1 shed dormer; 4 bays. Detached house. Vernacular. 1924.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk Historic District, Portsmouth, VA
Continuation sheet 49

Item number 7

Page 47

DESCRIPTION -- Inventory (continued)

HAMILTON AVENUE (continued)

300 Block

124-51-392

347: wood frame (weatherboard); 1½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with plain square posts on brick piers; screened in. Detached house. Bungalow. 1941.

-393

355: wood frame (weatherboard); 2½ stories; gable roof (composition); 1 hipped dormer; 2 bays; 1-story, 3-bay porch with plain square posts. Detached house. Vernacular. 1925.

-394

357: wood frame (asbestos shingles); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with wrought iron railing and supports. Detached house. Vernacular. 1952.

MARYLAND AVENUE

100 Block

-395

107: wood frame (shingle); 2½ stories; gable roof (composition); 4 bays; 1-story, 5-bay porch with Doric columns. Detached house. Queen Anne. 1907.

-396

108: wood frame (weatherboard); 2½ stories; hipped roof (composition); 1 hipped dormer (one on front, two small windows; 2 bays; 1-story, 2-bay porch with American foursquare roof line and porch; square wood columns. Detached house. American Four Square. 1908.

-397

117: wood frame (asbestos siding); 1½ stories; gable roof (asbestos); 3 bays. Detached house. Cottage style. 1938.

-398

118: wood frame (aluminum siding); 2½ stories; gable roof (slate); 2 bays; 1-story, 2-bay porch with wrought-iron posts and railing. Detached house. Vernacular. 1910.

-399

122: wood frame (asbestos siding); 2½ stories; gable roof (composition); 2 bays; 1-story, 5-bay porch with plain square posts. Detached house. Modified Queen Anne. 1900.

NC

126: brick (stretcher); 1 story; gable roof (composition); 4 bays; 1-story, 1-bay porch with wrought-iron supports. Detached house. Ranch. 1961.
* Noncontributing structure.

124-51-400

127: wood frame (weatherboard); 2½ stories; gable roof (slate); 3 bays; 1-story, 5-bay porch with turned posts, spindle frieze, brackets. Detached house. Queen Anne. 1907.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 50

Item number 7

Page 48

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

100 Block

124-51-401 128: wood frame (asbestos siding); 1 story; gable roof (composition); 3 bays; 1-story, 1-bay porch with square wood post. Detached house. Vernacular. 1950.

NC 131: brick (stretcher); 1 story; gable roof (compositon); 3 bays; 1-story, 1-bay porch with wrought iron supports. Detached house. Ranch. 1965.
* Noncontributing structure.

-402 132: brick (stretcher); 1½ stories; gable roof (asbestos); 1 gable dormer; 3 bays; 1-story, 1-bay porch with square posts. Detached house. Vernacular. 1950.

-403 135: wood frame (asbestos shingle); 2½ stories; hipped roof (slate); 3 bays; 1-story, 4-bay porch with turned posts; plain railing. Detached house. Vernacular. 1907.

-404 137: wood frame (weatherboard); 2½ stories; hipped roof (slate, imbricated); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with Doric columns, turned balusters. Detached house. Vernacular. 1910.

-405 143: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square columns on brick piers. Detached house. Vernacular. 1940.

-406 144: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 1 hipped dormer on front; 2 bays; 1-story, 2-bay porch with Doric columns on brick piers. Detached house. Vernacular. 1915.

-407 146: wood frame (aluminum siding); 1½ stories; gable roof (slate); 3 bays; 1-story, 2-bay porch with gable roof; paired square posts; plain balusters. Detached hosue. Vernacular. 1920.

124-51-408 147: wood frame (weatherboard); 2½ stories; gable roof (standing seam metal on porch, asbestos on tin on roof); 1 shed dormer; 3 bays; 1-story, 2-bay porch with square posts on brick piers; plain balusters. Detached house. Vernacular. 1915.

NC 151: brick (stretcher); 1 story; gable roof (composition); 3 bays; 1-story, 3-bay porch with square posts; no balusters. Detached house. Ranch. 1967. * Noncontributing structure.

United States Department of the Interior
National Park Service


National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 51

Item number 7

Page 49



DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

100 Block

124-51-409

150: wood frame (shingle); 2½ stories; gable roof (asbestos); 2 bays; 2-story, 2-bay porch with wood posts on brick piers; spindle frieze. Detached house. Modified Queen Anne. 1900.

-410

154: ½ brick, ½ stucco (stretcher); 1½ stories; gable roof (slate); 1 shed dormer; 3 bays; 1-story, 3-bay porch with heavy columns on brick piers; plain balusters. Detached house. Bungalow. 1930.

-411

155: wood frame (weatherboard) 2½ stories; gable roof (not visible); 3 bays; 1-story, 1-bay porch with square columns and bracketed eaves. Detached house. Vernacular. 1941.

-412

159: wood frame (aluminum siding); 2½ stories; gable roof (not visible); 3 bays; 1-story, 4-bay porch with no railing, Doric columns. Detached house. Vernacular. 1910.

-413

160: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 4-bay porch extends on two sides; Doric columns; turned balusters. Detached house. Vernacular. 1910.

-414

161: wood frame (shingle); 2½ stories; gable roof (asbestos); 2 bays; 1-story, 3-bay porch with Doric columns. Detached house. Vernacular. 1900.

200 Block

-415

200: wood frame (aluminum siding); 2½ stories; hipped roof (asbestos); 1 hipped dormer; 2 bays; 1-story, 3-bay porch with Doric columns; no railing; hipped roof. Detached house. Queen Anne. 1910.

-416

201-05: brick (stretcher); 2 stories; gable roof (not visible); 5 bays; two 2-story, 1-bay porches; brick piers; plain balusters. Apartment building. Vernacular. 1936.

-417

204: wood frame (weatherboard); 1½ stories; gable roof (slate); 2 gable dormers; 4 bays; 1-story, 3-bay porch with tapering square wood posts on brick piers. Detached house. Vernacular. 1920.

124-51-418

207: wood frame (weatherboard); 2½ stories; hipped roof (slate, imbricated pattern); 2 gable dormers; 3 bays; 1-story, 3-bay porch with square brick piers. Detached house. Queen Anne. 1910.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 52

Item number 7

Page 50

For NPS use only

received

date entered

DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

200 Block

- 124-51-419 209: wood frame (weatherboard); 2½ stories; gable roof (slate); 3 bays; 1-story, 2-bay porch with Doric columns; no balusters. Detached house. Vernacular. 1908.
- 420 215: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with round columns. Detached house. Vernacular. 1910.
- 421 216: wood frame (aluminum siding); 2½ stories; gable roof (composition); 2 bays; 1-story, 3-bay porch with slender turned posts; hipped roof. Detached house. Vernacular. 1900.
- 422 220-22: wood frame (asbestos siding); 2½ stories; gambrel roof (composition); 1 hipped dormer on front; 3 bays; 1-story, 2-bay porch with square wood posts on brick piers. Double house. Dutch colonial. 1900.
- 423 226: wood frame (weatherboard); 2 stories; gable roof (composition); 2 bays; 1-story, 1-bay porch with slender turned posts with brackets; no balusters; shed roof. Detached house. Vernacular. 1900.
- 424 230: wood frame (asbestos siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch screened; square posts on brick piers; no balusters; hipped roof. Detached house. Vernacular. 1900. Scalloped shingle pediment.
- 425 229: wood frame (weatherboard); 2 stories; gable roof (standing seam metal); 1 shed dormer; 2 bays; 1-story, 2-bay porch with square wood posts on brick piers. Detached house. Vernacular. 1918.
- NC 232: wood frame (aluminum siding); 1 story; gable roof (composition); 4 bays. Detached house. Ranch. 1955. * Noncontributing structure.
- 426 236: wood frame (shingle); 2½ stories; gable roof (asbestos); 2 bays; 1-story, 3-bay porch extends on two sides; Doric columns; plain balusters; dentils on cornice. Detached house. Vernacular. 1910.
- 124-51-427 239: wood frame (shingle); 2½ stories; hipped roof (slate); 1 hipped dormer on front; 3 bays; 1-story, 3-bay porch with Doric columns. Detached house. Vernacular. 1912.
- NC 241: wood frame (asbestos); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with plain square posts; no balusters; shed roof. Detached house. Vernacular. 1950. * Noncontributing structure.

United States Department of the Interior
National Park Service


National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 53

Item number 7

Page 51



DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

200 Block

- NC 243: brick (stretcher); 2 stories; gable roof (not visible); 2 bays. Apartment building. Modern brick apartments. 1971. * Noncontributing structure.
- 124-51-428 244: wood frame (vinyl siding); 2½ stories; gable roof (asbestos); 2 bays; 1-story, 3-bay porch with square posts on brick piers. Detached house. Two-story bungalow. 1910.
- 429 250: wood frame (asbestos siding); 2½ stories; gable roof (asbestos); 3 bays; 1-story, 2-bay porch screened; square posts on brick piers. Detached house. Vernacular. 1920.
- 430 251: wood frame (aluminum siding); 1½ stories; hipped roof (asbestos); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with square wood posts on brick piers. Detached house. Bungalow. 1922.
- 431 254: wood frame (aluminum siding); 2 stories; gable roof (asbestos); 2 bays; 1-story, 3-bay porch with Doric columns; no balusters; hipped roof. Detached house. Vernacular. 1910.
- 432 255: wood frame (asbestos shingle); 2½ stories; gable roof (slate); 1 hipped dormer; 4 bays; 2-story, 2-bay porch with Doric columns; turned balusters. Detached house. Vernacular. 1910.
- 433 257: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer on front. 2 bays; 1-story, 3-bay porch extends on 2 sides; Doric columns; no balusters. Detached house. Vernacular. 1900.
- 434 258: wood frame (asbestos siding); 2½ stories; gable roof (asbestos); 2 bays; 2-story, 3-bay porch with Ionic columns, second floor, Doric columns on first floor; turned balusters. Detached house. Modified Queen Anne. 1900.

300 Block

- NC 300: wood frame (aluminum siding); 1 story; gable roof (composition); 3 bays. Detached house. Vernacular. 1956. * Noncontributing structure.
- 124-51-435 301: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 2-bay porch extends on three sides; slender Doric columns; turned balusters; hipped roof. Detached house. Vernacular. 1917. Metal cresting on roof.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Portsmouth Historic District, Portsmouth, VA

Continuation sheet 54

Item number 7

Page 52

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

300 Block

- 124-51-436 304: wood frame (aluminum siding); 1½ stories; gable roof (composition); 1 gable dormer; 3 bays. Detached house. Vernacular. 1941.
- 437 305: wood frame (asbestos siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 2-bay porch with plain square posts; balustraded deck. Detached house. Vernacular. 1954.
- 438 308: wood frame (asbestos siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with front pediment with front pediment with dentils; turned posts with scroll brackets; spindle frieze. Detached house. Vernacular. 1910.
- 439 312: wood frame (aluminum siding); 1 story; gable roof (asbestos); 3 bays; 1-story, 3-bay porch with paired plain posts and balusters. Detached house. Vernacular. 1939.
- 440 313: wood frame (vinyl siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 4-bay porch with slender turned posts with brackets; turned balusters; hipped roof. Vernacular. 1910.
- 441 316: wood frame (asbestos siding); 2 stories; gable roof (asbestos); 2 bays; 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1900.
- 442 317: wood frame (weatherboard); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with slender, bracketed, turned posts and balusters; pediment over central bay. Detached house. Vernacular. 1900.
- 443 320: wood frame (asbestos siding); 2½ stories; gable roof (asbestos); 3 bays; 1-story, 4-bay porch with turned posts, cutout pattern frieze, turned balusters. Detached house. Vernacular. 1900.
- 444 322: Vacant lot.
- 445 321: wood frame (aluminum siding); 2½ stories; gable roof (composition); 3 bays. 1-story, 3-bay extends on two sides; turned balusters; hipped roof. Detached house. Vernacular. 1900.
- 124-51-446 323: wood frame (weatherboard); 2½ stories; hipped roof (asbestos); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with square wood posts on brick piers. Detached house. Vernacular. 1925.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 55

Item number 7

Page 53

For NPS use only

received

date entered

DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

300 Block

124-51-447 324: wood frame (vinyl siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 2 bays; 1-story, 3-bay porch with wrought iron posts; no balusters; hipped roof. Detached house. Vernacular. 1910.

448 325: wood frame (vinyl siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with Doric columns. Detached house. Vernacular. 1912.

449 327: wood frame (asbestos siding); 2½ stories; gable roof (standing seam metal); 3 bays; 1-story, 2-bay porch with square posts on brick piers. Detached house. Vernacular. 1910.

450 329: wood frame (aluminum siding); 1½ stories; hipped roof (standing seam metal); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with Doric columns. Detached house. Bungalow. 1900.

451 333: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 2 bays; 1-story, 3-bay porch screened, square posts on brick piers; no balusters; hipped roof. Detached house. Vernacular. 1910.

452 342-44: wood frame (weatherboard); 2½ stories; hipped roof (composition); 4 bays; 1-story, 3-bay porch with slender Doric columns. Detached house. Vernacular. 1910.

453 346-48: wood frame (asbestos siding); 1½ stories; gable roof (composition); 2 gable dormers; 3 bays. Detached house. Vernacular. 1940.

454 350: wood frame (asbestos siding); 2½ stories; gable roof (asbestos shingles); 2 bays; 1-story, 3-bay porch extends on two sides; Doric columns; no balusters; hipped roof, standing seam metal. Detached house. Vernacular. 1910.

455 351: wood frame (shingle on sides and rear, aluminum on front); 2 stories; 6 bays. Commercial (store). Vernacular. 1937. (Jayel's Private School for Dogs).

NC 353: brick (stretcher); 1 story; gable roof (not visible); 4 bays; 1-story, 1-bay porch with iron post. Commercial (office). 1958. * Noncontributing structure.

124-51-456 352: wood frame (aluminum siding); 2 stories; gable roof (composition); 5 bays; 1-story, 4-bay porch with square posts on brick piers; no balusters; hipped roof. Detached house. Vernacular. 1910.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA

For NPS use only
received
date entered

Continuation sheet 56

Item number 7

Page 54

DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

300 Block

124-51-457 358: wood frame (aluminum siding); 2 stories; gable roof (standing seam metal); 4 bays. Detached house. Vernacular. 1900.

-458 356: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 4 bays; 1-story, 3-bay porch with Doric columns, turned balusters. Detached house. Vernacular. 1910.

400 Block

-459 404: wood frame (weatherboard); 1 story; gable roof (standing seam metal); 3 bays; 1-story, 2-bay porch with turned posts with decorative brackets; no balusters. Detached house. Vernacular. 1900.

-460 405: wood frame (aluminum siding); 2½ stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch with turned posts and balusters; brackets. Detached house. Vernacular. 1910.

-461 408: wood frame (aluminum siding); 2 stories; gable roof (standing seam metal); 2 bays; 1-story, 2-bay porch with wrought iron posts; no balusters. Detached house. Vernacular. 1900.

-462 410: wood frame (bricktex, asbestos on upper floor); 2 stories; gable roof (slate); 2 bays; 1-story, 2-bay porch with shed roof; turned posts, scroll brackets. Detached house. Vernacular. 1900.

-463 416: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 4 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters; standing seam metal roof; screened. Detached house. Vernacular. 1915.

NC 407-417

NC 419-33: wood frame and brick (wood siding); 2 stories; gable roof (composition); 4 bays each unit. Apartment building. Modern apartment structure. 1973. * Noncontributing structure.

-464 420: wood frame (asbestos siding); 2 stories; gable roof (composition); 1 bay; 1-story, 4-bay porch with square posts on brick piers. Detached house. Vernacular. 1897.

124-51-465 424: wood frame (aluminum siding); 2½ stories; gable roof (asbestos); 1-shed dormer; 2 bays; 1-story, 2-bay porch with square posts on brick piers; turned balusters. Detached house. Vernacular. 1915.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Port Norfolk Historic District, Portsmouth, VA
Continuation sheet 57

Item number 7

Page 55

DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

400 Block

124-51-466

428: wood frame (weatherboard); 2½ stories; gable roof (asbestos); 1 shed dormer; 2 bays; 1-story, 2-bay porch with square wood posts on brick piers. Detached house. Vernacular. 1915,

NC 435-445

436: brick (stretcher); 2½ stories; gable roof (slate); 5 bays. 1-story, 1-bay porch with square posts; no balusters. Detached house. Vernacular. 1937. * Noncontributing structure.

-467

440: brick (stretcher); 1½ stories; hipped roof (asbestos); 1 hipped dormer; 3 bays; 1-story, 1-bay porch with square wood posts on brick piers. Detached house. Bungalow. 1930.

-468

444: wood frame (asbestos siding); 2 stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch with shed roof; screened; Doric columns. Detached house. Vernacular. 1900.

-469

450: wood frame (weatherboard); 2 stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with square wood posts. Detached house. Vernacular. 1900.

-470

454: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with hipped roof; plain square posts; turned balusters. Detached house. Vernacular. 1915.

-471

455: wood frame (wood shingle); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with turned posts; hipped roof. Detached house. Vernacular. 1910.

-472

458: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with square wooden posts; turned balusters. Detached house. Vernacular. 1915.

-473

459: wood frame (aluminum siding); 2½ stories; gable roof (asbestos); 3 bays; 1-story, 3-bay porch; slender turned posts; no balusters; hipped roof. Detached house. Vernacular. 1910.

500 Block

124-51-474

500: wood frame (weatherboard-1st floor, shingle-2nd floor); 2½ stories; hipped roof (slate); 2 bays; 1-story, 3-bay porch square wood posts on brick piers. Detached house. Vernacular. 1920.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 58

Item number 7

Page 56

DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

500 Block

- 124-51-475 502: wood frame (asbestos siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 4 bays; 1-story, 3-bay porch with hipped roof, Doric columns; no balusters. Detached house. Vernacular. Early 20th century.
- 476 503: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 4 bays; 1-story, 3-bay porch with hipped roof; Doric columns. Detached house. Vernacular. 1913.
- 477 509: wood frame (aluminum siding); 2 stories; hipped roof (composition); 4 bays; 2-story, 1-bay porch with plain square posts and railing. Detached house. Vernacular. 1941.
- 478 508: wood frame (vinyl siding); 2½ stories; hipped roof (composition); hipped dormer; 4 bays; 1-story, 3-bay porch with slender Doric columns, no balusters; hipped roof. Vernacular. Detached house. 1910.
- 479 512: wood frame (asbestos siding); 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with square wooden posts, no railing. Detached house. Vernacular. 1910.
- 480 513: wood frame (weatherboard); 2½ stories; 1 hipped roof (composition); 1 hipped dormer; 2 bays; 1-story, 3-bay porch with Doric columns; no railing. Detached house. Vernacular. 1926.
- 481 515: wood frame (weatherboard); 2½ stories; hipped roof (asbestos); 1 hipped dormer; 4 bays; 1-story, 3-bay porch screened; square posts on brick piers; plain balusters. Detached house. Vernacular. 1922.
- 482 516: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with round posts; no railing; screened. Detached house. Vernacular. 1910.
- 483 519: wood frame (weatherboard); 2½ stories; hipped roof (asbestos); 1 hipped dormer; 2 bays; 1-story, 2-bay porch screened; square posts on brick piers; plain balusters. Detached house. Vernacular. 1920.
- 484 517: wood frame (aluminum siding); 1 story; gable roof (composition); 3 bays; 1-story, 3-bay porch with wrought iron supports, no balusters. Detached house. Vernacular. 1915.
- 124-51-485 520: wood frame (weatherboard); 1½ stories; gable roof (composition); 3 bays; 1-story, 1-bay porch with square posts on brick piers; no balusters. Bungalow. 1925.


**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historic District, Portsmouth, VA
Continuation sheet 59

Item number 7

Page 57



DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

500 Block

124-51-486

524: wood frame (weatherboard); 2½ stories; hipped roof (asbestos); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with wood square posts on brick piers. Detached house. Vernacular. 1921.

-487

532: wood frame (asbestos siding); 1½ stories; hipped roof with cresting (slate); 1 hipped dormer; 1-story, 2-bay porch with Doric columns. Detached house. Vernacular. 1910.

-488

533: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with square posts; plain balusters; pediment over south bay; hipped roof. Detached house. Vernacular. 1915.

-489

535: wood frame (weatherboard); 2½ stories; hipped roof (asbestos); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with Doric columns. Detached house. Vernacular. 1915.

-490

536: wood frame (asbestos siding); 1 story; gable roof (asbestos); 3 bays; 1-story, 3-bay porch with square posts on brick piers. Detached house. Bungalow. 1920.

-491

540: wood frame (weatherboard); 2 stories; hipped roof (standing seam metal); 3 bays; 1-story, 3-bay porch with square posts; plain balusters, hipped roof. Detached house. Vernacular. 1908.

-492

537: wood frame (weatherboard); 1½ stories; gable roof (standing seam metal); 1 shed dormer; 3 bays; 1-story, 3-bay porch with square wood posts on brick piers. Detached house. Bungalow. 1920.

-493

541: wood frame (aluminum siding); 2 stories; hipped roof (composition); 4 bays; 1-story, 2-bay porch with square posts; hipped roof. Detached house. Vernacular. 1921.

-494

542: wood frame (aluminum siding); 2 stories; hipped roof (composition); 2 bays; 1-story, 2-bay porch with wrought-iron supports, no railing. Detached house. Vernacular. 1916.

-495

543: wood frame (aluminum siding); 1½ stories; gable roof (composition); 1 gable dormer; 3 bays; 1-story, 1-bay porch with plain square posts; wrought-iron railing. Detached house. Vernacular. 1938.

124-51-496

545: wood frame (aluminum siding); 1½ stories; gable roof (composition); 3 bays; 1-story, 1-bay porch with wrought-iron railing. Square posts (wooden). Detached house. Vernacular. 1946.

**United States Department of the Interior
National Park Service**

For NPS use only
received
date entered

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk, Historic District, Portsmouth, VA
Continuation sheet 60 item number 7

Page 58

DESCRIPTION -- Inventory (continued)

MARYLAND AVENUE (continued)

500 Block

124-51-497 546: wood frame (weatherboard); 2½ stories; gable roof (asbestos); 1 shed dormer; 2 bays; 1-story, 3-bay porch with square wood posts on brick piers. Detached house. Vernacular. 1910.

-498 547: wood frame (aluminum siding); 1½ stories; gable roof (asbestos); 1 large shed dormer; 2 bays; 1-story, 2-bay porch screened; paired square posts on brick piers. Detached house. Bungalow. 1923.

-499 556: wood frame (asbestos siding); 2½ stories; gable roof (slate); 3 bays; 1-story, 2-bay porch with Doric columns. Detached house. Vernacular. 1914.

MOUNT VERNON AVENUE

100 Block

-500 102: wood frame (aluminum siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch extends on two sides, Doric columns supporting hipped roof; turned balusters; pediment over center bay. Detached house. Vernacular. 1900.

-501 105: wood frame (weatherboard on sides) and brick (facade; 1 row of Flemish alternating with several rows of stretcher); 2 stories; gable and flat roof (composition); 5 bays; two 2-story porches on end bays with square wooden posts on brick piers; plain balusters. Apartment building. Vernacular. 1943.

-502 109: brick (stretcher); 2 stories; hipped roof (composition); 3 bays; 1-story, 1-bay porch with plain square posts; plain balusters; pediment. Apartment building. Vernacular. 1950. * Noncontributing structure.

-503 110: wood frame (asbestos siding); 2½ stories; gable roof (slate); 3 bays; 1-story, 2-bay porch extends on side; Doric columns supporting hipped roof; turned balusters; pediment over N. Bay. Detached house. Vernacular. 1900.

-504 116: wood frame (aluminum siding); 2 stories; gambrel roof (asbestos); 3 gable dormers; 3 bays; 1-story, 3-bay porch with plain square posts; no balusters; stick-style balustrade. Detached house. Dutch Colonial. 1939.

124-51-505 115-17: wood frame (weatherboard); 2½ stories; gable roof (slate alternately imbricated); 1 gable dormer (notched shingles); 5 bays; 1-story, 4-bay porch with paired Doric columns; turned balusters; hipped roof Pediment. Detached house. Vernacular. 1900.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, Va

Continuation sheet 61

Item number 7

Page 59

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

100 Block

124-51-506

120: wood frame (weatherboard); 2½ stories; hipped roof (slate alternately imbricated); 4 bays; 1-story, 4-bay porch extends on side; slender Doric columns supporting hipped roof; turned balusters; dentils on cornice. Detached house. Vernacular. 1900. Decorative sawn work.

-507

121: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with Ionic columns; fluted brackets; small front pediment, screened; turned balusters; bracketed cornice. Detached house. Vernacular. 1905.

-508

125: wood frame (cedar shakes); 1½ stories; hipped roof (asbestos shingles); 1 hipped dormer on front with bungalow brackets; 3 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters; hipped roof. Detached house. Bungalow. 1930.

-509

129: wood frame (aluminum siding); 2 stories; gable roof (slate); 3 bays. Detached house. Vernacular. 1935. Dentils on cornice.

-510

128: wood frame (aluminum siding); 2 stories; gable roof (slate); 3 gable dormers; 3 bays. Detached house. Vernacular. 1939.

-511

130: wood frame (weatherboard); 1½ stories; hipped roof (slate alternately imbricated); 1 gable dormer with notched shingles; 3 bays; 1-story, 2-bay porch, plain square posts; no balusters. Detached house. Vernacular. 1910.

-512

135: brick (stretcher); 2½ stories; gable roof (slate alternately imbricated); 1 shed dormer; 3 bays; 1-story, 3-bay porch with square posts on brick piers; bracketed cornice. Detached house. Vernacular. 1920.

-513

134: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with slender Doric columns supporting hipped roof; turned balusters. Detached house. Vernacular. 1904.

-514

139: wood frame (vinyl siding); 2½ stories; hipped roof (composition); 3 bays; 1-story, 3-bay porch with slender turned posts with brackets supporting hipped roof; turned balusters; decorative sawn work. Detached house. Vernacular. 1900.

124-51-515

140: wood frame (weatherboard); 2½ stories; hipped roof (composition); 1 gable dormer; 4 bays; 1-story, 1-bay porch extends on 2 sides; slender Doric columns supporting hipped roof; turned balusters; pediment over entrance bay. Detached house. Vernacular. 1905.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, Va

Continuation sheet 62

Item number 7

Page 60

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

100 Block

124-51-516 144: wood frame (aluminum siding); 2½ stories; hipped roof (slate alternately imbricated); 2 hipped dormers (one on each side); 5 bays; 1-story, 1-bay porch partially enclosed; square posts on brick piers; hipped roof. Detached house. Vernacular. 1925.

-517 149: wood frame (aluminum siding); 2½ stories; gable roof (slate alternately imbricated); 2 gable dormers; 3 bays; 1-story, 5-bay porch extends on three sides; slender Doric columns supporting hipped roof; turned balusters. Paired gable dormers with decorative sawn work; metal cresting on roof. Detached house. Vernacular. 1895.

NC 152: brick (stretcher); 1½ stories; gable roof (not visible); 3 bays. Detached house. Contemporary. 1971. * Noncontributing structure.

-518 156: brick (stretcher); 2½ stories; gable roof (slate); 1 shed dormer; 2 bays; 1-story, 3-bay porch extends on two sides; Doric columns supporting hipped roof; plain balusters. Detached house. Vernacular. 1910.

-519 166: wood frame (weatherboard); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch extends on three sides; Doric columns supporting hipped roof; turned balusters. Vernacular. 1904. Detached house.

NC 153-161: brick (stretcher); 2 stories; mansard roof (composition); 13 bays. Row house. Contemporary. 1983. * Noncontributing structure.

200 Block

-520 200: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 4 bays; 1-story, 1-bay porch with Doric columns; no balusters. Detached house. Vernacular. 1910.

NC 201: brick (stretcher); 2 stories; gable roof (composition); 4 bays; 1-story, 1-bay porch with brick piers supporting gable roof; broken pediment over entrance. Detached house. Vernacular. 1935. * Noncontributing structure.

124-51-521 204: wood frame (aluminum siding); 1 story; gable roof (asbestos); 3 bays; 1-story, 3-bay porch with plain square posts; hipped roof; wrought iron balusters. Detached house. Vernacular. 1940.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet


63

Item number

7

Page

61



DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

200 Block

124-51-522

209: wood frame (weatherboard); 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with Doric columns supporting hipped roof; no balusters. Detached house. Vernacular. 1910.

-523

210: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 5 bays; 1-story, 3-bay porch with Doric columns on hipped roof; plain balusters. Detached house. Vernacular. 1979;

-524

214: wood frame (cedar shakes); 2 stories; hipped roof (composition); 4 bays; 2-story, 2-bay porch, second floor screened; Doric columns; plain balusters. Double house. Vernacular. 1910.

-525

215: wood frame (vinyl siding); 2½ stories; gable roof (not visible); 4 bays; 2-story, 2-bay porches with giant order square posts; plain balusters on both stories; screened; pediment. Detached house. Vernacular. 1915.

-526

218: wood frame(weatherboard) ; 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 3-bay porch extends on two sides; Doric columns supporting hipped roof; turned balusters. Detached house. Vernacular. 1912.

-527

221: wood frame (aluminum siding); 2½ stories; gable roof (slate alternatively imbricated); 1 gable dormer; 3 bays; 1-story, 3-bay porch with plain square posts supporting hipped roof; plain balusters. Detached house. Vernacular. 1900.

-528

222: wood frame (asbestos siding); 2½ stories; hipped roof (composition); 3 bays; 1-story, 3-bay porch extends on two sides; Doric columns supporting hipped roof; turned balusters. Detached house. Vernacular. 1900.

-529

225: wood frame (vinyl, first floor; cedar shakes, top floor); 2½ stories; hipped roof (composition); 1 hipped roof; turned balusters; Doric columns. Detached house. Vernacular. 1910.

-530

227: wood frame (weatherboard); 2½ stories; gable roof (slate alternately imbricated); 3 bays; 1-story, 3-bay porch with slender Doric columns supporting hipped roof; turned balusters. Detached house. Vernacular. 1905. Center peak gable with decorative sawn work.

124-51-531

229: brick (stretcher); 2½ stories; hipped roof (slate alternatively imbricated); 4 bays; 1-story, 3-bay porch extends on two sides; hipped roof supported by paired square posts; turned balusters. Detached house. Vernacular. 1900.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk Historic District, Portsmouth, Va

Continuation sheet 64

Item number 7

Page 62

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

200 Block

- 124.51-532 234: wood frame (vinyl siding); 2½ stories; gable roof (composition); 3 bays; 1-story, 1-bay porch with plain square wooden posts; no balusters. Vernacular. 1900.
- 533 238: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, porch screened; Doric columns; no balusters. Detached house. Vernacular. 1910.
- 534 239: wood frame (first floor, bricktex; 2nd floor, asbestos siding); 1 pedimented dormer on front; 3 bays; 1-story, 3-bay porch with Doric columns; bracketed cornice; no balusters. Detached house. Vernacular. 1910.
- 535 242-44: wood frame (asbestos siding); 2½ stories; hipped roof (slate alternately imbricated); 4 bays; 1-story, 3-bay porch extends on 2 sides; Doric columns; no balusters. Detached house. Vernacular. 1910.
- 536 248: wood frame (vinyl siding); 2½ stories; hipped roof (asbestos shingles); 3 bays; 1-story, 3-bay porch extends on 2 sides; Doric columns supporting hipped roof; no balusters. Detached house. Vernacular. 1910.
- 537 250: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with Doric columns supporting hipped roof; no balusters. Detached house. Vernacular. 1910. Metal cresting on roof.
- 538 251: wood frame (asbestos siding); 2½ stories; gable roof (slate); 1 gable dormer; 3 bays; 1-story, 3-bay porch with Doric columns; hipped roof, turned balusters. Detached house. Vernacular. 1900.
- 539 257: wood frame (cedar shakes); 2 stories; gable roof (slate); 6 bays; 2-story, 1-bay porch with plain square posts; plain balusters; screened on first story. Double house. Vernacular. 1929.
- 540 258: wood frame (asbestos siding); 2½ stories; gable roof (composition); 4 bays; 2-story, 3-bay porch partially enclosed on second floor; square posts on brick piers. Commercial (store); Vernacular. 1910. (Wynn Shop).

300 Block

300:

- 124.51-541 wood frame (asbestos siding); 2½ stories; hipped roof (slate); 4 bays; 1-story, 3-bay porch extends on two sides; Doric columns; turned balusters; hipped roof. Detached house. Vernacular. 1910.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet


65

Item number

7

Page

63



DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

300 Block

124-51-542

301: brick (stretcher); 2 stories; flat roof (not visible); 3 bays; 2-story, porch with plain square posts and baluster on second floor; first floor enclosed. Commercial (store). Vernacular. 1921.

-543

306: wood frame (asbestos siding); 2½ stories; gable roof (asbestos); 3 bays; 1-story, 4-bay porch extends on 2 sides; Doric columns; no balusters; bracketed cornice. Detached house. Vernacular. 1910.

-544

308: wood frame (weatherboard); 1½ stories; gable roof (standing seam metal); 2 gable dormers; 3 bays; 1-story, 3-bay porch with square posts on brick piers; plain balusters. Detached house. Bungalow. 1927.

-545

309: Vacant lot.

-546

312: wood frame (weatherboard); 1½ stories; gable roof (composition); 1 gable dormer; 3 bays; 1-story, 4-bay porch with Doric columns; turned balusters. Vernacular. 1910. Detached house.

-547

319: wood frame (aluminum siding); 2 stories; gambrel roof (slate); 3 gable dormers; 3 bays. Detached house. Dutch Colonial. 1940.

NC

322: brick (stretcher); 2 stories; gable roof (composition); 2 bays. Apartment building. Contemporary. 1950s. * Noncontributing structure.

-548

323: wood frame (vinyl siding); 2½ stories; gable roof (slate); 3 bays; 1-story, 2-bay porch with slender square posts; turned balusters; hipped roof. Detached house. Vernacular. 1910.

-549

325: wood frame (asbestos shingle); 1 story; gable roof (composition); 2 bays; 1-story, 2-bay stoop with plain square posts; gable roof. Detached house. Vernacular. 1952.

-550

326-28: wood frame (weatherboard); 2½ stories; hipped roof (standing seam metal); 2 gable dormers; 6 bays; 1-story, 4-bay porch with hipped roof; Doric columns; no balusters. Double house. Vernacular. 1910.

-551

331: brick (stretcher); 2 stories; gable roof (composition); 5 bays (not facing street). Apartment building. Contemporary. 1973. * Noncontributing structure.

124-51-552

332: brick (American); 3 stories; flat roof (not visible); 3 bays; two 3-story porches; 1 bay each, screened; giant brick piers supporting clustered square posts; stick-style balusters. Vernacular. 1924. Apartment Building.

(See Continuation Sheet #66)

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Port Norfolk Historic District, Portsmouth, VA
Continuation sheet 66 Item number 7

Page 64

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

300 Block

- 124-51-553 336: wood frame (weatherboard); first two stories; cedar shakes painted, upper ¼. 2½ stories gable roof (slate); 1 shed dormer; 2 bays; 1-story, 2-bay porch with hipped roof supported by square posts on brick piers; plain balusters. Detached house. Vernacular. 1926.
- 554 339: wood frame (brick texture); 2 stories; gable roof (composition); 2 bays. Detached house. Vernacular. 1952. * Noncontributing structure.
- 555 342: wood frame (weatherboard); 2½ stories; gable roof (slate); 3 bays; 1-story, 2-bay porch with Doric columns supporting hipped roof; no balusters. Detached house. Vernacular. 1910.
- 556 343: wood frame (weatherboard); 2½ stories; hipped roof (asbestos shingles); 2 bays; 1-story, 2-bay porch with hipped roof supported by square posts on brick piers; plain balusters. Detached house. Vernacular. 1910.
- 557 345: wood frame (weatherboard); 2½ stories; gable roof (composition); 2 gable dormers on front; 6 bays; 1-story, 1 side, 3 center bay porch with screen and glass enclosed; Doric columns; plain balusters. Double house. Vernacular. 1900.
- 558 346: wood frame (weatherboard); 2½ stories; gable roof (slate alternately imbricated); 3 bays; 1-story, 3-bay porch with slender posts with decorative brackets; plain balusters; hipped roof. Detached house. Vernacular. 1910. Decorative sawn work in gable.
- 559 349: wood frame (weatherboard); 2½ stories; gable roof (asbestos shingles); 3 bays; 1-story, 3-bay porch extends on two sides; hipped roof; slender posts with brackets; turned balusters. Detached house. Vernacular. 1910.
- 560 350: wood frame (asbestos shingle); 2 stories; gable roof (composition); 3 bays; 1-story, 4-bay porch with hipped roof; slender posts with brackets; plain balusters. Detached house. Vernacular. 1910.
- 561 353: wood frame (weatherboard); 2½ stories; hipped roof (composition); 4 bays; 1-story, 2-bay porch with hipped roof; square posts on brick piers; plain balusters. Detached house. Vernacular. 1910.
- 562 355: wood frame (weatherboard); 1 story; gable roof (slate alternately imbricated); 2 bays. Church. Gothic Revival. 1900. Originally St. Stephen's Episcopal Church, now Fort Norfolk Pentecostal Assembly.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 67

Item number 7

Page 65

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

300 Block

124-51-563

356: brick (stretcher); 1½ stories; gable roof (asbestos shingles); 1 gable dormer; 4 bays; 1-story, 1-bay porch screened; square posts; decorative balustrade on deck. Detached house. Vernacular. 1948.

400 Block

-564

400: wood frame (weatherboard); 2½ stories; gable roof (composition); 5 bays; 1-story, 6-bay porch with hipped roof; slender turned posts with brackets; turned balusters. Detached house. Vernacular. 1900. Center peak gable; two interior end chimneys.

-565

401-03; wood frame (weatherboard, second floor; bricked in. 1st floor); 2½ stories; hipped roof (slate); 3 bays; 1-story, 2-bay porch with hipped roof, Doric columns; turned balusters. Detached house and businesses on first floor. Vernacular. Early-20th century. Garage in rear.

-566

408: wood frame (weatherboard); 2½ stories; hipped roof (slate); 4 bays; 1-story, 3-bay porch extends on two sides; hipped roof; Doric columns; turned balusters. Detached house. Vernacular. 1914.

-567

411: wood frame (asbestos shingle); 2 stories; hipped roof (standing seam metal); 3 bays; 1-story, 2-bay porch with hipped roof; square posts; plain balusters. Detached house. Vernacular. 1900.

-568

414: wood frame (weatherboard, first floor, cedar shakes, second floor); 2 stories; gambrel roof (asbestos shingles); 2 bays; 1-story, 2-bay porch with hipped roof; square posts on brick piers; turned balusters. Detached house. Vernacular. 1939.

NC

415: wood frame (aluminum siding); 1½ stories; gable roof (composition); 1 gable dormer; 2 bays. Detached house. Vernacular. 1948. * Noncontributing structure.

NC

417: wood frame (asbestos shingle, top floor; and brick stretcher, lower level); 1½ stories; gable roof (composition); 2 gable dormers on front; 3 bays; 1-story, 1-bay porch with plain square posts; no balusters. Detached house. Vernacular. 1957. * Noncontributing structure.

124-51-569

418-20: wood frame (first floor, vinyl; second floor, cedar shakes); 2 stories; 3 bays; 2-story, 3-bay porch with square posts; brick piers on first story; plain balusters on both stories; Double house. Vernacular. 1920.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk, Historic District, Portsmouth, VA
Continuation sheet 68 Item number 7

Page 66

DESCRIPTION -- Inventory (continued)


MOUNT VERNON AVENUE (continued)

400 Block

- 124-51-570 421-23: wood frame (weatherboard); 2½ stories; hipped roof (asbestos shingles); 4 bays; 1-story, 3-bay porch extends on three sides; Doric columns; no balusters. Double house. Vernacular. 1905.
- 571 422: wood frame (weatherboard); 2½ stories; hipped roof (composition); 1 hipped dormer; 5 bays; 1-story, 3-bay porch extends on 2 sides; Doric columns; turned balusters. Second story 2-bay porch with square posts and plain balusters. Double house. Vernacular. 1908.
- 572 425: wood frame (vinyl siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with paired Doric columns; no balusters. Detached house. Vernacular. 1905.
- 573 426: wood frame (weatherboard, 1st floor, cedar shakes, 2nd floor); 2½ stories; gable roof (composition); (not visible); 4 bays; 2-story, 4-bay porch with square posts on brick piers; plain balusters. Double house. Vernacular. 1920.
- 574 426: wood frame (weatherboard, 1st floor, cedar shakes, 2nd floor); 2½ stories; gable roof (composition); (not visible); 4 bays; 2-story, 4-bay porch with square posts on brick piers; plain balusters. Double house. Vernacular. 1920.
- 575 430: wood frame (weatherboard); 1 story; gable roof (asbestos shingles); 3 bays; 1-story, 3-bay porch with hipped roof; square posts; plain balusters. Detached house. Vernacular. 1900. Wooden shingles in pediment.
- 576 434: wood frame (weatherboard); 2½ stories; gable roof (composition); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with square posts on brick piers; plain balusters. Detached house. Vernacular. 1921.
- 577 435: wood frame (aluminum siding); 1½ stories; gable roof (standing seam metal); 1 gable dormer (exposed rafters); 3 bays; 1-story, 1-bay porch screened; brick piers. Detached house. Bungalow. 1924.
- 578 438: wood frame (asbestos shingle); 2 stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with hipped roof (standing seam metal); 3 bays; 1-story, 3-bay porch with hipped roof; slender turned posts; turned balusters. Detached house. Vernacular. 1900.
- 124-51-579 439: wood frame (asbestos shingle); 1 story, gable roof (composition); 3 bays; 1-story, 3-bay porch with turned posts; plain balusters. Detached house. Vernacular. 1915.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form



Port Norfolk, Portsmouth Historic District, Portsmouth, VA

Continuation sheet 69

Item number 7

Page 67

DESCRIPTION -- (continued)

MOUNT VERNON AVENUE (continued)

400 Block

124-51-580

442: wood frame (asbestos shingle); 2½ stories; gable roof (slate); 4 bays; 1-story, 3-bay porch with hipped roof; square posts; plain balusters. Detached house. Vernacular. 1910.

-581

443: wood frame (asbestos shingle, second floor) and (brick texture, 1st floor); 2½ stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with hipped roof; square posts on brick piers; no balusters. Detached house. Vernacular. 1905.

-582

445: wood frame (aluminum, 1st floor, cedar shakes, second floor); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with hipped roof; Doric columns; turned balusters. Detached house. Modified Queen Anne. 1910.

-583

446: wood frame (asbestos single, second floor; and brick texture, first floor); 2½ stories; gable roof (asbestos shingles); 3 bays; 1-story, 3-bay porch with hipped roof; Doric columns; no balusters. Vernacular. Detached house. 1900.

-584

449-51: wood frame (asbestos shingle); 2 stories; gable roof (standing seam metal); 4 bays; 52o 2-story porches, 2 bays each with square posts on giant brick piers; plain balusters. Apartment building. Vernacular. 1935.

-585

450: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with hipped roof; square posts on brick piers; wrought-iron balusters. Detached house. Vernacular. 1910. Center peak gable.

-586

455: wood frame (aluminum siding); 1½ stories; gable roof (asbestos shingles); 5 bays. Detached house. Vernacular. 1946.

-587

458: wood frame (aluminum siding); 2½ stories; gable roof (asbestos shingles); 1 hipped dormer; 4 bays; 1-story, 4-bay porch extends on two sides; Doric columns; turned balusters; hipped roof. Double house. Modified Queen Anne. 1905.

500 Block

124-51-588

500: wood frame (asbestos shingle); 2½ stories; gable roof (asbestos shingles); 3 bays; 1-story, 3-bay porch with hipped roof; square posts on brick piers; plain balusters. Detached house. 1907. Center peak gable.

NC

501: brick (American); 1 story; gable roof (composition); 4 bays; 1-story, 1-bay front stoop with pediment; wrought-iron posts. Detached house. Ranch. 1955. * Noncontributing structure.

(See Continuation Sheet #70)

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk, Portsmouth Historic District, Portsmouth, VA
Continuation sheet 70 Item number 7

Page 68

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

500 Block

- 124-51-589 504-06: wood frame (weatherboard); 2½ stories; hipped roof (composition); 3 bays; 1-story, 4-bay porch with hipped roof; Doric columns; no balusters. Double house. Vernacular. 1910.
- 590 509-11: wood frame (asbestos shingle); 2 stories; gable roof (standing seam metal); 6 bays; 1-story, 4-bay porch with slender shed roof; turned posts and balusters; brackets. Double house. Modified Queen Anne. 1900.
- 591 510; wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 gable dormer; 2 bays; 1-story, 3-bay porch extends on two sides; hipped roof; Doric columns; turned balusters. Detached house. Modified Queen Anne. 1910.
- 592 513-15: wood frame (weatherboard); 2½ stories; gable roof (composition); 3 bays; 2-story, 2-bay porch with paired square posts on giant brick piers; plain balusters. Double house. Vernacular. 1910.
- 593 516-18: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 2-story, 3-bay porch with giant brick piers; plain square balusters. Double house. Vernacular. 1915.
- 594 517: wood frame (asbestos shingle); 2 stories; gable roof (composition); 3 bays; 1-story, 1-bay porch with hipped roof; square posts. Detached house. Vernacular. 1940.
- 595 521: wood frame (weatherboard); 2½ stories; gable roof (composition); 4 bays; 1-story, 4-bay porch with shed roof; Doric columns; turned balusters. Detached house. Vernacular. 1895. Center peak gable.
- NC 525: wood frame (aluminum siding); 1 story; gable roof (composition); 3 bays. Detached house. Ranch. 1978. * Noncontributing structure.
- 594 526: wood frame (weatherboard); 2½ stories; hipped roof (asbestos shingles); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with solid panel railing screened; square post on brick piers. Hipped roof. Detached house. Vernacular. 1910.
- 597 528: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 1 hipped dormer; 2 bays; 1-story, 1-bay porch with hipped roof; clustered square posts on brick piers; plain balusters. Detached house. Vernacular. 1926.
- 124-51-598 529: wood frame (weatherboard, 1st floor; cedar shakes, 2nd floor); 2½ stories; gable roof (asbestos shingles); 3 bays; 1-story, 3-bay porch with hipped roof; slender turned posts with brackets; turned balusters. Detached house. Vernacular. 1900.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

For NPS use only
received
date entered

Port Norfolk, Portsmouth Historic District, Portsmouth, VA

Continuation sheet 71

Item number 7

Page 69

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

500 Block

124-51-599

531: wood frame (weatherboard); 2½ stories; gable roof (asbestos shingles); 2 bays; 1-story, 2-bay porch screened; hipped roof; square posts on brick piers; solid baluster. Detached house. Vernacular. ca. 1910.

-600

534: wood frame (weatherboard); 2½ stories; gable roof (slate); 1 shed dormer; 2 bays; 1-story, 2-bay porch with shed roof; square posts on brick piers; plain balusters. Detached house. Vernacular. 1915.

-601

537: wood frame (asbestos shingle); 2½ stories; gable roof (slate); number of bays not visible; 1-story, 2-bay porch screened; Doric columns; hipped roof. Detached house. Modified Queen Anne. 1900.

-602

538: wood frame (vinyl siding); 2½ stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with hipped roof; square posts on brick piers; plain balusters. Detached house. Vernacular. 1910.

-603

541: wood frame (asbestos shingle); 2½ stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with hipped roof; slender turned posts and balusters. Detached house. Vernacular. 1900.

-604

542: wood frame (weatherboard); 2½ stories; hipped roof (slate); 3 bays; 1-story, 3-bay porch with hipped roof; Doric columns; no balusters. Detached house. Vernacular. 1910.

-605

545-47: wood frame (asbestos shingle); 2½ stories; hipped roof (standing seam metal); 1 hipped dormer; 4 bays; 1-story, 4-bay porch with hipped roof; slender square posts; plain balusters. Detached house. Vernacular. 1900.

-606

546: wood frame (aluminum siding); 2½ stories; hipped roof (composition); 4 bays; 1-story, 3-bay porch with hipped roof; wrought iron supports. Detached house. Modified Queen Anne. 1910.

-607

549: wood frame (weatherboard); 2½ stories; gable roof (asbestos shingles); 3 bays; 1-story, 3-bay porch extends on two sides; hipped roof; slender turned posts with brackets; plain balusters. Detached house. Vernacular. 1900.

124-51-608

554: wood frame (vinyl siding); 2½ stories; gable hipped roof (composition); 3 bays; 1-story, 3-bay porch with hipped roof; slender turned posts with decorative brackets; turned balusters. Detached house. Vernacular. 1903.

NC

555: brick (Flemish); 1½ stories; gambrel roof (composition); 3 bays. Detached house. Modern. 1959. Large exterior end chimney. * Noncontributing structure.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk, Portsmouth Historic District, Portsmouth, VA
Continuation sheet 72 Item number 7 Page 71

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

500 Block

124-51-609 558: wood frame (vinyl siding); 2½ stories; hipped roof (composition); 3 bays; 1-story, 3-bay porch with hipped roof; Doric columns; no balusters. Detached house. Modified Queen Anne. 1910.

600 Block

-610 600: wood frame (aluminum siding); 2 stories; gable roof (composition); 3 bays; 1-story, 3-bay porch with hipped roof; square posts on brick piers. Detached house. Vernacular. 1895.

-611 601: wood frame (asbestos shingles); 2½ stories; hipped roof (standing seam metal); 1 hipped dormer; 4 bays; 1-story, 4-bay porch extends on two sides; hipped roof; Doric columns; no balusters. Detached house. Vernacular. 1910.

-612 604: wood frame (aluminum, first floor; cedar shake, top floors); 2½ stories; 1 gable roof (not visible); 3 bays; 1-story, 3-bay porch with Doric columns; plain balusters. Detached house. Vernacular. 1915.

-613 605: wood frame (asbestos shingle); 2 stories; shallow gable roof (not visible); 3 bays; 2-story, 2-bay porch screened on first floor; square posts on brick piers; plain balusters. Detached house. Vernacular. 1910.

-614 609: wood frame (asbestos shingle); 1 story; gable roof (slate); 3 bays; 1-story, 3-bay porch with Doric columns; turned balusters. Detached house. Vernacular. 1910.

NC 610: brick (stretcher); 1 story; gable roof (composition); 2 bays; 1-story, 2-bay porch with wrought-iron posts; no railing. Detached house. Ranch. 1961. * Noncontributing structure.

-615 613: wood frame (weatherboard); 2½ stories; 1 hipped dormer; 6 bays; 1-story, 4-bay porch with hipped roof; slender turned posts; plain balusters. Detached house. Vernacular. 1910.

-616 615-16: wood frame (weatherboard); 1½ stories; gable roof (standing seam metal); 1 shed dormer; 3 bays; 1-story, 2-bay porch with brick railing, bungalow posts. Detached house. Bungalow. 1910.

124-51-617 618: wood frame (weatherboard); 2½ stories; gable roof (slate); 1 pedimented dormer; 4 bays; 1-story, 1-bay porch with hipped roof; slender turned posts with decorative brackets; turned balusters. Detached house. Modified Queen Anne. 1900.

**United States Department of the Interior
National Park Service**


**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet 73

Item number 7

Page 71



DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

600 Block

124-51-618

615: wood frame (weatherboard); 1½ stories; hipped roof (composition); 1 hipped dormer; 6 bays; 1-story, 4-bay porch with slender turned posts and balusters; hipped roof. Detached house. Vernacular. 1910.

-619

619: wood frame (aluminum siding); 1½ stories; gable roof (standing seam metal); 1 shed dormer; 4-bays; 1-story, 1-bay porch with square posts on brick piers; brick balusters; gable roof. Detached house. Bungalow. 1915. Carport in south bay.

NC

622: brick (stretcher); 1½ stories; gable roof (composition); 3 bays; 1-story; 3-bay porch with wrought-iron railing. Detached house. Ranch. 1954. * Noncontributing structure.

-620

⁶²³
~~622~~ 623: brick (stretcher); 2½ stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with square posts on brick piers; side porch not visible. Detached house. Vernacular. 1910.

-621

625: wood frame (asbestos shingle); 2½ stories; hipped roof (standing seam metal); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with hipped roof; square posts on brick piers. Detached house. Vernacular. 1910.

-622

626: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 3 bays; 1-story, 3-bay porch with hipped roof; Doric columns; no balusters. Detached house. Vernacular. 1900.

-623

630: wood frame (asbestos shingle); 2½ stories; gable roof (asbestos shingles); 3 bays; 1-story, 3-bay porch with hipped roof; slender turned posts; no balusters; dentils on cornice. Detached house. Vernacular. 1900.

-624

631-33: wood frame (weatherboard); 2½ stories; hipped roof (slate); 1 hipped dormer; 4 bays; 1-story, 4-bay porch with hipped roof; slender turned posts; plain balusters. Detached house. Vernacular. 1900.

-625

634: wood frame (vinyl siding); 2½ stories; hipped roof (standing seam metal); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with hipped roof; square posts on brick piers; plain balusters. Detached house. Vernacular. 1910.

-626

635: wood frame (vinyl siding); 2½ stories; hipped roof (standing seam metal); 1 hipped dormer; 2 bays; 1-story, 2-bay porch with hipped roof; square posts on brick piers; plain balusters. Detached house. Vernacular. 1910.

124-51-627

638: wood frame (asbestos shingle); 2½ stories; hipped roof (composition); 3 bays; 1-story, 3-bay porch extends on two sides; Doric columns; turned balusters; hipped roof. Detached house. Modified Queen Anne. 1900.

(See Continuation Sheet # 74)

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form

For NPS use only
received
date entered

Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet

Item number

7

Page 622

DESCRIPTION -- Inventory (continued)

MOUNT VERNON AVENUE (continued)

600 Block

NC 653-55: brick (front - American) and concrete block; 1 story; parapet flat roof (not visible); 2 bays. Detached house. Vernacular. 1953. * Non-contributing structure.

124-51-628 659-61: wood frame (weatherboard in gable) and brick (stretcher); 2½ stories; 3 bays. Detached house. Commercial (store, bottom). Vernacular. 1910.

NC 660-62: wood frame (aluminum siding on rear and sides); 1 story; gable roof in rear (not visible); 2 bays; 1-story, 3-bay porch with shed roof; plain square posts. Commercial (store). Commercial vernacular. 1940. * Noncontributing structure.

-629 639-41: wood frame (asbestos shingle); 2½ stories; hipped roof (standing seam metal); 1 hipped dormer; 6 bays; 1-story, 4-bay porch with hipped roof; slender turned posts; plain balusters. Detached house. Vernacular. 1910.

-630 642: wood frame (aluminum siding); 1 story; gable roof (composition); 2 bays; 2-story, 2-bay porch with plain square posts; no balusters. Detached house. Vernacular. 1952. * Noncontributing structure.

-631 643: wood frame (brick texture); 2 stories; hipped roof (composition); 1 hipped dormer; 3 bays; 1-story, 2-bay porch with hipped roof; Doric columns; turned balusters. Detached house. Vernacular. 1910.

-632 646: wood frame (vinyl siding); 2½ stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch with hipped roof; square posts on brick piers. Detached house. Vernacular. 1900.


-633 647: wood frame (weatherboard); 2½ stories; gable roof (composition); 2 bays; 2-story, 3-bay porch extends on two sides; slender turned balusters. Detached house. Vernacular. 1910.

-634 649: brick (stretcher); 2½ stories; gable roof (slate); 4 bays; 1-story, 3-bay porch remodeled; slender metal posts. Detached house. Vernacular. 1900.

124-51 -635 654: wood frame (aluminum siding), first floor; cedar shakes, second floor); 2½ stories; gable roof (standing seam metal); 3 bays; 1-story, 3-bay porch extends on two sides; hipped roof; slender turned posts; turned balusters. Detached house. Vernacular. 1895.

United States Department of the Interior
National Park Service

National Register of Historic Places
Inventory—Nomination Form



Port Norfolk, Historic District, Portsmouth, VA

Continuation sheet 75

Item number 7

Page 73

DESCRIPTION -- Inventory (continued)

ROLFE TERRACE

100 Block

124-51-636

100: brick (stretcher); 2 stories; gable roof (composition); 3 bays; 1-story, 1-bay porch with square wooden posts; wrought iron balustrade. Detached house. Georgian Revival. 1950.

-637

136: wood frame (weatherboard, first floor; wood shakes, second floor); 1½ stories; gable roof (not visible); 1 shed dormer on front looks like part of roof; 2 bays; 1-story, 2-bay porch with brick piers; center pier square wood post on brick pier. Plain balusters. Detached house. Bungalow. 1915.

-638

154: wood frame (aluminum siding); 1½ stories; gable roof (asbestos shingles); 4 bays. Detached house. Vernacular. 1938.

-639

150: wood frame (weatherboard); 2½ stories; gable roof (composition); 4 bays; 2-story, 5-bay porch screened in (not visible); Detached house. Vernacular. 1915.

-640

124: wood frame (aluminum siding); 2½ stories; hipped roof (slate); 1 hipped dormer on each side; 3 bays; 1-story, 2-bay porch with hipped roof. Doric columns; no balusters. Detached house. Modified Queen Anne. 1900.

WESLEY STREET

2700 Block

124-51-641

2716: wood frame (asbestos); 2 stories; gable roof (asbestos); 2 bays; 1-story, 1-bay porch with plain square posts and balusters. Detached house. Vernacular. 1900.

2900 Block

124-51-642

2910-12: brick (American); 2 stories; gable roof (composition). Apartment building. Pre-ranch style. 1940. *Noncontributing structure.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

Port Norfolk Historic District, Portsmouth, VA

Continuation sheet

76

Item number

7

Page 74

For NPS use only
received
date entered

DESCRIPTION -- Inventory (continued)

HARTFORD STREET

2900 Block

124-51-643 2915: wood frame (weatherboard); 1½ stories; gable roof (slate); 3 bays; 1-story, 3-bay porch extends on two sides; screened; square posts; plain balusters; hipped roof. Detached house. Vernacular. 1900.

3000 Block

124-51-644 3009: wood frame (asbestos shingle) 1½ stories; gable roof (not visible); 3 bays; 1-story, 1-bay porch with wrought iron posts. Detached house. Vernacular. 1925.

FLORIDA AVENUE

NC 645: wood frame (asbestos shingle); 1 story; 3 bays; 1-story, 1-bay porch with wrought-iron posts. Detached house. Vernacular. 1951.
* Noncontributing structure.

**United States Department of the Interior
National Park Service**

**National Register of Historic Places
Inventory—Nomination Form**

PORT NORFOLK HISTORIC DISTRICT, PORTSMOUTH, VA.

Continuation sheet # 77

Item number 7

Page 75

For NPS use only
received
date entered

7. DESCRIPTION (CON.) Criteria for noncontributing structures

Noncontributing structures are those elements which do not contribute to the overall cohesiveness of the district. They are not compatible in design, scale, or fabric. In some cases, the contributing structures may be less than 50 years old; however, these buildings maintain the integrity of the district in use, design, scale, and fabric. They also maintain the facade line and the aesthetics of the streetscapes of the neighborhood.

SUMMARY OF NONCONTRIBUTING STRUCTURES

Bayview Boulevard: 2501, 2525, 2609, 2915

Broad Street: 100-102, 104, 106, 108-110, 162, 254, 352-356, 429, 533, 554-556, 600

Bruce Place: 117, 119, 120

Chatauqua: 160, 216-220, 231, 235, 238, 239, 301, 312, 411, 415, 416, 423, 440, 507, 511, 513

Detroit Avenue: 2715-2717

Douglas Avenue: 117, 119-127, 122, 126, 136-138, 241, 251-253, 348, 352, 358, 635

Florida Avenue: 106, 109, 148-150, 153, 204, 218, 220, 222, 224, 245, 250, 300, 325, 443, 446,
501, 515, 537, 601, 618, 622, 631, 645

Hamilton Avenue: 309, 332


Maryland Avenue: 126, 131, 151, 232, 241, 243, 300, 353, 407-417, 419-433, 435-445, 436

Mount Vernon Avenue: 152, 153-161, 201, 322, 415, 417, 501, 525, 555, 610, 622, 653-655, 660=662

Total noncontributing structures: 96

COMMONWEALTH OF VIRGINIA
DIVISION OF MINERAL RESOURCES

379 380 381 20' 382 5757 IV NE (NORFOLK NORTH) 384 17'30" 385



USGS 7.5 QUADRANGLE (scale: 1:24000)
Norfolk South, VA. 1965 (PR: 1980)
● PORT NORFOLK HISTORIC DISTRICT
PORTSMOUTH, VA.

- A 18/381110/4079280
- B 18/381200/4078950
- C 18/381160/4078210
- D 18/380910/4078050
- E 18/380550/4078020
- F 18/380320/4078850
- G 18/380460/4079240

Map 1 of 4
Pinner Point