

000-7819 AIR 6/23/03
VLR 12/4/02

NPS Form 10-900
(Rev. 11-90)

OMB No. 10024-0018

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
REGISTRATION FORM**

This form is for use in nominating or requesting determinations for individual properties or districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property

Historic name: ASHTON HEIGHTS HISTORIC DISTRICT
Other names/site number: (VDHR File Number 000-7819)

2. Location

Street & Number: Roughly bounded by Wilson Boulevard, North Irving Street, Arlington Boulevard, North Oxford Street, North Piedmont Street, and North Oakland Street [] Not for Publication
City or town: [] Vicinity
State: Virginia Code: VA County: Arlington Code: 013 Zip Code: 22201

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this [X] nomination [] request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property [X] meets [] does not meet the National Register criteria. I recommend that this property be considered significant [] nationally [] statewide [X] locally. ([] See continuation sheet for additional comments.)

[Signature] 3/13/03
Signature of certifying official/Title Date

Virginia Department of Historic Resources

State or Federal agency and bureau

In my opinion, the property [] meets [] does not meet the National Register criteria. ([] See continuation sheet for additional comments.)

Signature of certifying official/Title Date

State or Federal agency and bureau

4. National Park Service Certification

I hereby certify that this property is:
[] entered in the National Register. _____ Signature of the Keeper _____ Date of Action
 [] see continuation sheet
[] determined eligible for the National Register _____
 [] see continuation sheet
[] determined not eligible for the National Register _____
[] removed from the National Register _____
[] other, (explain) _____

ASHTON HEIGHTS HISTORIC DISTRICT**ARLINGTON COUNTY, VA**

Name of Property

County and State

5. Classification

Ownership of Property	Category of Property	No. Resources within Property		
		Contributing	Noncontributing	
<input checked="" type="checkbox"/> Private	<input type="checkbox"/> Building(s)			
<input type="checkbox"/> Public-Local	<input checked="" type="checkbox"/> District	<u>1,097</u>	<u>159</u>	Buildings
<input type="checkbox"/> Public-State	<input type="checkbox"/> Site	<u>1</u>	<u>0</u>	Sites
<input type="checkbox"/> Public-Federal	<input type="checkbox"/> Structure	<u>1</u>	<u>3</u>	Structure
	<input type="checkbox"/> Object	<u>0</u>	<u>0</u>	Objects
		<u>1,099</u>	<u>162</u>	Total

Name of related multiple property listing

N/ANumber of contributing
Resources previously
listed in the National
Register 1**6. Function or Use**Historic Functions (enter categories
from instructions)Current Functions (enter
categories from instructions)DOMESTIC/Single DwellingsDOMESTIC/Single DwellingsDOMESTIC/Multiple DwellingsDOMESTIC/Multiple DwellingsDOMESTIC/Secondary ResourcesDOMESTIC/Secondary ResourcesSOCIAL/ClubhouseSOCIAL/ClubhouseCOMMERCE/Specialty StoreCOMMERCE/Specialty Store See continuation sheet**7. Description**Architectural Classification
(enter categories from instructions)LATE VICTORIAN/Queen AnneLATE 19th & 20th CENTURY REVIVALS/Colonial RevivalLATE 19th & 20th CENTURY REVIVALS/Tudor Revival See continuation sheet

Materials (enter categories from instructions)

Foundation: BRICK; CONCRETE; STONEWalls: WOOD: Weatherboard, Shingle; METAL: Aluminum; ASBESTOS; CONCRETE; BRICK;STUCCO; SYNTHETICS: VinylRoof: ASPHALT; ASBESTOS; STONE: Slate; TERRA COTTA**Narrative Description**

Describe the historic and current condition of the property on one or more continuation sheets

 See continuation sheet

ASHTON HEIGHTS HISTORIC DISTRICT

ARLINGTON COUNTY, VA

Name of Property

County and State

8. Statement of Significance

Applicable National Register Criteria

(Mark x in one or more boxes for the criteria qualifying the property for National Register listing.)

A Property is associated with events that have made a significant contribution to the broad patterns of our history.

B Property is associated with the lives of persons significant in our past.

C Property embodies the distinctive characteristics of a type, period, or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.

D Property has yielded, or is likely to yield, information important in prehistory or history.

Criteria Considerations

(Mark x in all the boxes that apply.)

A owned by a religious institution or used for religious purposes.

B removed from its original location.

C a birthplace or grave.

D a cemetery.

E a reconstructed building, object, or structure.

F a commemorative property.

G less than 50 years of age or achieved significance within the past 50 years.

Narrative Statement of Significance

(Explain the significance of the property on one or more continuation sheets.)

See continuation sheet

Areas of Significance

(Enter categories from instructions)

ARCHITECTURE
COMMUNITY PLANNING
AND DEVELOPMENT

Period of Significance

Ca. 1900 to 1950

Significant Dates

1911, 1918, 1919, 1920, 1921,
1922, 1925, 1929, 1931, 1932,
1933, 1935, 1937, 1938, 1939

Significant Person

(Complete if Criterion B is marked above.)

N/A

Cultural Affiliation

N/A

Architect/Builder

Broyhill, Marvin T.
England, Walter
Jones, Ashton C., Developer
Kay-Alger Company
Westenberger, Frederick E.

ASHTON HEIGHTS HISTORIC DISTRICT
Name of Property

ARLINGTON COUNTY, VA
County and State

9. Major Bibliographic References

See continuation sheet

Previous documentation on file (NPS):

preliminary determination of individual listing (36 CFR 67)

previously listed in the NR

previously determined eligible by the National Register

designated a National Historic Landmark

recorded by Historic American Buildings Survey # _____

recorded by Historic American Engineering Record # _____

Primary location of additional data:

State SHPO office

Other State agency

Federal agency

Local government

University

Other

Specify repository: _____

10. Geographical Data

Acreage of property 220.598 acres

UTM References Washington West and Alexandria USGS Maps

1) 1/8/ 3/1/8/0/9/4/ 4/3/0/5/7/6/4/
Zone Easting Northing

2) 1/8/ 3/1/8/2/6/4/ 4/3/0/4/7/8/2
Zone Easting Northing

3) 1/8/ 3/1/7/2/2/7/ 4/3/0/4/3/5/7/
Zone Easting Northing

4) 1/8/ 3/1/7/2/9/7/ 4/3/0/5/0/6/8/
Zone Easting Northing

See continuation sheet

Verbal Boundary Description

See continuation sheet

Boundary Justification

See continuation sheet

11. Form Prepared By

Name/title Kristie Baynard, Gerald M. Maready, and Laura V. Trieschmann, Architectural Historians

Organization EHT Traceries, Inc. Date August 2002

Street & Number 1121 5th Street, NW Telephone (202) 393-1199

City or Town Washington State D.C. Zip code 20001

ASHTON HEIGHTS HISTORIC DISTRICT

ARLINGTON COUNTY, VA

Name of Property

County and State

Additional Documentation

Submit the following items with the completed form:

Continuation Sheets

Maps

A **USGS map** (7.5 or 15 minute series) indicating the property's location.

A **Sketch map** for historic districts and properties having large acreage or numerous resources.

Photographs

Representative **black and white photographs** of the property.

Additional items

(Check with the SHPO or FPO for any additional items)

Property Owner

(Complete this item at the request of the SHPO or FPO.)

name See attached list of property owners

street & number _____ telephone _____

city or town _____ state _____ zip code _____

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 *et seq.*)

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of the Management and Budget, Paperwork Reductions Projects (1024-0018), Washington, DC 20503.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 1

6. Function or Use

<u>EDUCATION/School</u>	<u>EDUCATION/School</u>
<u>RELIGION/Church</u>	<u>RELIGION/Church</u>
<u>DOMESTIC/Single Dwelling</u>	<u>RELIGION/Church-Related Residence</u>
<u>FUNERARY/Cemetery</u>	<u>FUNERARY/Cemetery</u>

7. Description

<u>LATE 19th & EARLY 20TH CENTURY AMERICAN MOVEMENTS/Late Gothic Revival</u>
<u>LATE 19th & EARLY 20TH CENTURY AMERICAN MOVEMENTS/Bungalow/Craftsman</u>
<u>OTHER/Modern</u>

SUMMARY DESCRIPTION

Located approximately three miles from Washington, D.C., Ashton Heights is a residential neighborhood in central Arlington County. The neighborhood is bounded by Wilson Boulevard and 10th Street North to the north, Arlington Boulevard to the south, North Irving Street on the east, and North Oxford Street on the west. Ashton Heights was first platted and subdivided in 1921 by Ashton C. Jones, who had acquired approximately sixty-one acres of land in 1919. The neighborhood was later expanded on the west to include the area east of North Oakland Street and north of Arlington Boulevard. The northernmost portion of what is today Ashton Heights, to the north of 5th Street North, began to develop before 1921 as part of Clarendon. Thus, the neighborhood includes buildings that date from as early as 1900 to the few examples of infill construction dating to the latter part of the 20th century. The original Ashton Heights neighborhood has expanded with numerous additions, totaling 23 sections, and encompassing just over 220 acres. In all, there are 1,100 contributing resources, and 162 non-contributing resources within the Ashton Heights Historic District. The community consists today of 781 properties with a total of 1,262 buildings, sites, and structures. Located within the Historic District, the Clarendon (Matthew Maury) School is listed individually on the National Register of Historic Places.

Ashton Heights is defined by a variety of early 20th century architectural styles and building forms.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 2

Ranging from early-20th-century high style to vernacular interpretations of the elaborate styles traditionally erected decades earlier. Architectural styles and forms presented in Ashton Heights illustrate modest examples of Gothic Revival, Queen Anne, Bungalow/Craftsman, Colonial Revival, Dutch Colonial Revival, and Tudor Revival, Cape Cods, American Foursquare, and pre-fabricated kit houses. Single-family dwellings built prior to 1950, primarily in the Bungalow/Craftsman and Colonial Revival styles, dominate the neighborhood. Ashton Heights is also home to a number of multiple-family apartment buildings, three churches, the Women's Club of Ashton Heights, and Columbia Gardens Cemetery.

The streets in Ashton Heights generally run in a grid pattern with North Pershing Drive, which runs northeast to southwest, bisecting the neighborhood. Mature shade trees, planted as part of the subdivision plan, line many of the streets. The residential lots vary in size with the standard lot being fifty feet wide. The domestic buildings, constructed of both wood frame and masonry, are set back from the road with wide sidewalks buffering them from the public roadways. Many residential properties incorporate driveways, attached or freestanding garages, and sheds. Most of these buildings date from the second quarter of the 20th century, displaying the fashionable architectural styles of the period in which they were constructed.

DETAILED DESCRIPTION

Development Prior to the Platting of Ashton Heights (1900-1920)

Only one example of the Gothic Revival style was noted in Ashton Heights, located at 812 North Jackson Street. The dwelling, dating from the first decades of the 20th century, has a central-passage, single-pile plan that is augmented by a one-story rear ell. A full-width one-story porch marks the three-bay-wide façade of this modest wood-frame building. Tuscan columns support the porch, which is ornamented by a wide molded cornice. Paired 1/1-replacement windows flank the central entry, which holds a single-leaf door. The Gothic Revival influence is strongly reflected in the very steep pitch of the front gable, set directly over the center bay of the façade. Framed with an overhanging raked cornice, the gable is pierced by a single 1/1 double-hung, wood sash replacement window.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 3

Three examples of Queen Anne-style dwellings are located within the Historic District at 3509 7th Street North, 635 North Lincoln Street, and 502 North Kenmore Street. Popular in the late 19th century, the Queen Anne style was typically represented by irregular forms and the extensive use of ornamental motifs executed in wood. Through the early 20th century, the irregular form was lost in favor of the rectangular box. This front-gabled box, complete with full-width or wrapping porch, turned posts, and cornice detailing, typically displayed more restrained applied ornament.

The first example of the Queen Anne style in Ashton Heights at 3509 7th Street North represents the earlier irregular form. This dwelling, constructed circa 1905, is two-and-a-half stories in height clad with German wood siding and features an L-shaped footprint capped with a cross-gable roof. The house rests on a solid rock-faced concrete block pier foundation. Across the façade is a one-story wrap-around porch, three bays across and two bays deep, supported with turned posts, square balusters and resting on a rock-faced concrete block pier foundation. The front off-center entry contains a 15-light wood single-leaf door. The façade is illuminated with six 6/1 double-hung, wood sash windows, and a 6-light wood awning window in the upper half story. Features of the house include square-edged wood sills and surrounds, cornerboards, wide eaves with a wood soffit and exposed roof rafters. Rising above the roof, clad in pressed metal shingles, is one central-interior parged brick corbelled chimney.

The wood-frame dwelling at 635 North Lincoln Street, constructed circa 1915, is representative of the dilution of the popular Queen Anne style using the rectangular form. It measures three bays across and two-and-a-half-stories high with a front gable roof. The house rests on a solid rock-faced concrete block foundation and features a one-story full-width half-hipped porch across the façade. The porch is supported with turned posts and square-cut balusters, and sits on rock-faced concrete block piers. The dwelling is clad in weatherboard siding and features an off-center entry with a single-leaf wood door. Other details of the dwelling include cornerboards, square-edged sills and surrounds, wide eaves, and a molded wood cornice.

One of the most prevalent building forms noted in Ashton Heights is the bungalow, making up over 31 percent of the building stock. Like most of the modest bungalows of the 20th century, these dwellings are often trimmed with stone and brick, half-timbering, exposed rafter ends, multi-light fixed windows, and massive porch supports, thus, melding the bungalow form with the Craftsman style perpetually. This is

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 4

illustrated, for example, on the bungalow at 505 North Jackson Street. Stylistic elements include the rock-faced concrete block foundation, tapered Tuscan posts on masonry piers, full-width front porch, and paired window openings with three vertical lights in the upper sash. As the popularity of the form was heightened during the second quarter of the 20th century, the bungalow form of Arlington County was equally embellished with Queen Anne- and Colonial Revival-style detailing. Other examples of Craftsman-style bungalows exist at 526 North Ivy, 508 North Irving, 627 North Jackson, and 429 North Lincoln Streets.

Another of the building forms of the early 20th century noted in Ashton Heights is the American foursquare, which was commonly ornamented with Colonial Revival- and Craftsman-style detailing. The two-story, four-room-per-floor house plan without a hall is a much-used concept that refers to the hall/parlor plan of the 18th century. One illustration of the several American foursquares exhibiting architectural detailing fashionable in the early part of the 20th century is the house at 904 North Irving Street. This imposing freestanding dwelling was constructed in 1900, twenty years prior to the platting of the surrounding community of Ashton Heights. The building has the characteristically distinguished two-story height, hipped or pyramidal roof with pronounced eaves and dormers that light an extra half-story, large front porch, and the lack of ornate exterior ornament. The overall shape is a cube, and the main entry opening is located off-center. The dwelling at 928 North Ivy Street, constructed in 1906, is clad in stucco and includes features such as thin square wood sills, battered porch posts, a hipped dormer on each elevation, and a central-interior chimney.

The Evolution of Ashton Heights (1921-1950)

A surge in residential construction between 1933 and 1940 in Ashton Heights saw the addition of numerous brick Colonial Revival-style buildings constructed on the neighborhood's remaining unimproved lots. The Colonial Revival style, the most popular architectural style in Ashton Heights making up over 60 percent of the building stock, was adapted to meet the housing needs of many suburban neighborhoods in Arlington County in the middle part of the 20th century. Consequently, the larger high-style dwellings were reduced to three-bay-wide rectangular structures with projecting porticos, cornice returns, open pediments, and Tuscan columns. Other features of the Colonial Revival style include stretcher and rowlock beltcourses and water tables, segmental arch lintels, Colonial Revival door

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 5

surrounds with either broken, open, or full pediments, a dentilated cornice, and fluted or flush pilasters.

The two-and-a-half-story dwelling at 612 North Kenmore Street in Ashton Height is an excellent example of a modest Colonial Revival-style dwelling. The brick-clad dwelling has a side entry covered by a wood frame portico. The portico has a front-gable roof with a coved ceiling supported by square Tuscan posts and pilasters. The flanking 6/6 double-hung, wood sash windows have brick sills and soldier-coursed lintels. The side-gable roof has a shallow cornice largely obscured by the metal drainpipe and gutter. Examples of this form are seen at 404 North Nelson Street (clad in stone), 316 North Oakland Street, and 3803 4th Street North. More examples, which include an attached garage, are seen at 3741 4th Street North, 100 North Oakland Street, 3229 1st Place North, and 428 North Nelson Street (featuring a front gable roof).

Another example of the Colonial Revival style is very similar to the one previously described, however, it does not feature a full second story. Wall dormers piercing the cornice serve as the second story on a handful of rectangular brick Colonial Revival-style dwellings. One such dwelling stands at 409 North Oakland Street. This dwelling measures three bays wide and features a stretcher-bond veneer. Two exterior-end corbelled brick chimneys rise above the side-gable roof, and originally an attached garage was seen to the rear of the north (side) elevation. The garage door was removed and sized down, and this space is no longer maintained as a garage. The façade is illuminated with four 6/6 double-hung wood sash windows. The first-story windows feature paneled spandrels, and the second-story wall dormers feature an open pediment clad in weatherboard. The central entry contains a single-leaf paneled wood door and is flanked by 4-light sidelights over a paneled dado and topped by an elliptical transom. Covering the entrance is a gable portico supported with paired Tuscan columns. The roof features overhanging eaves and a molded wood cornice. More modest examples of the Colonial Revival style with wall dormers on the second story are seen at 3718 and 3734 4th Street North. These two dwellings feature recessed attached garages with the original two-leaf wood doors in tact.

Similarly, the one-and-a-half-story Cape Cod cottages of the 1930s and 1940s exhibit the familiar detailing and form commonly associated with the Colonial Revival style. This form provided an adequate and affordable housing mode for the growing population of working- and middle-class residents of Arlington County, while mimicking the fashionable style of the period. A form identified numerous times

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 6

throughout the survey area, the Cape Cod dwelling is typically constructed of brick with a side-gable roof and front gable dormers. The examples identified in Ashton Heights are typically three bays wide, two bays deep, and have a central-passage plan. Detailing includes the flat door surrounds with shallow Tuscan pilasters supporting a slightly projecting entablature, a corbeled brick cornice on the facade, and 6/6 double-hung, wood sash windows with brick sills. It is noted that in addition to the denticulated brick cornice, a carved panel was often applied over the main entry. Several examples of Cape Cod dwellings in Ashton Heights include 323 North Oxford Street, 130 and 223 North Oakland Street, and 3223 1st Road North.

Ashton Heights has a handful of modest Tudor Revival-style dwellings with 36 examples from this period between 1921 and 1940. As with the Queen Anne and Colonial Revival styles, many of the Tudor Revival-style resources found in Ashton Heights, and Arlington County as a whole, reflect the suburbanization of the style rather than the initial high-style expression. The distinguishing features in Ashton Heights include multiple-gabled roofs, the placement of an exterior brick chimney on the facade, application of stone as an accenting material around openings or on chimneys, and steeply pitched front gables, sometimes detailed with half-timbering. Both wood frame and brick facing are found as cladding materials on these dwellings.

Examples of Tudor Revival dwellings in Ashton Heights are most often constructed of brick. One example is located at 504 North Lincoln Street. Constructed between 1921 and 1930, this dwelling measures four bays across and is capped with a side-gable roof. It features the typical front-facing shouldered chimney and the front-gabled projecting bay with a steeply pitched roof. Seen here and scattered throughout the neighborhood in the Tudor Revival style and Colonial Revival style is the use of skintled brick. This dwelling rests on a solid stretcher-bond brick foundation, and is illuminated with three 6/6 double-hung wood sash windows and one 8-light casement window. Other features of the house include a 3-light sidelight at the entry, rowlock sills, and a side porch later enclosed. Examples of other masonry Tudor Revival-style dwellings are located at 608 North Jackson, 502 and 510 North Norwood, 600 and 608 North Kenmore Streets.

One example of a wood-frame Tudor Revival dwelling in Ashton Heights is the two-story dwelling at 803 North Kenmore Street. Constructed circa 1930, this three-bay-wide building has the emblematic front-end

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 7

shouldered chimney and a side-gable roof with a front projecting gable. The front-gable bay features a steeply pitched roof typical of Tudor Revival dwellings. It rests on a solid stretcher-bond brick foundation and is illuminated with two 8/8 double-hung wood sash windows. Sheltering the entrance is a portico supported with wood posts. Other wood frame examples throughout the community are located at 548 North Piedmont, and 600 and 650 North Jackson Streets.

The Tudor Revival and Colonial Revival styles are sometimes used together to ornament the dwellings in Ashton Heights. For example, a brick one-and-a-half-story dwelling at 18 North Oakland Street, typical of the Cape Cod building form, features a front-gable vestibule with a steeply pitched sloping roof. Other example of this mixture of styles are located at 8 North Oakland Street and 3812 North Pershing Drive. The latter uses the typical rectangular block of the two-story Colonial Revival dwelling and adds a large projecting front-gable bay and a wall dormer, both with steeply pitched roofs.

Ashton Heights and many other early-20th-century subdivisions in Arlington County contain examples of kit houses or mail-order houses. The largest, and by far the best known, of the mail-order companies was Sears, Roebuck and Company of Chicago, Illinois. The company began to design and sell house kits in the mid-1890s, and in its three decades of operation, Sears made a substantial contribution to 20th-century housing in America. One of the reasons for the popularity of Sears houses was that they consciously reflected popular American tastes of the period. Sears, however, was not the only American company to manufacture or sell houses through mail-order catalogs, nor was it the only company to sell house designs. The late 19th and early 20th centuries were ripe for entrepreneurs who sold architectural plans as well as the houses themselves. The Hodgson Company, Aladdin Homes, Ray H. Bennett Lumber Company, and Montgomery Ward all had their start in the housing business between 1895 and 1910. All shipping was done by rail; consequently the largest concentration of mail-order houses exist in the Northeast and Midwest, areas that were served by many rail lines.¹

It has been documented that Arlington County contained numerous genuine examples of mail-order and catalog houses, particularly in those communities located within close proximity to Washington, D.C. and the rail lines. Commonly, builders and real estate developers purchased a plan and proceeded to erect numerous examples of the building based on the original mail-order design. Consequently, positive identification of mail-order and catalog houses during a reconnaissance survey is nearly impossible.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 8

However, at least ten Sears houses have been identified in Ashton Heights. These include the Clyde, Americus, Sunbeam, Vallonia, Mitchell, Conway, Lenox, Roseberry, Windsor, Westly, and #52 models.² An example of the Sunbeam is located at 136 North Irving Street, and at 3203 4th Street North is an example of the Vallonia form.

With a total of 67 resources, multiple dwellings also comprise part of the domestic housing stock in Ashton Heights, particularly near the northwest boundaries of the neighborhood. Constructed between 1930 and 1950, these multiple dwellings include both low-rise garden apartments and twin dwellings. Many of these multiple dwellings have diluted references to the Colonial Revival style as frequently seen in buildings that were constructed during the middle of the 20th century. Constructed in the 1940s, the Kenmore Apartments at 700-708 North Monroe Street is a prime example of the low-rise garden apartment complexes found in Ashton Heights. The three brick apartment buildings that comprise Kenmore Apartments are two stories in height and four bays in width. Colonial Revival-style detailing is largely confined to the entries, which have fluted pilasters and pedimented porticos with brackets.

The community of Ashton Heights also includes the Buckingham Apartments, a garden apartment complex built between 1937 and 1953 in the southwest corner of the neighborhood. Constructed in phases, Buckingham was designed by pioneering garden city architect Henry Wright. The design applied the pioneering principles of garden city planning, which included the use of low-density superblocks, curving streets, the separation of automobiles and pedestrians, shallow building plans, and landscaped common spaces. Although Buckingham Apartments is included in the Ashton Heights neighborhood, the complex is not included in the Ashton Heights Historic District. Instead, the existing Buckingham Historic District, which consists of the oldest section of the complex and was listed on the National Register of Historic Places in 1999, should be expanded to include the entire complex.

In addition to the domestic buildings throughout Ashton Heights, there are also civic, religious, educational and commercial buildings. The Women's Club of Ashton Heights at 413 North Irving Street was constructed between 1924 and 1927 in the Bungalow/Craftsman style. Reading as a single-family dwelling, the modest wood-frame clubhouse is set upon a concrete block foundation and has a symmetrical façade with an entrance highlighted by sidelights and a transom. The building has a low-pitched hipped roof and a hipped entry porch supported by Tuscan columns.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 9

The Arlington Church of Christ at 20 North Irving Street displays many of the architectural elements seen at the Virginia Avenue Christian Church in Lyon Park. Built in 1941, the Arlington Church of Christ is constructed of coursed stone accented by limestone coping and surrounds. The original portion of the building, consisting of a one-story, open nave plan, is dominated by a 1954 addition and a crenellated tower, which acts as a hyphen between the main block and the addition. The Clarendon United Methodist Church at North 6th and North Irving Street was constructed in 1920 to meet the growing needs of the community. The church is designed in the Colonial Revival style, with Gothic Revival-style elements.

The Columbia Gardens Cemetery, maintained by the Alexandria Park Association, dominates the southern portion of the Ashton Heights community. The current boundaries of the non-sectarian cemetery extend along Arlington Boulevard to the south. Although the corporation had more land extending southward, it was relinquished to the County in 1929 when the boulevard was expanded. The western edge of the cemetery is adjacent to the domestic architecture along Oakland Street. The northern boundary fronts Jackson Street, intersecting with Arlington Boulevard. As one enters through the main gate located on Arlington Boulevard, a park-like view is the first impression. To the right stands the modest one-story office and private dwelling of the managing director. At the head of the bisecting lane is the mausoleum of Admiral George Dewey (1837-1917), which was moved there from Arlington National Cemetery after his body was re-interred in the Washington Cathedral. With an open policy allowing patrons to choose their gravesite and style of marker, there is a mixture of historically inspired monuments and modern markers. Unlike memorial parks that regulated uniformity beginning in the 1950s, the Columbia Gardens Cemetery reflects the changing styles occurring from the first interments in 1917 to the present day.

The Clarendon School, also known as the Matthew Maury School, is located at 3550 Wilson Boulevard. Constructed in two phases, the main block of the building dates from 1910, with a 1954 addition on the rear elevation.³ The imposing brick building features stylistic elements from the Classical Revival style, an architectural trend fashionable during the period of construction. Featuring brickwork laid in five- and six-course American bond, the school rises two-and-a-half stories with a hipped roof. Set on a raised, stucco-clad foundation, the building is three bays wide and two bays deep. Horizontal massing is provided by the tall stuccoed watertable and belt course, the one-story portico over the main entry, the recessed panels between the first- and second-story openings, and the shallow hipped roof with its

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 10

expansive overhanging eaves. Yet, the symmetrically placed openings, wide mullions, and enclosed pediments on the projecting front bays emphasize verticality. The Clarendon School was listed on the National Register of Historic Places in 1999.

Wilson Boulevard and 10th Street North, major transportation corridors extending through Arlington County, bound the Ashton Heights community on the north. As such, there is modern commercial development along this route that provides services to the neighborhood and passing automobile traffic. There are some resources that were constructed during the second quarter of the 20th century that remain. Many of these are automobile-related, reflecting the importance of the car on the development of the suburban neighborhood. Since these buildings are commercial rather than residential, they are not included within the Historic District boundaries.

Development After 1950

Ashton Heights experienced little construction after the middle of the 20th century as residential buildings had improved most of the interior lots by that time. A few of the remaining unimproved lots, however, have subsequently been improved in the last quarter of the 20th century with single-family dwellings. For the most part, these houses are compatible with the historic housing stock seen throughout Ashton Heights. One of the more recent dwellings, compatible to its neighboring building stock, is at 108 North Jackson Street (circa 1990). This house features a Colonial Revival form and characteristics. It is two stories in height and measures five bays across. It is wood-frame construction clad in a brick veneer, and capped with a hipped roof. Features include cast concrete jack-arch lintels with keystones, exterior-end corbelled chimneys, overhanging eaves, and a heavy molded dentilated cornice. The center entrance is recessed, flanked by 5-light sidelights, and features a Colonial Revival door surround with fluted pilasters and a molded entablature. Other examples of this modest infill housing can be seen at 117 North Jackson, 3223 4th Street North, 3201 1st Place North, and 3218 1st Road North.

Although most of the infill housing from this period is compatible, there are a few buildings that are not characteristic of the neighborhood. The split-level dwelling at 629 North Monroe Street is modest in details, however, its T-shaped form is not in keeping with the neighborhood. This dwelling was constructed in 1973 and is comprised of two blocks. One section is two stories and gable oriented and the

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 7 Page 11

second is one story and eave oriented. The one-story section contains an attached garage and is clad with a brick veneer. The two-story section is clad with a brick veneer and the second story is overhanging and clad with aluminum siding. The off-center doorway is flanked by diamond-pattern sidelights. The roof features overhanging eaves and is clad in asphalt shingles.

ENDNOTES

¹ Katherine Cole Stevenson and H. Ward Jandl, *Houses by Mail: A Guide to Houses from Sears, Roebuck and Company*, (Washington, DC: The Preservation Press, 1986), pp. 19-30; Aladdin *"Built in a Day" House Catalog, 1917: The Aladdin Company*, (New York, New York: Dover Publications, Inc., 1995), passim.

² Kathy Holt Springston, "Sears Houses of Arlington," unpublished brochure.

³ The Clarendon School is currently under contract to enlarge the rear addition.

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 15

3222 1st Road North **000-7819-0259** **Other DHR ID#: 000-5685**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay house has a centered entry topped by a front l
gable hood and flanked by paired windows. The roof has wide l
eaves supported by decorative brackets. There is a side gable l
porch on the northeast elevation.

Individual Resource Status: Shed

Contributing

Individual Resource Status: Single Dwelling

Contributing

3223 1st Road North **000-7819-0037**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

This three bay wide Cap Cod dwelling features a denticulated cornice, and a Colonial Revival door surround with
fluted pilasters.

Individual Resource Status: Single Dwelling

Contributing

3226 1st Road North **000-7819-0257** **Other DHR ID#: 000-5683**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay brick house has a centered entry and flanking l
windows, one of which is paired, with rowlock sills and l
soldier lintels. The front gable end is clad in wood l
weatherboard.

Individual Resource Status: Shed

Non-contributing

Individual Resource Status: Single Dwelling

Contributing

1st Street North

3207 1st Street North **000-7819-0272** **Other DHR ID#: 000-5699**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Wide, wood trim with a beaded edge surrounds the centered l
entry and windows of the three-bay house. The dormer, l
containing four one-light casement windows, is set on the side l
gable roof that is detailed with wide eaves, exposed rafters, l
and decorative brackets. The porch is set on a random, rubble l
stone foundation.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3208 1st Street North **000-7819-0213**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

Four bays wide, this dwelling features a wood cornice, rowlock sills, and a Colonial Revival door surround with
fluted pilasters and an arched
dentilated entablature.

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 16

- 3211 1st Street North** **000-7819-0217** -
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This three-bay, two-story Colonial Revival wood-framed house sits on a solid stretcher bond brick masonry foundation, is clad in aluminum siding, and has a side-gabled roof sheathed in asphalt shingles. The facade fenestration is comprised of two 8/8 wood sash windows on the first floor, and two 6/6 wood sash windows in the each of the front-gabled dormers. The structure is further defined by an exterior end stretcher bond brick chimney, affixed wood shutters, a soldier course brick stoop, and a Colonial Revival door surround with a dentiled entablature.
Individual Resource Status: Single Dwelling **Contributing**
- 3214 1st Street North** **000-7819-0266** *Other DHR ID#: 000-5693*
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a rock-faced concrete block foundation, the Craftsman 1 style four-square house is two bays wide and has a one-story, 1 one-bay frame wing on the northeast side of the house. There 1 is a hipped-roof hood over the front door. The roof has wide 1 eaves supported by brackets. The paired windows are 1 six-over-one double-hung wood sash.
Individual Resource Status: Garage **Non-contributing**
Individual Resource Status: Shed **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3215 1st Street North** **000-7819-0274** *Other DHR ID#: 000-5701*
Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,
Set on a rock-faced concrete block foundation, the three-bay 1 house has an off-center entry that is inset beneath the front 1 porch. The front gable porch roof is supported by square 1 dwarf columns atop wood-shingles piers. The roof is 1 embellished by wide eaves with decorative, exposed beam ends. Additions and alterations
Individual Resource Status: Shed **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3219 1st Street North** **000-7819-0276** *Other DHR ID#: 000-5703*
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a rock-faced concrete block foundation, the three-bay 1 house has a porch that extends along the southwest side of the 1 dwelling. The shed dormer, containing two six-light casement 1 windows, sits atop the side gable roof with wide eaves.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3220 1st Street North** **000-7819-0019**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1950
This four bay wide dwelling features rowlock sills.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 17

- 3223 1st Street North** **000-7819-0278** **Other DHR ID#: 000-5705**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a panel-faced, concrete block foundation and constructed of "econo" bricks, the three-bay house has a side passage entry sheltered by a front gable hood. The triple windows have rowlock sills and the dwelling is detailed with a concrete water table.
Individual Resource Status: Shed **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3226 1st Street North** **000-7819-0268** **Other DHR ID#: 000-5695**
Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,
Set on a panel-faced concrete block foundation, the two-bay house has a side passage entry framed by sidelights with wood panels and lights. The front gable dormer, containing two six-light casement windows with stone lintels, sits atop the flared hipped roof with wide eaves and exposed rafters. The second story windows are surrounded by wide, wood trim with an outside, beaded edge.
Individual Resource Status: Single Dwelling **Contributing**
- 3227 1st Street North** **000-7819-0224** **Other DHR ID#: 000-5650**
Primary Resource Information: Single Dwelling,
Set on a panel-faced concrete block foundation, the three-bay house has an off-center entry and flanking windows that are surrounded by wide, wood trim and square-edged sills. The porch and shed dormers have wide, overhanging eaves and exposed rafter tails. The porch has a stick style railing.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3311 1st Street North** **000-7819-0029**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1970
This dwelling exhibits rowlock sills, and aluminum encased soffit with wide eaves. It measures five bays across.
Individual Resource Status: Single Dwelling **Non-contributing**
- 3313 1st Street North** **000-7819-0028**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1980
Five bays wide, this dwelling has an attached garage. It exhibits soldier course lintels, rowlock sills, and a dentilated wood cornice.
Individual Resource Status: Single Dwelling **Non-contributing**

2nd Road North

- 3203 2nd Road North** **000-7819-0146**
Primary Resource Information: Single Dwelling, Stories 3, Style: Other, ca 1985
This dwelling features a roof-top balustrade on the porch. A skirt roof is seen around the facade of the dwelling. The doorway is illuminated with a stained and leaded sidelights. The roof features overhanging eaves.
Individual Resource Status: Single Dwelling **Non-contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 19

3851 2nd Street North **000-7819-0340** *Other DHR ID#:* **000-5767**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Tudor Revival,**

Set on a flush concrete block foundation, the three-bay frame house has paired windows in the front gable. The projecting front gable vestibule is asymmetrical.

Individual Resource Status: **Single Dwelling** **Contributing**

3854 2nd Street North **000-7819-0147**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945**

Three bays wide, this dwelling features rowlock sills, a wood cornice, a shouldered chimney, and a center entry. A large brick projecting center gable bay covers the entrance. The portico features round-arched openings and a casement window in the gable.

Individual Resource Status: **Single Dwelling** **Contributing**

3855 2nd Street North **000-7819-0145**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940**

This dwelling is three bays wide featuring rowlock sills, a wood cornice, and a Colonial Revival door surround with fluted pilasters.

Individual Resource Status: **Single Dwelling** **Contributing**

3859 2nd Street North **000-7819-0144**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940**

Features of this three bay wide dwelling include rowlock sills, a wood cornice, and a Colonial Revival door surround with fluted pilasters and a dentilated pediment. A one story screened porch supported with wood posts is located on the north side elevation.

Individual Resource Status: **Single Dwelling** **Contributing**

3863 2nd Street North **000-7819-0148**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945**

Features of this two bay wide dwelling include rowlock sills, a boxed wood cornice, and a Colonial Revival door surround. The door surround has fluted pilasters and a triglyph and metope frieze. The bay window flanking the entry is not original. The roof features a flush fascia board. A sun porch is located on the side elevation.

Individual Resource Status: **Single Dwelling** **Contributing**

3rd Street North

3308 3rd Street North **000-7819-0051**

Primary Resource Information: **Garage, Stories 1, Style: Other, ca 1940**

This building has a molded wood cornice and weatherboard siding in the front gable.

Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Non-contributing**

3311 3rd Street North **000-7819-0233** *Other DHR ID#:* **000-5659**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**

Set on a panel-faced concrete block foundation, the three-bay house has an off-center entry and flanking paired windows with square-edged wood trim. There is a one-story, one-bay frame wing on the northeast side of the house.

Individual Resource Status: **Single Dwelling** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 20

3316 3rd Street North **000-7819-0286** **Other DHR ID#: 000-5713**

Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,

The three-bay frame house has an off-center entry framed by a 1
seven-light transom and sidelights with both panels and 1
lights. The hipped roof has flared, wide eaves.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Shed

Non-contributing

Individual Resource Status: Single Dwelling

Contributing

3317 3rd Street North **000-7819-0235** **Other DHR ID#: 000-5661**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

Set on a rock-faced concrete block foundation, the two-bay 1
house has a side passage entry flanked by five-light 1
sidelights and capped by a fanlight. The windows have wide, 1
wood surrounds and there is a lunette vent in the front of the 1
gambrel roof.

Individual Resource Status: Single Dwelling

Contributing

3320 3rd Street North **000-7819-0288** **Other DHR ID#: 000-5715**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Set on a panel-faced concrete block foundation, the five-bay 1
house has a centered entry and a centered front gable porch. 1
The porch roof, supported by clustered square posts atop 1
piers, has decorative, wood brackets in the eaves.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3321 3rd Street North **000-7819-0237** **Other DHR ID#: 000-5663**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Set on a rock-faced concrete block foundation, the three-bay 1
house has an off-center entry flanked by paired windows. The 1
overlapping front gables have wide eaves and projecting beam 1
ends. The porch is supported by square dwarf columns atop 1
concrete piers.

Individual Resource Status: Single Dwelling

Contributing

3324 3rd Street North **000-7819-0290** **Other DHR ID#: 000-5717**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Set on a granite-textured, flush concrete block foundation, 1
the two-bay brick house has the entry set on the southwest 1
wall of the inset front porch. An eyebrow dormer with a 1
four-light fixed window sits on the side gable roof, that has 1
wide eaves and exposed rafter tails. The windows have brick 1
rowlock sills.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 21

- 3330 3rd Street North** **000-7819-0052** -
Primary Resource Information: Single Dwelling,
This dwelling is three bays wide and features paired windows on the second story, corner boards, and square-edged wood surrounds. It has one gable dormer on the facade.
Individual Resource Status: Single Dwelling **Non-contributing**
- 3402 3rd Street North** **000-7819-0262** *Other DHR ID#: 000-5688*
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a panel-faced concrete block foundation, the three-bay house has two sets of paired windows with wide, molded wood surrounds and square-edged sills. The roof has wide, overhanging eaves and decorative wood brackets. The front gable dormer has exposed rafter tails, decorative brackets, and a group of three four-light casement windows. There is a wide, wood trim between the foundation and the first story.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3406 3rd Street North** **000-7819-0776** *Other DHR ID#: 000-5690*
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on an unpainted flush concrete block foundation, the five-bay house has wide, wood surrounds with an outer beaded edge surrounding the fenestration. The hipped roof has wide, overhanging eaves and a boxed cornice. The porch columns are fluted and there is a strip of wide, wood weatherboard between the foundation and the first story.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3407 3rd Street North** **000-7819-0220** *Other DHR ID#: 000-5646*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick house is embellished by soldier lintels, rowlock sills, a single water table course, and a rowlock beltcourse. The gable ends have cornice returns.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3411 3rd Street North** **000-7819-0054**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
Features of this three bay wide dwelling include rowlock sills, soldier lintels, a stretcher course water table, and a boxed wood cornice with returns. The central entrance features a Colonial Revival door surround.
Individual Resource Status: Single Dwelling **Contributing**
- 3412 3rd Street North** **000-7819-0296** *Other DHR ID#: 000-5723*
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a rock-faced concrete block foundation, the three-bay house has a centered entry. The shed dormer, containing a group of three six-over-one double-hung wood sash windows, is set upon a side gable roof with wide eaves.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 22

3416 3rd Street North **000-7819-0298** **Other DHR ID#: 000-5725**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay house has a centered entry and a one-story, 1
one-bay brick wing on the northeast side. The brick is 1
detailed with rowlock sills, soldier lintels and a soldier 1
course water table. The dormers are clad in vinyl German 1
siding and contain six-over-six double-hung wood sash windows. Additions and
alterations

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3500 3rd Street North **000-7819-0265** **Other DHR ID#: 000-5692**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The three-bay brick house has a soldier water table, soldier 1
lintels, and rowlock sills. The front facing chimney has a 1
rowlock chimney cap. The front gable section of the house has 1
cornice returns.

Individual Resource Status: Single Dwelling

Contributing

3504 3rd Street North **000-7819-0300** **Other DHR ID#: 000-5727**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The three-bay brick house has an asymmetrical facade and a 1
shed roof portico supported by paired, square posts. The 1
windows have rowlock sills and jack-arch lintels.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

3508 3rd Street North **000-7819-0302** **Other DHR ID#: 000-5729**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay brick house has a side passage entry and a 1
one-and-a-half story, enclosed, side porch on the northeast 1
elevation. The windows have rowlock sills and soldier 1
lintels. The shed dormer contains two, six-over-six 1
double-hung metal sash replacement windows.

Individual Resource Status: Single Dwelling

Contributing

3511 3rd Street North **000-7819-0299** **Other DHR ID#: 000-5726**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay brick house has a side passage entry and a 1
one-story, one-bay frame wing on the northeast side of the 1
house, that has a shed roof and wood weatherboard cladding. 1
The brick is detailed with rowlock sills, soldier lintels, and 1
a soldier course water table.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 23

- | | | |
|--|----------------------|--------------------------------|
| 3512 3rd Street North | 000-7819-0267 | Other DHRID#: 000-5694 |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,</i>
The three-bay brick house has a side passage entry framed by a 1
door surround with fluted pilasters. Brick detailing includes 1
a soldier course water table, rowlock sills, and soldier 1
lintels. The side porch is enclosed with screening and the 1
gable ends of the house exhibit cornice returns. | | |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 3515 3rd Street North | 000-7819-0301 | Other DHR ID#: 000-5728 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay brick house has a centered entry and a 1
one-story, one-bay, shed-roof porch on the southwest side of 1
the house. Brick detailing includes rowlock sills, a rowlock 1
water table, a one-course corbelled cornice, raised and hooded 1
lintels, and a Flemish bond corbelled beltcourse above the 1
first story windows. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 3516 3rd Street North | 000-7819-0055 | |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940</i>
This building features rowlock sills, and the side porch has been enclosed. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 3521 3rd Street North | 000-7819-0056 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940</i>
This dwelling measures three bays wide and features rowlock sills, a denticulated wood cornice, and two gable
dormers. The Colonial Revival door
surround has fluted pilasters and a denticulated entablature. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| 3522 3rd Street North | 000-7819-0277 | Other DHR ID#: 000-5704 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,</i>
The entry of the three-bay house is set in a projecting front 1
gable vestibule and framed by a random stone surround. The 1
brick dwelling is embellished with rowlock sills, soldier 1
lintels, a herringbone pattern water table, and a round-headed 1
window in the front Jerkinhead. The shed dormer contains two 1
six-over-six double-hung metal sash windows. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 24

3526 3rd Street North **000-7819-0269** **Other DHR ID#: 000-5696**

Primary Resource Information: Single Dwelling, Stories 3, Style: Tudor Revival,

The three-bay brick house is constructed of skintled brick l walls with rowlock sills and a front facing chimney. The side l gable roof is steeply pitched with flared ends and a molded l wood vergeboard.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3602 3rd Street North **000-7819-0279** **Other DHR ID#: 000-5706**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay brick house has a side passage entry framed by a l front gable portico. The windows have rowlock sills and l soldier lintels.

Individual Resource Status: Garage

Non-contributing

Individual Resource Status: Single Dwelling

Contributing

3603 3rd Street North **000-7819-0289** **Other DHR ID#: 000-5716**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay brick house is detailed with rowlock sills, l soldier lintels and a soldier course water table. There are l two front gable wall dormers.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3606 3rd Street North **000-7819-0281** **Other DHR ID#: 000-5708**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay brick house has a side porch on the northeast l side and a front gable portico over the side passage entry. l Brick detailing includes rowlock sills and soldier lintels.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

3607 3rd Street North **000-7819-0287** **Other DHR ID#: 000-5714**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The entry of the two-bay brick house is set in an inset porch l with an arched opening. The windows have rowlock sills. An l enclosed one-story, one-bay porch sits on the southwest side l of the house.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3610 3rd Street North **000-7819-0271** **Other DHR ID#: 000-5698**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay house has a side passage entry sheltered by a l pedimented portico. Brick detailing includes rowlock sills, l soldier lintels and a basketweave patterned water table.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 25

3611 3rd Street North **000-7819-0273** **Other DHR ID#: 000-5700**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

Brick detailing on the two-bay house includes rowlock sills, 1
two-course rowlock lintels, and a single course stretcher 1
water table. A brick arch on the southeast corner of the 1
facade leads to the rear of the house. The side porch is 1
enclosed with screening.

Individual Resource Status: Single Dwelling

Contributing

4th Street North

3200 4th Street North **000-7819-0044**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945

Two bays wide, this dwelling features rowlock sills, a beltcourse, a boxed wood cornice, and a Colonial Revival
door surround. The surround features
a sunburst transom. A shed roof porch is seen on the side elevation, and there is a 1-story addition on the rear
elevation.

Individual Resource Status: Single Dwelling

Contributing

3203 North 4th Street **000-7819-0219** **Other DHR ID#: 000-5645**

Primary Resource Information: Single Dwelling, Stories 1.5, Style: Bungalow/Craftsman, ca. 1920

Concrete Block Foundation, Side Gable Roof with Asphalt Shingle, Wood Frame Structural System with Vinyl
Siding

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

3209 4th Street North **000-7819-0010** **Other DHR ID#: 000-5636**

Primary Resource Information: Single Dwelling, Stories 1.5, Style: Bungalow/Craftsman, 1920

Wood Frame Structural System with Weatherboard Siding, Concrete Block Foundation, Side Gable Roof with
Asphalt Shingle

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

3210 4th Street North **000-7819-0045**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945

This four bay wide dwelling features rowlock sills, and a Colonial Revival door surround. A wing connects the
garage to the main house. The
chimney is shouldered

Individual Resource Status: Single Dwelling

Contributing

3213 4th Street North **000-7819-0221** **Other DHR ID#: 000-5647**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The two-bay Craftsman style four-square house has paired 1
windows on the first story. The windows have rowlock sills 1
and soldier lintels. The porch roof is supported by clustered 1
square wood posts atop brick piers.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 26

- 3216 4th Street North** **000-7819-0227** **Other DHRJD#: 000-5653**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The symmetrical three-bay house has a centered entry framed by fluted pilasters. There is a one-story wing with a half-hipped roof on the northeast elevation. The brick house is adorned with a soldier course water table, rowlock sills, and soldier lintels. The dormers each contain one six-over-six double-hung wood sash window.
Individual Resource Status: Single Dwelling **Contributing**
- 3219 4th Street North** **000-7819-0046**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1965
Features of this five bay wide dwelling include rowlock sills, and a scalloped cornice. The gables are covered with weatherboard and formstone covers part of the facade.
Individual Resource Status: Single Dwelling **Non-contributing**
- 3223 4th Street North** **000-7819-0047**
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1980
Measuring four bays wide, this dwelling features an attached carport supported with wood posts. Seen on the second story are applied wood beams to provide a Tudor Revival stylistic element.
Individual Resource Status: Single Dwelling **Non-contributing**
- 3708 4th Street North** **000-7819-0089**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Features of this five bay wide Cape Cod dwelling include rowlock sills, decorative brick work above the basement story, and a partial soldier stringcourse over the center three bays. Two gable dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 3714 4th Street North** **000-7819-0088**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling is four bays wide and features rowlock sills, soldier lintels, and decorative brickwork above the basement story. Two gable dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3715 4th Street North** **000-7819-0123**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1945
Three bays wide, this dwelling features rowlock sills, soldier lintels, and a molded wood cornice. The center entry features a Colonial Revival door surround with a full pediment and fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3718 4th Street North** **000-7819-0087**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Four bays wide, this dwelling features a Colonial Revival door surround, jackarch lintels with keystones, and rowlock sills. The center entry surround has fluted pilasters, a full pediment, and a denticulated entablature.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 28

- 3803 4th Street North** **000-7819-0099**
- Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940*
Measuring three bays wide, this dwelling includes features as rowlock sills, segmental arch lintels, and both brick and wood denticulated cornices.
The center entry features a Colonial Revival door surround with fluted pilasters, broken pediment with an urn, and a denticulated entablature.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3809 4th Street North** **000-7819-0098**
- Primary Resource Information: Garage, 1940*
The brick garage is one bay wide with a roll-up wood door and is capped with a front gable asphalt shingle roof.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Garage **Contributing**
- 3810 4th Street North** **000-7819-0075**
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940*
This dwelling is a total of five bays across and includes features as rowlock sills, arched entries on porch, soldier lintels, and paneled spandrels.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3813 4th Street North** **000-7819-0091**
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940*
Three bays wide, this dwelling features rowlock sills, aluminum encased surrounds, and a denticulated wood cornice. The center entry features a Colonial Revival swans neck door surround and fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Non-contributing**

5th Street North

- 3201 5th Street North** **000-7819-0372** *Other ID#* **000-6346**
- Single Dwelling 1930-1945 Colonial Revival 1.5 *Foundation: Solid Brick Stretcher Bond*
Structural System: Masonry Brick Stretcher Bond
Window(s): Sash, double-hung Wood 8/8
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Gable, Side Asphalt Shingle
Chimney: Exterior end Brick Corbeled
Porch: 1-story, 1-bay Metal Rod Support
Dormer: Gable Vinyl Siding
Individual Resource Status: Shed **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3202 5th Street North** **000-7819-0446** *Other DHR ID#: 000-6605*
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,*
The four bay wide dwelling features a front gable projecting 1 bay, some paired windows, and a shed roof portico. Brick 1 detailing includes rowlock sills and soldier lintels.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 29

3208 5th Street North **000-7819-0445** **Other DHR ID#: 000-6604**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The windows of the three-bay wide dwelling have rowlock brick l
sills and soldier lintels. The centered entry is dominated by l
an elliptical portico with a rooftop balustrade and fluted l
pilasters.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

3209 5th Street North **000-7819-0371** *Other ID#* **000-6345**

Single Dwelling 1933 Colonial Revival 1.5 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Vinyl 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Dormer: Gable Vinyl Siding

Individual Resource Status: Single Dwelling

Contributing

3214 5th Street North **000-7819-0444** **Other DHR ID#: 000-6603**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling has a centered entry and paired l
windows with square-edged surrounds. The full-width porch is l
supported by tapered columns atop stucco clad piers. The roof l
has wide, overhanging eaves and the box bays on the east and l
west have shed roofs.

Individual Resource Status: Single Dwelling

Contributing

3220 5th Street North **000-7819-0443** **Other DHR ID#: 000-6602**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling has a centered entry flanked by l
paired windows . The shed dormer contains a triple 6/1 l
window. The full-width front porch features arched openings l
supported by tapered wood columns atop stucco clad piers.

Individual Resource Status: Single Dwelling

Contributing

3226 5th Street North **000-7819-0442** **Other DHR ID#: 000-6601**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling has a centered entry flanked by l
paired windows with square-edged surrounds. The roof has wide l
eaves and exposed rafter tails and the porch has arched l
openings.

Individual Resource Status: Single Dwelling

Contributing

3234 5th Street North **000-7819-0441** **Other DHR ID#: 000-6600**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling has a centered entry flanked by l
paired windows with square-edged surrounds. The porch l
openings have canted corners and the roof had wide eaves and l
exposed rafter tails.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 30

3300 5th Street North

000-7819-0774

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1985**

Three bays wide, this brick dwelling features a Colonial Revival door surround with a broken pediment, fluted pilasters, and a dentilated cornice. The house features bay windows on the first story, an attached garage, and a dentilated cornice. Illuminating the entry are 1-light sidelight over a dado panel.

Individual Resource Status: **Single Dwelling**

Non-contributing

6th Road North

3610 6th Road North

000-7819-0697

Other DHR ID#: **000-6868**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Other,**

The three-bay wide dwelling has a front gable bay with cornice 1 returns and a diamond shaped louvered ventilator. The porch 1 has scroll-sawn brackets and a half-hipped roof.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-contributing

3618 6th Road North

000-7819-0698

Other DHR ID#: **000-6869**

Primary Resource Information: **Single Dwelling, Stories 1, Style: Bungalow/Craftsman,**

The three-bay wide bungalow has narrow weatherboard cladding, 1 cornerboards, and wide eaves with cut-out brackets. The front 1 gable porch has a concrete foundation with a stone veneer.

Individual Resource Status: **Single Dwelling**

Contributing

3622 6th Road North

000-7819-0699

Other DHR ID#: **000-6870**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**

The three-bay wide bungalow has wide eaves, cut-out brackets 1 and a projecting gable bay on the west elevation. The front 1 gable porch has tapered square columns atop low panel-faced 1 concrete block piers.

Individual Resource Status: **Single Dwelling**

Contributing

3700 6th Road North

000-7819-0651

Other DHR ID#: **000-6822**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**

The three-bay wide bungalow has a full-width front porch 1 supported by tapered wood columns atop of rock-faced concrete 1 block piers. The dormer contains two sets of paired 4/1 1 windows.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-contributing

3710 6th Road North

000-7819-0652

Other DHR ID#: **000-6823**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**

The three-bay wide dwelling has a centered entry, a front 1 gable portico with a segmental soffit, and rowlock sills.

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 31

3714 6th Road North **000-7819-0632** **Other DHR ID#: 000-6803**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling features rowlock sills, exposed l
rafter tails, and a front gable portico with weatherboard in l
the gable end. The side elevations each have a gable dormer l
with asbestos shingle cladding, a l/l window, and exposed l
rafter tails.

Individual Resource Status: Single Dwelling

Contributing

3715 6th Road North **000-7819-0623** **Other DHR ID#: 000-6794**

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The four-bay wide twin dwelling features a front gable bay l
with siding in the gable end, rowlock sills, and a bay window l
with bracket supports. There is a Colonial Revival style door l
surround with fluted pilasters and an entablature with dentil l
molding.

Individual Resource Status: Multiple Dwelling

Contributing

3719 6th Road North **000-7819-0622** **Other DHR ID#: 000-6793**

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The four-bay wide twin dwelling features tripartite windows at l
the second story and three-sided window bays at the first l
story. There are brick quoins, rowlock sills, and slate l
tile-clad hoods over the entries and the adjoining bay l
windows.

Individual Resource Status: Shed

Non-contributing

Individual Resource Status: Multiple Dwelling

Contributing

3723 6th Road North **000-7819-0621** **Other DHR ID#: 000-6792**

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The four-bay wide twin dwelling features rowlock sills and bay l
windows with bracket supports. There is a continuous lintel l
over each entry and its adjoining bay window.

Individual Resource Status: Multiple Dwelling

Contributing

3727 6th Road North **000-7819-0620** **Other DHR ID#: 000-6791**

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The four-bay wide twin dwelling features three-sided window l
bays at the first story, rowlock sills, and brick quoins. The l
dominant bond of the building is 6-course American bond, but l
there are also 4- and 8-courses. There are half-hipped, slate l
tile clad entrance hoods over each entry and adjoining bay l
window.

Individual Resource Status: Multiple Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 32

3731 6th Road North **000-7819-0619** **Other DHR ID#: 000-6790**

Primary Resource Information: Multiple dwelling, Stories 3, Style: Colonial Revival,

The four-bay wide twin dwelling features rowlock sills and a front gable bay with siding in the gable end. The gable bay is painted white, visually defining it from the other twin dwelling.

Individual Resource Status: Shed

Non-contributing

Individual Resource Status: Multiple Dwelling

Contributing

3804 6th Road North **000-7819-0718** **Other DHR ID#: 000-6889**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The dwelling has a three-bay wide main block with a two-story projecting bay on the east elevation and a one-story enclosed porch with a flat roof and a balustrade. The entry is framed by a front gable portico with a round arched opening.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3808 6th Road North **000-7819-0719** **Other DHR ID#: 000-6890**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The windows and doors of the three-bay wide dwelling feature wood sills, double rowlock arched lintels, and louvered shutters. The roof has overhanging eaves and the header courses of the American bonding are glazed.

Individual Resource Status: Single Dwelling

Contributing

3812 6th Road North **000-7819-0720** **Other DHR ID#: 000-6891**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry framed by a Colonial Revival style door surround with a molded wood fanlight and pilasters. The windows have rowlock sills and the cornice has a wide entablature.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

6th Street North

3508 6th Street North **000-7819-0143**

Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1970

This split level home is five bays wide and features rowlock sills, and a boxed wood cornice with overhanging eaves.

Individual Resource Status: Single Dwelling

Non-contributing

3515 6th Street North **000-7819-0767** **Other DHR ID#: 000-6726**

Primary Resource Information: Single Dwelling, Stories 2, Style: Other,

The four-bay wide dwelling has a projecting front gable bay with a triangular ventilator in the gable end. The casement windows are grouped and have fixed multi-light transom above them. The non-historic carport is attached to the west of the house by a brick wall.

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 33

3829 6th Street North **000-7819-0762** **Other DHR ID#: 000-7362**

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The L-shaped apartment building has a five-bay wide facade with a brick enclosed vestibule under a half-hipped copper roof. There are Colonial Revival style door surrounds with broken pediments and fluted pilasters. The windows have rowlock sills and at the first story, there are soldier lintels.

Individual Resource Status: Multiple Dwelling

Contributing

7th Street North

3500 7th Street North **000-7819-0557** **Other DHR ID#: 000-6721**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The four-bay wide dwelling features an attached basement level garage and a front gable portico with a segmental soffit. Each dormer contains a 6/6 double-hung sash window.

Individual Resource Status: Single Dwelling

Contributing

3506 7th Street North **000-7819-0558** **Other DHR ID#: 000-6722**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The four-bay wide dwelling features a basement level garage, a chimney with a corbeled cap, and a front gable portico with a segmental soffit.

Individual Resource Status: Single Dwelling

Contributing

3509 7th Street North **000-7819-0590** **Other DHR ID#: 000-6760**

Primary Resource Information: Single Dwelling, Stories 3, Style: Queen Anne,

The three-bay wide, L-shaped house features crosssetted window surrounds, some paired windows, cornerboards, and a half-hipped porch that is three bays wide and two bays deep. The roof is clad in pressed shingles and features wide eaves, exposed rafter tails, and a ridge pole.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Contributing

3514 7th Street North **000-7819-0152**

Primary Resource Information: Single Dwelling, Stories 3, Style: Other, ca 1990

Three bays wide this dwelling features a 1-light transom, a vinyl encased boxed cornice, and overhanging eaves.

Individual Resource Status: Single Dwelling

Non-contributing

3515 7th Street North **000-7819-0589** **Other DHR ID#: 000-6759**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling has a half-hipped front porch supported by square columnettes. There are paired windows in the half-story.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 34

- 3516 7th Street North** **000-7819-0151** **Other DHR ID#: 000-6758**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1995
Three bays wide, this dwelling includes features such as overhanging eaves, and aluminum encased surrounds, sills, and boxed cornice. It has an attached garage and a projecting off-center gable roof section. The entrance is illuminated with a 1-light transom.
Individual Resource Status: Single Dwelling **Non-contributing**
- 3517 7th Street North** **000-7819-0588** **Other DHR ID#: 000-6758**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features paired windows with wide l wood, crosssetted surrounds and a roof with wide eaves and l exposed rafter tails. The half-hipped porch is supported by l tapered wood posts atop panel-faced concrete block piers.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 3710 7th Street North** **000-7819-0629** **Other DHR ID#: 000-6800**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide apartment building features stretcher course l sills, soldier lintels, and a stylized brick stringcourse that l imitates dentil molding. The entry has a fluted door surround l and a front gable hood with slate tile cladding and l scroll-sawn brackets.
Individual Resource Status: Multiple Dwelling **Contributing**
- 3714 7th Street North** **000-7819-0630** **Other DHR ID#: 000-6801**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide apartment building features rowlock sills, l soldier lintels, and a stylized brick stringcourse that l simulates dentil molding. The front gable entry hood has l slate tiles and scroll-sawn brackets.
Individual Resource Status: Multiple Dwelling **Contributing**
- 3718 7th Street North** **000-7819-0631** **Other DHR ID#: 000-6802**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide apartment building features stretcher bond l sills, soldier lintels, and a stylized brick stringcourse that l simulated dentil molding. The front gable entry hood has l slate tiles and scroll-sawn brackets.
Individual Resource Status: Multiple Dwelling **Contributing**
- 3808 7th Street North** **000-7819-0761** **Other DHR ID#: 000-6945**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other,
The five-bay wide ranch house has some paired and some tripled l windows, all with rowlock sills. On the facade, there is a l slightly projecting front gable bay and on the northwest l elevatio, there is an enclosed side porch.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 35

3814 7th Street North **000-7819-0764** **Other DHR ID#: 000-7364**

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The five-bay wide apartment building has an L-shaped footprint and a vestibule with a half-hipped metal roof. There are Colonial Revival style door surrounds and the windows have rowlock sills and soldier lintels.

Individual Resource Status: Multiple Dwelling

Contributing

3822 7th Street North **000-7819-0763** **Other DHR ID#: 000-7363**

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The five bay wide apartment has an L-shaped footprint and an enclosed brick vestibule with a half-hipped metal roof. There are Colonial Revival style door surrounds and the windows have rowlock sills and soldier lintels.

Individual Resource Status: Multiple Dwelling

Contributing

8th Street North

3505 8th Street North **000-7819-0675** **Other DHR ID#: 000-6846**

Primary Resource Information: Single Dwelling, Stories 2, Style: Other,

The four-bay wide vernacular dwelling has a full-width front porch with a shed roof, square-cut balusters, and paired posts at the opening. There is a square, louvered ventilator in the gable end.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

3509 8th Street North **000-7819-0676** **Other DHR ID#: 000-6847**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide bungalow has a full-width front porch with a half-hipped roof supported by rock-faced concrete block piers. The roof has wide eaves.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Non-contributing

3510 8th Street North **000-7819-0583** **Other DHR ID#: 000-6753**

Primary Resource Information: Single Dwelling, Stories 2, Style: Other,

The two-bay wide vernacular dwelling features paired windows, vertical board wood siding beneath the front gable portico, a molded wood cornice, and an octagonal-shaped window next to the front door.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

3514 8th Street North **000-7819-0584** **Other DHR ID#: 000-6754**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The half-hipped porch is supported by rock-faced piers with Tuscan columns. Other details on the three-bay wide house include a centered entry and wide eaves.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 36

3518 8th Street North **000-7819-0585** **Other DHR ID#: 000-6755**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features an off-center entry, 1 square-edged surrounds, and a box bay on the west elevation. 1 The front gable porch is supported by Tuscan columns atop 1 rock-faced concrete block piers.

Individual Resource Status: Single Dwelling **Contributing**

3522 8th Street North **000-7819-0586** **Other DHR ID#: 000-6756**

Primary Resource Information: Single Dwelling, Stories 1, Style: Other,

The two-bay wide vernacular house has a shouldered chimney and 1 windows that have both casement and fixed sashes. There is a 1 three-sided window bay with 1-light casement windows flanking 1 a 16-light fixed center window.

Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**

3524 8th Street North **000-7819-0587** **Other DHR ID#: 000-6757**

Primary Resource Information: Single Dwelling, Stories 2, Style: Queen Anne,

The shed roof front porch has scroll-sawn wood brackets and 1 latticework at the pier foundation. The two-bay wide dwelling 1 has some paired windows at the first story.

Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

Arlington Boulevard

3221 Arlington Boulevard **000-7819-0001**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

Features of the house include rowlock sills and a below ground attached garage.

Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Contributing**

3229 Arlington Boulevard **000-7819-0002**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940

Features of this dwelling include a stone door surround, rowlock sills, soldier lintels, and a gable vestibule.

Individual Resource Status: Single Dwelling **Contributing**

3237 Arlington Boulevard **000-7819-0004**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945

Features of this three bay wide dwelling include wide eaves, rowlock sills, a corbeled entry surround with soldier bricks.

Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 38

- 120 North Irving Street** **000-7819-0027**
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1936*
Three bays wide, this dwelling features rowlock sills, four gable dormers, and a center vestibule. The side porch and porte cochere feature roof balustrades. The house has a heavy dentilated wood cornice with returns.
- Individual Resource Status: Single Dwelling* **Contributing**
Individual Resource Status: Shed **Contributing**
- 136 North Irving Street** **000-7819-0248** *Other DHR ID#: 000-5674*
- Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,*
Set on a panel-faced concrete block foundation and constructed of "econo" bricks, the three-bay house has a centered entry flanked by triple windows with rowlock sills. The shed dormer contains eight eight-light casement windows and is clad in wood shingles.
- Individual Resource Status: Garage* **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 202 North Irving Street** **000-7819-0246** *Other DHR ID#: 000-5672*
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,*
Set on a rock-faced concrete block foundation, the three-bay house has a centered entry flanked by paired windows. The shed dormer contains two six-over-one double-hung wood sash windows and two multi-light wood casement windows. The front eaves are supported by scroll-cut brackets:
- Individual Resource Status: Garage* **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 210 North Irving Street** **000-7819-0244** *Other DHR ID#: 000-5670*
- Primary Resource Information: Single Dwelling,*
Set on a rock-faced concrete block foundation, the two-bay house has an off-center entry covered by a front gable hood and an inset side porch on the north corner. The boxed bay contains an eight-over-one window flanked by six-over one wood sash windows.
- Individual Resource Status: Single Dwelling* **Contributing**
- 214 North Irving Street** **000-7819-0242** *Other DHR ID#: 000-5668*
- Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,*
Set on a rock-faced concrete block foundation, the three-bay house has a projecting front gable vestibule with a steeply pitched roof. The shed roof wall dormer is situated above the triple window on the first story. The brick chimney displays randomly placed rough stone and the gable end of the side porch has half-timbering.
- Individual Resource Status: Garage* **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 39

- 218 North Irving Street** **000-7819-0043** -
Primary Resource Information: **Single Dwelling, Stories 1, Style: Tudor Revival, ca 1940**
Five bays across, this dwelling has features such as soldier lintels, and rowlock sills, and an arched entrance with a stone surround.
Individual Resource Status: **Single Dwelling** **Contributing**
- 224 North Irving Street** **000-7819-0240** *Other DHR ID#:* **000-5666**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Tudor Revival,**
The three-bay house has a centered entry that is topped by a l
segmental arch and is set in a projecting front gable l
vestibule. Paired windows lie to the east of the front door.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Non-contributing**
- 302 North Irving Street** **000-7819-0238** *Other DHR ID#:* **000-5664**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The three-bay frame house has a centered entry framed by l
sidelights and a segmentally arched portico roof. The wide, l
wood cornice has a beaded edge.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 306 North Irving Street** **000-7819-0236** *Other DHR ID#:* **000-5662**
Primary Resource Information: **Single Dwelling, Stories 1, Style: Other,**
Set on a flush concrete block foundation, the three-bay house l
has an inset porch and a molded wood cornice with returns on l
the front gable section. The windows have wide, wood l
surrounds with a beaded edge.
Individual Resource Status: **Single Dwelling** **Contributing**
- 413 North Irving Street** **000-7819-0003** *Other DHR ID#:* **000-5509**
Primary Resource Information: **Single Dwelling, Stories 1, Style: Bungalow/Craftsman, 1924**
Wood Frame Structural System with Aluminum Siding, Concrete Block Foundation, Hipped Roof with Asphalt
Shingle
Individual Resource Status: **Single Dwelling** **Contributing**
- 420 North Irving Street** **000-7819-0140**
Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival, ca 1940**
This three bay wide dwelling includes a Colonial Revival door surround with a broken pediment, rowlock sills,
overhanging eaves, and a boxed
wood cornice.
Individual Resource Status: **Multiple Dwelling** **Contributing**
- 508 North Irving Street** **000-7819-0373** *Other ID#* **000-6347**
Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 *Foundation:* Solid Concrete Block, Rock-Faced
Structural System: Frame Wood German Siding
Window(s): Sash, double-hung Wood 1/1
Door(s): Single Leaf Wood 1-light
Roof: Gable, Side Asphalt Shingle
Porch: 1-story, 3-bay Wood Post, Square
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 40

512 North Irving Street **000-7819-0374** **Other ID#** **000-6348**

Single Dwelling 1915-1930 Colonial Revival 2.0 *Foundation:* Solid Concrete Parged

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Porch: 1-story, 1-bay Wood Post, Square

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

516 North Irving Street **000-7819-0375** **Other ID#** **000-6349**

Single Dwelling 1915-1930 Bungalow/Craftsman 2.5 *Foundation:* Solid Concrete Parged

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped, Pyramidal Asphalt Shingle

Chimney: Exterior end Brick Corbeled/Shouldered

Porch: 1-story, 2-bay Wood Craftsman

Dormer: Hipped Asphalt Shingle

Individual Resource Status: **Garage**

Non-contributing

Individual Resource Status: **Single Dwelling**

Contributing

520 North Irving Street
000-7819-0376 **Other ID#** **000-6350**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Multi-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Porch: 1-story, 3-bay Wood Craftsman

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

606 North Irving Street **000-7819-0377** **Other ID#** **000-6351**

Church

1920s Colonial Revival 2.0 *Foundation:* Solid Brick Flemish Bond

North Irving Street

Structural System: Masonry Brick Flemish Bond

Window(s): Fixed, Lancet Stone Stained Glass

Door(s): Double leaf Wood 1-light

Roof: Gable, Cross Slate Shingle

Chimney: Exterior end Brick Cap, Concrete

Chimney: Interior end Brick Cap, Concrete

Chimney: Central interior Brick Cap, Concrete

Individual Resource Status: **Church**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 41

620 North Irving Street **000-7819-0409** *Other ID#* **Single Dwelling 1929 Bungalow/Craftsman 1.5**

Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Aluminum Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled/Shoulderd

Porch: 1-story, 3-bay Wood Post, Square

Dormer: Shed Aluminum Siding

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Gazebo**

Non-contributing

624 North Irving Street

000-7819-0408 *Other ID#* **000-6382**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 6/1

Window(s): Casement Wood 6-light

Door(s): Single Leaf Wood Multi-light

Roof: Gable, Front Asphalt Shingle

Chimney: Exterior end Brick Corbeled/Shoulderd

Porch: 1-story, 2-bay Wood Post, Square

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

630 North Irving Street

000-7819-0407 *Other ID#* **000-6381**

Single Dwelling 1905-1920 Colonial Revival 2.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Aluminum Siding

Window(s): Sash, double-hung Wood 8/8

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped, Pyramidal Asphalt Shingle

Chimney: Central interior Brick Corbeled

Porch: 1-story, 3-bay Wood Column, Tuscan

Dormer: Hipped Aluminum Siding

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

702 North Irving Street

000-7819-0406 *Other ID#* **000-6380**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 *Foundation:* Solid Concrete Block, Panel-Faced

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Multi-light

Roof: Gable, Front Asphalt Shingle

Chimney: Central interior Brick Corbeled

Porch: 1-story, 3-bay Wood Craftsman

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 42

708 North Irving Street

000-7819-0405 Other ID# **000-6379**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Vinyl 6/1

Window(s): Sash, double-hung Vinyl 4/1

Window(s): Fixed Vinyl 6-light

Door(s): Single Leaf Wood Multi-light

Roof: Gable, Front Asphalt Shingle

Chimney: Exterior end Brick Corbeled/Shouldered

Porch: 1-story, 1-bay Wood Piers

Individual Resource Status: **Single Dwelling**

Contributing

714 North Irving Street

000-7819-0404 Other ID# **000-6378**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Multi-light

Roof: Gable, Side Asphalt Shingle

Chimney: Central interior Brick Corbeled

Porch: 1-story, 3-bay Wood Post, Square

Dormer: Gable Wood Weatherboard

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

720 North Irving Street

000-7819-0403 Other ID# **000-6377**

Single Dwelling 1910-1925 Colonial Revival 1.0 *Door(s):* Single Leaf None Listed Not visible

Foundation: Solid Concrete Block, Rock-Faced

Porch: 1-story, 3-bay Wood Column, Tuscan

Roof: Hipped Metal Standing Seam

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/1

Individual Resource Status: **Single Dwelling**

Contributing

802 North Irving Street

000-7819-0402 Other ID# **000-6376**

Single Dwelling 1915-1930 Bungalow/Craftsman 2.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Concrete Stucco

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Multi-light

Roof: Hipped, Pyramidal Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Porch: 1-story, 2-bay Wood Craftsman

Dormer: Hipped Asphalt Shingle

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 43

808 North Irving Street

000-7819-0401 Other ID# **000-6375**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 9/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Interior end Brick Corbeled

Porch: 1-story, 3-bay Wood Piers

Dormer: Gable Wood Weatherboard

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Non-contributing

Contributing

812 North Irving Street

000-7819-0400 Other ID# **000-6374**

Single Dwelling 1900-1915 Colonial Revival 1.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Weatherboard

Walls: Frame Wood Shingle

Window(s): Casement Metal 1-light

Window(s): Casement Wood Multi-light

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Cross Asphalt Shingle

Chimney: Central interior Brick Cap, Metal

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Contributing

Contributing

822 North Irving Street

000-7819-0399 Other ID# **000-6373**

Single Dwelling 1924 Colonial Revival 1.5 *Chimney:* Interior end Brick Corbeled

Door(s): Single Leaf Wood Multi-light

Foundation: Solid Concrete Block, Rock-Faced

Porch: 1-story, 1-bay Wood Column, Tuscan

Roof: Gambrel, Cross Asphalt Shingle

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Individual Resource Status: **Shed**

Individual Resource Status: **Single Dwelling**

Non-contributing

Contributing

904 North Irving Street

000-7819-0398 Other ID# **000-6372**

Single Dwelling 1900 Colonial Revival 2.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Metal Standing Seam

Chimney: Central interior Brick Corbeled

Porch: 1-story, 3-bay Wood Column, Tuscan

Dormer: Hipped Wood Weatherboard

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Contributing

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 44

910 North Irving Street

000-7819-0397 Other ID# **000-6371**

Single Dwelling 1926 Colonial Revival 2.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped, Pyramidal Asphalt Shingle

Chimney: Central interior Brick Corbeled

Porch: 1-story, 3-bay Wood Column, Tuscan

Dormer: Hipped Asbestos Shingle

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

914 North Irving Street

000-7819-0396 Other ID# **000-6370**

Single Dwelling 1915-1930 Bungalow/Craftsman 2.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Multi-light

Roof: Hipped, Pyramidal Asphalt Shingle

Chimney: Central interior Brick Corbeled

Porch: 1-story, 3-bay Concrete Post, Stucco

Dormer: Hipped Vinyl Siding

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

920 North Irving Street

000-7819-0395 Other ID# **000-6369**

Single Dwelling 1915-1930 Bungalow/Craftsman 2.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Multi-light

Roof: Hipped Asphalt Shingle

Chimney: Central interior Brick Corbeled

Porch: 1-story, 3-bay Wood Post, Square

Dormer: Hipped Vinyl Siding

Individual Resource Status: **Shed**

Non-contributing

Individual Resource Status: **Single Dwelling**

Contributing

924 North Irving Street

000-7819-0212

Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman, ca 1925**

Three bays wide, this dwelling is constructed of rock-faced concrete blocks. It is capped with a cross gable roof clad in asphalt shingles. It

features wide eaves, stucco clad gables, and square-edged surrounds and sills. The porch rests on a pier foundation. The entry is illuminated with

a lancet transom. The roof features a molded wood cornice.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 45

North Ivy Street

502 North Ivy Street

000-7819-0351 Other ID# **000-6307**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood 15-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 3-bay Wood Post, Square

Dormer: Gable Vinyl Siding

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

505 North Ivy Street

000-7819-0370 Other ID# **000-6344**

Single Dwelling 1930s Colonial Revival 1.0 *Foundation:* Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Casement Wood 1-light

Door(s): Single Leaf Wood 1-light

Roof: Gable, Cross Asphalt Shingle

Chimney: Exterior, Front Brick Shouldered

Chimney: Central interior Brick Stretcher Bond

Porch: 1-story Wood Enclosed

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

506 North Ivy Street

000-7819-0350 Other ID# **000-6306**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Concrete Stucco

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood 15-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 1-bay Wood Craftsman

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 46

509 North Ivy Street

000-7819-0369 Other ID# **000-6343**

Single Dwelling 1949 ca Colonial Revival 1.5 *Foundation: Solid Brick Stretcher Bond*

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Porch: 1-story, 2-bay Wood Post, Square

Dormer: Gable Wood Weatherboard

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

510 North Ivy Street

000-7819-0349 Other ID# **000-6305**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation: Solid Concrete Block, Rock-Faced*

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf None Listed Not visible

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 3-bay Brick Craftsman

Dormer: Gable Asbestos Shingle

Individual Resource Status: Single Dwelling

Contributing

513 North Ivy Street

000-7819-0368 Other ID# **000-6342**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation: Solid Concrete Block, Panel-Faced*

Structural System: Frame Concrete Formstone

Window(s): Sash, double-hung Wood 7/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled/Shouldered

Porch: 1-story, 3-bay Concrete Piers

Dormer: Shed Wood German Siding

Individual Resource Status: Single Dwelling

Contributing

514 North Ivy Street

000-7819-0348 Other ID# **000-6304**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation: Solid Concrete Block, Panel-Faced*

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Metal 1/1

Door(s): Single Leaf Wood Flush

Roof: Gable, Side Asphalt Shingle

Porch: Enclosed Vinyl Siding

Chimney: Exterior end Brick Shouldered

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Non-contributing

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 47

517 North Ivy Street

000-7819-0367 Other ID# 000-6341

Single Dwelling 1949 ca Colonial Revival 2.0 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

518 North Ivy Street

000-7819-0347 Other ID# 000-6303

Single Dwelling 1924 Bungalow/Craftsman 1.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 3-bay Wood Column, Tuscan

Dormer: Gable Vinyl Siding

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

521 North Ivy Street

000-7819-0366 Other ID# 000-6340

Single Dwelling 1949 Tudor Revival 1.5 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior, Front Brick Shouldered

Porch: Stoop Brick Hood

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

522 North Ivy Street

000-7819-0346 Other ID# 000-6302

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 Chimney: Exterior end Brick Shouldered

Door(s): Single Leaf Wood Paneled w/ lights

Foundation: Solid Concrete Block, Rock-Faced

Porch: 1-story, 3-bay Wood Craftsman

Roof: Gable, Front Asphalt Shingle

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/1

Dormer: Gable Wood Shingle

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 48

525 North Ivy Street

000-7819-0365 Other ID# **000-6339**

Single Dwelling 1949 ca Tudor Revival 1.5 *Foundation:* Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Casement Wood Multi-light

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior, Front Brick Stretcher Bond

Porch: Stoop Concrete Hood

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

526 North Ivy Street

000-7819-0345 Other ID# **000-6301**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood 15-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Porch: 1-story, 1-bay Wood Craftsman

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

600 North Ivy Street

000-7819-0357 Other ID# **000-6314**

Single Dwelling 1935-1940 Colonial Revival 1.0 *Foundation:* Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Stone Shouldered

Dormer: Gable Wood Weatherboard

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

602 North Ivy Street

000-7819-0358 Other ID# **000-6315**

Single Dwelling 1930-1945 Colonial Revival 1.5 *Foundation:* Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 2-bay Wood Post

Dormer: Gable Aluminum Siding

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 49

604 North Ivy Street

000-7819-0359 Other ID# **000-6316**

Single Dwelling 1930-1945 Colonial Revival 1.5 *Foundation: Solid Brick Stretcher Bond*

Structural System: Masonry Stone Facing

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Dormer: Gable Wood Weatherboard

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

606 North Ivy Street

000-7819-0360 Other ID# **000-6317**

Single Dwelling 1930-1945 Tudor Revival 1.5 *Foundation: Solid Brick Stretcher Bond*

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Window(s): Casement Wood Diamond Pane

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Porch: 1-story, 2-bay Wood Post

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

608 North Ivy Street

000-7819-0361 Other ID# **000-6318**

Single Dwelling 1930-1945 Colonial Revival 1.5 *Foundation: Solid Brick Stretcher Bond*

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Dormer: Gable Wood Weatherboard

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

620 North Ivy Street

000-7819-0778 Other ID# **000-6319**

Single Dwelling 1921 Bungalow/Craftsman 2.0 *Foundation: Solid Concrete Block, Panel-Faced*

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Metal 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Front Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 1-bay Wood Craftsman

Dormer: Hipped Vinyl Siding

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 50

625 North Ivy Street

000-7819-0378 Other ID# 000-6352

Single Dwelling 1923 ca Colonial Revival 2.0 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Concrete Stucco

Window(s): Sash, double-hung Wood 6/1

Window(s): Sash, double-hung Wood 4/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Exterior Rear Brick Corbeled/Shouldered

Porch: 1-story, 1-bay Wood Column, Tuscan

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

626 North Ivy Street

000-7819-0362 Other ID# 000-6320

Single Dwelling 1923 Bungalow/Craftsman 2.0 Chimney: Central interior Brick Corbeled Cap

Door(s): Single Leaf Wood Paneled w/ lights

Dormer: Hipped Wood Shingle

Foundation: Solid Concrete Block, Panel-Faced

Porch: 1-story, 1-bay Wood Craftsman

Roof: Gable, Front Asphalt Shingle

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/1

Dormer: Shed Wood Shingle

Walls: Frame Wood Shingle

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

632 North Ivy Street

000-7819-0363 Other ID# 000-6321

Single Dwelling 1920-1925 Colonial Revival 2.0 Foundation: Solid Concrete Parged

Structural System: Frame Concrete Stucco

Window(s): Sash, double-hung Wood 4/1

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Jerkinhead Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Portico: 1-story, 1-bay Wood Bracketed

Dormer: Shed Concrete Stucco

Individual Resource Status: **Garage**

Non-contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 51

633 North Ivy Street

000-7819-0379 Other ID# **000-6353**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Aluminum Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Multi-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 3-bay Wood Craftsman

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Non-contributing

Contributing

700 North Ivy Street

000-7819-0364 Other ID# **000-6322**

Single Dwelling 1926 Colonial Revival 2.0 *Foundation:* Solid Concrete Block, Panel-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood 15-light

Roof: Gambrel, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled/Shouldered

Portico: 1-story, 1-bay Wood Bracketed

Dormer: Shed Vinyl Siding

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Contributing

Contributing

703 North Ivy Street

000-7819-0380 Other ID# **000-6354**

Single Dwelling 1915-1930 Bungalow/Craftsman 2.0 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Vinyl 1/1

Window(s): Casement Vinyl 1-light

Door(s): Single Leaf Wood Paneled

Roof: Hipped, Pyramidal Asphalt Shingle

Chimney: Central interior Brick Corbeled

Porch: 1-story, 2-bay Wood Post, Square

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Contributing

Contributing

706 North Ivy Street

000-7819-0410 Other ID# **000-6384**

Single Dwelling 1915-1930 Other 2.0 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Asbestos Shingle

Walls: Frame Aluminum Siding

Window(s): Sash, double-hung Wood 6/6

Window(s): Sash, double-hung Metal 1/1

Door(s): Single Leaf Wood Vertical Board

Roof: Gable, Front Asphalt Shingle

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 52

707 North Ivy Street

000-7819-0381 Other ID# 000-6355

Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 Foundation: Solid Concrete Block, Panel-Faced

Structural System: Frame Wood Shingle

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Wood Shingle

Porch: 1-story, 2-bay Wood Post, Square

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Non-contributing

Contributing

712 North Ivy Street

000-7819-0411 Other ID# 000-6385

Single Dwelling 1910-1925 Bungalow/Craftsman 2.0 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Column, Tuscan

Dormer: Hipped Asbestos Shingle

Individual Resource Status: **Shed**

Individual Resource Status: **Single Dwelling**

Non-contributing

Contributing

713 North Ivy Street

000-7819-0382 Other ID# 000-6356

Single Dwelling 1915-1925 Bungalow/Craftsman 2.0 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick 6-Course Flem Bond

Walls: Frame Wood Shingle

Window(s): Sash, double-hung Wood 1/1, Paired

Door(s): Single Leaf Wood Paneled

Roof: Hipped Asphalt Shingle

Chimney: Exterior end Brick Corbeled/Shouldered

Porch: 1-story, 3-bay Wood Post, Square

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Non-contributing

Contributing

719 North Ivy Street

000-7819-0383 Other ID# 000-6357

Single Dwelling 1940s Other 2.0 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Casement Wood 1-light

Door(s): Single Leaf Wood 1-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 1-bay Brick Recessed

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Contributing

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 53

720 North Ivy Street

000-7819-0412 Other ID# **000-6386**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 Foundation: Solid Concrete Block, Panel-Faced

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Window(s): Casement Wood 6-light

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Porch: 1-story, 1-bay Wood Post, Square

Dormer: Gable Asbestos Shingle

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Contributing

Contributing

723 North Ivy Street

000-7819-0384 Other ID# **000-6358**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Vinyl 6/1, Paired

Window(s): Sash, double-hung Vinyl 1/1, Paired

Door(s): Single Leaf Wood Multi-light

Roof: Gable, Front Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 3-bay Wood Column, Tuscan

Dormer: Shed Vinyl Siding

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Contributing

Contributing

724 North Ivy Street

000-7819-0413 Other ID# **000-6387**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Concrete Stucco

Window(s): Sash, double-hung Wood 6/1

Window(s): Sash, double-hung Wood 8/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Porch: 1-story, 3-bay Concrete Craftsman

Dormer: Gable Concrete Stucco

Individual Resource Status: **Garage**

Individual Resource Status: **Single Dwelling**

Contributing

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 54

727 North Ivy Street

000-7819-0385 Other ID# **000-6359**

Single Dwelling 1915-1930 Colonial Revival 2.5 *Foundation: Solid Concrete Parged*

Structural System: Frame Wood Aluminum Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped, Pyramidal Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Porch: 1-story, 1-bay Wood Post, Square

Dormer: Hipped Aluminum Siding

Individual Resource Status: Shed

Individual Resource Status: Single Dwelling

Contributing

Contributing

802 North Ivy Street

000-7819-0414 Other ID# **000-6388**

Single Dwelling 1910-1925 Colonial Revival 2.0 *Foundation: Solid Concrete Block, Rock-Faced*

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Metal 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Front Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 2-bay Wood Column, Tuscan

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

806 North Ivy Street

000-7819-0415 Other ID# **000-6389**

Single Dwelling 1930-1939 Colonial Revival 2.0 *Foundation: Solid Brick Stretcher Bond*

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 2-bay Brick Piers

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

807 North Ivy Street

000-7819-0386 Other ID# **000-6360**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 *Foundation: Solid Concrete Block, Rock-Faced*

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 12/1

Door(s): Single Leaf Wood Multi-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Porch: 1-story, 3-bay Wood Post, Square

Individual Resource Status: Shed

Individual Resource Status: Single Dwelling

Non-contributing

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 55

810 North Ivy Street

000-7819-0416 Other ID# **000-6390**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Aluminum Siding

Window(s): Sash, double-hung Metal 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 1-bay Concrete Craftsman

Dormer: Gable Wood Shingle

Walls: Frame Wood Shingle

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

811 North Ivy Street

000-7819-0387 Other ID# **000-6361**

Single Dwelling 1940-1949 Colonial Revival 1.5 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6, Paired

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Porch: 1-story, 1-bay Wood Post, Square

Dormer: Gable Vinyl Siding

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

812 North Ivy Street

000-7819-0417 Other ID# **000-6391**

Single Dwelling 1920-1935 Colonial Revival 1.5 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Metal 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled/Shouldered

Portico: 1-story, 1-bay Wood Post, Square

Dormer: Hipped Asbestos Shingle

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 56

819 North Ivy Street

000-7819-0388 Other ID# **000-6362**

Single Dwelling 1915-1930 Bungalow/Craftsman 2.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled

Roof: Hipped, Pyramidal Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 2-bay Wood Craftsman

Dormer: Hipped Asbestos Shingle

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

825 North Ivy Street

000-7819-0389 Other ID# **000-6363**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 Foundation: Solid Concrete Block, Panel-Faced

Structural System: Frame Wood Shingle

Window(s): Sash, double-hung Wood Multi-light

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled

Porch: 1-story, 2-bay Wood Post, Square

Individual Resource Status: **Shed**

Non-contributing

Individual Resource Status: **Single Dwelling**

Contributing

900 North Ivy Street

000-7819-0162

Primary Resource Information: **Multiple dwelling, Stories 3, Style: Other, ca 1945**

This building is three bays wide and features a rowlock sills. The first story entry is illuminated with 10-light sidelights using glass blocks.

The second story entryway uses a 1-light transom, and the doorway on the uppermost story uses a 4-light transom.

Individual Resource Status: **Multiple Dwelling**

Contributing

903 North Ivy Street

000-7819-0390 Other ID# **000-6364**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.0 Foundation: Solid Concrete Block

Structural System: Frame Wood German Siding

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Front Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Chimney: Central interior Brick Corbeled

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 57

904 North Ivy Street

000-7819-0418 Other ID# **000-6392**

Multiple dwelling 1935-1949 Colonial Revival 2.0 *Foundation: Solid Brick Stretcher Bond*

Structural System: Masonry Brick 6-Course Flem Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Stretcher Bond

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

909 North Ivy Street

000-7819-0391 Other ID# **000-6365**

Single Dwelling 1900-1915 Colonial Revival 2.0 *Foundation: Solid Concrete Block, Rock-Faced*

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Window(s): Casement Wood 6-light

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Front Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Column, Tuscan

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

910 North Ivy Street

000-7819-0419 Other ID# **000-6393**

Single Dwelling 1929 Bungalow/Craftsman 1.5 *Foundation: Solid Concrete Block, Rock-Faced*

Structural System: Frame Wood Aluminum Siding

Window(s): Sash, double-hung Wood 9/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Central interior Brick Cap, Concrete

Porch: 1-story, 2-bay Wood Post, Square

Dormer: Gable Aluminum Siding

Individual Resource Status: Single Dwelling

Contributing

913 North Ivy Street

000-7819-0392 Other ID# **000-6366**

Single Dwelling 1915-1930 Bungalow/Craftsman 2.5 *Foundation: Solid Concrete Block, Rock-Faced*

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped, Pyramidal Metal Shingle, Pressed

Chimney: Central interior Brick Corbeled

Porch: 1-story, 3-bay Wood Post, Square

Dormer: Hipped Asbestos Shingle

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 58

914 North Ivy Street

000-7819-0420 Other ID# **000-6394**

Single Dwelling 1915-1930 Tudor Revival 2.0 *Foundation:* Solid Concrete Block, Rock-Faced
Structural System: Frame Wood Aluminum Siding
Window(s): Sash, double-hung Metal 1/1
Door(s): Single Leaf Wood 15-light
Roof: Gable, Front Asphalt Shingle
Chimney: Central interior Brick Corbeled Cap
Porch: 1-story, 2-bay Wood Column, Tuscan
Dormer: Shed Aluminum Siding
Individual Resource Status: **Single Dwelling** **Contributing**

917 North Ivy Street

000-7819-0393 Other ID# **000-6367**

Single Dwelling 1900-1915 Colonial Revival 2.0 *Foundation:* Solid Concrete Block, Rock-Faced
Structural System: Frame Concrete Stucco
Window(s): Sash, double-hung Wood 6/1
Door(s): Single Leaf Wood Paneled
Roof: Gable, Front Asphalt Shingle
Porch: 1-story, 3-bay Wood Column, Tuscan
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**

923 North Ivy Street

000-7819-0394 Other ID# **000-6368**

Single Dwelling 1900-1915 Colonial Revival 1.0 *Foundation:* Not Visible None Listed Not visible
Door(s): Single Leaf Wood Paneled w/ lights
Structural System: Frame Wood Weatherboard
Roof: Gambrel, Cross Asphalt Shingle
Window(s): Sash, double-hung Wood Multi-light
Chimney: Central interior Brick Corbeled
Porch: 1-story, 3-bay Wood Column, Tuscan
Individual Resource Status: **Single Dwelling** **Contributing**

928 North Ivy Street

000-7819-0421 Other ID# **000-6395**

Single Dwelling 1906 Colonial Revival 2.0 *Foundation:* Solid Concrete Block, Rock-Faced
Structural System: Frame Concrete Stucco
Window(s): Sash, double-hung Metal 1/1
Window(s): Sash, double-hung Wood 1/1
Window(s): Casement Wood 1-light
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Hipped Asphalt Shingle
Chimney: Central interior Brick Corbeled Cap
Porch: 1-story, 3-bay Wood Craftsman
Dormer: Hipped Concrete Stucco
Individual Resource Status: **Single Dwelling** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 59

North Jackson Street

- 20 North Jackson Street** **000-7819-0775**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Three bays wide, this brick dwelling is constructed in a 6-course Flemish bond. It sits on a stretcher-bond brick foundation, and is capped with a side gable roof covered in asphalt shingles. The dwelling features a projecting center brick vestibue and a Colonial Revival door surround with a broken pediment. Other features of the house include rowlock sills, a flush fascia board, an attached garage, and a roof-top balcony on a side porch.
Individual Resource Status: Single Dwelling **Contributing**
- 31 North Jackson Street** **000-7819-0018**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1970
This dwelling exhibits rowlock sills and a boxed cornice.
Individual Resource Status: Single Dwelling **Non-contributing**
- 100 North Jackson Street** **000-7819-0030**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Five bays wide, this Cape Cod dwelling features overhanging eaves, cast concrete sills, and three gable dormers on the facade. The center entry features a Colonial Revival door surround with fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**
- 103 North Jackson Street** **000-7819-0022**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
This five bay wide dwelling features rowlock sills, a wide fascia board, a molded wood cornice with returns, and a side screened porch.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 104 North Jackson Street** **000-7819-0031**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1980
This dwelling features wide overhanging eaves and has one roll-up flush wood garage door.
Individual Resource Status: Single Dwelling **Non-contributing**
- 107 North Jackson Street** **000-7819-0023**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Three bays wide, this dwelling features rowlock sills, a wide fascia board, and a wood cornice with returns. The side porch is enclosed with aluminum siding and features a roof balustrade.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 60

- 108 North Jackson Street** **000-7819-0032** -
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1990
Features of this five bay wide dwelling include cast concrete jack arch lintels with keystones, rowlock sills, overhanging eaves, and a heavy molded dentilated cornice. The center entrance is recessed, is illuminated with 5-light sidelights, and features a Colonial Revival door surround with fluted pilasters and a molded entablature.
Individual Resource Status: Single Dwelling **Non-contributing**
Individual Resource Status: Garage **Non-contributing**
- 114 North Jackson Street** **000-7819-0226** *Other DHR ID#: 000-5652*
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a rock-faced concrete blockk foundation, the three-bay l house has a side passage entry and double-hung windows with l square-edged wood sills. The porch has paired wood columns l with decorative detailing atop concrete block piers and the l arches of the porch have wood keystones. The hipped roof has l scroll-cut wood brackets, a boxed cornice, and wide, l overhanging eaves.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 117 North Jackson Street** **000-7819-0024**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1990
Five bays wide, this dwelling features overhanging eaves with a dentilated cornice, and drip moldings over the first story windows. The center entry is illuminated with a 5-light transom and 3-light and dado panel sidelights.
Individual Resource Status: Single Dwelling **Non-contributing**
- 118 North Jackson Street** **000-7819-0033**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Features of this three bay wide dwelling include rowlock sills, soldier lintels, overhanging eaves, and a recessed door.
Individual Resource Status: Single Dwelling **Contributing**
- 130 North Jackson Street** **000-7819-0280** *Other DHR ID#: 000-5707*
Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,
The four-bay house has an off-center entry set in a projecting l vestibule with a sweeping, hipped roof. The Jerkinhead roof l has wide eaves with decorative brackets. Tudor Revival l detailing is evident on the Craftsman style dwelling.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 61

- | | | |
|---|----------------------|--------------------------------|
| 131 North Jackson Street | 000-7819-0222 | Other DHR ID#: 000-5648 |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,</i>
Set on a standard brick foundation and constructed of "econo" bricks, the 1
three-bay house has wide, wood door and window surrounds and a patterned 1
soldier beltcourse. The porch is supported at the center by two wood square 1
columns and at the ends by "econo" brick piers. The dormer contains a pair 1
of six-over-one double-hung windows. The upper story of the facade is clad 1
in slate shingles. A boxed cornice, cornice returns and overhanging eaves 1
detail the side gable roof. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 134 North Jackson Street | 000-7819-0282 | Other DHR ID#: 000-5709 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
Set on a parged, concrete block foundation, the three-bay 1
house has a centered entry and flanking windows surrounded by 1
wood trim with a beaded edge. The dormer, containing two 1
six-over-one double-hung wood sash windows, is set on the side 1
gable roof that has wide eaves. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 138 North Jackson Street | 000-7819-0258 | Other DHR ID#: 000-5684 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
Set on a rock-faced concrete block foundation, the two-bay house has a shed wall dormer with two sets of paired
windows. The side gable roof has decorative wood brackets. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| 200 North Jackson Street | 000-7819-0038 | |
| <i>Primary Resource Information: Single Dwelling, Stories 1, Style: Colonial Revival, ca 1945</i>
Three bays across, this dwelling features rowlock sills. It has a one-story gable roof frame addition on the side
elevation. The center recessed door features a paneled reveal, and a Colonial Revival surround with canted fluted
pilasters and a denticulated entablature. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 201 North Jackson Street | 000-7819-0216 | Other DHR ID#: 000-5642 |
| <i>Primary Resource Information: Single Dwelling, Stories 2.5, Style: Colonial Revival, ca. 1920</i>
Brick laid in 6-course American. Bond, Side Gable Roof with Slate Tiles | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| 204 North Jackson Street | 000-7819-0284 | Other DHR ID#: 000-5711 |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,</i>
Set on a panel-faced concrete block foundation, the two-bay 1
house has a side passage entry framed by sidelights. The 1
windows are framed by wide, wood trim with an outside beaded 1
edge. The dormer contains two six-light metal casement 1
windows. There is a one-story, one-bay frame wing at the east 1
corner of the facade. | | |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 62

- 205 North Jackson Street** **000-7819-0040** -
Primary Resource Information: Single Dwelling, Stories 3, Style: Other, ca 1975
Four bays wide, this dwelling features rowlock sills, and a brick porch foundation.
Individual Resource Status: Single Dwelling **Non-contributing**
Individual Resource Status: Garage **Non-contributing**
- 210 North Jackson Street** **000-7819-0039**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Features of this three bay wide dwelling include soldier beltcourse, rowlock sills, and a molded wood denticulated cornice with returns. The central entry features 4-light 1-panel sidelights and a sunburst transom.
Individual Resource Status: Single Dwelling **Contributing**
- 211 North Jackson Street** **000-7819-0041**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Features of this three bay wide dwelling include rowlock sills, a denticulated wood cornice, a soldier course door lintel, and three-pane sidelights.
Individual Resource Status: Single Dwelling **Contributing**
- 216 North Jackson Street** **000-7819-0260** *Other DHR ID#: 000-5686*
Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,
Set on a flush concrete block foundation, the three-bay house has a projecting one-story side bay with a pressed tin roof. There is a wood trim between the foundation and the first story and the fenestration has wide, wood surrounds. The side gable roof has wide, overhanging eaves with exposed principle rafters.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 217 North Jackson Street** **000-7819-0231** *Other DHR ID#: 000-5675*
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay house has a centered entry with a keyhole shaped light at the center and is framed by a three-light transom and sidelights. The entry is set in a polygonal shaped porch that is flanked by polygonal projections. The wide wood window surrounds have a beaded edge and the roof has an enclosed cornice.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 224 North Jackson Street** **000-7819-0249** *Other DHR ID#: 000-5675*
Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,
The two-bay house is built in the four-square form and has a one-story, one-bay frame wing on the southeast elevation. The windows are grouped in two's and three's and the side passage entry is framed by one-light sidelights. The hipped roof has wide, enclosed eaves and the hipped-roof dormer contains three three-light casement windows.
Individual Resource Status: Garage **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 63

- | | | |
|---|----------------------|--------------------------------|
| 225 North Jackson Street | 000-7819-0215 | Other DHR ID#: 000-5640 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay house has a symmetrical facade and a side gable roof with wide, overhanging eaves. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| <i>Individual Resource Status: Shed</i> | | |
| | | Contributing |
| | | Non-contributing |
| 230 North Jackson Street | 000-7819-0050 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940</i>
Features of this three bay wide dwelling include rowlock sills, a molded wood boxed cornice, and a round arched doorway. The front cross gable has a sloped roof. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing |
| 231 North Jackson Street | 000-7819-0229 | Other DHR ID#: 000-5655 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
Set on a rock-faced concrete block foundation, the three-bay house has a centered entry flanked by paired windows. the side gable roof has wide eaves. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| <i>Individual Resource Status: Garage</i> | | |
| | | Contributing |
| | | Non-contributing |
| 300 North Jackson Street | 000-7819-0256 | Other DHR ID#: 000-5682 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The two-bay brick dwelling has a side passage entry framed by a Colonial Revival door surround with a heavy entablature. The projecting three-sided window bay has a heavy, molded cornice and is set atop a brick base. | | |
| <i>Individual Resource Status: Garage</i> | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing |
| | | Contributing |
| 301 North Jackson Street | 000-7819-0049 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1945</i>
This dwelling measures five bays across with a central entrance. Two shed-roof dormers are located on the facade. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing |
| 304 North Jackson Street | 000-7819-0254 | Other DHR ID#: 000-5680 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay house has a centered entry and a centered front gable porch with half-timbering in the gable end. The fenestration has wide, wood surrounds with a beaded edge. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing |
| 305 North Jackson Street | 000-7819-0225 | Other DHR ID#: 000-5651 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The two-bay house has a side passage entry framed by a door surround with fluted pilasters and a pediment with dentil molding. The projecting front gable section has paired windows on the first story. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 64

- 310 North Jackson Street** **000-7819-0048** -
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1970
Measuring four bays wide, this dwelling includes features such as rowlock sills, wide eaves, and a boxed cornice. The facade has a front cross gable clad with vinyl siding.
Individual Resource Status: Single Dwelling **Non-contributing**
- 311 North Jackson Street** **000-7819-0223** *Other DHR ID#: 000-5649*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick house has a centered entry sheltered by a 1 front gable portico with a segmental arch. There is a 1 one-story, one-bay brick wing on the northwest side of the 1 house and a garage on the southeast elevation that is attached 1 via a breezeway. The windows have rowlock sills and soldier 1 lintels and there are two front gable wall dormers on the 1 facade.
Individual Resource Status: Single Dwelling **Contributing**
- 402 N. Jackson Street** **000-7819-0021** *Other DHR ID#: 000-5638*
Primary Resource Information: Single Dwelling, Stories 1.5, Style: Tudor Revival, 1926
Wood Frame Structural System with Aluminum Siding, Concrete Block Foundation, Front Gable Roof with Asphalt Shingle
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 410 North Jackson Street** **000-7819-0061**
Primary Resource Information: Single Dwelling, Stories 3, Style: Other, ca 1990
Featuring tudor details, this dwelling is four bays wide with an exterior front chimney and a sloping cross gable roof. The roof features overhanging eaves and cornice returns. The window and door surrounds are square-edged.
Individual Resource Status: Single Dwelling **Non-contributing**
- 418 North Jackson Street** **000-7819-0457** *Other DHR ID#: 000-6616*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The entry of the four-bay wide dwelling is framed by a wide 1 wood door surround with ears and the windows have rowlock 1 brick sills. The second story is slightly projecting, 1 creating an overhang from which two acorn drops are suspended. 1
Other details include a rowlock water table, a dentiled brick 1 cornice beneath the second story overhang, and a 6/6 window in 1 the dormer above the attached garage.
Individual Resource Status: Single Dwelling **Contributing**
- 419 North Jackson Street** **000-7819-0453** *Other DHR ID#: 000-6612*
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,
The entry of the four bay wide dwelling is framed by 1 pilasters. Brick detailing includes a rowlock watertable, 1 rowlock sills, and soldier lintels. Below some of the 1 windows, there are inset wood panels.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 65

- 420 North Jackson Street** **000-7819-0772** -
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1990
Three bays wide, this wood frame dwelling sits on a solid foundation and is capped with a side gable roof with asphalt shingles. It is clad with aluminum siding and brick facing. It features a large Colonial Revival door surround with a broken pediment and fluted pilasters. Other features include quoins on the facade, overhanging eaves, and a boxed cornice.
Individual Resource Status: Single Dwelling **Non-contributing**
- 425 North Jackson Street** **000-7819-0454** *Other DHR ID#: 000-6613*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The entry of the four bay wide house is framed by a Colonial Revival style door surround with a broken pediment and pilasters. Other details include a rowlock watertable, rowlock sills, soldier lintels, cornice returns and a three-sided window bay.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 429 North Jackson Street** **000-7819-0455** *Other DHR ID#: 000-6614*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
Brick detailing on the three-bay wide dwelling includes a basketweave water table, rowlock sills, and soldier lintels. The centered entry is framed by panel-and-light sidelights and a front gable portico with an enclosed tympanum.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 430 North Jackson Street** **000-7819-0456** *Other DHR ID#: 000-6615*
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide bungalow features a centered entry, triple windows and a dormer with four 9-light wood casement windows. The roof has wide eaves supported by cut-out wood brackets and the full-width front porch is supported by square wood posts atop weatherboard clad piers. the weatherboard cladding is narrow.
Individual Resource Status: Single Dwelling **Contributing**
- 501 North Jackson Street**
000-7819-0352 *Other ID# 000-6308*
Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation: Solid Concrete Block, Rock-Faced*
Structural System: Frame Concrete Stucco
Window(s): Sash, double-hung Wood 6/1
Door(s): Single Leaf Wood 15-light
Roof: Gable, Front Asphalt Shingle
Chimney: Exterior end Brick Shouldered
Porch: 1-story, 1-bay Wood Craftsman
Dormer: Gable Concrete Stucco
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 66

502 North Jackson Street 000-7819-0484 *Other DHR ID#:* 000-6646

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The two-bay wide house has an L-shaped footprint and some 1
paired windows. It retains historic 1/1 storm windows that 1
are hinged at the top and work like awning windows.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

505 North Jackson Street

000-7819-0353 *Other ID#* 000-6309

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Metal 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Front Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 3-bay Wood Craftsman

Dormer: Gable Vinyl Siding

Individual Resource Status: Single Dwelling

Contributing

506 North Jackson Street

000-7819-0485

Other DHR ID#: 000-6647

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features a centered entry flanked 1
by two windows to each side. The dormer and the roof have 1
scroll-sawn exposed rafter tails. On both the north and south 1
elevations, there is a gable roof dormer.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

510 North Jackson Street

000-7819-0486

Other DHR ID#: 000-6648

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The entry of the three-bay wide dwelling is framed by 1
Craftsman style sidelights and flanked by paired windows. The 1
dormer contains two six-light windows.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

511 North Jackson Street

000-7819-0777

Other DHR ID#: 000-6310

Primary Resource Information: Single Dwelling, Stories 1.5, Style: Bungalow/Craftsman, ca. 1920

Panel-Faced Concrete Block Foundation, Wood Frame Structural System with Asbestos Shingle, Side Gable Roof
with Asphalt Shingle, Wood Frame Garage with Board-and-Batten Siding

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 67

515 North Jackson Street

000-7819-0354 Other ID# **000-6311**

Single Dwelling 1926 Bungalow/Craftsman 2.0 *Foundation:* Solid Concrete Parged

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 10/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 3-bay Wood Post

Dormer: Gable Wood Shingle

Individual Resource Status: **Single Dwelling**

Contributing

516 North Jackson Street

000-7819-0487

Other DHR ID#: 000-6649

Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**
the three-bay wide dwelling features a centered entry flanked l

by paired windows with square-edged surrounds. The porch has l
a half-hipped roof with a center gable peak.

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

519 North Jackson Street

000-7819-0355 Other ID# **000-6312**

Single Dwelling 1922 Bungalow/Craftsman 1.5 *Foundation:* Solid Concrete Block

Structural System: Frame Concrete Stucco

Window(s): Sash, double-hung Wood 6/1 .

Door(s): Single Leaf Wood 15-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 3-bay Wood Craftsman

Dormer: Gable Wood Shingle

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

520 North Jackson Street

000-7819-0488

Other DHR ID#: 000-6650

Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**

The two-bay wide dwelling has a front gable porch and l
asymmetrically placed openings. There is a triangular vent in l
the gable end of the house.

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

524 North Jackson Street

000-7819-0489

Other DHR ID#: 000-6651

Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**

The three-bay wide dwelling features wood shingles in the l
gable ends, exposed rafter tails on both the roof and dormer l
and a box bay on the north elevation. The dormer contains l
three 6/1 double hung sash windows.

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 68

525 North Jackson Street

000-7819-0356 Other ID# 000-6313

Single Dwelling 1922-1923 Bungalow/Craftsman 1.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Jerkinhead Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Craftsman

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

600 North Jackson Street

000-7819-0508

Other DHR ID#: 000-6670

Primary Resource Information: **Single Dwelling, Stories 2, Style: Tudor Revival,**

The two-bay wide house features a side oriented entry beneath 1

a portico with a single Tuscan column. Other details include 1

a single shouldered front facing chimney and a shed dormer.

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

601 North Jackson Street

000-7819-0440 Other ID# 000-6597

Single Dwelling 1925-1940 Colonial Revival 2.0 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick 6-course Amer. Bond

Window(s): Sash, double-hung Metal 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Cap, Rowlock

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

604 North Jackson Street

000-7819-0509

Other DHR ID#: 000-6671

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide dwelling has a centrally placed gable dormer 1

with three 6/6 double-hung sash windows. Interior

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

605 North Jackson Street

000-7819-0439 Other ID# 000-6596

Single Dwelling 1925-1940 Colonial Revival 2.0 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick 6-course Amer. Bond

Window(s): Sash, double-hung Metal 8/8

Window(s): Casement Metal 1-light

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Cap, Soldier

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 69

608 North Jackson Street **000-7819-0510** **Other DHRJD#: 000-6672**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

Details of the two-bay wide house include a soldier l
stringcourse and a projecting front gable bay with a slightly l
overhanging second story that is supported by corbeled brick l
brackets. The gable dormer holds a single 8/8 double-hung l
sash window.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

609 North Jackson Street

000-7819-0438 *Other ID#* **000-6595**

Single Dwelling 1920s Colonial Revival 2.0 Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Aluminum Siding

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Cap, Soldier

Dormer: Gable Aluminum Siding

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

612 North Jackson Street

000-7819-0511

Other DHR ID#: 000-6673

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The shed roof porch of the three-bay wide dwelling has paired l
posts and a balustrade with square balusters. Other details l
include a fixed 6-light window in the gable end of the l
projecting gable bay and a 6/6 double-hung sash window in the l
gable dormer. The door has diamond-paned lights.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

616 North Jackson Street

000-7819-0512

Other DHR ID#: 000-6674

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide Cape Cod has a centered entry beneath a l
shed roof hood with scroll-sawn brackets. The dormers each l
contain a 6/6 double-hung window.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

617 North Jackson Street

000-7819-0437 *Other ID#* **000-6411**

Single Dwelling 1930-1945 Colonial Revival 2.0 Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 8/8

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 70

620 North Jackson Street 000-7819-0513 Other DHR ID#: 000-6675

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide bungalow features wood shingles in the l
gable ends, a box bay with exposed rafter tails on the south l
elevation, and three 6/1 double-hung sash windows in the l
dormer.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

621 North Jackson Street

000-7819-0436 Other ID# 000-6410

Single Dwelling 1936 ca Colonial Revival 2.0 *Foundation: Solid Concrete Parged*

Structural System: Frame Asbestos Shingle

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

626 North Jackson Street

000-7819-0514

Other DHR ID#: 000-6676

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling is similar ot the Cape Cod house l
form and the two gable wall dormers each contain a 6/6 window. l
Brick detailing includes rowlock sills, soldier lintels, and a l
brick cornice with dentils.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

627 North Jackson Street

000-7819-0435 Other ID# 000-6409

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation: Solid Concrete Block, Panel-Faced*

Structural System: Frame Wood Shingle

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood 15-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Post, Square

Dormer: Gable Wood Shingle

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

634 North Jackson Street

000-7819-0515 Other DHR ID #: 000-6677

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The roof of the three-bay wide dwelling has wide, overhanging eaves and exposed rafter tails. The centered entry
is framed by the front gable Tuscan portico.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Non-contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 71

- 635 North Jackson Street** **000-7819-0159** -
Primary Resource Information: **Single Dwelling, Stories 2, Style: Other, ca 1965**
Three bays wide, this dwelling has an attached carport, wide eaves, and rowlock sills. The entry is illuminated with 5-light and dado sidelights.
Individual Resource Status: **Single Dwelling** **Non-contributing**
- 638 North Jackson Street** **000-7819-0516** *Other DHR ID#:* **000-6778**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Bungalow/Craftsman,**
The two-bay wide foursquare features a wrap-around porch with 1
the two northernmost bays containing raftsmen style brackets 1
with curved diagonal members. Other details include 1
overhanging eaves and two 6-light casement windows in the 1
dormer.
Individual Resource Status: **Garage** **Non-contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 641 North Jackson Street**
000-7819-0434*Other ID#* **000-6408**
Single Dwelling 1910-1925 Colonial Revival 2.0 *Foundation:* Solid Concrete Block, Rock-Faced
Structural System: Frame Wood Weatherboard, Beaded
Window(s): Sash, double-hung Metal 1/1
Door(s): Single Leaf Wood 1-light
Roof: Hipped Asphalt Shingle
Chimney: Exterior end Wood Weatherboard, Beaded
Porch: 1-story, 3-bay Wood Column, Tuscan
Walls: Frame Wood Shingle
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 644 North Jackson Street** **000-7819-0517** *Other DHR ID#:* **000-6679**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**
The three-bay wide bungalow features exposed rafter tails, 1
wide eaves, and brackets. The dormer contains two sets of 1
paired casement windows with diamond panes.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Non-contributing**
- 645 North Jackson Street**
000-7819-0433*Other ID#* **000-6407**
Single Dwelling 1915-1930 Bungalow/Craftsman 2.0 *Foundation:* Solid Concrete Block, Rock-Faced
Structural System: Frame Wood Weatherboard
Window(s): Sash, double-hung Metal 1/1
Door(s): Single Leaf Wood 1-light
Roof: Gable, Front Asphalt Shingle
Chimney: Central interior Brick Corbeled Cap
Porch: 1-story, 2-bay Wood Column, Tuscan
Dormer: Shed Wood Weatherboard
Individual Resource Status: **Shed** **Non-contributing**
Individual Resource Status: **Single Dwelling** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 72

650 North Jackson Street **000-7819-0518** **Other DHR ID#: 000-6680**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The two-bay wide dwelling has a projecting front gable bay, a l
wall dormer with two 8/1 windows, and a chimney with l
basketweave brickwork.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

651 North Jackson Street

000-7819-0432 *Other ID#* **000-6406**

Single Dwelling 1910 ca Colonial Revival 2.5 *Foundation: Solid Concrete Block, Rock-Faced*

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Metal 1/1

Window(s): Fixed Wood 6-light

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Column, Tuscan

Dormer: Hipped Vinyl Siding

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

702 North Jackson Street

000-7819-0519

Other DHR ID#: 000-6681

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide bungalow features wide eaves with l
horizontal beam brackets. The Jerkinhead porch is supported l
by two large, tapered piers with stone facing. The dormer l
contains two 2-leaf casement windows with Craftsman style l
panes.

Individual Resource Status: Single Dwelling

Contributing

703 North Jackson Street

000-7819-0431 *Other ID#* **000-6405**

Single Dwelling 1915-1930 Bungalow/Craftsman 1.5 *Foundation: Solid Concrete Stucco*

Structural System: Frame Concrete Stucco

Window(s): Sash, double-hung Wood 1/1

Window(s): Casement Wood 6-light

Door(s): Single Leaf Wood 3-light

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 2-bay Wood Column, Tuscan

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

708 North Jackson Street

000-7819-0520

Other DHR ID#: 000-6682

Primary Resource Information: Single Dwelling, Stories 3, Style: Other,

The three-bay wide vernacular house has a centrally located l
dormer with a 1/1 double-hung sash window. The half-hipped l
porch features scroll-sawn corner brackets and a square-cut l
balustrade.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Non-contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 73

709 North Jackson Street

000-7819-0430 Other ID# 000-6404

Single Dwelling 1925-1940 Bungalow/Craftsman 2.0 Foundation: Solid Concrete Parged

Structural System: Frame Wood Shingle

Window(s): Sash, double-hung Metal 6/1

Door(s): Single Leaf Wood 1-light

Roof: Gable, Front Asphalt Shingle

Chimney: Exterior end Brick Shouldered

Porch: 1-story, 1-bay Wood Post, Square

Dormer: Gable Wood Shingle

Individual Resource Status: **Garage**

Non-contributing

Individual Resource Status: **Single Dwelling**

Contributing

712 North Jackson Street

000-7819-0521

Other DHR ID#: 000-6683

Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival,**

Details on the two-bay wide dwelling include cornice returns, 1
sidelights framing the entry, and a tripartite window in the 1
gable end. The half-hipped front porch has a gablet and is 1
supported by Tuscan columns atop diminutive piers.

Individual Resource Status: **Single Dwelling**

Contributing

715 North Jackson Street

000-7819-0429 Other ID# 000-6403

Single Dwelling 1910-1925 Colonial Revival 2.5 Foundation: Solid Concrete Block

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Metal 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Column, Tuscan

Dormer: Gable Vinyl Siding

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Shed**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

716 North Jackson Street

000-7819-0522

Other DHR ID#: 000-6684

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**

The two-bay wide dwelling has an front gable entry vestibule 1
with aluminum siding in the gable end and a slightly curved 1
metal hood that projects over the stoop. The windows have 1
fixed center lights with 2/2 sidelights and rowlock sills. 1
There is a triangular ventilator with a rowlock sill in the 1
gable end.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 74

719 North Jackson Street

000-7819-0428 Other ID# **000-6402**

Single Dwelling 1925-1940 Colonial Revival 1.5 Foundation: Solid Concrete Parged

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Stretcher Bond

Dormer: Gable Vinyl Siding

Individual Resource Status: **Garage**

Non-contributing

Individual Resource Status: **Single Dwelling**

Contributing

720 North Jackson Street

000-7819-0160

Primary Resource Information: **Single Dwelling, Stories 1, Style: Other, ca 1965**

This dwelling measures five bays wide and features rowlock sills, wide eaves, and a wood fascia board.

Individual Resource Status: **Single Dwelling**

Non-contributing

801 North Jackson Street

000-7819-0427 Other ID# **000-6401**

Single Dwelling 1929 Bungalow/Craftsman 2.5 Foundation: Solid Concrete Stucco

Structural System: Frame Wood Vinyl Siding

Window(s): Sash, double-hung Wood 9/1

Window(s): Fixed Wood 9-light

Door(s): Single Leaf Wood 9-light

Roof: Gable, Side Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 2-bay Wood Post, Square

Dormer: Gable Vinyl Siding

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

802 North Jackson Street

000-7819-0523

Other DHR ID#: 000-6685

Primary Resource Information: **Single Dwelling, Stories 3, Style: Bungalow/Craftsman,**

The two-bay wide masonry foursquare has a one-story l wrap-around porch with Tuscan columns atop rock-faced concrete l block piers and turned balusters. On the south elevation, l there is a two-story, three-sided projecting bay. The roof l has wide eaves and the dormer contains two square fixed l l-light windows.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 75

807 North Jackson Street

000-7819-0426 Other ID# **000-6400**

Single Dwelling 1910-1925 Colonial Revival 2.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Metal 2/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: Wrap-around Wood Column, Tuscan

Dormer: Hipped Wood Weatherboard

Individual Resource Status: **Single Dwelling**

Contributing

808 North Jackson Street

000-7819-0524

Other DHR ID#: **000-6686**

Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival,**

Details on the two-bay wide house include wide eaves with 1 exposed rafter tails, square-edged surrounds, and two square 1 openings in the gable end. The north end of the porch extends 1 past the wall of the house to form a porte cochere.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Non-contributing

812 North Jackson Street

000-7819-0525

Other DHR ID#: **000-6687**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Gothic Revival,**

The three-bay wide house has a center gable with cornice 1 returns. The centered entry and flanking windows have 1 square-edged surrounds.

Individual Resource Status: **Single Dwelling**

Contributing

813 North Jackson Street

000-7819-0425 Other ID# **000-6399**

Single Dwelling 1910-1925 Colonial Revival 2.5 Foundation: Solid Concrete Block, Rock-Faced

Structural System: Frame Concrete Stucco

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood 20-light

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Cross Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Portico: 1-story, 1-bay Wood Column, Tuscan

Individual Resource Status: **Single Dwelling**

Contributing

818 North Jackson Street

000-7819-0526

Other DHR ID#: **000-6688**

Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**

The three-bay wide bungalow has a full-width porch supported 1 by Tuscan columns atop rock-faced concrete block piers. Other 1 details include wide eaves, a 3-sided bay on the south 1 elevation, beaded cornerboards, and three diamond pane windows 1 in the dormer. The gable ends have wood shingle cladding and 1 cornice returns.

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 76

821 North Jackson Street

000-7819-0424 Other ID# **000-6398**

Multiple dwelling 1920-1935 Colonial Revival 2.0 *Foundation:* Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Metal 1/1

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable, Side Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Portico: 1-story, 1-bay Wood Post, Square

Dormer: Shed Asbestos Shingle

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

905 North Jackson Street

000-7819-0423 Other ID# **000-6397**

Single Dwelling 1929 Colonial Revival 2.0 *Foundation:* Solid Concrete Parged

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 8/1

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled

Roof: Gable, Side Asphalt Shingle

Chimney: Exterior end Brick Cap, Concrete

Portico: 1-story, 1-bay Wood Post, Square

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Single Dwelling**

Contributing

923 North Jackson Street

000-7819-0161

Primary Resource Information: **Commercial Building, Stories 1, Style: Other, ca 1965**

This building features rowlock sills and measures four bays across.

Individual Resource Status: Commercial Building

Non-contributing

925 North Jackson Street

000-7819-0422 Other ID# **000-6396**

Single Dwelling 1911 Bungalow/Craftsman 2.0 *Foundation:* Solid Concrete Block, Rock-Faced

Structural System: Frame Concrete Stucco

Window(s): Sash, double-hung Metal 1/1

Door(s): Single Leaf Wood Flush

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Stretcher Bond

Porch: 1-story, 1-bay Wood Post

Dormer: Hipped Wood Shingle

Walls: Frame Wood Shingle

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 77

North Kenmore Street

- 302 North Kenmore Street** **000-7819-0218** **Other DHR ID#: 000-5644**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca. 1920
Brick Laid in Stretcher Bond, Side Gable Roof with Asphalt Shingle
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 305 North Kenmore Street** **000-7819-0053**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940**
Four bays wide, this dwelling features an arched entrance with a header course lintel, rowlock sills, and a screened porch.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 308 North Kenmore Street** **000-7819-0292** **Other DHR ID#: 000-5719**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The three-bay symmetrical, brick house has a centered entry l and a one-story, one-bay porch on the southeast side. The l entry is framed by a Colonial Revival style door surround with l a pediment. The brick dwelling has rowlock sills and a l herringbone pattern water table. The gable ends sport l cornice returns.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 313 North Kenmore Street** **000-7819-0239** **Other DHR ID#: 000-5665**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**
Set on a parged concrete block foundation, the three-bay house l has a centered entry and an off-center porch. The windows l are surrounded by a wide, wood trim with an outside beaded l edge. Wide eaves and decorative brackets grace the side gable l roof.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 316 North Kenmore Street** **000-7819-0294** **Other DHR ID#: 000-5721**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The three-bay brick house has a centered entry framed by l paneled and lighted sidelights and a fanlight. A keystone is l set in the rowlock arch above the fanlight. Paired windows l with rowlock sills and lintels flank the entry.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 317 North Kenmore Street** **000-7819-0058**
Primary Resource Information: **Single Dwelling, Stories 1, Style: Other, ca 1950**
Features of this four bay wide dwelling include rowlock sills, and a wood cornice.
Individual Resource Status: **Single Dwelling** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 78

- | | | |
|---|----------------------|--------------------------------|
| 404 North Kenmore Street | 000-7819-0462 | Other DHR ID#: 000-6621 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling features stone quoins, a molded l
wood cornice with returns, and rowlock sills. On the first l
story, the windows are paired. There is a one-story, one-bay l
wide wing on the south elevation. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 410 North Kenmore Street | 000-7819-0463 | Other DHR ID#: 000-6622 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
Brickwork on the three-bay wide dwelling includes a slightly l
corbeled cornice, rowlock sills, and soldier lintels. The l
center bay of the second story holds a circular vent with a l
rowlock surround. A hyphen connects the garage to the house. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 415 North Kenmore Street | 000-7819-0773 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1985</i>
Three bays wide, this wood frame dwelling is clad with beaded vinyl siding. It sits on a stretcher-bond brick
foundation, and is capped with a side
gable roof with asphalt shingles. Features include paired windows, overhanging eaves, and a hipped roof portico. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Non-contributing |
| 416 North Kenmore Street | 000-7819-0464 | Other DHR ID#: 000-6623 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The two-bay wide dwelling features a triple 6/6 double hung l
window in the dormer and wide, overhanging eaves. The porch l
has tapered wood posts atop brick piers. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| 419 North Kenmore Street | 000-7819-0460 | Other DHR ID#: 000-6619 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide bungalow has a centered entry flanked by l
triple windows. Other details include triple 6-light fixed l
windows in the dormer, wide eaves with brackets on the roof, l
and an arched opening on the porch. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 422 North Kenmore Street | 000-7819-0779 | Other DHR ID#: 000-6624 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling features flanking one-story side l
wings with half-hipped roofs. Detailing includes a pedimented l
portico, wide eaves, paired windows with rowlock sills, and l
two basketweave stringcourses. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 79

425 North Kenmore Street **000-7819-0459** **Other DHR ID#: 000-6618**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The entry of the three-bay wide dwelling is framed by a front l
gable portico. the windows have rowlock sills and soldier l
lintels.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

430 North Kenmore Street **000-7819-0780** **Other DHR ID#: 000-6625**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features a triple window within a l
continuous frame at the gable end. the roof has wide eaves l
and the porch has tapered columns.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

431 North Kenmore Street **000-7819-0458** **Other DHR ID#: 000-6617**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features a centered entry framed l
by paired windows and a half-hipped porch roof with a center l
gable peak. Other details include wide eaves, exposed rafter l
tails, and cornerboards.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

500 North Kenmore Street **000-7819-0468** **Other DHR ID#: 000-6629**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

the three-bay wide Cape Cod dwelling has a centered entry l
beneath a shed roof portico. The dormers contain 6/6 double l
hung windows and the windows on the face of the house have l
rowlock sills.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

501 North Kenmore Street **000-7819-0483** **Other DHR ID#: 000-6645**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The dwelling is two-bays wide with stucco cladding at the l
first story and wood shingles at the second story. The bed l
molding serves as the lintel for the second story windows.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

504 North Kenmore Street **000-7819-0469** **Other DHR ID#: 000-6630**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features a centered entry flanked l
by paired windows with wide, wood surrounds. The roof has l
scroll-sawn exposed rafter tails and the half-hipped porch l
roof is supported by wood posts atop concrete block piers. On l
the north and south elevations, there a projecting gable bays.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 80

- 508 North Kenmore Street** **000-7819-0470** **Other DHR ID#: 000-6631**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features a centered entry flanked l
by paired windows, scroll-sawn exposed rater tails, paired l
6-light wood casement windows in the dormer, and a box bay. l
The central porch support is a tapered column atop a concrete l
block pier.
Individual Resource Status: Single Dwelling **Contributing**
- 509 North Kenmore Street** **000-7819-0770**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1980
This wood frame three bay wide dwelling features a shouldered chimney, paired windows, and battered porch
posts. It has a random rubble
foundation and a side gable roof with asphalt shingles.
Individual Resource Status: Single Dwelling **Non-contributing**
Individual Resource Status: Garage **Non-contributing**
- 512 North Kenmore Street** **000-7819-0471** **Other DHR ID#: 000-6632**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features narrow weatherboards, a cetered entry, l
paired windows, a triple 6/l window in the dormer, and a porch with tapered l
wood columns atop rock-faced concrete block piers. The roof has exposed l
rafter tails and the dormer and box bay have scroll-sawn exposed rafter l
tails.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 513 North Kenmore Street** **000-7819-0482** **Other DHR ID#: 000-6644**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The porch of the two-bay wide dwelling is supported by tapered l
wood posts atop stone piers. The dormer has paired6-light l
casement windows and scroll-sawn exposed rater tails. On the l
south elevation, there is a box bay.
Individual Resource Status: Single Dwelling **Contributing**
- 516 North Kenmore Street** **000-7819-0472** **Other DHR ID#: 000-6633**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling has a centered entry flanked by l
paired windows with wide wood surrounds. The porch has a l
half-hipped roof and the roof has wide eaves and exposed l
rafter tails.
Individual Resource Status: Single Dwelling **Contributing**
- 517 North Kenmore Street** **000-7819-0481** **Other DHR ID#: 000-6643**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The porch of the three-bay wide house has a half-hipped roof l
supported by brick columns atop of brick piers. There is a l
box bay on the north elevation and on both the north and south l
elevations, there are shed dormers.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 81

520 North Kenmore Street **000-7819-0473** **Other DHR ID#: 000-6634**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features a centered entry and 1
paired windows with wide, wood surrounds. The porch has a 1
half-hipped roof and the roof has wide eaves.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

521 North Kenmore Street **000-7819-0781** **Other DHR ID#: 000-6642**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling has a centered entry framed by 1
paired windows. The dormer contains two pairs of 6/1 windows 1
and on the north elevation there is a box bay.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

524 North Kenmore Street **000-7819-0474** **Other DHR ID#: 000-6635**

Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,
The three-bay wide dwelling features an off-center entry, 1
wide, wood surrounds, a box bay on the north elevation, and 1
triangular vents in the roof. The roof has wide eaves and 1
exposed rafter tails.

Individual Resource Status: Single Dwelling

Contributing

525 North Kenmore Street **000-7819-0480** **Other DHR ID#: 000-6641**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features wide eaves and exposed 1
rafter tails and a dormer which contains three 6/1 double-hung 1
sash windows in a continuous frame. On the north elevation, 1
there is a box bay.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

600 North Kenmore Street **000-7819-0528** **Other DHR ID#: 000-6690**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,
The three-bay wide dwelling has a projecting gable bay with a 1
steeply pitched roof and diminutive cornice returns. 1
Brick details include a corbeled stringcourse, rowlock sills, 1
raised brick quoins, and, at the second story, an arched 1
rowlock lintel. Set into the breast of the chimney is a round 1
arched 6/6 window.

Individual Resource Status: Single Dwelling

Contributing

601 North Kenmore Street **000-7819-0507** **Other DHR ID#: 000-6669**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The four-bay wide dwelling features a front gable porch and 1
windows with square edged surrounds. Flanking the chimney are 1
four-light square casement windows.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 82

- | | | |
|--|----------------------|--------------------------------|
| 604 North Kenmore Street | 000-7819-0529 | Other DHR ID#: 000-6691 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
Detailing on the three-bay wide dwelling includes a corbeled l
brick cornice, a rowlock stringcourse, a raised stretcher bond l
stringcourse, and a reeded door surround. The openings on the l
first story are round arched with a rowlock surround, l
keystones, stucco infill around the fenestration. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 605 North Kenmore Street | 000-7819-0506 | Other DHR ID#: 000-6668 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Other,</i>
The three-bay wide house has a shouldered chimney and a shed l
dormer with two one-light sliding windows. Interior | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 608 North Kenmore Street | 000-7819-0530 | Other DHR ID#: 000-6692 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,</i>
The projecting gable bay has a steeply pitched roof and l
half-timbering in the gable end. Other details on the two-bay l
wide dwelling include a round-arched entry, soldier lintels l
and rowlock sills, a soldier stringcourse, and a slight shed l
wall dormer. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 609 North Kenmore Street | 000-7819-0505 | Other DHR ID#: 000-6667 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling has a front gable entrance l
vestibule with brick cladding on the facade with a rowlock l
sill. The shed dormer on the north elevation has two coupled l
windows with 6/6 double-hung sash windows. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 612 North Kenmore Street | 000-7819-0531 | Other DHR ID#: 000-6693 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The side oriented entry is framed by the front gable portico l
with an arched opening, broken pediment and cornice returns. l
Other details on the three-bay wide house include soldier l
lintels, a soldier water table, rowlock sills, and a l
one-story, one-bay wide side porch. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 83

- | | | |
|--|----------------------|--------------------------------|
| 613 North Kenmore Street | 000-7819-0504 | Other DHR ID#: 000-6666 |
| <i>Primary Resource Information: Single Dwelling, Stories 1, Style: Colonial Revival,</i>
Features of the three-bay wide dwelling include a projecting 1
front gable bay with a fanlight, a side oriented entry, and a 1
front facing chimney. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 616 North Kenmore Street | 000-7819-0532 | Other DHR ID#: 000-6694 |
| <i>Primary Resource Information: Single Dwelling,</i>
The two-bay wide house features a shed roof portico, a 1
corbeled brick cornice, and a brick water table. The window 1
on the first story has a rowlock sill and a brick jack lintel 1
with a concrete keystone. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 617 North Kenmore Street | 000-7819-0503 | Other DHR ID#: 000-6665 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The two-bay wide dwelling features a projecting front gable 1
bay which contains a bank of windows. On both the east and 1
west elevations, there are gable dormers. The foundation 1
appears to be both brick and poured concrete. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| 621 North Kenmore Street | 000-7819-0502 | Other DHR ID#: 000-6664 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The porch of the three-bay wide dwelling resembles a temple 1
front and features a front gable roof supported by tapered 1
columns and a balustrade with square balusters. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 622 North Kenmore Street | 000-7819-0533 | Other DHR ID#: 000-6695 |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,</i>
The three-bay wide foursquare features wide, overhanging 1
eaves, a shouldered chimney, cornerboards, square-edged wood 1
surrounds, and paired 6-light casement windows in the dormer. 1
The half-hipped porch is set on a brick pier foundation. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 626 North Kenmore Street | 000-7819-0534 | Other DHR ID#: 000-6696 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling has a front-facing shouldered 1
chimney with quarter round windows flanking the shaft. The 1
house features a projecting gable bay, rowlock sills, an inset 1
porch to the north of the gable bay, and a 6/6 double-hung 1
vinyl sash window in the dormer. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 84

- | | | |
|--|----------------------|--------------------------------|
| 627 North Kenmore Street | 000-7819-0501 | Other DHR ID#: 000-6663 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The portico of the three-bay wide dwelling has paired square posts, a segmental soffit, and a broken pediment. The shallow pitched roof has wide, overhanging eaves and exposed rafter tails. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 630 North Kenmore Street | 000-7819-0535 | Other DHR ID#: 000-6697 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The four-bay wide dwelling has been extensively altered with a large addition. Details include a second story deck, a half-hipped porch roof, and wide, wood window surrounds. | | |
| <i>Individual Resource Status: Shed</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 633 North Kenmore Street | 000-7819-0500 | Other DHR ID#: 000-6662 |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,</i>
The two-bay wide dwelling features a half-hipped porch roof with a gablet that is supported by Tuscan colonnettes atop of stone piers. Other details include some paired windows and wide, overhanging eaves. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 638 North Kenmore Street | 000-7819-0536 | Other DHR ID#: 000-6698 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The six-bay wide dwelling features wide eaves with exposed rafter tails, cornerboards, a shed roof porch, and an attached garage. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 640 North Kenmore Street | 000-7819-0158 | |
| <i>Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1960</i>
Three bays wide this dwelling features a center entry, wide eaves, rowlock sills, and an attached car port. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Non-contributing |
| 643 North Kenmore Street | 000-7819-0499 | Other DHR ID#: 000-6661 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The roof of the three-bay wide dwelling has wide eaves, exposed rafter tails, and cut-out brackets. The half-hipped roof of the porch is supported by tapered columns. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 85

- 644 North Kenmore Street** **000-7819-0537** **Other DHR-ID#: 000-6699**
Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,
The three-bay wide dwelling has a centered entry and a 1
full-width porch with a Jerkinhead roof. The roof has wide, 1
overhanging eaves supported by wood brackets.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Contributing**
- 647 North Kenmore Street** **000-7819-0498** **Other DHR ID#: 000-6660**
Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,
The three-bay wide dwelling features a centered entry framed 1
by a 4-light transom and 3-light sidelights. The porch 1
columns are tapered and the roof has wide eaves 1
with scroll-sawn exposed rafter tails. There are paired 1
window on the first story.
Individual Resource Status: Single Dwelling **Contributing**
- 648 North Kenmore Street** **000-7819-0538** **Other DHR ID#: 000-6700**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide bungalow features wide eaves, a centered 1
entry, and some paired windows. The shed dormer contains two 1
1/1 horizontal sash windows.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Non-contributing**
- 701 North Kenmore Street** **000-7819-0157**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1965
This building measures three bays across and features rowlock sills, wide eaves, and the front gable is clad with
aluminum siding.
Individual Resource Status: Single Dwelling **Non-contributing**
- 702 North Kenmore Street** **000-7819-0539** **Other DHR ID#: 000-6701**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
On the first story of the facade there is a side oriented 1
entry framed by sidelights and a three-sided canted bay 1
window. The two-bay wide dwelling is covered by a pyramidal 1
roof with wide eaves and fronted by a half-hipped porch with 1
square columns. There is a box bay on the north elevation.
Individual Resource Status: Single Dwelling **Contributing**
- 705 North Kenmore Street** **000-7819-0497** **Other DHR ID#: 000-6659**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The roof of the three-bay wide dwelling has wide, overhanging 1
eaves, exposed rafter tails, and brackets. The dormer 1
contains a one-light window and the porch has three piers 1
topped by concrete caps.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 86

- | | | |
|--|----------------------|--------------------------------|
| 708 North Kenmore Street | 000-7819-0540 | Other DHR ID#: 000-6702 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide dwelling features a centered entry, square l
edged surrounds, a front gable porch with tapered columns, and l
a roof with wide eaves and exposed rafter tails. The dormer l
contains a triple 6/1 window and a 4-light casement window. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 709 North Kenmore Street | 000-7819-0496 | Other DHR ID#: 000-6658 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide Cape Cod has a centered entry frame by a Colonial Revival l
style door surround with fluted pilasters and a dentiled lintel. Other l
details include a dentiled cornice, rowlock sills, and 6/6 double-hung sash l
windows in the dormer. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 714 North Kenmore Street | 000-7819-0541 | Other DHR ID#: 000-6703 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The two-bay wide dwelling features paired windows, tapered l
porch supports, and wide eaves with cut-out wood brackets. l
The dormer contains two 1/1 horizontal sash windows. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Guest House</i> | | Contributing |
| 715 North Kenmore Street | 000-7819-0495 | Other DHR ID#: 000-6657 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide house has a centered entry with a l
square-edged surround. The dormer contains three 2/2 l
double-hung sash windows and the porch has a square-cut l
balustrade. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 718 North Kenmore Street | 000-7819-0155 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1990</i>
This building measures two bays across and features an aluminum encased surrounds boxed cornice, and
cornerboards. Other features include
square wood balusters, a wood pier porch foundation, and a round aluminum louvered vent is seen in the gable. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Non-contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 87

719 North Kenmore Street 000-7819-0494 *Other DHR ID#:* 000-6656

Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,

The three-bay wide dwelling features paired windows in 1 continuous surrounds and a porch with square-cut balusters. 1 The house was originally clad in wood weatherboard, which is 1 still in existence beneath the current aluminum siding. Also, 1 there were originally sidelights flanking the main entry. :The interior retains much of its original moldings and floors. The 1 mantel is composed of bricks with bookshelves to the sides. The plan 1 has been altered by the removal of arched openings, the ghosting of 1 which is visible in the floors. A stair to the basement was located in 1 the bedroom, set directly behind the living room. Entry openings 1 between several of the original spaces have been infilled. The 1 basement, running the full depth of the building, is partially 1 finished.

Individual Resource Status: Single Dwelling Contributing

721 North Kenmore Street 000-7819-0493 *Other DHR ID#:* 000-6655

Primary Resource Information: Single Dwelling, Stories 1, Style: Colonial Revival,

The three-bay wide dwelling has turned balusters and picture 1 windows with 2/2 horizontal sash sidelights. The windows 1 facing the street have aluminum fanlight motifs above them.

Individual Resource Status: Single Dwelling Contributing

722 North Kenmore Street 000-7819-0542 *Other DHR ID#:* 000-6704

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry with a 1 one-light transom, gable ends with enclosed tympanums, and a 1 three-sided window bay on the north elevation. The dormers 1 feature 1/1 metal windows and molded wood cornices.

Individual Resource Status: Single Dwelling Contributing
Individual Resource Status: Shed Non-contributing

803 North Kenmore Street 000-7819-0492 *Other DHR ID#:* 000-6654

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The entry of the three-bay wide dwelling is set in a front 1 gable projecting bay. The front-facing chimney is shouldered 1 and the shed dormer contains a 6/6 double-hung vinyl window.

Individual Resource Status: Single Dwelling Contributing

804 North Kenmore Street 000-7819-0543 *Other DHR ID#:* 000-6705

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The modest two-bay wide dwelling has a projecting gable bay 1 containing the entry and rowlock brick window sills. The 1 porch is supported by one brick pier at the corner and a 1 square wood post.

Individual Resource Status: Garage Contributing
Individual Resource Status: Single Dwelling Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 88

- 808 North Kenmore Street** **000-7819-0544** **Other DHR ID#: 000-6706**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling has an off-center entry with a 1
transom, and a hipped roof carport with square wood post 1
supports and brackets. There are two 1/1 metal windows in the 1
dormer.
Individual Resource Status: Single Dwelling **Contributing**
- 809 North Kenmore Street** **000-7819-0156**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman, ca 1920
Measuring three bays across, this dwelling features exposed roof rafters, wide eaves, and one shed roof
dormer. The porch sits on a concrete block
pier foundation.
Individual Resource Status: Single Dwelling **Contributing**
- 812 North Kenmore Street** **000-7819-0545** **Other DHR ID#: 000-6707**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide house has a centered entry, some paired 1
windows, a box bay on the North elevation, and a roof with 1
wide eaves, exposed rafter tails, and wood brackets. The 1
porch is supported by short Tuscan columns atop rock-faced 1
concrete block piers.
Individual Resource Status: Single Dwelling **Contributing**
- 815 North Kenmore Street** **000-7819-0491** **Other DHR ID#: 000-6653**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling has a centered entry and flanking 1
windows with square-edged surrounds. It is set on a raised 1
basement which has three 9-light windows on the south wall. 1
the roof has exposed rafter tails.
Individual Resource Status: Single Dwelling **Contributing**
- 816 North Kenmore Street** **000-7819-0546** **Other DHR ID#: 000-6708**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features a centered entry flanked 1
by tripartite windows with wide, square-edged wood surrounds. 1
It has a front gable porch.
Individual Resource Status: Single Dwelling **Contributing**
- 819 North Kenmore Street** **000-7819-0490** **Other DHR ID#: 000-6652**
Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,
Although not a biungalow in form, this two-bay wide dwelling 1
features elements of the Craftsman style of architecture. 1
Both the main roof and the porch roof have wide, overhanging 1
eaves, exposed rafter tails, and brackets.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 89

820 North Kenmore Street **000-7819-0547** **Other DHR ID#: 000-6709**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,
The three-bay wide dwelling features a centered entry flanked l
by paired windows and framed by 8-light and panel sidelights l
and a pedimented portico. Other details include cornice l
returns, an asymmetrical gable and wide, wood surrounds.
Individual Resource Status: Single Dwelling **Contributing**

North Lincoln Street

302 North Lincoln Street **000-7819-0297** **Other DHR ID#: 000-5724**
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,
The projecting front gable bay of the two-bay house contains a semi-circular, l
brick arch with stone quoining which surrounds the entry and a half-timbering l
in the gable end above the entry. The groups of three windows have rowlock l
sills and soldier lintels and there is a soldier course water table. Additions and
alterations
Individual Resource Status: Single Dwelling **Contributing**

305 North Lincoln Street **000-7819-0241** **Other DHR ID#: 000-5667**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The symmetrical three-bay brick house has a centered entry l
framed by a wood surround with a molded wood cornice. The l
brick dwelling is detailed with a raised brick water table, l
rowlock sills, and soldier lintels. There are three front l
gable dormers, each containing one six-over-six double-hung l
wood sash windows.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

306 North Lincoln Street **000-7819-0293** **Other DHR ID#: 000-5720**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other,
The three-bay brick dwelling has a front gable projecting bay l
and a flared porch roof. The brick is detailed with rowlock l
sills, soldier lintels and a soldier course water table. The l
front gable dormer contains a replacement six-over-six l
double-hung metal sash window.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

312 North Lincoln Street **000-7819-0057**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1970
Features of this four bay wide dwelling include rowlock sills connected by a course of stretchers, and wide eaves.
Individual Resource Status: Single Dwelling **Non-contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 90

- | | | |
|--|----------------------|--------------------------------|
| 410 North Lincoln Street | 000-7819-0318 | Other DHR-ID#: 000-5745 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay house has a centered entry flanked by paired l
windows. The side gable roof and front gable porch roof have l
wide eaves. There is a box bay on the northwest side of the l
house. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 416 North Lincoln Street | 000-7819-0062 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman, ca 1935</i>
This dwelling measures two bays across and features wide eaves with wood corner brackets, and square-edged
aluminum surrounds. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| 419 North Lincoln Street | 000-7819-0467 | Other DHR ID#: 000-6628 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide dwelling features a centered entry, wide l
eaves, paired windows, and a square-edged door surround. | | |
| <i>Individual Resource Status: Other</i> | | Non-contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 424 North Lincoln Street | 000-7819-0316 | Other DHR ID#: 000-5743 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay brick house has a side passage entry set in a l
projecting front gable vestibule. The second story has a l
slight overhang. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 429 North Lincoln Street | 000-7819-0466 | Other DHR ID#: 000-6627 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide dwelling features a centered entry, wide l
eaves, paired 6/6 windows in the dormer, and a shed roof porch l
supported by tapered stucco clad piers. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 430 North Lincoln Street | 000-7819-0139 | |
| <i>Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1965</i>
This house features rowlock sills, an attached wood post car port, cornerboards, and a wood boxed cornice. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Non-contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 91

434 North Lincoln Street **000-7819-0315** **Other DHR ID#: 000-5742**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Set on a panel-faced concrete block foundation, the three-bay l house has a projecting side bay and a centered entry. The l windows have wide, wood surrounds with a beaded edge. The l dormers have exposed rafter tails, molded vergeboards and each l contains six-over-one windows.

Individual Resource Status: Single Dwelling

Contributing

435 North Lincoln Street **000-7819-0465** **Other DHR ID#: 000-6626**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features paired windows, wide l eaves, and a one-story, one-bya side porch. Interior

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

500 North Lincoln Street **000-7819-0563** **Other DHR ID#: 000-6733**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide bungalow features a full-width porch l supported by tapered columns atop of brick piers with concrete l caps. The gable ends are clad in square-butt shingles and the l dormer has a triple 6/1 double-hung window.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

501 North Lincoln Street **000-7819-0479** **Other DHR ID#: 000-6640**

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features a centered entry, paired l windows with wide, wood surrounds, and a roof with wide eaves l and exposed rafter tails. The porch is supported by brick l piers and on the south elevation there is a one-story, one-bay l wide porch.

Individual Resource Status: Single Dwelling

Contributing

504 North Lincoln Street **000-7819-0564** **Other DHR ID#: 000-6734**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The four-bay wide dwelling has a front gable projecting bay, a l front facing, shouldered chimney, rowlock sills, a 3-light l sidelight at the entry, and skintled brick. The dormer l contains a 6/6 double-hung sash window.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

507 North Lincoln Street **000-7819-0478** **Other DHR ID#: 000-6639**

Primary Resource Information: Single Dwelling, Stories 3, Style: Other,

This house is a late 20th century interpretation of the Tudor l Revival style. The two-bay wide dwelling features beaded l siding, an arched portico with cornice returns, and grouped l windows. There is a projecting gable bay with a steeply l pitched roof and stucco cladding.

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 92

- | | | |
|--|----------------------|--------------------------------|
| 510 North Lincoln Street | 000-7819-0565 | Other DHR ID#: 000-6735 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide dwelling features squared balusters on the 1 porch and a dormer with two three-light casement windows and 1 exposed rafter tails. The roof has wide eaves with brackets. | | |
| <i>Individual Resource Status: Garage</i> Contributing | | |
| <i>Individual Resource Status: Single Dwelling</i> Contributing | | |
| 511 North Lincoln Street | 000-7819-0477 | Other DHR ID#: 000-6638 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Other,</i>
The two-bay wide dwelling has a projecting gable bay with 1 banks of windows at both the first and second stories. the 1 first story windlows have rowlock sills and there is a small 1 gable bay on the north elevation. | | |
| <i>Individual Resource Status: Single Dwelling</i> Contributing | | |
| 514 North Lincoln Street | 000-7819-0141 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940</i>
The Cape Cod is four bays wide and includes features such as rowlock sills, a wood cornice, and two gable dormers. A screened porch is located on the side elevation. | | |
| <i>Individual Resource Status: Single Dwelling</i> Contributing | | |
| <i>Individual Resource Status: Garage</i> Contributing | | |
| 515 North Lincoln Street | 000-7819-0476 | Other DHR ID#: 000-6637 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The five-bay wide Cape Cod has a centered entry with a 1 Colonial Revival style door surround featuring fluted 1 pilasters and a broken pediment. The windows have wide, wood 1 surrounds and the dormers contain 6/6 double-hung sash 1 windows. | | |
| <i>Individual Resource Status: Single Dwelling</i> Contributing | | |
| 518 North Lincoln Street | 000-7819-0142 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940</i>
Four bays wide, this dwelling features rowlock sills, an aluminum encased cornice, and an arched entry portico. The side elevation has a shed screened porch. | | |
| <i>Individual Resource Status: Single Dwelling</i> Contributing | | |
| <i>Individual Resource Status: Garage</i> Contributing | | |
| 521 North Lincoln Street | 000-7819-0475 | Other DHR ID#: 000-6636 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling has a centered entry framed by 1 five-light sidelights. The shed roof porch is supported by 1 paneled wood posts and the roof has cornice returns. | | |
| <i>Individual Resource Status: Single Dwelling</i> Contributing | | |
| <i>Individual Resource Status: Garage</i> Contributing | | |
| <i>Individual Resource Status: Bomb Shelter</i> Non-contributing | | |
| <i>Individual Resource Status: Blacksmith Shop</i> Contributing | | |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 93

600 North Lincoln Street 000-7819-0527 Other DHR-ID#: 000-6689

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The four-bay wide house has rowlock sills. The first story is clad in brick stretcher bond and the second story with weatherboard. The two stories are further divided by a narrow stringcourse.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

601 North Lincoln Street 000-7819-0580 Other DHR ID#: 000-6750

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

Detailing on the three-bay wide dwelling includes rowlock sills, a soldier course water table, round-arched rowlock lintels at the first story windows and soldier lintels at the second story windows. The dentiled cornice rests above a course of dentiled brickwork and the narrow, steeply pitched dormers contain round-arched 12-light casement windows.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

604 North Lincoln Street 000-7819-0550 Other DHR ID#: 000-6714

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a projecting front gable bay with vinyl siding in the gable end. The windows have rowlock sills and the dormer contains a 6/6 window.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

605 North Lincoln Street 000-7819-0579 Other DHR ID#: 000-6749

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

Details on the modest dwelling include rowlock sills, a soldier course water table, brick dentils below the cornice, louvered windows in the gable end, and arched rowlock lintels on the first story windows. The pedimented portico has dentils at the cornice and the dormers have round wood arches above the 8-light windows.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

608 North Lincoln Street 000-7819-0551 Other DHR ID#: 000-6715

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a projecting front gable bay with weatherboard and a lunette window in the gable end. The windows have rowlock sills and the dormer contains a 6/6 window.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 94

- | | | |
|--|----------------------|--------------------------------|
| 609 North Lincoln Street | 000-7819-0578 | Other DHRJD#: 000-6748 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide house has a slightly recessed center entry framed by a Colonial Revival style door surround with fluted pilasters, a dentiled broken pediment and a finial. Detailing includes rowlock sills, a soldier water table, and a dentil molded cornice with dentiled brick below. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 612 North Lincoln Street | 000-7819-0552 | Other DHR ID#: 000-6716 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling has a projecting front gable bay with westherboard in the gable end. The windows have rowlock sills and the dormer contains a 6/6 double-hung sash window. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 613 North Lincoln Street | 000-7819-0577 | Other DHR ID#: 000-6747 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The entry of the three-bay wide dwelling is framed by a Colonial Revival style door surround with fluted pilasters and a two-light transom. Details include a soldier water table, a dentiled cornice of both wood and brick, a rowlock arched lintels on the side windows. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 616 North Lincoln Street | 000-7819-0553 | Other DHR ID#: 000-6717 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The facade of the three-bay wide house is dominated by a front gable porch with vinyl siding in the gable end. The windows have rowlock sills and the dormers each have 1/1 double-hung sash windows. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 617 North Lincoln Street | 000-7819-0576 | Other DHR ID#: 000-6746 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The slightly recessed center entry is framed by a Colonial Revival style door surround with fluted pilasters, a broken pediment with dentil molding, and a finial. Other details include rowlock sills, soldier lintel, rowlock arches around the first story windows, and a dentil molded cornice. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 95

- | | | |
|---|----------------------|--|
| 620 North Lincoln Street | 000-7819-0554 | Other DHR ID#: 000-6718 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling features an elliptical portico, a centered entry with four-light sidelights, and rowlock sills. The dormers each contain a 6/6 double-hung sash window. | | |
| <i>Individual Resource Status: Garage</i> | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing
Contributing |
| 625 North Lincoln Street | 000-7819-0575 | Other DHR ID#: 000-6745 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
Brick detailing on the three-bay wide house includes rowlock sills, soldier lintels, a soldier course water table, a dentiled brick course below the cornice. The flat roof porch has paired Tuscan posts, a dentil molded cornice and arched openings. | | |
| <i>Individual Resource Status: Garage</i> | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing
Contributing |
| 627 North Lincoln Street | 000-7819-0574 | Other DHR ID#: 000-6744 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling features a dentiled cornice above a rowlock course of bricks, a lunette in the gable end, soldier lintels and rowlock sills. The first story windows are paired with keystones in the lintels. The porch has a dentiled cornice and paired square columns. | | |
| <i>Individual Resource Status: Garage</i> | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing
Contributing |
| 628 North Lincoln Street | 000-7819-0555 | Other DHR ID#: 000-6719 |
| <i>Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,</i>
The three-bay wide bungalow features an off-center entry, narrow weatherboard, eave brackets, and a front gable porch with squared balusters. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing |
| 629 North Lincoln Street | 000-7819-0573 | Other DHR ID#: 000-6743 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling features a centered entry framed by a Colonial Revival style door surround with fluted pilasters and a broken pediment. The house and dormers all contain paired windows and the roof has slightly flared eaves. The roof has a slight overhang supported by wood posts, simulating a one-story, three-bay wide porch. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing |
| 632 North Lincoln Street | 000-7819-0556 | Other DHR ID#: 000-6720 |
| <i>Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,</i>
The front gable porch of the three-bay wide dwelling features a 4-light diamond shaped window in the gable end and is supported by tapered wood posts atop stucco clad piers. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | |
| | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 96

- | | | |
|---|----------------------|--------------------------------|
| 635 North Lincoln Street | 000-7819-0572 | Other DHR-ID#: 000-6742 |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Queen Anne,</i>
Details on the three-bay wide house include square-edged 1
surrounds, a half-hipped porch with square-cut balusters, 1
corners, and a molded wood cornice and entablature. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 641 North Lincoln Street | 000-7819-0571 | Other DHR ID#: 000-6741 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The front gable porch has square wood columns atop rock-faced 1
concrete block piers and the gable end contains two paired 1
wood casement windows with 6-lights. On the north elevation, 1
there is a projecting square bay. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 700 North Lincoln Street | 000-7819-0581 | Other DHR ID#: 000-6751 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide dwelling, clad in narrow weatherboard, 1
features a centered entry, square-edged surrounds, wide eaves 1
over exposed rafter tails, and wood shingle clad gable ends. 1
The porch is supported by paired wood posts atop brick piers. 1
The large dormer features a walk-out deck with a single-leaf 1
door and two 1/1 windows. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 701 North Lincoln Street | 000-7819-0153 | |
| <i>Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1965</i>
This dwelling is four bays wide and features overhanging eaves, an aluminum encased boxed cornice, and rowlock
sills. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Non-contributing |
| 707 North Lincoln Street | 000-7819-0570 | Other DHR ID#: 000-6740 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide dwelling features square-edged surrounds, 1
wide eaves with exposed rafter tails, and a front gable porch 1
with tapered piers. The 4/1 windows are grouped together. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 713 North Lincoln Street | 000-7819-0569 | Other DHR ID#: 000-6739 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide dwelling features a shed roof porch, paired 1
windows, and wide, overhanging eaves. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 97

714 North Lincoln Street 000-7819-0582 *Other DHR ID#:* 000-6752

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Detailing on the three-bay wide dwelling includes wide eaves, 1
louvered openings in the gable end, a projecting square bay on 1
the first story, and corner brackets.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

717 North Lincoln Street 000-7819-0568 *Other DHR ID#:* 000-6738

Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,

The three-bay wide dwelling features some paired windows, wide 1
eaves, wide wood surrounds, and a shed roof porch. In the 1
gable end, there is a fixed oval-shaped window.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Non-contributing

802 North Lincoln Street 000-7819-0674 *Other DHR ID#:* 000-6845

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry with a 1
Colonial Revival style door surround with fluted pilasters and 1
a broken pediment. The windows have rowlock sills and the 1
cornice serves as a continuous lintel for the second story 1
windows.

Individual Resource Status: Single Dwelling

Contributing

803 North Lincoln Street 000-7819-0567 *Other DHR ID#:* 000-6737

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features four 6/1 paired window in 1
the dormer, wide eaves, cornerboards, and a slight overhang at 1
the second story. The hipped roof porch has square tapered 1
columns.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

807 North Lincoln Street 000-7819-0549 *Other DHR ID#:* 000-6713

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling has a centered entry, a shed roof 1
porch, and wide eaves. The dormer contains two 6/6 1
double-hung sash windows.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

808 North Lincoln Street 000-7819-0673 *Other DHR ID#:* 000-6844

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The two-bay wide bungalow has an asymmetrical gable roof with 1
wide eaves and brackets. The entry is framed by a transom and 1
5-light sidelights.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 98

- 812 North Lincoln Street** **000-7819-0672** **Other DHR ID#: 000-6843**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling has a centered entry with flanking 1
windows. The dormer contains two 6-light wood casement 1
windows.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Barbecue Pit **Non-contributing**
- 813 North Lincoln Street** **000-7819-0154**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1990
Two bays wide this dwelling features a bay window on the facade, overhanging eaves, and the off-center entry is
illuminated with 1-light and dado
panel sidelights.
Individual Resource Status: Single Dwelling **Non-contributing**
- 816 North Lincoln Street** **000-7819-0671** **Other DHR ID#: 000-6842**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The four-bay wide dwelling has a front gable porch with 1
square-cut balusters. The windows and doors have square-edged 1
surrounds.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 817 North Lincoln Street** **000-7819-0566** **Other DHR ID#: 000-6736**
Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,
The two-bay wide dwelling features a front gable porch with 1
round-butt shingles in the gable end. Details include wide 1
eaves, sidelights, and a box bay on the north elevation.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Non-contributing**
- 823 North Lincoln Street** **000-7819-0548** **Other DHR ID#: 000-6712**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The two-bay wide dwelling features wide eaves, a triple window 1
on the first story and a paired 1/1 window in the dormer. The 1
porch is supported by two-part columns atop of rock-faced 1
concrete block piers.
Individual Resource Status: Single Dwelling **Contributing**

North Monroe Street

- 308 North Monroe Street** **000-7819-0308** **Other DHR ID#: 000-5735**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick house has a projecting two-story bay on 1
the southeast side of the facade and a one-story, one-bay 1
brick porch on the northwest side. Brick detailing includes 1
rowlock sills, a heavy brick cornice below the parapet wall, 1
and a soldier course capping the parapet wall.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 99

- | | | |
|---|----------------------|--------------------------------|
| 410 North Monroe Street | 000-7819-0327 | Other DHR ID#: 000-5754 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay brick dwelling has a side passage entry and a 1
one-and-a-half story side bay. The windows have rowlock sills 1
and those on the first story have soldier lintels as well. 1
The dormer contains a six-over-six double-hung wood sash 1
window. | | |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 414 North Monroe Street | 000-7819-0332 | Other DHR ID#: 000-5759 |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,</i>
The three-bay brick dwelling has a centered entry framed by a 1
front gable portico with a segmental arch. Brick detailing 1
includes rowlock sills, a soldier course water table, a 1
Flemish bond raised brick beltcourse, and a rowlock cornice. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 415 North Monroe Street | 000-7819-0136 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Dutch Colonial Revival, ca 1945</i>
Two bays wide this dwelling features a shouldered chimney, and a large shed dormer on the facade with two sets
of paired windows. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| 418 North Monroe Street | 000-7819-0330 | Other DHR ID#: 000-5757 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The centered entry of the three-bay brick dwelling is framed 1
by a Colonial Revival door surround with ears and a heavy 1
entablature. The dormers each contain an eight-over-eight 1
double-hung wood sash window. Brick detailing includes 1
rowlock sills, jack arch lintels, a soldier course water 1
table, and a diagonal brick pattern at the cornice line. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 421 North Monroe Street | 000-7819-0321 | Other DHR ID#: 000-5748 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The front gable dormers of the three-bay house are clad in 1
wood weatherboard and each contains a six-over-six double-hung 1
wood sash window and a molded vergeboard. Brick detailing 1
includes slanted soldier lintels, rowlock sills, struck mortar 1
joints, and turned basketweave brick at the cornice. Cornice 1
returns grace the gabled roof. The garage is attached with a 1
hyphen. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 100

- | | | |
|---|----------------------|--------------------------------|
| 424 North Monroe Street | 000-7819-0325 | Other DHR-ID#: 000-5752 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The two-bay brick house has an enclosed side porch and a portico with modillions. Brick detailing includes a two course water table, rowlock sills, slanted soldier lintels with soldier brick "keystones," and an angled brick cornice. There are three dormers, two on the main house and one above the enclosed side porch. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 425 North Monroe Street | 000-7819-0324 | Other DHR ID#: 000-6751 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,</i>
The three-bay brick house has an off-center entry with patterned brick to the west of the door. The double-hung windows have rowlock sills and jack arch lintels. The diamond paned casement windows are set in irregular places on the facade. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 428 North Monroe Street | 000-7819-0328 | Other DHR ID#: 000-5755 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay brick house has a side passage entry framed by a Colonial Revival door surround with flush pilasters and a heavy entablature. Brick detailing includes rowlock sills, soldier lintels and a soldier course water table. There is a one-story, one-bay brick wing on the southeast side of the house. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 431 North Monroe Street | 000-7819-0137 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945</i>
Standing three bays across on the facade, this dwelling features a Flemish bond beltcourse, a soldier beltcourse above the basement level, rowlock sills, and a molded wood cornice with returns. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| 432 North Monroe Street | 000-7819-0133 | |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1940</i>
Four bays wide this dwelling features rowlock sills and soldier lintels on the first story. The side porch has been enclosed with multi-light windows and wood siding. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 101

- 435 North Monroe Street** **000-7819-0138** -
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
Three bays wide, this dwelling includes rowlock sills, brick jack arch lintels, and a rowlock beltcourse with continuous sills on the second story.
The center recessed entrance features a Colonial Revival door surround with a broken pediment with an urn, fluted pilasters, and a modillion cornice.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 436 North Monroe Street** **000-7819-0326** *Other DHR ID#: 000-5753*
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,
The three-bay brick house has a one-story, one-bay brick wing l on the southeast side of the facade and a front gable dormer l with a one-over-one metal sash replacement window. Brick l detailing includes rowlock sills, soldier lintels, and a l soldier course water table.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 440 North Monroe Street** **000-7819-0132**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
Three bays wide this dwelling features rowlock sills, soldier lintels, and a molded wood cornice. The center entrance has a wood Colonial Revival door surround with fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 445 North Monroe Street** **000-7819-0323** *Other DHR ID#: 000-5750*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick dwelling has a symmetrical facade with a l centered entry framed by a Federal style door surround with l fluted pilasters. The windows have soldier lintels and l rowlock sills. The side porch is enclosed with screening.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 500 North Monroe Street** **000-7819-0677** *Other DHR ID#: 000-6848*
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,
The three-bay wide dwelling has a projecting front gable bay l with a steeply pitched roof and a front facing chimney. There l are brick jack arch lintels and rowlock sills and the dormers l are pedimented.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 102

- | | | |
|---|----------------------|--------------------------------|
| 503 North Monroe Street | 000-7819-0562 | Other DHR-ID#: 000-6732 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling has a centered entry with a 1
crosssetted surround and cornice molding and flanking windows 1
with rowlock sills. The dormers each contain a 8/8 1
double-hung sash window. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 506 North Monroe Street | 000-7819-0689 | Other DHR ID#: 000-6860 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide Cape Cod has a wide entablature, rowlock 1
sills, a stone door surround, and triangular shaped louvered 1
ventilators in the gable ends. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 507 North Monroe Street | 000-7819-0561 | Other DHR ID#: 000-6731 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
Brick detailing on the four-bay wide dwelling includes 1
rowlock sills and soldier lintels. The entry is framed by 1
fluted pilasters and a front gable portico and the main block 1
is flanked by shed roof side wings. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 510 North Monroe Street | 000-7819-0688 | Other DHR ID#: 000-6859 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide bungalow has a centered entry framed by a 1
4-light transom and 3-light and panel sidelights. The dormer 1
has two 6-light casement windows and scroll-sawn exposed 1
rafter tails. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 511 North Monroe Street | 000-7819-0560 | Other DHR ID#: 000-6830 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
Brick detailing on the three-bay wide dwelling includes 1
rowlock sills and soldier lintels. The centered entry is 1
framed by fluted pilasters and a front gable portico. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 514 North Monroe Street | 000-7819-0687 | Other DHR ID#: 000-6858 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling features rowlock sills and an 1
octagonal shaped fixed window at the second story. The porch 1
is partially enclosed with 6-course American bond brickwork 1
and the open area of the porch has arched lintels. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 103

- 515 North Monroe Street** **000-7819-0660** -
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The three-bay wide dwelling features a shouldered chimney, rowlock sills, soldier lintels, and a soldier stringcourse.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 519 North Monroe Street** **000-7819-0658** *Other DHR ID#:* **000-6728**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The three-bay wide Cape Cod house features a front gable portico with a segmental soffit, rowlock sills, and a soldier stringcourse. The dormers each contain a 6/6 double-hung sash window.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 520 North Monroe Street** **000-7819-0686** *Other DHR ID#:* **000-6857**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The two-bay wide dwelling has an attached garage on the south elevation. Both the shed roof dormer and the gable dormer contain 6/6 windows. The door is framed by fluted pilasters and a paneled lintel and there is a heavy dentil molded cornice.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 524 North Monroe Street** **000-7819-0685** *Other DHR ID#:* **000-6856**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The three-bay wide dwelling features rowlock sills, jack arch lintels on the first story windows and a Colonial Revival style door surround with fluted pilasters and molded pediment with a fan motif.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**
- 525 North Monroe Street** **000-7819-0768** *Other DHR ID#:* **000-6727**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Bungalow/Craftsman,**
The three-bay wide dwelling has a full-width front porch with a shed roof. The windows have wide, square-edged surrounds.
Individual Resource Status: **Single Dwelling** **Contributing**
- 530 North Monroe Street** **000-7819-0684** *Other DHR ID#:* **000-6855**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The two-bay wide dwelling has a front gable bay with both paired and triple windows, rowlock sills, and a rectangular louvered ventilator in the gable end. There is an eyebrow arch above the entry and the dormer contains a 6/6 window.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 104

- 534 North Monroe Street** **000-7819-0683** **Other DHR ID#: 000-6854**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
Detailing on the three-bay wide dwelling includes rowlock l
sills, soldier lintels and a front gable vestibule with a l
round-arched opening and double rowlock lintel. There is an l
attached garage set below grade, with a one-story wing above l
it. The wing has a flat roof with a balustrade and paired l
windows.
Individual Resource Status: Single Dwelling **Contributing**
- 538 North Monroe Street** **000-7819-0682** **Other DHR ID#: 000-6853**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
Set on a raised basement, the three-bay wide house has rowlock l
sills, a centered entry, and brick brackets that at one time l
supported window boxes. The two end dormers contain 6/6 l
windows and the center dormer has paired diamond paned l
casement windows.
Individual Resource Status: Single Dwelling **Contributing**
- 601 North Monroe Street** **000-7819-0766** **Other DHR ID#: 000-6725**
Primary Resource Information: Single Dwelling, Stories 1, Style: Colonial Revival,
The four-bay wide dwelling features a Colonial Revival style l
door surround with pilasters and a molded lintel. The windows l
have rowlock sills.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 609 North Monroe Street** **000-7819-0765** **Other DHR ID#: 000-6724**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide dwelling features a random rubble stone l
facade with stone quoins and jack arch lintels. Other details l
include a dentiled cornice, an attached garage on the rear of l
the house, and rowlock sills.
Individual Resource Status: Single Dwelling **Contributing**
- 617-619 North Monroe Street** **000-7819-0559** **Other DHR ID#: 000-6723**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The ten-bay wide apartment building features rowlock sills l
and some paired windows. The two entries have Colonial l
Revival style door surrounds with fluted pilasters, cornice l
moldings, and pediments.
Individual Resource Status: Multiple Dwelling **Contributing**
- 624-626 North Monroe Street** **000-7819-0592** **Other DHR ID#: 000-6772**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The 10-bay wide apartment building features paired windows, l
rowlock sills, a soldier stringcourse, and Colonial l
Revival style door surrounds with pediments and fluted l
pilasters. The outermost windows on the first story have l
rowlock surrounds.
Individual Resource Status: Multiple Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 105

- 627 North Monroe Street** **000-7819-0149** -
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1980
This dwelling is three bays wide and features a boxed cornice, overhanging eaves, and thin aluminum encased surrounds. The entry is illuminated with 3-light and panel sidelights.
Individual Resource Status: Single Dwelling **Non-contributing**
- 629 North Monroe Street** **000-7819-0150**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1973
This split level dwelling is five bays wide and includes features such as rowlock sills, overhanging eaves, and a wood cornice. The entry is illuminated with 3-light sidelights. The chimney is half shouldered.
Individual Resource Status: Single Dwelling **Non-contributing**
- 632-634 North Monroe Street** **000-7819-0591** *Other DHR ID#: 000-6761*
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The 10-bay wide apartment building has some paired windows and 1 Colonial Revival style door surrounds with fluted pilasters 1 and molded pediments. Details include rowlock sills and 1 soldier course water table. The outermost windows on the 1 first story are framed by rowlock surrounds and soldier 1 lintels.
Individual Resource Status: Multiple Dwelling **Contributing**
- 700 North Monroe Street** **000-7819-0597** *Other DHR ID#: 000-6767*
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide apartment building features slightly 1 projecting concrete sills and a concrete stringcourse. The 1 entry is framed by fluted pilasters, a lintel, and 1 cornerblocks with "X" patterns.
Individual Resource Status: Multiple Dwelling **Contributing**
- 704 North Monroe Street** **000-7819-0598** *Other DHR ID#: 000-6768*
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide apartment building features some paired 1 windows, rowlock sills, a corbeled brick stringcourse, soldier 1 lintels, and a pedimented portico. The entry is framed by 1 fluted pilasters, a lintel, and cornerblocks with "X" designs.
Individual Resource Status: Multiple Dwelling **Contributing**
- 708 North Monroe Street** **000-7819-0599** *Other DHR ID#: 000-6769*
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide apartment building is side-oriented with a 1 pedimented portico with scroll-sawn brackets on the south 1 elevation. The windows on the first story have paneling below 1 them and there are brick dentils at the roofline.
Individual Resource Status: Multiple Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 106

- 712 North Monroe Street 000-7819-0653 *Other DHR ID#:* 000-6824
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The four-bay wide apartment building has textured brick, a
stone stringcourse, concrete sills, some paired windows and
reeded pilasters at the entry. There is a corbeled
rectangular design in the wall above the entry. The front
gable hood has scroll-sawn brackets, weatherboard in the
gable end, and a slate roof.
Individual Resource Status: **Multiple Dwelling** **Contributing**
- 716 North Monroe Street 000-7819-0654 *Other DHR ID#:* 000-6825
Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
The four-bay wide apartment building features textured brick,
a stone stringcourse, concrete sills, and a corbeled brick
detail in the wall above the entry. The entry features
reeded pilasters and a front gable hood with scroll-sawn
brackets and a slate roof.
Individual Resource Status: **Multiple Dwelling** **Contributing**
- 720 North Monroe Street 000-7819-0655 *Other DHR ID#:* 000-6826
Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
Masonry details on the four-bay wide apartment building
include textures brick, rowlock sills, soldier lintels,
a corbeled stringcourse, and a rectangular corbeled
design in the wall above the entry. The entry has
reeded pilasters and a front gable hood with scroll-sawn
brackets and a slate roof.
Individual Resource Status: **Multiple Dwelling** **Contributing**
- 724 North Monroe Street 000-7819-0656 *Other DHR ID#:* 000-6827
Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
Masonry detailing on the four-bay wide apartment
building includes a corbeled cornice, a rectangular
corbeled design above the entry, rowlock sills,
soldier lintels, and textured brick. The entry has
reeded pilasters and a front gable hood with scroll-sawn
brackets and a slate roof.
Individual Resource Status: **Multiple Dwelling** **Contributing**
- 737 North Monroe Street/3550 Wilson Boulevard 000-7819-0769 *Other DHR ID#:* 000-0453
Primary Resource Information: **School, 1911**
Clarendon (Matthew Maury) School
Individual Resource Status: **School** **Contributing (Individual NR)**
- 740 North Monroe Street/3606 Wilson Boulevard 000-7819-0657 *Other DHR ID#:* 000-6828
Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
The 17-bay wide apartment building has a rectangular
main block with staggered wings. Details include
paired windows, gablets with louvered vents,
hipped and shed roof door hoods, and rowlock
sills. Two entries have corbeled lintels and
surrounds, and one entry has brick quoins.
Individual Resource Status: **Multiple Dwelling** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 107

North Nelson Street

- 224 North Nelson Street** **000-7819-0163**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1935**
This three bay wide Cape Cod features a center entrance flanked by paired windows. The entry has a Colonial Revival wood door surround with a paneled entablature. A screened porch is located on the side elevation. The facade has two gable dormers.
Individual Resource Status: **Single Dwelling** **Contributing**
- 228 North Nelson Street** **000-7819-0283** *Other DHR ID#:* **000-5710**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The three-bay brick house has a centered entry flanked by 1 fluted pilasters. The windows have rowlock sills and soldier 1 lintels. The three dormers, clad in asbestos shingles, each 1 contain a six-over-six double-hung wood sash window.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Non-contributing**
- 232 North Nelson Street** **000-7819-0285** *Other DHR ID#:* **000-5712**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**
The "Cape Cod" three-bay brick house has a centered entry 1 framed by a wood door surround with fluted pilasters. Brick 1 detailing includes rowlock sills and soldier lintels. The 1 three front gable dormers each contain a six-over-six 1 double-hung wood sash window.
Individual Resource Status: **Single Dwelling** **Contributing**
- 306 North Nelson Street** **000-7819-0063**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Other, ca 1940**
Features of this three bay wide dwelling include gable wall dormers, overhanging eaves, a molded wood boxed cornice, and jack arch lintels with brick keystones. The center entrance features a Colonial Revival door surround with fluted pilasters and a dentilated cornice.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 404 North Nelson Street** **000-7819-0124**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940**
Features of this five bay wide dwelling include cast concrete sills, keystone lintels, and a molded wood denticulated cornice. The off-center recessed door is round arched and features a canted reveal. It has two gable wall dormers on the facade.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 407 North Nelson Street** **000-7819-0336** *Other DHR ID#:* **000-5763**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival,**
The three-bay brick house has a side passage entry and a 1 one-story, one-bay porch with a shed roof on the northwest 1 side of the house. The windows are adorned with rowlock sills 1 and soldier lintels.
Individual Resource Status: **Garage** **Contributing**
Individual Resource Status: **Single Dwelling** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 108

- 411 North Nelson Street** **000-7819-0125**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Three bays wide this dwelling features rowlock sills, a soldier stringcourse, and a plain wood door surround. The cross gable porch roof is clad with beaded board siding.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 415 North Nelson Street** **000-7819-0126**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1945
Five bays wide this dwelling includes rowlock sills, soldier course lintels, a front vestibule with an arched doorway with a double course of headers.
Individual Resource Status: Single Dwelling **Contributing**
- 418 North Nelson Street** **000-7819-0122**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Two bays wide, this dwelling features rowlock sills, a boxed and molded wood cornice, and a canted bay window on the first story with a copper roof. The center entry features a Colonial Revival door surround with an elliptical arch, fluted pilasters, and a denticulated entablature.
Individual Resource Status: Single Dwelling **Contributing**
- 419 North Nelson Street** **000-7819-0127**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Features of this four bay wide dwelling include rowlock sills, jack arch lintels with brick keystones, and spandrel panels below the first story windows. The off-center entry features a Colonial Revival door surround with a scrolled broken pediment. Located on the rear elevation is a two-story shed roof addition.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 424 North Nelson Street** **000-7819-0121**
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940
Three bays wide, this dwelling features rowlock sills, overhanging eaves, and a brick corbeled cornice with returns. A wood louvered vent is seen in the gable. The chimney is shouldered.
Individual Resource Status: Single Dwelling **Contributing**
- 428 North Nelson Street** **000-7819-0120**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1939
Two bays wide, this dwelling features rowlock sills, a molded boxed wood cornice with returns, and a corbeled lintel above the first story tripartite window. A two-story frame addition is seen on the side elevation.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 109

- 429 North Nelson Street** **000-7819-0128**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca. 1940**
This two-story, four-bay 6:1 bond brick masonry dwelling sits upon a solid stretcher bond brick foundation, and is capped by a gabled roof sheathed with asphalt shingles. The facade fenestration consists of three wood six-pane fixed windows, one wood single-paned fixed window, and five wood 6/6 sash windows. The structure is further defined by an exterior end brick chimney, a Colonial Revival door surround, rowlock sills, and jack arches with keystones above two of the windows. There is a two-story wood-framed shed addition on the rear of the structure.
Individual Resource Status: **Single Dwelling** **Contributing**
- 432 North Nelson Street** **000-7819-0119**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival, ca 1945**
Three bays wide, this dwelling includes features as rowlock sills, rowlock beltcourse, and a molded wood cornice with returns. The central entrance has a Colonial Revival door surround with a broken pediment, fluted pilasters, and a modillion cornice.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 433 North Nelson Street** **000-7819-0129**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940**
Three bays wide this dwelling features rowlock sills, and jack arch lintels with brick keystones. The center entrance features a Colonial Revival door surround with a full pediment and dentilated cornice. Two gable wall dormers are seen on the facade.
Individual Resource Status: **Single Dwelling** **Contributing**
- 436 North Nelson Street** **000-7819-0118**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival, ca 1945**
This building measures three bays wide and includes rowlock sills, jack arch lintels with brick keystones, a rowlock beltcourse above the basement story, and a dogtooth brick cornice.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 437 North Nelson Street** **000-7819-0130**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940**
This dwelling is three bays wide and features soldier lintels, rowlock sills, a wood cornice, and two gable dormers on the front cross gable. The porch sits on a brick pier foundation.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 440 North Nelson Street** **000-7819-0117**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival, ca 1945**
This building is three bays wide and features soldier lintels, rowlock sills, a molded wood cornice with returns, and grapevine joints. The side gable roof porch is screened.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 110

- 441 North Nelson Street** **000-7819-0131**
- Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1945*
Three bays wide this dwelling includes rowlock sills, soldier lintels, a soldier beltcourse above the basement story, one gable dormer, and a stepped shouldered chimney. Located on the side elevation is a one-story frame addition.
- Individual Resource Status: Single Dwelling* **Contributing**
Individual Resource Status: Garage **Contributing**
- 500 North Nelson Street** **000-7819-0690** *Other DHR ID#: 000-6861*
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,*
The three-bay wide Cape Cod has rowlock sills and dormers with 1 6/6 windows. The centered entry is flanked by the 8/8 windows 1 and framed by a front gable portico.
- Individual Resource Status: Garage* **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 503 North Nelson Street** **000-7819-0678** *Other DHR ID#: 000-6849*
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,*
The three-bay wide dwelling has two soldier course 1 stringcourses; one lies between the first and second stories 1 and the other imitates a water table. The entry is framed by 1 a Colonial Revival style door surround with fluted pilasters 1 and a broken pediment. There is a shed roof wing on the south 1 elevation.
- Individual Resource Status: Garage* **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 508 North Nelson Street** **000-7819-0691** *Other DHR ID#: 000-6862*
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,*
The two-bay wide dwelling has a three-sided canted bay, a 1 dentil molded cornice, and rowlock sills. The entry has a 1 soldier lintel and is framed by a Half-hipped portico with 1 Tuscan posts.
- Individual Resource Status: Garage* **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 509 North Nelson Street** **000-7819-0679** *Other DHR ID#: 000-6850*
- Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,*
The three-bay wide house has a centered entry with a front 1 gable portico and windows with rowlock sills and soldier 1 lintels. On the south elevation, there is a one-story wood 1 frame wing with weatherboard siding and a half-hipped roof.
- Individual Resource Status: Single Dwelling* **Contributing**
Individual Resource Status: Garage **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 111

- 510 North Nelson Street** **000-7819-0692** **Other DHR ID#: 000-6863**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide Cape Cod has a slightly projecting front l
gable bay that acts as a vestibule; it contains weatherboard l
in the gable end and a Colonial Revival style door surround l
with fluted pilasters and a dentiled lintel. The garage is l
attached and the dormers each contain a 6/6 window. The l
window has a rowlock sill and a soldier lintel.
Individual Resource Status: Single Dwelling **Contributing**
- 514 North Nelson Street** **000-7819-0693** **Other DHR ID#: 000-6864**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling has a steeply pitched roof. The l
centered entry has a soldier lintel and is flanked by windows l
with rowlock sills and soldier lintels.
Individual Resource Status: Single Dwelling **Contributing**
- 515 North Nelson Street** **000-7819-0680** **Other DHR ID#: 000-6851**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,
The three-bay wide brick dwelling features rowlock sills and a l
shouldered chimney. The house sits on a raised foundation and l
has a shed roof porch.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 518 North Nelson Street** **000-7819-0694** **Other DHR ID#: 000-6865**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling has rowlock sills at the windows l
and a soldier lintel over the door. The porch has a shed roof l
and a metal balustrade.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 519 North Nelson Street** **000-7819-0681** **Other DHR ID#: 000-6852**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other,
The three-bay wide dwelling has a projecting gable bay with a l
pedimented gable end and a triangular shaped, louvered l
ventilator. Rowlock sills lie beneath the tripartite windows. l
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 526 North Nelson Street** **000-7819-0695** **Other DHR ID#: 000-6866**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other,
The three-bay wide dwelling has a stretcher bond veneer on the l
facade, a tripartite window, and a projecting gable bay with l
vinyl siding in the gable end. The entry is covered by a shed l
roof portico.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 112

- | | | |
|---|----------------------|--------------------------------|
| 530 North Nelson Street | 000-7819-0696 | Other DHR ID#: 000-6867 |
| <i>Primary Resource Information: Multiple dwelling, Stories 3, Style: Colonial Revival,</i>
The three-bay wide multiple dwelling has the appearance of a 1
single dwelling. It has a front gable portico, rowlock sills, 1
soldier lintels on the second story windows, and rowlock 1
lintels on the first story windows. | | |
| <i>Individual Resource Status: Barbecue Pit</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| 620-622 North Nelson Street | 000-7819-0624 | Other DHR ID#: 000-6795 |
| <i>Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,</i>
The four-bay wide twin dwelling features rowlock sills and a 1
rowlock stringcourse. The porches have shed roofs and the 1
wrap-around porch is one story in height, two bays wide, and 1
one bay deep. | | |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| 621-623 North Nelson Street | 000-7819-0593 | Other DHR ID#: 000-6763 |
| <i>Primary Resource Information: Multiple Dwelling, Stories 2.5, Style: Colonial Revival, ca. 1940</i>
Parged Concrete Foundation, Wood Frame Structural System with Facing and Weatherboard, Side Gable Roof
with Asphalt Shingle | | |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| 624-626 North Nelson Street | 000-7819-0625 | Other DHR ID#: 000-6763 |
| <i>Primary Resource Information: Multiple dwelling, Stories 3, Style: Colonial Revival,</i>
The four-bay wide twin dwelling features 6-course American 1
bond veneer, rowlock sills, and a front gable bay. There are 1
projecting window bays beside the entries, both of which are 1
covered by hoods. | | |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| 625-627 North Nelson Street | 000-7819-0594 | Other DHR ID#: 000-6764 |
| <i>Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,</i>
The four-bay wide twin dwelling features a projecting square 1
bay on the facade and brick piers on the porch. The gable end 1
is clad in asbestos shingles. | | |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| 628-630 North Nelson Street | 000-7819-0626 | Other DHR ID#: 000-6797 |
| <i>Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,</i>
The four-bay wide twin dwelling features rowlock sills and a 1
rowlock stringcourse that acts as a continuous sill for the 1
second story windows. The porches have shed roofs and wrought 1
iron balustrades. | | |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 113

629-631 North Nelson Street 000-7819-0595 Other DHR ID#: 000-6765

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The brick veneer of the four-bay wide twin dwelling is laid in 1
6-course American bond. Details include rowlock sills, wood 1
weatherboard cladding in the gable end, projecting window bays 1
on the first story, and extended eaves that simulate entry 1
hoods.

Individual Resource Status: **Multiple Dwelling**

Contributing

632-634 North Nelson Street 000-7819-0627 Other DHR ID#: 000-6798

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide twin dwellings have shed roof porches with 1
metal balustrades. There is a stretcher bond stringcourse 1
that acts as a continuous sill for the second story windows.

Individual Resource Status: **Multiple Dwelling**

Contributing

633-635 North Nelson Street 000-7819-0596 Other DHR ID#: 000-6766

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide twin dwelling has a projecting front gable 1
bay, a triple window, a box bay on the north elevation, and a 1
louvered opening in the gable end. The door surrounds feature 1
fluted pilasters.

Individual Resource Status: **Multiple Dwelling**

Contributing

636-638 North Nelson Street 000-7819-0628 Other DHR ID#: 000-6799

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide twin dwelling has a stretcher bond 1
stringcourse that acts as a continuous sill for the second 1
story windows. The porches have shed roofs and the 1
wrap-around porch is one story in height, two bays in width, 1
and one bay deep.

Individual Resource Status: **Shed**

Non-contributing

Individual Resource Status: **Multiple Dwelling**

Contributing

700-702 North Nelson Street 000-7819-0600 Other DHR ID#: 000-6770

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide twin dwelling features rowlock sills, 1
soldier lintels at the first story, and a Colonial Revival 1
style door surround with fluted pilasters, and a broken 1
pediment with dentil molding. The entrance to 700 North 1
Nelson Street is located on the south elevation.

Individual Resource Status: **Shed**

Non-contributing

Individual Resource Status: **Multiple Dwelling**

Contributing

701-703 North Nelson Street 000-7819-0666 Other DHR ID#: 000-6835

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide twin dwelling has a slightly projecting 1
front gable bay, rowlock sills, some soldier lintels, a 1
louvered vent in the gable end, and a one-story side porch. 1
The entry has a Colonial Revival style door surround with a 1
broken pediment, finial, dentil modling, and fluted pilasters.

Individual Resource Status: **Multiple Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 114

- | | | |
|--|----------------------|--------------------------------|
| 704-706 North Nelson Street | 000-7819-0601 | Other DHR ID#: 000-6771 |
| <i>Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,</i>
The four-bay wide twin dwelling features rowlock sills, 1
soldier lintels on the first story windows, and a Colonial 1
Revival style door surround with fluted pilasters, a 1
semi-circular lintel, and dentil molding. The entrance to 704 1
North Nelson Street is on the south elevation. | | |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| 705-707 North Nelson Street | 000-7819-0665 | Other DHR ID#: 000-6834 |
| <i>Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide twin dwelling features rowlock sills, some 1
soldier lintels, two tripartite windows, and a Colonial 1
Revival style door surround with a molded, round-arched lintel 1
and fluted pilasters. The side entry has a front gable 1
portico with a slate roof and metal post supports. | | |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| 708-710 North Nelson Street | 000-7819-0602 | Other DHR ID#: 000-6772 |
| <i>Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,</i>
Brick detailing on the four-bay wide twin dwelling includes rowlock sills and soldier lintels on the first story
windows. The entries are framed by Colonial Revival style door surrounds with fluted pilasters and round-arched
pediments with dentil molding and sunburst motifs. | | |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| 709-711 North Nelson Street | 000-7819-0664 | Other DHR ID#: 000-6833 |
| <i>Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,</i>
The four-bay wide twin dwelling has two Colonial Revival style 1
door surrounds with molded fanlight motifs, dentil molding, 1
and fluted pilasters. The windows have rowlock sills and some 1
have soldier lintels. | | |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 712-714 North Nelson Street | 000-7819-0603 | Other DHR ID#: 000-6773 |
| <i>Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,</i>
The four-bay wide twin dwelling features rowlock sills and 1
soldier lintels on the first story windows. The entry is 1
framed by a Colonial Revival style door surround with fluted 1
pilasters and a round-arched lintel with dentil molding and a 1
sunburst motif. The entry to 714 North Nelson Street is on 1
the north elevation. | | |
| <i>Individual Resource Status: Multiple Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 115

- 713-715 North Nelson Street** **000-7819-0663** **Other DHR ID#: 000-6832**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide twin dwelling has a Colonial Revival style 1 door surround with fluted pilasters, a round-arched lintel, 1 and dentil molding. There are two tripartite windows on the 1 facade and the windows have rowlock sills and some have 1 soldier lintels. One entrance is on the facade and the other 1 is on the north elevation.
Individual Resource Status: Multiple Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 716--718 North Nelson Street** **000-7819-0604** **Other DHR ID#: 000-6774**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide twin dwelling features rowlock sills, soldier lintels on 1 the first story windows, a horizontal vinyl sash window at the basement 1 level, and a front gable bay with a narrow, elongated window opening. The 1 entry is framed by a Colonial Revival style door surround with fluted 1 pilasters and a broken pediment with dentil molding. The entrance to 718 1 North Nelson Street is on the north elevation.
Individual Resource Status: Multiple Dwelling **Contributing**
- 717-719 North Nelson Street** **000-7819-0662** **Other DHR ID#: 000-6731**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide twin dwelling has two Colonial REvival style 1 door surrounds with fluted pilasters, molded fanlight motifs, 1 and dentil molding. The windows have rowlock sills and some 1 have soldier lintels.
Individual Resource Status: Multiple Dwelling **Contributing**
- 721-723 North Nelson Street** **000-7819-0661** **Other DHR Id #: 000-6830**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide twin dwelling has a slightly projecting front gable bay, textured brick, and one entrance on the facade and the other on the north elevation. Details include rowlock sills, soldier lintels, and a door surround with fluted pilasters.
Individual Resource Status: Multiple Dwelling **Contributing**
- 726 North Nelson Street** **000-7819-0667** **Other DHR ID#: 000-6836**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The nine-bay wide apartment building features wide eaves, a 1 corbeled stringcourse, rowlock sills, some paired windows, and 1 a louvered ventilator in the gable end. The entry is framed 1 by a Colonial Revival style door surround with fluted 1 pilasters, dentil molding, and a broken pediment.
Individual Resource Status: Multiple Dwelling **Contributing**
- 737 North Nelson Street/3610 Wilson Boulevard** **000-7819-0659** **Other DHR ID#: 000-6729**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The 17-bay wide apartment building has a rectangular main block with flat roofed side wings. Details include paired windows, rowlock sills, gablets with louvered vents, and entry hoods with both shed and half-hipped roofs. Two doors have soldier, corbeled surrounds, and two have brick quoins.
Individual Resource Status: Multiple Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 116

738 North Nelson Street **000-7819-0668** **Other DHR JD#: 000-6837**

Primary Resource Information: Multiple dwelling, Stories 2, Style: Other,

The nine-bay wide apartment building has some paired windows, 1 rowlock sills, and a corbeled brick stringcourse above the 1 second story windows.

Individual Resource Status: Multiple Dwelling **Contributing**

North Norwood Street

400 North Norwood Street **000-7819-0110**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1945

This dwelling measures three bays across and features rowlocks sills, a molded wood cornice with returns, and paneled spandrels. The center entry features an elliptical transom with leaded lights and leaded sidelights.

Individual Resource Status: Single Dwelling **Contributing**

Individual Resource Status: Garage **Contributing**

405 North Norwood Street **000-7819-0112**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940

Three bays wide, this dwelling features rowlock sills, a molded wood boxed cornice with a wide fascia board, and a front gable vestibule. The center entry has a corbeled brick surround.

Individual Resource Status: Single Dwelling **Contributing**

Individual Resource Status: Garage **Contributing**

412 North Norwood Street **000-7819-0108**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940

Three bays wide, this dwelling features rowlock sills, denticulated molded wood cornice, and wood louvered shutters.

Individual Resource Status: Single Dwelling **Contributing**

Individual Resource Status: Garage **Contributing**

415 North Norwood Street **000-7819-0113**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940

This dwelling measures three bays across and features rowlock sills, a wood cornice, and a side screened porch with a roof balcony.

Individual Resource Status: Single Dwelling **Contributing**

Individual Resource Status: Garage **Contributing**

416 North Norwood Street **000-7819-0107**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945

Three bays wide, this dwelling features rowlock sills, rowlock panels above the windows, a wood cornice, and square balusters. It has two gable dormers on the facade.

Individual Resource Status: Single Dwelling **Contributing**

Individual Resource Status: Garage **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 117

419 North Norwood Street 000-7819-0114

Primary Resource Information: Single Dwelling, Stories 2, Style:

This dwelling measures three bays across and features soldier lintels, rowlock sills, and a soldier stringcourse above the basement story. The center entry is illuminated by 4-light and dado sidelights. The side screened porch has a roof balcony, as well as the portico.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

424 North Norwood Street 000-7819-0106

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

This building measures three bays across and features a boxed cornice, soldier lintels, and cast concrete lug sills. The side porch is enclosed.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

425 North Norwood Street 000-7819-0115

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

Features of this three bay wide dwelling include rowlock sills, a wood cornice, square balusters, wood door surround, and two gable dormers on the facade.

Individual Resource Status: Single Dwelling

Contributing

429 North Norwood Street 000-7819-0116

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

This building has rowlock sills for its windows.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

430 North Norwood Street 000-7819-0105

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940

Features of this three bay wide dwelling include rowlock sills, a soldier beltcourse above the basement story, and a molded wood cornice. The side enclosed porch has a roof balcony.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

502 North Norwood Street 000-7819-0642 Other DHR ID#: 000-6813

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The three-bay wide dwelling has a steeply pitched front gable bay with vinyl siding in the gable end. The entry is framed by stone veneer and features a Tudor Revival style arch, fluted pilasters, and carved oak leaf spandrels at the corners.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 118

503 North Norwood Street 000-7819-0708 Other DHR ID#: 000-6879

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide Cape Cod has a centered entry framed by a
Colonial Revival style door surround with fluted pilasters and
a dentil molded lintel. Detailing includes rowlock sills, 1
basketweave chimney caps, a dentiled cornice, a steeply
pitched roof, and a side porch with a half-hipped roof.

Individual Resource Status: Single Dwelling

Contributing

506 North Norwood Street 000-7819-0643 Other DHR ID#: 000-6814

Primary Resource Information: Single Dwelling, Stories 1, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry with a
Colonial Revival style door surround with a broken pediment
and fluted pilasters. The windows have rowlock sills and the
dormers are wall dormers. There is a shed roof side porch on
the south elevation.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

507 North Norwood Street 000-7819-0707 Other DHR ID#: 000-6878

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The entry of the two-bay wide house is covered by a flared,
half-hipped hood with standing seam metal cladding and metal
brackets. Detailing on the house includes rowlock sills, 1
tripled windows, a dentiled cornice, and brick brackets to
support window boxes.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

510 North Norwood Street 000-7819-0644 Other DHR ID#: 000-6833

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The three-bay wide dwelling has a projecting front gable bay
with a recessed entry behind the round-arched opening with a
double rowlock surround. The door is round-arched and the
dormer contains paired 6-light casement windows.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

511 North Norwood Street 000-7819-0706 Other DHR ID#: 000-6877

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The five-bay wide dwelling has a centered entry with a
Colonial Revival style door surround with fluted pilasters and
a round arched lintel. Details include a dentiled cornice
above a flush entablature, rowlock sills, and brick brackets
to support window boxes on the first story.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 119

- 514 North Norwood Street** **000-7819-0645** **Other DHR ID#: 000-6816**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The five-bay wide Cape Cod has a centered entry that is framed by pilasters, a molded lintel, and a four-light transom. The wall dormers contain 6/6 windows and all of the windows have rowlock sills. Beneath the first story windows on the facade, there are corbeled brick brackets to support window boxes.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 515 North Norwood Street** **000-7819-0705** **Other DHR ID#: 000-6876**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide main block is characteristic of Cape Cod houses, featuring a centered entry with a Colonial Revival style door surround with fluted pilasters and a molded lintel and two gable dormers each containing a 6/6 window. On the south elevation, there is an attached garage. Details include rowlock sills, a basketweave chimney cap, a dentiled cornice, cornice returns, and brick brackets for window boxes.
Individual Resource Status: Single Dwelling **Contributing**
- 518 North Norwood Street** **000-7819-0771**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
Three bays wide, this dwelling is constructed in a 6-course American bond. It sits on a solid stretcher bond brick foundation, and is capped with a side gable roof with asphalt shingles. The building features rowlock sills, a boxed aluminum cornice, and a shouldered chimney.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 519 North Norwood Street** **000-7819-0704** **Other DHR ID#: 000-6875**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The two-bay wide dwelling has a triple window on the first story, an attached garage on the south elevation, a front gable portico, and a side porch on the north elevation. Detailing includes a dentiled cornice and rowlock sills. Additions and alteration.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 522 North Norwood Street** **000-7819-0646** **Other DHR ID#: 000-6817**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The two-bay wide main block is flanked by one-story wings, one of which is a screen enclosed porch and the other which is an attached garage. The main block features rowlock sills and a Colonial Revival style door surround with fluted pilasters, a round-arched pediment, and dentil molding.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 526 North Norwood Street** **000-7819-0647** **Other DHR ID#: 000-6818**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide Cape Cod has a centered entry beneath a front gable portico with square-cut balusters. The windows have rowlock sills and the dormers each contain a 6/6 window.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 120

527 North Norwood Street 000-7819-0703 Other DHR ID#: 000-6874

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has rowlock sills, a shed roof l side porch, and a Colonial Revival style door surround with a l broken pediment, a finial, and fluted pilasters.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

530 North Norwood Street 000-7819-0648 Other DHR ID#: 000-6819

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a Cape Cod form and the l centered entry is set beneath a front gable portico with l squared balusters. The windows have rowlock sills and the l dormers each contain a 6/6 window.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

533 North Norwood Street 000-7819-0702 Other DHR ID#: 000-6873

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

Details on the three-bay wide dwelling include rowlock sills, l gablets, a centered entry, a side porch, and chimneys with l corbeled caps. The portico has a front gable with a l round-arched entry.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

534 North Norwood Street 000-7819-0649 Other DHR ID#: 000-6820

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a projecting front gable l vestibule with a flared roof. The windows have rowlock sills l and the chimney is shouldered with a soldier cap.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

537 North Norwood Street 000-7819-0701 Other DHR ID#: 000-6872

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has shouldered chimneys with l corbeled caps, rowlock sills, 6/6 windows in the dormers, and l a diminutive shed roof hood that extends over the first story l openings.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

558 North Norwood Street 000-7819-0650 Other DHR ID#: 000-6821

Primary Resource Information: Single Dwelling, Stories 1, Style: Other,

The three-bay wide dwelling has a front gable portico, some l paired windows, and rowlock sills. There is a projecting l gable bay on the north elevation.

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 121

559 North Norwood Street 000-7819-0700 *Other DHRJD#:* 000-6871

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling originally had a bungalow form. It

has scroll-sawn exposed rafter tails, a triple window, and

a three-light transom.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

North Oakland Street

8 North Oakland Street 000-7819-0164

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940

This dwelling measures three bays wide and has an attached garage below ground level. The dwelling features

rowlock sills and a soldier course

frieze.

Individual Resource Status: Single Dwelling

Contributing

14 North Oakland Street 000-7819-0165

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940

This dwelling measures three bays across and features a soldier course frieze, rowlock sills, and a round-arched

doorway. Two shed roof dormers

are seen on the facade.

Individual Resource Status: Single Dwelling

Contributing

18 North Oakland Street 000-7819-0166

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940

Three bays wide, this dwelling features rowlock sills, a round-arched doorway, and a sloping roof on the front

vestibule. Two gable dormers are

seen on the facade.

Individual Resource Status: Single Dwelling

Contributing

22 North Oakland Street 000-7819-0167

Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1940

Three bays wide, this dwelling features rowlock sills, round arched door with small square balusters, wide eaves,

and lug lintels.

Individual Resource Status: Single Dwelling

Contributing

28 North Oakland Street 000-7819-0168

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940

This dwelling measures three bays across and features a front vestibule with a sloping gable roof, a round-arched

door, rowlock sills, and the garage

door has a lug lintel. Two shed roof dormers are seen on the facade.

Individual Resource Status: Single Dwelling

Contributing

32 North Oakland Street 000-7819-0169

Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1940

Measuring three bays wide, this dwelling features rowlock sills, a lug lintel over the garage door, and overhanging

eaves.

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 122

- 36 North Oakland Street** **000-7819-0170**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1950
This dwelling measures three bays across and features rowlock sills, a corner enclosed porch, and 1-light sidelights around the door.
Individual Resource Status: Single Dwelling **Contributing**
- 40 North Oakland Street** **000-7819-0171**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1950
This dwelling is three bays wide, has rowlock sills, and overhanging eaves.
Individual Resource Status: Single Dwelling **Contributing**
- 44 North Oakland Street** **000-7819-0172**
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940
This dwelling has a vestibule with a sloping front gable roof. It features rowlock sills, overhanging eaves, and a round-arched door. Two shed dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 100 North Oakland Street** **000-7819-0173**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
This dwelling measures four bays wide and has a garage below ground level with a screened porch above. The house features rowlock sills, a fascia board, and a plain wood door surround.
Individual Resource Status: Single Dwelling **Contributing**
- 106 North Oakland Street** **000-7819-0174**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1936
Three bays wide, this dwelling features rowlock sills, soldier lintels, and a below ground level garage.
Individual Resource Status: Single Dwelling **Contributing**
- 110 Oakland Street, North** **000-7819-0175**
Primary Resource Information: Single Dwelling, Stories 1, Style: Other, ca 1945
This building features exposed roof rafters, and rowlock sills.
Individual Resource Status: Single Dwelling **Contributing**
- 113 North Oakland Street** **000-7819-0177**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod measures three bays wide and includes features such as overhanging eaves, rowlock sills, and a wood cornice. Two gable roof dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 114 North Oakland Street** **000-7819-0176**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling is four bays wide and features rowlock sills, and a Colonial Revival door surround with fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 123

- 117 North Oakland Street 000-7819-0178**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This dwelling measures two bays across and features rowlock sills, overhanging eaves, and a wood Colonial Revival door surround.
Individual Resource Status: Single Dwelling Contributing
Individual Resource Status: Garage Contributing
- 118 North Oakland Street 000-7819-0179**
Primary Resource Information: Single Dwelling, Stories 3, Style: Other, ca 1940
This dwelling measures four bays wide and features an attached garage, rowlock sills, a Colonial Revival door surround with flat pilasters, a full pediment, and a plain entablature.
Individual Resource Status: Single Dwelling Contributing
- 121 North Oakland Street 000-7819-0181**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Two bays wide, this dwelling includes features such as rowlock sills, and a rowlock beltcourse with continuous sills on the second story. The off-center entry has a Colonial Revival door surround with a full pediment.
Individual Resource Status: Single Dwelling Contributing
Individual Resource Status: Shed Non-contributing
- 122 North Oakland Street 000-7819-0180**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod measures four bays across and features stone sills, and jack arch lintels with keystones, and two gable roof dormers on the facade. The central entry has a Colonial Revival door surround with fluted pilasters and an arch with a sunburst motif.
Individual Resource Status: Single Dwelling Contributing
- 125 North Oakland Street 000-7819-0182**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
This dwelling is three bays wide and features rowlock sills, a wood cornice, and a side screened porch. Two gable roof wall dormers are seen on the facade.
Individual Resource Status: Single Dwelling Contributing
Individual Resource Status: Garage Contributing
- 129 North Oakland Street 000-7819-0184**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
This building measures two bays wide and features rowlock sills, and a rowlock beltcourse with continuous sills on the second story. It also has overhanging eaves, and a Colonial Revival door surround with an elliptical sunburst transom.
Individual Resource Status: Single Dwelling Contributing
Individual Resource Status: Garage Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 124

- 130 North Oakland Street** **000-7819-0183**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod measures four bays across and features stone sills, jack arch lintels with keystones, and a Colonial Revival door surround with fluted pilasters. A screened porch on a stone foundation is on the side elevation. Two gable dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 133 North Oakland Street** **000-7819-0186**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This dwelling measures three bays across and features rowlock sills, an aluminum encased cornice, and a Colonial Revival wood door surround with fluted pilasters. A two-story addition is located on the rear elevation. Two gable roof dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 134 North Oakland Street** **000-7819-0185**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Four bays wide, this dwelling features a screened porch on the side elevation, and stone sills and jack arch lintels with keystones. The center entrance features a Colonial Revival door surround with plain pilasters and an arched entablature.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 137 North Oakland Street** **000-7819-0187**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
Two bays wide, this dwelling features overhanging eaves, rowlock sills, and a rowlock beltcourse with continuous sills on the second story. The plywood portico is ornamented with a dentilated cornice. The side porch has been enclosed.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 138 North Oakland Street** **000-7819-0188**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1940
This dwelling measures three bays across and features drip moldings over the windows, a shouldered chimney, and a wood fascia board. One gable roof dormer is seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 141 North Oakland Street** **000-7819-0190**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Three bays wide, this dwelling has a center recessed entry with a Colonial Revival door surround with plain pilasters and a paneled entablature. The house features a wood cornice, two gable roof dormers, and rowlock sills.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 125

142 North Oakland Street 000-7819-0189

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1936

This Cape Cod measures three bays across and includes rowlock sills, a rowlock course above the basement story, and a dentilated wood cornice.

The center entry features a wood door surround with plain pilasters. Two gable roof dormers are seen on the facade.

Individual Resource Status: Single Dwelling Contributing

201 North Oakland Street 000-7819-0191

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

This dwelling measures three bays across and features a center brick vestibule, overhanging eaves, and rowlock sills. The vestibule is illuminated

with a 4-light transom. The side porch has been enclosed with vinyl siding. Two gable roof dormers are seen on the facade.

Individual Resource Status: Single Dwelling Contributing

202 North Oakland Street 000-7819-0192

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

This dwelling measures four bays wide and includes rowlock sills, two gable wall dormers on the facade, and a dentilated wood cornice. The center

entry features a wood door surround with fluted pilasters.

Individual Resource Status: Single Dwelling Contributing

206 North Oakland Street 000-7819-0193

Primary Resource Information: Single Dwelling, Stories 3, Style: Other, ca 1940

This dwelling measures three bays wide and features rowlock sills, and a Colonial Revival door surround with fluted pilasters. A two-story addition is located on the rear elevation.

Individual Resource Status: Single Dwelling Contributing

Individual Resource Status: Garage Contributing

207 North Oakland Street 000-7819-0194

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

Features of this three bay wide dwelling include a molded wood cornice, and two gable wall dormers on the facade. The center entry has a wood

Colonial Revival door surround with fluted pilasters, and a modillion raking cornice. The broken pediment is missing. A two-story wood frame

addition with a shed roof is seen on the rear elevation. The side porch has been enclosed.

Individual Resource Status: Single Dwelling Contributing

Individual Resource Status: Garage Contributing

210 North Oakland Street 000-7819-0196

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

Features of this four bay wide Cape Cod dwelling include rowlock sills, segmental arch lintels, a front vestibule, and a sawtooth cornice. Two gable

roof dormers are seen on the facade.

Individual Resource Status: Single Dwelling Contributing

Individual Resource Status: Garage Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 126

- 211 North Oakland Street** **000-7819-0195**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling features stone sills, jack arch lintels with brick keystones, and two gable dormers on the facade. The center entry has a wood Colonial Revival door surround with small fluted pilasters, and a sunburst motif wood transom. A one-story wood frame addition with a shed roof is located on the rear elevation.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 214 North Oakland Street** **000-7819-0197**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling features rowlock sills, and a wood door surround with plain pilasters. Two gable roof dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 215 North Oakland Street** **000-7819-0198**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This dwelling measures three bays across and features a boxed wood cornice, rowlock sills and water table, and door surround with a broken pediment and fluted pilasters. A two-story addition is located on the rear elevation.
Individual Resource Status: Single Dwelling **Contributing**
- 218 North Oakland Street** **000-7819-0200**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
This dwelling is four bays wide and features rowlock sills, a wood dentilated cornice, and a wood door surround with paneled pilasters and an arched entablature.
Individual Resource Status: Single Dwelling **Contributing**
- 219 North Oakland Street** **000-7819-0199**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling is three bays wide and features a Colonial Revival door surround with fluted pilasters. It also has a molded wood dentilated cornice, rowlock sills and water table, and two gable roof dormers on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 222 North Oakland Street** **000-7819-0201**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1935
This Cape Cod measures three bays across and includes rowlock sills, an attached garage, a wood fascia board, and a Colonial Revival door surround with plain pilasters and a dentilated cornice. Two gable roof dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 223 North Oakland Street** **000-7819-0202**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling is three bays wide and features rowlock sills and water table, and an aluminum clad cornice. The center entry has a wood Colonial Revival door surround with fluted pilasters. Two gable dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 127

- 226 North Oakland Street** **000-7819-0204**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Tudor Revival, ca 1937**
This dwelling is three bays wide and features a header course water table, rowlock sills, and a front vestibule with a sloping front gable roof. There is an attached garage and one gable roof dormer on the facade.
Individual Resource Status: **Single Dwelling** **Contributing**
- 227 North Oakland Street** **000-7819-0203**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940**
Three bays wide, this dwelling features rowlock sills, soldier lintels and water table, and an aluminum encased cornice. A frame one-story gable-roof addition is located on the rear elevation. The side porch has been enclosed.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 310 North Oakland Street** **000-7819-0069**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940**
Features of this four bay wide dwelling include rowlock sills, header lintels, and a wood denticulated cornice.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 316 North Oakland Street** **000-7819-0080**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940**
Features of this three bay wide dwelling include rowlock sills, a protruding beltcourse of stretchers above the first story, and a course of headers at the cornice level. The center entry features a Colonial Revival door surround with fluted pilasters, a broken pediment, and a denticulated entablature.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**
- 321 North Oakland Street** **000-7819-0081**
Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940**
This 4-Square dwelling measures three bays across and includes features such as overhanging eaves, a soldier course above the basement, and a rowlock stringcourse at the second story lintel level. The center entry features a Colonial Revival door surround with fluted pilasters and a modillion cornice. A cast concrete cartouche of a family seal is seen above the entrance. The chimney is shouldered.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Shed** **Non-contributing**
- 322 North Oakland Street** **000-7819-0079**
Primary Resource Information: **Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940**
Features of this three bay wide dwelling include a soldier beltcourse above the basement level, paneled spandrels with the first story windows, and rowlock sills on the second story.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Garage** **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 128

- 325 North Oakland Street** **000-7819-0082**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1945
This dwelling is three bays wide and features rowlock sills, splayed soldier lintels, and attached garage. The side porch has a roof balcony.
Individual Resource Status: Single Dwelling **Contributing**
- 326 North Oakland Street** **000-7819-0078**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1938
This building is three bays wide and features rowlock sills, headers surrounding the door surround, a denticulated wood cornice, and a soldier beltcourse above the basement level.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 330 North Oakland Street** **000-7819-0077**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1940
Features of this three bay wide dwelling include a soldier beltcourse below the first story, rowlock sills, a denticulated brick frieze, and a denticulated wood cornice. The center entry features a Colonial Revival door surround with fluted pilasters and a broken pediment with a denticulated entablature.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 334 North Oakland Street** **000-7819-0076**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1950
This Cape Cod dwelling measures three bays across and features rowlock sills, and a denticulated cornice. There is a porch addition on the rear elevation.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 409 North Oakland Street** **000-7819-0101**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Three bays wide, this dwelling features a denticulated molded cornice, 4-lights and dado panel sidelights, a elliptical transom, and lug wood sills.
The first story windows feature paneled spandrels. Two gable wall dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 415 North Oakland Street** **000-7819-0102**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1945
This three bay wide dwelling features rowlock sills, and brick lintels with brick keystones, and a corbeled cornice. The off-center entry features a Colonial Revival door surround with a broken pediment, fluted pilasters, and a modillion cornice. A large two-story frame addition is seen on the rear elevation. The side porch has been enclosed.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 129

- 416 North Oakland Street** **000-7819-0097**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Four bays wide, this dwelling features a soldier beltcourse, and square-edged wood sills.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 419 North Oakland Street** **000-7819-0103**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Features of this three bay wide dwelling include brick keystone lintels, rowlock sills, a boxed wood cornice, and a denticulated cornice on the portico. The side porch is screened with a wood rooftop balcony.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 420 North Oakland Street** **000-7819-0096**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Four bays wide, this dwelling features rowlock sills, and a wood Colonial Revival door surround with a broken pediment, urn and fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 423 North Oakland Street** **000-7819-0104**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
Three bays wide, this dwelling features three gable dormers on the facade, keystone lintels, and a 1-story brick addition on the side elevation.
Individual Resource Status: Single Dwelling **Contributing**
- 426 North Oakland Street** **000-7819-0095**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1940
This building measures 4-bays across, and features a center vestibule, cast concrete sills, and two gable dormers on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 501 North Oakland Street** **000-7819-0641** *Other DHR ID#: 000-6812*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The imposing three-bay wide dwelling has a recessed center l entry with a segmental brick arch, delicate fluted pilasters, l and 4-light sidelights. The windows, some of which are paired l and tripled, have rowlock sills.
Individual Resource Status: Single Dwelling **Contributing**
- 506 North Oakland Street** **000-7819-0709** *Other DHR ID#: 000-6880*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide Cape Cod has a one-story, one-bay wide side l wing with a flat roof on the south elevation. The centered l entry is set in a projecting gable bay and features a round l arched opening with a segmental soldier arch and rowlock l sides. The windows, which are paired at the first story, have l rowlock sills and the dormers each contain a 6/6 window.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 130

512 North Oakland Street 000-7819-0710 Other DHR ID#: 000-6881

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry framed by a 1
Colonial Revival style door surround with a broken pediment, a 1
finial, a molded wood lintel, and fluted pilasters. The 1
windows have rowlock sills and soldier lintels, operable 1
shutters and are smaller at the second story. The chimney is 1
shouldered.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

515 North Oakland Street 000-7819-0640 Other DHR ID#: 000-6811

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling features rowlock sills and a 1
centered entry that is covered by a front gable portico with a 1
segmental soffit.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

518 North Oakland Street 000-7819-0711 Other DHR ID#: 000-6882

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide Cape Cod has a centered entry framed by a 1
front gable portico with an arched opening and Tuscan posts 1
and pilasters. The windows have rowlock sills and the 1
shouldered chimney has a rowlock cap. The dormers each 1
contain a 6/6 window.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

519 North Oakland Street 000-7819-0639 Other DHR ID#: 000-6810

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The four-bay wide dwelling has a steeply pitched roof, a front 1
facing chimney, and rowlock sills. The front gable entry 1
vestibule has a Colonial Revival style door surround with 1
fluted pilasters and a broken pediment.

Individual Resource Status: Single Dwelling

Contributing

520 North Oakland Street 000-7819-0712 Other DHR ID#: 000-6883

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay wide main block features a centered entry 1
beneath a portico with a roof top balustrade with finials. 1
The windows have rowlock sills and the chimneys have rowlock 1
caps. There are shed roof porches on both the south and west 1
elevations.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 131

523 North Oakland Street 000-7819-0638 Other DHRJD#: 000-6809

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The windows on both the three-bay wide main block and the 1
north addition feature rowlock sills. The front gable entry 1
vestibule has a Colonial Revival style door surround with 1
fluted pilasters and a broken pediment.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

526 North Oakland Street 000-7819-0713 Other DHR ID#: 000-6884

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay wide block is flanked by one-story side wings, 1
one of which is an attached garage and the other which is a 1
screen-enclosed porch. The entry is set in a projecting gable 1
vestibule with an asymmetrical gable and a Colonial Revival 1
style door surround with fluted pilasters and a dentiled 1
pediment. The windows have rowlock sills and the dormer 1
contains a 6/6 window.

Individual Resource Status: Single Dwelling

Contributing

527 North Oakland Street 000-7819-0637 Other DHR ID#: 000-6808

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide Cape Cod has a centered entry framed by a 1
Colonial Revival style door surround with fluted pilasters and 1
a broken pediment with dentil molding. The cornice is 1
dentiled and each dormer contains a 6/6 window.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

530 North Oakland Street 000-7819-0714 Other DHR ID#: 000-6885

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay wide main block is flanked by one-bay wide 1
wings, one of which is an enclosed porch and the other which 1
is a one-and-a-half story attached garage. The front gable 1
portico has weatherboard in the gable end and a balustrade on 1
the sides. Other details include a wall dormer above the 1
garage, rowlock sills, and a rowlock chimney cap.

Individual Resource Status: Single Dwelling

Contributing

533 North Oakland Street 000-7819-0636 Other DHR ID#: 000-6807

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a front gable entrance 1
vestibule with an asymmetrical gable, rowlock sills, and a 1
bracketed cornice. The front gable dormer has one 6/6 window 1
and the shed roof dormer has two.

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 132

536 North Oakland Street **000-7819-0715** **Other DHR ID#: 000-6886**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide Cape Cod has a centered entry with a 1 Colonial Revival style door surround with pilasters and a 1 molded lintel. Details include paired windows with rowlock 1 sills, a stretcher bond chimney cap, a one-story 1 screen-enclosed side porch, and 6/6 windows in the dormers.

Individual Resource Status: Single Dwelling

Contributing

538 North Oakland Street **000-7819-0716** **Other DHR ID#: 000-6887**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay wide main block is flanked by one-story side 1 wings, one of which is an attached garage with a wide 1 entablature and a dentiled cornice. The entry is framed by a 1 front gable portico with an arched opening, Tuscan posts and 1 pilasters, and balustrades on the sides.

Individual Resource Status: Single Dwelling

Contributing

542 North Oakland Street **000-7819-0717** **Other DHR ID#: 000-6888**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

A randomly patterned stone veneer clads the facade of both the 1 three-bay wide main block and the one-bay wide, one-and-a-half 1 story high attached garage. Details include stone sills, flat 1 stone lintels with keystones at the first story and dormer, a 1 front gable portico with Colonial Revival details, a shouldered 1 chimney, and a wall dormer.

Individual Resource Status: Single Dwelling

Contributing

543 North Oakland Street **000-7819-0635** **Other DHR ID#: 000-6806**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling features rowlock sills, a front 1 gable portico with a segmental soffit, and a gable end with 1 weatherboard cladding and a lunette in the enclosed tympanum. 1

On the south elevation, there is a screen enclosed side 1 porch.

Individual Resource Status: Single Dwelling

Contributing

551 North Oakland Street **000-7819-0634** **Other DHR ID#: 000-6805**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The two-bay wide main block features a front gable portico 1 with a segmental soffit, a paired window, and rowlock sills. 1 On the south elevation, there is a one-story side wing with a 1 flat roof.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 133

- 559 North Oakland Street** **000-7819-0633** **Other DHR ID#: 000-6804**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features rowlock sills, squared l
balusters on the front porch, and exposed rafter tails. The l
gable end is clad in asbestos shingles and contains a 9-light l
wood casement window.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Non-contributing**
- 620-622 North Oakland Street** **000-7819-0758** **Other DHR ID#: 000-6942**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide twin dwelling has a Colonial Revival style l
door surround with a broken pediment, dentil molding, and l
fluted pilasters. The second entry is on the south elevation. l
Details include a front gable bay, rowlock sills, soldier l
lintels, and a side porch.
Individual Resource Status: Multiple Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 621-623 North Oakland Street** **000-7819-0618** **Other DHR ID#: 000-6789**
Primary Resource Information: Multiple dwelling, Stories 3, Style: Colonial Revival,
The four-bay wide twin dwelling features rowlock sills, l
soldier lintels, a side porch with brick pier supports, and a l
front gable bay with a louvered vent in the gable end. The l
entry is framed by a a Colonial Revival style door surround l
with fluted pilasters and a broken pediment with dentil l
molding.
Individual Resource Status: Multiple Dwelling **Contributing**
- 624-626 North Oakland Street** **000-7819-0759** **Other DHR ID#: 000-6943**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide twin dwelling has two Colonial Revival style l
door surrounds with fluted pilasters, arched sunburst l
pediments, and dentil molding. The windows have rowlock sills l
and soldier lintels.
Individual Resource Status: Multiple Dwelling **Contributing**
- 625-627 North Oakland Street** **000-7819-0617** **Other DHR ID#: 000-6788**
Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,
The four-bay wide twin dwelling features rowlock sills, l
soldier lintels, and Colonial Revival style door surrounds l
with fluted pilasters and round-arched pediments with dentil l
molding.
Individual Resource Status: Multiple Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 134

628-630 North Oakland Street 000-7819-0760 Other DHR ID#: 000-6944

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide twin dwelling has an entry on the north elevation and one on the facade, which has a Colonial Revival style door surround with a broken pediment, a finial, and fluted pilasters. The building has a front gable bay, rowlock sills, and soldier lintels.

Individual Resource Status: **Multiple Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-contributing

629-631 North Oakland Street 000-7819-0616 Other DHR ID#: 000-6787

Primary Resource Information: **Multiple dwelling, Stories 3, Style: Colonial Revival,**

The four-bay wide twin dwelling features a Colonial Revival style door surround with fluted pilasters and a broken pediment. The windows have rowlock sills and soldier lintels.

Individual Resource Status: **Shed**

Non-contributing

Individual Resource Status: **Multiple Dwelling**

Contributing

700-702 North Oakland Street 000-7819-0610 Other DHR ID#: 000-6780

Primary Resource Information: **Multiple dwelling, Stories 3, Style: Colonial Revival,**

The four-bay wide twin dwelling features rowlock sills, soldier lintels, a one-story, one-bay wide side porch with brick pier supports, and a front gable bay with weatherboard and a lunette in the gable end. The doors are framed by Colonial Revival style door surrounds with fluted pilasters and broken pediments with dentil molding.

Individual Resource Status: **Shed**

Non-contributing

Individual Resource Status: **Multiple Dwelling**

Contributing

701-703 North Oakland Street 000-7819-0605 Other DHR ID#: 000-6775

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide twin dwelling features rowlock sills, soldier course lintels, brick pier supports on the side porch, and wood weatherboard in the gable end. The entry is framed by a Colonial Revival style door surround with fluted pilasters and a broken pediment with dentil molding.

Individual Resource Status: **Shed**

Non-contributing

Individual Resource Status: **Multiple Dwelling**

Contributing

704-706 North Oakland Street 000-7819-0611 Other DHR ID#: 000-6781

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**

The four-bay wide twin dwelling features rowlock sills, soldier lintels, and Colonial Revival style door surrounds with fluted pilasters and segmental pediments with dentil molding. One entry is on the facade and the other is on the south elevation.

Individual Resource Status: **Multiple Dwelling**

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 135

705-707 North Oakland Street 000-7819-0606 Other DHR ID#: 000-6776

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
The four-bay wide twin dwelling features rowlock sills, soldier lintels and 1
Colonial Revival style door surrounds with fluted pilasters and round-arched 1
lintels with dentil molding and sunburst motifs. The entrance to the 1
dwelling at 705 North Oakland Street is located on the north elevation. Additions and
alterations

Individual Resource Status: **Multiple Dwelling Contributing**

708-710 North Oakland Street 000-7819-0612 Other DHR ID#: 000-6782

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
The four-bay wide twin dwelling features soldier course 1
lintels at the first story windows, rowlock sills, and a 1
rowlock beltcourse between the two stories. The entries are 1
frame by Colonial Revival style surrounds with fluted 1
pilasters and pediments with heavy cornice molding.

Individual Resource Status: **Multiple Dwelling Contributing**

709-711 North Oakland Street 000-7819-0607 Other DHR ID#: 000-6777

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
The four-bay wide twin dwelling has rowlock sills, soldier 1
lintels, weatherboard cladding in the gable ends, and two 1
Colonial Revival style door surrounds. The door surrounds 1
have fluted pilasters and molded pediments.

Individual Resource Status: **Multiple Dwelling Contributing**

712-714 North Oakland Street 000-7819-0613 Other DHR ID#: 000-6783

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
The four-bay wide twin dwelling features rowlock sills, 1
soldier lintels on the first story windows, and two 1
tripartite windows on the facade. The entry is framed by a 1
Colonial REvival style door surround with fluted pilasters and 1
a segmental pediment with dentil molding.

Individual Resource Status: **Multiple Dwelling Contributing**

713-715 North Oakland Street 000-7819-0608 Other DHR ID#: 000-6778

Primary Resource Information: **Multiple dwelling, Stories 2, Style: Colonial Revival,**
The four-bay wide twin dwelling has soldier lintels on the 1
first story windows, rowlock sills, and Colonial Revival style 1
door surrounds with fluted pilasters and a round-arched 1
pediment with dentil molding. One entrance is on the facade 1
and the other is on the north elevation.

Individual Resource Status: **Multiple Dwelling Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 136

716-718 North Oakland Street 000-7819-0614 Other DHR ID#: 000-6784

Primary Resource Information: Multiple dwelling, Stories 3, Style: Colonial Revival,

The four-bay wide twin dwelling features rowlock sills, 1 soldier lintels, a side porch with brick pier supports, and a 1 front gable bay with vinyl siding and a lunette in the gable 1 end. The entry is framed by a Colonial Revival style door 1 surround with fluted pilasters and a broken pediment with 1 dentil molding.

Individual Resource Status: Multiple Dwelling

Contributing

717-719 North Oakland Street 000-7819-0609 Other DHR ID#: 000-6779

Primary Resource Information: Multiple dwelling, Stories 3, Style: Colonial Revival,

The four-bay wide twin dwelling features soldier course 1 lintels, rowlock sills, a one-story, one-bay side porch, and a 1 front gable bay with weatherboard and a lunette in the gable 1 end. The doors are framed by Colonial Revival style door 1 surrounds with fluted pilasters and broken pediments with 1 dentil molding.

Individual Resource Status: Multiple Dwelling

Contributing

727 North Oakland Street 000-7819-0670 Other DHR ID#: 000-6839

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The nine-bay wide apartment building has some paired windows, 1 a corbeled stringcourse above the second story windows, and 1 rowlock sills. The door is framed by a Colonial Revival style 1 door surround with a pediment and pilasters.

Individual Resource Status: Multiple Dwelling

Contributing

730 North Oakland Street 000-7819-0615 Other DHR ID#: 000-6785

Primary Resource Information: Multiple dwelling, Stories 2, Style: Other,

The 10-bay wide apartment building has an asymmetrical 1 footprint. The windows, most of which are paired, feature 1 rowlock sills. The brick beltcourse acts as a 1 continuous lintel for the second story windows.

Individual Resource Status: Multiple Dwelling

Contributing

739 North Oakland Street 000-7819-0669 Other DHR ID#: 000-6838

Primary Resource Information: Multiple dwelling, Stories 2, Style: Colonial Revival,

The nine-bay wide apartment building has some paired windows, 1 rowlock sills, a corbeled brick stringcourse, and a Colonial 1 Revival style door surround with a pediment and pilasters.

Individual Resource Status: Multiple Dwelling

Contributing

North Oxford Street

311 North Oxford Street 000-7819-0070

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940

Measuring four bays wide, this dwelling features a denticulated wood cornice, an attached flat roof garage, and a Colonial Revival door surround.

The door surround features fluted pilasters, and a denticulated entablature.

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 137

- 315 North Oxford Street** **000-7819-0071**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling measures six bays wide and includes features such as rowlock sills, molded wood surrounds, and a decorative cornice. The center entry features a Colonial Revival door surround using fluted pilasters. There are two gable dormers on the facade both with one 6/6 double-hung sash window.
Individual Resource Status: Single Dwelling **Contributing**
- 319 North Oxford Street** **000-7819-0072**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This dwelling measures three bays wide and features a soldier course water table, concrete sills, and a denticulated wood cornice. The center entry features a Colonial Revival door surround with fluted pilasters. Two gable dormers with 6/6 double-hung sash windows are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 323 North Oxford Street** **000-7819-0073**
Primary Resource Information: Single Dwelling,
Three bays wide, this dwelling features a soldier course water table, stone sills and stone keystones, and a wood cornice. The center entry features a Colonial Revival door surround with pilasters. Two gable dormers with a 6/6 double-hung sash window are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 329 North Oxford Street** **000-7819-0074**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling measures three bays wide and features rowlock sills, a denticulated wood cornice, and stone sills.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 409 North Oxford Street** **000-7819-0092**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling measures five bays wide and features square cast concrete sills, a wood denticulated cornice, and operable wood louvered shutters. The center entry features a Colonial Revival surround with fluted pilasters and a denticulated entablature.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 415 North Oxford Street** **000-7819-0093**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling measures three bays across and features a wood cornice, stone sills, and stone lintels with keystones. The center entry features a Colonial Revival door surround with pilasters and an entablature with triglyphs. Two gable dormers each with a 6/6 double-hung vinyl sash windows are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 138

- 419 North Oxford Street** **000-7819-0094**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This Cape Cod dwelling measures five bays across and features stone square sills, a molded wood cornice, a soldier course water table, and a crossette door surround. It has two gable dormers on the facade.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 500 North Oxford Street** **000-7819-0731** *Other DHR ID#: 000-6902*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide main block features a corbeled chimney cap, 1 rowlock sills, and a centered entry with a Colonial Revival 1 style door surround with a dentiled lintel and fluted 1 pilasters.
Individual Resource Status: Single Dwelling **Contributing**
- 501 North Oxford Street** **000-7819-0730** *Other DHR ID#: 000-6901*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide main block features louvered ventilators in 1 the gable ends, rowlock sills, and a centered entry with a 1 Colonial Revival style door surround with a broken pediment, a 1 finial, and fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**
- 504 North Oxford Street** **000-7819-0732** *Other DHR ID#: 000-6903*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling has a centered entry framed by 1 fluted pilasters, rowlock sills, and louvered ventilators in 1 the gable ends.
Individual Resource Status: Single Dwelling **Contributing**
- 505 North Oxford Street** **000-7819-0729** *Other DHR ID#: 000-6900*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide main block features rowlock sills, louvered 1 ventilators in the gable ends and a Colonial Revival style 1 door surround with a dentiled lintel and fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 508 North Oxford Street** **000-7819-0733** *Other DHR ID#: 000-6904*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling has a centered entry with a 1 Colonial Revival style door surround with fluted pilasters and 1 a broken pediment. The windows have rowlock sills and there 1 are louvered ventilators in the gable ends.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 139

- 509 North Oxford Street** **000-7819-0728** **Other DHR ID#: 000-6899**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide main block features rowlock sills, a centered entry, and triangular shaped ventilators in the gable ends. The enclosed side porch is one-story in height and one-bay in width.
Individual Resource Status: Single Dwelling **Contributing**
- 512 North Oxford Street** **000-7819-0734** **Other DHR ID#: 000-6905**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling has a centered entry framed by a Colonial Revival style door surround with a broken pediment, a finial, and fluted pilasters. The screen-enclosed side porch is supported by brick piers and features weatherboard in the gable end.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 513 North Oxford Street** **000-7819-0727** **Other DHR ID#: 000-6898**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide main block features rowlock sills and louvered ventilators in the gable end. The centered entry is framed by a Colonial Revival style door surround with a pediment and fluted pilasters.
Individual Resource Status: Shed **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 516 North Oxford Street** **000-7819-0735** **Other DHR ID#: 000-6906**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling features a central entry framed by a Colonial Revival style door surround with fluted pilasters, a broken pediment and a finial. The windows have rowlock sills and there is a one-bay wide screen-enclosed side porch.
Individual Resource Status: Single Dwelling **Contributing**
- 517 North Oxford Street** **000-7819-0726** **Other DHR ID#: 000-6897**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide main block has a centered entry with a Colonial Revival style door surround with fluted pilasters and a dentil molded lintel. The windows have rowlock sills and the screen enclosed side porch has a side gable roof.
Individual Resource Status: Single Dwelling **Contributing**
- 520 North Oxford Street** **000-7819-0736** **Other DHR ID#: 000-6907**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling has a centered entry framed by fluted piasters and a dentil molded lintel. The windows have rowlock sills and the side porch has wood weatherboard beneath the shed roof and a rowlock course beneath the screening.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 140

521 North Oxford Street **000-7819-0725** **Other DHR ID#: 000-6896**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide main block features a centered entry framed by a Colonial Revival style door surround with a dentil molded lintel and fluted pilasters. The windows on both the main block and the one-story side wing have rowlock sills.

Individual Resource Status: Single Dwelling

Contributing

524 North Oxford Street **000-7819-0737** **Other DHR ID#: 000-6908**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry framed by a dentil molded lintel and fluted pilasters. The windows have rowlock sills and the chimney has a stretcher bond cap. The basement is lit by fixed 2-light windows.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

525 North Oxford Street **000-7819-0724** **Other DHR ID#: 000-6895**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide main block features a centered entry framed by a Colonial Revival style door surround with a broken pediment, a finial, and fluted pilasters. The windows on both the main block and the one-story side wing have rowlock sills.

Individual Resource Status: Single Dwelling

Contributing

528 North Oxford Street **000-7819-0738** **Other DHR ID#: 000-6909**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry and symmetrically placed window openings with rowlock sills. There are louvered ventilators in the gable ends.

Individual Resource Status: Single Dwelling

Contributing

529 North Oxford Street **000-7819-0723** **Other DHR ID#: 000-6894**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry, pressed brick, and rowlock sills. There is a one-bay wide side porch with a shed roof.

Individual Resource Status: Single Dwelling

Contributing

532 North Oxford Street **000-7819-0739** **Other DHR ID#: 000-6910**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry that is framed by a dentiled lintel and fluted pilasters. The side porch is screen-enclosed and the windows have rowlock sills.

Individual Resource Status: Single Dwelling

Contributing

533 North Oxford Street **000-7819-0722** **Other DHR ID#: 000-6893**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay wide dwelling has a centered entry, a front gable door hood, and rowlock sills.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Non-contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 141

- | | | |
|--|----------------------|--------------------------------|
| 537 North Oxford Street | 000-7819-0721 | Other DHR ID#: 000-6892 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The three-bay wide dwelling has a centered entry with a Colonial Revival style door surround with a dentil molded lintel and fluted pilasters. The windows have rowlock sills and there are louvered ventilators in the gable ends. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 538 North Oxford Street | 000-7819-0740 | Other DHR ID#: 000-6911 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
<i>Individual Resource Status: Garage</i> | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

North Pershing Drive

- | | | |
|---|----------------------|--------------------------------|
| 3201 North Pershing Drive | 000-7819-0447 | Other DHR ID#: 000-6606 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three-bay wide house has a centered entry flanked by paired windows. The shed dormer has a slightly flared roof and a one-light sliding window. Other details include cornerboards and on the east elevation there is a box bay. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 3202 North Pershing Drive | 000-7819-0228 | Other DHR ID#: 000-5654 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,</i>
The five-bay symmetrical facade has a centered entry framed by sidelights and a transom. The hipped roof has wide eaves and exposed rafter tails. There is a one-story frame wing with a half-hipped roof on the northeast elevation. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| 3205 North Pershing Drive | 000-7819-0448 | Other DHR ID#: 000-6607 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The three bay wide dwelling has a centered entry, paired windows with wide wood surrounds, and a roof with exposed rafter tails and wide eaves. The front gable porch is supported by tapered columns atop brick piers. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 3210 North Pershing Drive | 000-7819-0230 | Other DHR ID#: 000-5656 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i>
The entry of the three-bay house is set in a projecting three-sided bay and is flanked by one-light wood slit windows and paired windows. The roof has wide eaves with brackets and the front porch gable has flared eaves. | | |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| <i>Individual Resource Status: Garage</i> | | Non-contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 142

- 3216 North Pershing Drive** **000-7819-0232** **Other DHR ID#: 000-5658**
Primary Resource Information: Single Dwelling, Stories 1.5, Style: Colonial Revival, ca. 1920
Parged Concrete Foundation, Side Gambrel Roof with Asphalt Shingle, Wood Frame Structural System with Vinyl Siding
Individual Resource Status: Single Dwelling **Contributing**
- 3217 North Pershing Drive** **000-7819-0449** **Other DHR ID#: 000-6608**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The two-bay wide four-square has a pyramidal roof with wide, l overhanging eaves. While not a bungalow in form, the house l displays some elements of the Craftsman style. Other details l include cornerboards and tapered wood posts on the porch.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Contributing**
- 3221 North Pershing Drive** **000-7819-0450** **Other DHR ID#: 000-6609**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features a centered entry, rowlock l sills, soldier lintels, and wide, overhanging eaves. The l gable end has wood shingles in the gable end and the l front gable porch is supported by wood posts atop brick piers. Additions and alterations
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3222 North Pershing Drive** **000-7819-0234** **Other DHR ID#: 000-5660**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,
The three-bay house has a centered entry flanked by sidelights l and crowned by a sunburst wood panel. the brick dwelling has l a rowlock water table, rowlock sills, and a soldier l stringcourse below the second story windows. The gable roof l has cornice returns and there is a one-story porch on the l northeast side of the dwelling.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3225 North Pershing Drive** **000-7819-0451** **Other DHR ID#: 000-6610**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay wide dwelling features a centered entry, paired l windows, and a front gable dormer with a triple 6/l window. l The roof has wide eaves with exposed, scroll-sawn rafter l tails.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 143

- 3228 North Pershing Drive** **000-7819-0275** **Other DHR ID#: 000-5702**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a rock-faced concrete block foundation, the three-bay house has a centered entry framed by paired windows and a tri-partite window in the upper story of the facade. The half-hipped porch roof, with its wide eaves and decorative, scroll-cut rafters, is supported by columns atop random, rubble stone piers.
Individual Resource Status: Single Dwelling **Contributing**
- 3233 North Pershing Drive** **000-7819-0452** **Other DHR ID#: 000-6611**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,
The three bay wide dwelling has an enclosed side porch with a shed roof. On the facade, there are two canted window bays and the second story projects slightly from the wall plane. Other details include cornice returns, a rowlock water table, and semi-circular windows in the gable ends.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 3234 North Pershing Drive** **000-7819-0291** **Other DHR ID#: 000-5718**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a flush concrete block foundation, the five-bay house has half-timbering in the front gable and paired windows in the upper half-story of the house. The windows have wide, wood surrounds and concrete sills.
Individual Resource Status: Garage **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3300 North Pershing Drive** **000-7819-0060**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Features of this four bay wide dwelling, include rowlocks sills, a wood cornice, and an arched door surround.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3305 North Pershing Drive** **000-7819-0461** **Other DHR ID#: 000-6620**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay wide dwelling has a projecting gable bay with vertical board wood siding in the gable end. Other details include an inset porch, rowlock brick sills, and a molded wood cornice.
Individual Resource Status: Single Dwelling **Contributing**
- 3308 North Pershing Drive** **000-7819-0059**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Features of this four bay wide dwelling include 4-light 1-panel sidelights and fluted pilasters around the door.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 144

- | | | |
|--|----------------------|--------------------------------|
| 3311 North Pershing Drive | 000-7819-0311 | Other DHR ID#: 000-5738 |
| <i>Primary Resource Information: Single Dwelling, Stories 3, Style: Bungalow/Craftsman,</i> | | |
| Set on a rock-faced concrete block foundation, the Craftsman 1 four-square house is three bays wide and has a hipped roof 1 with wide eaves and exposed rafters. The side passage entry 1 is framed by fluted, wood molding with bullseye corner blocks. 1 The dormer contains two six-light wood casement windows. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 3314 North Pershing Drive | 000-7819-0243 | Other DHR ID#: 000-5669 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i> | | |
| Set on a panel-faced concrete block foundation, the three-bay 1 house has a centered entry and flanking paired windows with 1 wide, wood surrounds with a beaded edge. The front gable end 1 is clad in wood shingles. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 3315 North Pershing Drive | 000-7819-0312 | Other DHR ID#: 000-5739 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i> | | |
| Set on a rock-faced concrete block foundation, the three-bay 1 house has an off-center entry and flanking windows surrounded 1 by wide, wood trim with a beaded edge. The upper story is 1 clad in wood shingles. The side gable roof has wide eaves. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 3407 North Pershing Drive | 000-7819-0313 | Other DHR ID#: 000-5740 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i> | | |
| Set on a panel-faced concrete block foundation, the three-bay 1 house has a centered entry and a front gable dormer with 1 paired six-over-one double-hung metal sash windows. The roof 1 has wide eaves and exposed beam ends. | | |
| <i>Individual Resource Status: Shed</i> | | Non-contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |
| 3408 North Pershing Drive | 000-7819-0245 | Other DHR ID#: 000-5671 |
| <i>Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,</i> | | |
| Set on a panel-faced concrete block foundation, the three-bay 1 house has a centered entry and flanking windows with wide, 1 wood surrounds with a beaded edge. The roof has wide eaves 1 supported by decorative wood brackets. An eight-light 1 casement window is situated in the front gable end of the 1 porch. | | |
| <i>Individual Resource Status: Garage</i> | | Contributing |
| <i>Individual Resource Status: Single Dwelling</i> | | Contributing |

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 145

3411 North Pershing Drive 000-7819-0314 Other DHR ID#: 000-5741

Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,

The four-bay frame house is clad in vinyl siding, with a brick veneer on the southwest bay and the original wood weatherboard under the porch. The Craftsman style door is wood-paneled with lights.

Individual Resource Status: Single Dwelling

Contributing

3414 North Pershing Drive 000-7819-0247 Other DHR ID#: 000-5673

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay house has a centered antry and flanking paired windows surrounded by wide, wood surrounds with a beaded edge. The front gable porch roof is supported by tapered square columns atop brick piers.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3415 North Pershing Drive 000-7819-0317 Other DHR ID#: 000-5744

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Set on a rock-faced concrete block foundation, the three-bay house has a projecting side bay and a gable roof with wide, overhanging eaves and exposed rafter tails. The fenestration has wide, wood surrounds with a beaded edge and square-edged sills. The porch gable has paired six-over-one windows.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

3418 North Pershing Drive 000-7819-0295 Other DHR ID#: 000-5722

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Set on a rock-faced concrete block foundation, the three-bay house has a centered entry and flanking paired windows surrounded by a wide, wood trim with a beaded edge. The off-center front gable porch is supported by Craftsman style wood columns atop brick piers.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3501 North Pershing Drive 000-7819-0343 Other DHR ID#: 000-5770

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Set on panel-faced concrete block foundation, the three-bay frame house has a centered entry and flanking windows surrounded by wide, wood trim. The shed dormer contains paired six-over-one double-hung wood sash windows. The side gable roof has wide, overhanging eaves and exposed rafters.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 146

- 3507 North Pershing Drive** **000-7819-0320** **Other DHR ID#: 000-5747**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
Set on a panel-faced concrete block foundation, the three-bay house has a centered antry and flanking, paired windows that are surrounded by wide, wood trim with a beaded edge. The shed dormer, containing two six-over-one double-hung wood sash windows, is set on a side gable roof with wide eaves and exposed rafters. The gable ends are clad in wood shingles.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3510 North Pershing Drive** **000-7819-0310** **Other DHR ID#: 000-5737**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick house has a centered entry framed by a semi-circular arched pediment and fluted pilasters. Brick detailing includes a soldier course water table, soldier lintels and rowlock sills.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3511 North Pershing Drive** **000-7819-0319** **Other DHR ID#: 000-5746**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay frame house has a projecting side bay and two dormers with six-over-six windows and molded cornice returns. The windows have wide, wood surrounds with molded outer beads and square-edged sills. The side gable roof has molded cornice returns and wood trim at the eaves. The flared hood over the entry is supported by curved, wood brackets.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Shed **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3515 North Pershing Drive** **000-7819-0322** **Other DHR ID#: 000-5749**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick house has a centered entry framed by a door surround with a broken pediment and flanked by double-hung windows. There are three wall dormers and a side porch sits on the northeast side of the house.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3519 North Pershing Drive** **000-7819-0135**
Primary Resource Information: Single Dwelling, Stories 3, Style: Other, ca 1930
Features of this three bays wide dwelling include rowlock sills, jack arch lintels with brick keystones, a shouldered chimney, and a pedimented decorative brick surround.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 147

- 3520 North Pershing Drive** **000-7819-0309** **Other DHR ID#: 000-5736**
Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,
The three-bay house has flanking one-story, one-bay flat roof wings. The hipped roof porch has semi-circular arched bay openings and a garage is set beneath the porch, below grade. The hipped roof has wide eaves and scroll-cut wood rafter tails. Rowlock sills adorn the windows.
Individual Resource Status: Single Dwelling **Contributing**
- 3603 North Pershing Drive** **000-7819-0134**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Four bays wide this dwelling features rowlock sills, brick jack arch lintels, a sawtooth cornice and a molded wood cornice. The off-center entrance has a Colonial Revival door surround with a broken pediment featuring an urn and fluted pilasters. Located on the rear elevation is a rear gambrel roof addition.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 3606 North Pershing Drive** **000-7819-0307** **Other DHR ID#: 000-5734**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick dwelling has a side passage entry and a one-story, one-bay shed roof porch on the northeast side and a two-story brick wing with a first story garage on the southwest side. Brick detailing includes a rowlock water table, a corbeled brick beltcourse, jack arch lintels with keystones above the first story windows, and segmental arched lintels above the second story windows.
Individual Resource Status: Single Dwelling **Contributing**
- 3607 North Pershing Drive** **000-7819-0334** **Other DHR ID#: 000-5761**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick dwelling has a side passage entry set in a one-story projecting vestibule with a front gable roof and a semi-circular arch with a keystone. The windows have concrete sills. On the southwest side of the house, there is a two-story garage extension.
Individual Resource Status: Garage **Non-contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3611 North Pershing Drive** **000-7819-0329** **Other DHR ID#: 000-5756**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The two-bay brick house has a Federal style door surround with fluted pilasters. Brick detailing includes a rowlock water table, soldier lintels with a decorative header band above, an angled brick cornice, a two-course header band above the first story, and a rowlock chimney cap. The wood garage doors have modillion wood detailing.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 148

- 3612 North Pershing Drive** **000-7819-0306** *Other DHR ID#:* 000-5733
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,
The four-bay brick dwelling has a front gable projecting 1
section that has a slight overhang above the first story. 1
Brick detailing includes skintled brick, a raised and hooded 1
lintel above a first story window, a soldier course water 1
table, and rowlock sills.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3703 North Pershing Drive** **000-7819-0090**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Measuring five bays wide, this dwelling features jack arch lintels, rowlock sills, a wood cornice with modillions,
and wood surrounds.
Individual Resource Status: Single Dwelling **Contributing**
- 3706 North Pershing Drive** **000-7819-0064**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
Three bays wide this dwelling features rowlock sills, and a molded wood boxed cornice with returns. The central
entrance features fluted pilasters.
The side elevation has a garage bay addition topped with a gambrel roof.
Individual Resource Status: Single Dwelling **Contributing**
- 3711 North Pershing Drive** **000-7819-0338** *Other DHR ID#:* 000-5765
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick dwelling has a centered entry framed by a 1
Colonial Revival door surround with flush pilasters and a 1
pediment. The windows have rowlock sills and soldier lintels. 1
Individual Resource Status: Single Dwelling **Contributing**
- 3712 North Pershing Drive** **000-7819-0305** *Other DHR ID#:* 000-5732
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,
The three-bay brick dwelling has an off-center entry, rowlock 1
sills and soldier lintels. The enclosed, one-story, one-bay 1
frame porch on the northeast elevation has a below grade 1
garage beneath it.
Individual Resource Status: Single Dwelling **Contributing**
- 3715 North Pershing Drive** **000-7819-0337** *Other DHR ID#:* 000-5764
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick house has two dormers with wood 1
weatherboard cladding, molded vergeboards, and each contains a 1
six-over-six double-hung wood sash window. Detailing includes 1
rowlock sills, a rowlock lintel over the entry and an arched 1
window over the main door. The roof has a boxed cornice and 1
cornice returns.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 149

3716 North Pershing Drive **000-7819-0304** **Other DHR ID#: 000-5731**

Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,

The three-bay, brick dwelling has a side passage entry and a one-and-a-half story attached garage on the northeast side of the facade. Brick detailing includes a soldier course water table, a rowlock beltcourse below the second story windows, and segmental arched lintels with keystones on the first story windows.

Individual Resource Status: Single Dwelling

Contributing

3719 North Pershing Drive **000-7819-0342** **Other DHR ID#: 000-5769**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay brick dwelling has a centered entry framed by a door surround with a broken pediment and fluted pilasters. Detailing includes a soldier course water table, rowlock sills, segmental arch rowlock lintels, and a dentiled cornice. There is a one-story, one-bay frame wing on the northeast side of the house.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

3720 North Pershing Drive **000-7819-0065**

Primary Resource Information: Single Dwelling, 1940

Features of this four bay wide dwelling include a Colonial Revival door surround with fluted pilasters. The entry is seen under overhanging eaves on the facade. An addition is seen on the side elevation, which has an infilled garage opening.

Individual Resource Status: Contributing

3722 North Pershing Drive **000-7819-0303** **Other DHR ID#: 000-5730**

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The three-bay brick house has a front gable hood over the entry and a front gable bay with half-timbering in the gable end. Brick detailing includes rowlock sills, soldier lintels, and raised brick quoining around the entry. On the southwest side of the house, there is a side porch with a half-hipped roof.

Individual Resource Status: Single Dwelling

Contributing

3723 North Pershing Drive **000-7819-0344** **Other DHR ID#: 000-5771**

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The three-bay brick dwelling has a centered entry framed by a pedimented Colonial Revival door surround with fluted pilasters. Detailing includes a soldier course water table, rowlock sills, segmental rowlock lintels, and a dentiled wood cornice.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 150

- 3724 North Pershing Drive** **000-7819-0066** -
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
This dwelling measures three bays wide and features rowlock sills, and a wood cornice. The Colonial Revival door surround features a closed pediment, fluted pilasters, and a denticulated entablature.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3729 North Pershing Drive** **000-7819-0339** *Other DHR ID#: 000-5766*
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,
The three-bay brick dwelling has a centered entry framed by a Federal Revival style door surround with fluted pilasters. Brick detailing includes a soldier course water table, rowlock sills, rowlock arched lintels on the first story, and a single course stretcher beltcourse. The cornice has a brick modillion course above a wood modillion course and there are cornice returns on the gable ends.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**
- 3730 North Pershing Drive** **000-7819-0067**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1945
Features of this three bay wide dwelling include soldier lintels, rowlock sills, a boxed wood cornice, and a soldier water table. The central entry features a Colonial Revival door surround with a full pediment with triglyphs and fluted pilasters.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3734 North Pershing Drive** **000-7819-0068**
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival, ca 1940
Features of the three bay wide dwelling include soldier lintels, rowlock sills, and a soldier course water table. The center entry features a Colonial Revival door surround with a closed pediment, and fluted pilasters. The one chimney is shouldered.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3735 North Pershing Drive** **000-7819-0341** *Other DHR ID#: 000-5768*
Primary Resource Information: Single Dwelling, Stories 2, Style: Colonial Revival,
The three-bay brick dwelling has a centered entry framed by a pedimented door surround with fluted pilasters. Detailing includes a soldier course water table, rowlock sills, segmental arched rowlock lintels, and a dented wood cornice. There is a one-story, one-bay brick wing on the southeast side of the facade.
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 151

- 3738 North Pershing Drive** **000-7819-0205**
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1935
This dwelling is two bays wide and features rowlock sills, soldier lintels, glazed headers, a basketweave water table, and a front gable vestibule.
The front and side elevations are Flemish bond and the rear elevation is in a 6 course Flemish bond. One wall gable-roof dormer is seen on the facade. A one-story porch on the side has been enclosed.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 3802 North Pershing Drive** **000-7819-0206**
Primary Resource Information: Single Dwelling, Stories 2, Style: Other, ca 1945
Features of this three bay wide dwelling include a header course water table, rowlock sills, and soldier course lintels. Three gable roof dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 3807 North Pershing Drive** **000-7819-0210**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
This four bay wide dwelling features segmental arch header lintels, rowlock sills, a soldier stringcourse above the basement story, and a dentilated wood cornice.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Garage **Contributing**
- 3808 North Pershing Drive** **000-7819-0207**
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940
Features of this two bay wide dwelling include rowlock sills, soldier course lintels and water table, and a sloping front gable roof vestibule. Two gable roof wall dormers are seen on the facade.
Individual Resource Status: Single Dwelling **Contributing**
- 3811 North Pershing Drive** **000-7819-0209**
Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival, ca 1940
Three bays wide, this dwelling includes features such as a soldier stringcourse above the basement story, rowlock sills, and a dentilated wood cornice. The center entry features a Colonial Revival door surround with fluted pilasters, bull's eye and sunburst motif.
Individual Resource Status: Single Dwelling **Contributing**
Individual Resource Status: Shed **Non-contributing**
- 3812 North Pershing Drive** **000-7819-0208**
Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival, ca 1940
Two bays wide, this dwelling has rowlock sills and water table, soldier course lintels, and a molded wood cornice. One gable roof wall dormer is seen on the facade. The side shed roof porch has been enclosed.
Individual Resource Status: Single Dwelling **Contributing**

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 152

North Piedmont Street

225 North Piedmont Street 000-7819-0333 Other DHR ID#: 000-5760

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

Set on a panel-faced concrete block foundation, the two-bay 1
frame house has a shed dormer with paired metal sash windows 1
and a front gable section that has shingles in the gable end 1
with a molded wood trim below. The roof has wide, overhanging 1
eaves, exposed rafter tails, decorative wood brackets, and a 1
wide vergeboard.

Individual Resource Status: Garage

Non-contributing

Individual Resource Status: Single Dwelling

Contributing

525 North Piedmont Street 000-7819-0748 Other DHR ID#: 000-6919

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling has paired windows and an 1
off-center entry. The enclosed front gable porch has 1
paired posts at the corners and wide, overhanging eaves with 1
exposed rafter tails and cut-out brackets.

Individual Resource Status: Single Dwelling

Contributing

528 North Piedmont Street 000-7819-0757 Other DHR ID#: 000-6928

Primary Resource Information: Single Dwelling, Stories 2, Style: Other,

The three-bay wide vernacular house has a centered entry 1
flanked by windows with square-edged surrounds. Interior

Individual Resource Status: Single Dwelling

Contributing

529 North Piedmont Street 000-7819-0747 Other DHR ID#: 000-6918

Primary Resource Information: Single Dwelling, Stories 3, Style: Colonial Revival,

The main block of the Cape Cod house is three bays wide with a 1
centered entry set in a front gabled, flared roof 1
vestibule. The one-story, one-bay wide side wing has a shed 1
roof and the windows have rowlock sills.

Individual Resource Status: Single Dwelling

Contributing

532 North Piedmont Street 000-7819-0749 Other DHR ID#: 000-6920

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide bungalow has paired windows, a Jerkinhead 1
front porch, and wide, overhanging eaves.

Individual Resource Status: Single Dwelling

Contributing

533 North Piedmont Street 000-7819-0746 Other DHR ID#: 000-6917

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The four-bay wide dwelling has a full-width porch with a 1
beaded board ceiling and a front gable roof supported by 1
tapered square columns atop of concrete piers. The gable end 1
of the porch is clad in wood shingles and the roof has wide, 1
overhanging eaves.

Individual Resource Status: Garage

Contributing

Individual Resource Status: Single Dwelling

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 154

548 North Piedmont Street 000-7819-0752 Other DHR ID#: 000-6923

Primary Resource Information: Single Dwelling, Stories 2, Style: Tudor Revival,

The three-bay wide dwelling has a front facing chimney and a projecting gable bay with a steeply pitched roof. The entry is set beneath a shed roof hood and there is a shed roof side porch on the north elevation.

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

549 North Piedmont Street 000-7819-0742 Other DHR ID#: 000-6913

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide bungalow has a full-width front porch with a half-hipped roof. Details include wide eaves, a louvered ventilator in the gable end, projecting side bays, a wood storm door, and a rear shed roof porch.

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

552 North Piedmont Street 000-7819-0753 Other DHR ID#: 000-6924

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling features an inset porch, paired windows, and a one-story shed roof ell on the north elevation. The dormer has a single-leaf entry, two windows, and a balcony.

Individual Resource Status: Single Dwelling

Contributing

553 North Piedmont Street 000-7819-0741 Other DHR ID#: 000-6912

Primary Resource Information: Single Dwelling, Stories 1, Style: Bungalow/Craftsman,

The three-bay wide dwelling has a centered entry and a half-hipped porch with spindlework. The roof has wide overhanging eaves and there are projecting side bays on the house.

Individual Resource Status: Single Dwelling

Individual Resource Status: Garage

Contributing

Non-contributing

556 North Piedmont Street 000-7819-0754 Other DHR ID#: 000-6925

Primary Resource Information: Single Dwelling, Stories 2, Style: Bungalow/Craftsman,

The three-bay wide dwelling has a full-width front porch with a front gable roof and tapered, square columns atop concrete piers. Both the main block and the porch have wide eaves with cut-out brackets.

Individual Resource Status: Garage

Individual Resource Status: Single Dwelling

Contributing

Contributing

United States Department of the
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VA (VDHR 000-7819)

Section number 7 Page 155

560 North Piedmont Street 000-7819-0755 Other DHR ID#: 000-6926

Primary Resource Information: **Single Dwelling, Stories 2, Style: Colonial Revival,**

The three-bay wide dwelling has a Cape Cod form with 6/6 l windows in the dormers and rowlock sills. There is a shed l roof porch with a brick foundation and the exterior end l chimney is shouldered with a basketweave cap. The side porch l is set on a brick pier foundation

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Garage**

Individual Resource Status: **Shed**

Contributing

Non-contributing

Non-contributing

Total Number of Resources: 780

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 156

STATEMENT OF SIGNIFICANCE

The Ashton Heights neighborhood of Arlington County, Virginia is significant as a planned suburb of Washington, D.C. The growth of this historic community is tied to the arrival of the commuter railroads in Arlington County during the early 20th century and the housing needs of government employees. Developed in 1921, Ashton Heights was the first neighborhood in Arlington County platted by Ashton Jones, a speculative developer from southern Virginia. The community developed over several decades between 1921 and 1950, under the direction of the George H. Rucker & Company. A total of twenty-three separate divisions make up Ashton Heights, with eighteen different developers.¹ Restricted to white middle-class families, Ashton Heights became home to many Washington D.C. residents looking to move out of the nation's capital. It became a convenient locale for many federal government workers due to the availability of public transportation to and from the nation's capital. Architecturally, the community features a number of early-20th-century buildings that reflect the fashionable styles and building forms of the period. Surrounded now by major transportation and commercial corridors, Ashton Heights retains a substantial number of early-20th-century dwellings and apartment buildings representing popular styles and forms including the Bungalow/Craftsman, Cape Cod, Colonial Revival, American Foursquare, Tudor Revival styles and a single example of the Gothic Revival style. Civic, religious, and educational structures, as well as low-rise commercial buildings, and a cemetery support the residential community.

Eligible under criteria A and C of the National Register of Historic Places, the Ashton Heights Historic District has a period of significance extending from 1900 to 1950 and reflects the themes of architecture and community planning/development. In all, there are 1,100 contributing resources, and 162 non-contributing resources within the Ashton Heights Historic District. The community consists today of 781 properties with a total of 1,262 buildings, sites, and structures. Located within the Historic District, the Clarendon (Matthew Maury) School is listed individually on the National Register of Historic Places.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 157

Criterion A: That are associated with events that have made a significant contribution to the broad patterns of our history.

Ashton Heights meets Criterion A of the National Register of Historic Places as a planned community that developed because of its attraction to the expanding middle- and upper-middle-class population of Washington, D.C. in the second quarter of the 20th century. The Washington and Old Dominion Electric Railway, which ran from Rosslyn to Fairfax traveled parallel along the road that eventually became Fairfax Drive. Part of the Southern Railway's Bluemont Branch extended through the growing commercial enclave at Clarendon by 1912. The arrival of the streetcar lines prompted the transformation of Ashton Heights from its rural setting to its present status as one of central Arlington County's residential neighborhood. The increasing acceptance of the automobile and the need for efficient transportation routes into the District of Columbia dictated the 1932 construction of the Memorial Bridge, the opening of the George Washington Memorial Highway, and the ultimate demise of the railway.² Surrounded by major automobile thoroughfares, Ashton Heights was firmly established as a commuting suburb of Washington, D.C. by 1950.

Criteria C: That embody the distinctive characteristics of a type, period, or method of construction or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

The suburban neighborhood of Ashton Heights meets Criterion C of the National Register of Historic Places for its substantial concentration of domestic architecture, representing the Queen Anne, Gothic Revival, Colonial Revival, Craftsman, and Tudor Revival styles that were popular during the first half of the 20th century. Local builders and architects, including Frederick E. Westenberger and M.T. Broyhill, speculatively designed the majority of the residences according to the restrictions established by developer Ashton Jones. These restrictions concerned the race of residents, builders, and minimum construction limits, and required approval from Rucker Realty of any proposed building plan or specification. The earliest houses erected within the original Ashton Heights subdivision were Craftsman-, Colonial Revival- and Tudor Revival-style

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 158

residences built for middle-class residents. Set back from the street, these larger dwellings were augmented by sun porches, side wings, rear ell, and garages.

The dwellings of the second quarter of the 20th century are similar in style to the earlier dwellings, using essentially Colonial Revival-style elements. Much of the difference between the earlier houses and the later dwellings rests primarily in the level of ornament, the later being much more modest in detail. Many of the houses from the second quarter of the 20th century are of brick construction, and are either one-and-a-half or two stories in height and typically three bays wide. Large-scale multiple-family housing was built during the later 1930s and early 1940s. A large number of apartment buildings, constructed just south of Wilson Boulevard, maintain the Colonial Revival style dominant in the area, except in a much less adorned manner.

The influx of residents in the northern and western sections of Ashton Heights at that time provided a setting for commercial zoning in the area. The commercial enclave constructed during the 1940s is an extension of the commercial development of Clarendon, east along Wilson Avenue. Commercial development along Glebe Road served the needs of the residents of Buckingham Village, a large garden apartment complex between North Oxford Street and Glebe Road.

A significant feature of Ashton Heights is the Columbia Gardens Cemetery, platted in 1917. The cemetery covers over fifteen acres and contains over a thousand graves. It is significant as an example of a rural cemetery design in Arlington County.

HISTORICAL BACKGROUND

Arlington County

Arlington is a twenty-six-square-mile county located in Northern Virginia across the Potomac River from Washington, D.C. The county is bounded by Fairfax County to the north and west, the city of Alexandria and Four Mile Run to the south, and the waters of the Potomac River to the east. The county's association with the nation's capital began as early as 1791, when

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 159

Virginia ceded approximately thirty-one square miles of land that is now known as Arlington County and the City of Alexandria as the site for the nation's capital. At the time of the founding of the nation's capital, Arlington was still a small crossroads community with only scattered development within the environs. Andrew Ellicott commented on Arlington's rural character on June 26, 1791 in the "Surveyors Camp, State of Virginia:"

The country through which we are now cutting one of the ten-mile lines is very poor. I think for near seven miles, on it there is not one house that has any floor except the earth, and what is more strange is it is in the neighborhood of Alexandria and Georgetown..."³

At the time that Virginia officially ceded the land in 1801, the population of the county was 5,949 with all but 978 living in Alexandria.⁴ It was during this period that Arlington ceased to be under the jurisdiction of Virginia and Fairfax County and became part of the County of Alexandria of the District of Columbia. With the introduction of a circuit court, orphan's court, and levy court, Alexandria became the seat of local government, and the commercial and social center for the thirty-one-square-miles ceded by Virginia. Referred to as the "country part" of the county, Arlington remained rural with agricultural interests. The land was improved and maintained by just a few large plantations throughout this period, most notably the Alexander-Custis plantation known as Abingdon, and the George Washington Parke Custis plantation, also known as Arlington Plantation. The remainder of the cultivated land was primarily made up of small plots held by farmers and tenants.

Although the population of the Arlington area continued to increase in the early 19th century, the majority of the county's population remained concentrated in Alexandria. Of the 8,552 who lived in the county in 1810, only 1,325 lived in the rural part of the county. By 1820, the rural population had increased by only 160 persons with a total of 1,485 of the 9,703 total county residents living outside the town limits.⁵

The ties of the Arlington area to Washington, D.C. were physically manifested with the construction of bridges that replaced the ferries of colonial times. The first bridge to cross the

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 160

Potomac River into Arlington was located at the site of the current Chain Bridge. The new bridges, and Arlington's proximity to the city of Alexandria, resulted in the development of local turnpike companies and several turnpikes running west to Leesburg.⁶

Alexandria County, including the city of Alexandria and what is now known as Arlington County, was returned to the Commonwealth of Virginia following a referendum among its citizens in 1846-1847. Alexandria remained the area's center of commerce, trade, and domestic development, spurred on by the construction of canals, railroads, and trading routes. Improved roadways and the railroad further encouraged commercial prosperity by providing the necessary links between farms and commercial centers. The railroads, however, did not cross the river until after the Civil War, when Union forces laid rails along the Long Bridge.⁷

In the decades leading up to the Civil War (1861-1865), the population of Alexandria County continued to grow with 9,573 residents in 1830. By 1840, the population had increased by only 394 residents. Census records show a steady increase from 10,008 in 1850 to 12,652 in 1860. Those living in the rural part of the county in this period remained in the minority, numbering 1,332 residents in 1830 and 1,508 residents in 1840, with a decline to 1,274 residents in 1850.⁸ Most of those employed in rural areas were listed in the census of 1850 as farmers or laborers, although other professions included teachers, merchants, papermakers, carpenters, millers, shoemakers, clerks, tollgate keepers, blacksmiths, and clergymen. The Civil War and the period of Reconstruction that followed weakened the local government of Arlington, allowing corrupt local politicians to dominate from 1870 to about 1900. It was during this period that the county seat was moved from Alexandria City to the site of the present-day Arlington Courthouse. G.M. Hopkins's *Atlas of Fifteen Miles Around Washington including the Counties of Fairfax and Alexandria, Virginia*, published in 1879, documented just a handful of commercial establishments and a few blacksmith shops in Arlington.

New farms continued to be developed in the Arlington area throughout the early to mid-19th century. Attracted by a less industrial way of life and the availability of good inexpensive land, a number of new residents from New England and the Middle Atlantic states settled in the vicinity. Many of the residents erected houses in the county, although not all buildings were constructed

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 161

as permanent residences. Providing a refuge from the sweltering heat of the District of Columbia swamps, the ridge of rural Arlington was home to a number of summer cottages and hunting lodges. Beginning in 1824 George Washington Parke Custis invited friends to the area for a Fourth of July celebration in 1824. Eventually becoming a commercial enterprise, Custis's Arlington Springs was improved by the construction of various structures including a kitchen, dining hall, and dancing pavilion. Frequented by as many as 200 guests a day, the resort was accessible by boat from Washington, D.C. and Alexandria.⁹

The Development of Ashton Heights: 1921-1933

The area today known as Ashton Heights was originally a portion of "Brookdale," a 425-acre tract of land patented by James Robertson in 1742. After changing ownership several times, Brookdale was acquired by Lieutenant Bushrod Washington Hunter in 1851. The Hunter family, which possessed significant land holdings in Northern Virginia at the time, is better known for its association with Abingdon plantation, which once stood on the present site of National Airport.¹⁰

Born in 1807, Bushrod Hunter was the son of Nathaniel Chapman Hunter and Sarah Ann Tyler. He married Mary Frances Blow in 1838 and half a century later, he passed away leaving his land to his eldest daughter, Fannie Blow Hunter.¹¹

Residential development in the area around Clarendon, from which Ashton Heights began to emerge, started in 1897, when Bostonian Robert Treat Paine, Jr. purchased twenty-five acres of land near the intersection of what was then the Falls Church-Georgetown Road (now Wilson Boulevard) and the Washington, Arlington & Falls Church Electric Railway line (today the path of Washington Boulevard). In 1900, Paine had the property platted as "Clarendon," which consisted of four north-south streets and one east-west street. The new subdivision was named in honor of the Earl of Clarendon (1609-1674), and the formal dedication was held on March 31, 1900.

Paine employed Wood, Harmon and Company of Washington, D.C. to advertise and sell the building lots. An advertisement for the new suburb emphasized Clarendon's natural features, its accessibility to Washington, D.C., and the advantages of home ownership in the suburb, a

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 162

common theme throughout the next three decades.¹² Officially known as the Village of Clarendon, the area grew so rapidly that by 1907 several additions had been subdivided and developed to meet housing and commercial needs. This included "Lyon's Addition to Clarendon" in 1904, "George Rucker's Addition" in 1906, "Moore's Addition to Clarendon" and "Porters Addition to Clarendon" in 1907, "Clement's Addition to Clarendon" in 1908, and "Latterner's Addition to Clarendon" in 1909. Six more additions to Clarendon were made between March and November of 1910. With the influx of residents, commercial and public facilities began to appear along the streetcar line and along Wilson Boulevard.

Seeking refuge from the nation's capital, many Washingtonians began moving out to the more rural landscape that was to become Arlington County by the turn of the 20th century. The rush of residents to the area required the installation of amenities, new roads, and public transportation. The Great Falls and Old Dominion Railroad, organized in January 1900, established a streetcar line in 1906 from Rosslyn to Great Falls (along present-day Lee Highway) that conveniently was connected to a line that went into Washington, D.C. A second line was laid from Rosslyn to Fairfax, running parallel along the road that was eventually known as Fairfax Drive, through Clarendon. Part of the Southern Railway's Bluemont Branch, this second line first traveled through Arlington County under the organization of the Washington & Old Dominion Railway in 1912. The arrival of the streetcar lines began the transformation of Clarendon from its rural setting to its present status as central Arlington County's social and commercial center. A substantial number of local developers and builders, like Robert Treat Paine, Jr. before them, recognized the economic prosperity and residential possibilities in Arlington County and began to subdivide the area, creating neighborhoods supported by small local commercial enterprises.

In 1914, a county ordinance mandating approval of new subdivisions by the county engineer was passed by Arlington County. The next county ordinance concerning subdivision control was in April 1930. This ordinance established basic categories for land use.¹³ Between 1921, when Ashton Heights was subdivided, and 1930 this new neighborhood was not under much county government control. Many of the decisions regarding its platting, design, aesthetics, and residential character were left up to the real estate agents and builders.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 163

In 1920, the Clarendon Citizens Association, which had been aggressively promoting the area since its formation in 1912, applied to the state to incorporate the area as an independent town. After two years of ensuing court battles, the Virginia Supreme Court denied the request stating that Arlington was a "continuous, contiguous and homogenous community which could not have cities or towns incorporated within it."¹⁴ Despite this defeat, the Clarendon area continued to prosper, surrounded by new residential subdivisions developing through the 1920s and into the 1930s. The three most successful of these neighboring subdivisions--Lyon Village, Lyon Park, and Ashton Heights--still retain their character as individual residential communities today.

Ashton Heights was platted and subdivided in 1921 by Ashton C. Jones, who had acquired approximately sixty-one acres of land in 1919 from Fannie Blow Hunter. The original plat of Ashton Heights was smaller than the present neighborhood, consisting of an area bounded roughly by North Irving Street on the east, 5th Street North on the north, on the west by North Nelson Street, and on the south by the northern edge of Columbia Gardens Cemetery and 2nd Street North. The neighborhood combined two previously platted subdivisions, namely Ashton Jones's Addition to Clarendon (the section north of Pershing Drive) and Moore's Fourth Addition to Clarendon (south of Pershing Drive). The street layout of Ashton Heights consisted of a grid pattern framing Pershing Drive (then Cathcart Avenue), which ran northeast to southwest bisecting the neighborhood. The neighborhood was later expanded on the west to include the area east of North Oakland Street and north of Arlington Boulevard. The northernmost portion of what is today Ashton Heights, north of 5th Street North, began to develop before 1921 as part of Clarendon.¹⁵ These include sections platted by Strickler (1911), Straight (1911), Slack (1911), Moyler (1918), Wilson (1919), J.W. Glennan (1919), and Ellen E. Fuss (1920). Jones's second addition further developed Ashton Heights by acquiring fourteen acres of the Ellen Fuss subdivision in 1922. This area consisted of a total of five blocks located between Sixth and Fifth Streets and between Irving and Monroe Streets.

Ashton Jones, born in 1878, came from a large family in Lunenburg County, Virginia, having nine brothers and sisters. He attended the College of William & Mary for two years and then served as the circulation manager for the *Times-Herald* in Newport News for three years. Afterwards, he worked in the furniture business for three years. In 1909, Jones moved to

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 164

Clarendon after marrying Margaret Rucker. Persuaded by his brother-in-law, George H. Rucker, to work in real estate with him, Jones joined Rucker Realty, which was located in Arlington County. Rucker Realty was incorporated in 1906 immediately after George H. Rucker arrived in Clarendon. Soon after his arrival to Clarendon, Jones acquired a position as deputy county court clerk under, Rucker who served as county court clerk. He maintained this position from 1912 to 1919.¹⁶

Extremely active in the community through his entire life, Ashton Jones was engaged in a number of positions including political, religious, financial, and social. He served as organizer and chairman of the board for the First Federal Savings and Loan Association and for the Clarendon Trust. He owned and developed subdivisions in the county including Ashton Heights and Lee Heights. Jones also served as deacon for the Baptist Church, president of the Arlington Chamber of Commerce, and was a member of Columbia Lodge, Clarendon Lodge, and Fraternal Americans of Alexandria. Jones continued his partnership with George H. Rucker & Company until his death in 1960.

The George H. Rucker & Company began with Ashton C. Jones, Sr., George Rucker, and N.A. Rees as the original partners. Rucker passed away in the early 1920s and left his third of the partnership to his daughter and her husband, Rees. During the late 1930s, Rees died and Jones bought his third of the company from Rucker's daughter. This gave Jones the majority ownership with two-thirds of the company.¹⁷

The George H. Rucker & Company continued to place advertisements in the Arlington County directories from 1915 to 1955. First, the advertisement illustrated a Cape Cod dwelling, which housed the firm, and then an advertisement with a statement of guarantee. "Rucker Realty will give your house a good home" was their motto in 1974.¹⁸ The George H. Rucker & Company is still in business today with an office in McLean, Virginia.

Ashton Heights is an excellent representation of community development directed singularly towards Anglo-American middle-class families. Interestingly, many of the builders were given minimum income and racial restrictions in their contracts. Because of its accessibility to Washington, D.C., its desirable suburban lots, and its proximity to the commercial and civic

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 165

facilities of Clarendon, Ashton Heights grew steadily after its establishment in 1921. Advertisements in newspapers claimed that Ashton Heights was only three miles from Washington and twenty-two minutes by streetcar. In order to guarantee the type of neighborhood the agents and builders wanted for Ashton Heights, restrictions were incorporated into many of the deeds contracted at the time. There were racial, financial, commercial, and aesthetic restrictions applied to many of the deeds, between 1921 and 1930. These restrictions prohibited non-Caucasians from owning, renting, or occupying the dwellings in the neighborhood. A minimum construction cost was placed on many of the units to ensure that only members of the middle to upper-middle class would reside in Ashton Heights. This minimum construction cost normally ranged from \$4,000 to \$6,000. The average annual income of many of the residents buying in Ashton Heights during the 1920s was \$2,300. The cost of a lot and house at that time ranged from about \$5,500 to approximately \$9,000.

The neighborhood was promoted in advertisements as having streets, sidewalks, magnificent shade trees, and electricity for the low price of ten cents per square foot. By 1925, thirty-four houses had been erected in the expanded Ashton Heights. The houses consisted of mainly wood-frame bungalows and vernacular dwellings. During the early years of its development, a common building practice among Ashton Heights residents was to erect a small shed at the rear of a lot in which the family lived until the main dwelling was finished. These sheds were then converted to utilitarian structures when the family moved into the completed main dwelling.

Another restriction given by Ashton Jones prohibited the sale of alcoholic beverages or the "establishment of any business considered a nuisance."¹⁹ In addition to these standards, the number of houses built on a single lot was restricted and a minimum set back distance between a building and the street was established. In developing Ashton Heights, Jones mandated required approval from George H. Rucker & Company of any proposed building plan or specification.

Ashton Heights grew to include numerous additions by builders other than Ashton Jones. These builders prescribed to Jones's restrictions of minimum income and race. Additions included those platted by Kay-Alger Company (1922), M.W. Bowen (1925), Robert R. Dye's Section 1 and 2 (1929 and 1933), and Section 1 of Crack's addition (1932). One other subdivision not

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 166

originally a part of Ashton Heights, platted by Ball and Douglas, was an addition to South Ballston that developed in 1925.

In a 1928 publication, *The Book of Arlington County, Virginia*, Ashton Heights is noted on a map showing the railway lines, highways, and high schools of the area. Yet, a 1930 map of Arlington County, which noted the location of its chief subdivisions and roads, did not include Ashton Heights. Other subdivisions plotted on this map include Lyon Park, Clarendon, Ballston, and Cherrydale to name a few.

The high influx of residents moving to Ashton Heights and commuting to Washington, D.C. follows the trend set in the adjacent neighborhoods such as Clarendon, Lyon Park, and Lyon Village. *Polk's Directory* of 1927-1928 only lists approximately 150 people, half of the area's population, and in some cases, their occupations were noted, in addition to the names of their respective wives. Many of the occupations listed were federal government positions. Twenty clerks were listed working for various departments including War, Treasury, Post Office, Navy, and Interior. Two attorneys were listed, one working for the Interstate Commerce Commission. The Patent Office and the Department of Commerce had a few employees residing in Ashton Heights. Other occupations listed in the directory included carpenter, realtor, builder, weatherstriper, artist, nurse, salesman, printer, welder, and librarian.²⁰ By 1928, Ashton Heights had grown to a population of approximately 300 people. At that time, Hugh McGrath served as president of Ashton Heights Citizens Association. The Women's Club of Ashton Heights was headed by Hazel Davies.

A sampling of the 1930 census supports the information given in *Polk's Directory*. For the neighborhood of Ashton Heights, the United States Government was the predominant employer. The neighborhood was comprised of all Anglo-American residents and ranged in ages from early twenties to retirement age. The residents were native to a variety of states including Rhode Island, New York, Missouri, West Virginia, Illinois, Pennsylvania, Virginia, Oklahoma, Ohio, and California. No one state was the dominant place of origin. It also appears that with many of the families in this 1930 sample the parents came from outside of the immediate metropolitan area and the children were born in the District of Columbia. In addition to the occupations listed

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 167

in *Polk's Directory*, others include soil scientist, freight agent for the railroad, bookkeeper, police officer, and store manager.

Thirty-eight churches were located in Arlington County by 1924, eleven of which were Methodist churches. One of the eleven was the Clarendon United Methodist Church, presently located at 6th Street North and North Irving Street. It had its start after the turn of the 20th century in the North Herndon Street home of William H. Overal. In 1906, with the help of Reverend Ballengee of Georgetown's Calvary Methodist Episcopal Church, the congregation moved into its new home at North Jackson and North Irving Streets. It was not until 1910 that the church received its first full-time fully ordained minister, Dr. Theodore M. Swan. The congregation decided in the early 1920s to move into a second church at the east corner of North Irving and 10th Streets, presently an apartment building. The land for the present-day Clarendon United Methodist Church was purchased in 1932 and the church was completed by 1941 at 606 North Irving Street. In 1951, the church acquired the Kirkside property and a parking area across Irving Street. Kirkside is a circa 1923 single-family dwelling located at 625 North Ivy Street. It is a Colonial Revival-style hip-roof building clad with stucco with a wood frame garage at the rear of the house. It was in 1951 that the educational building for the Clarendon United Methodist Church was constructed.²¹ Kirkside was converted from a single-family dwelling to a young adult center at this time.²² According to a *Virginia Sun* article, in 1974, there were approximately 1500 members of the Clarendon United Methodist Church, a decline from previous years. The pastor indicated this decrease was due to the number of apartment dwellers in the area.²³

Other churches in and surrounding the Ashton Heights community include the Clarendon First Baptist Church, Trinity Chapel, Clarendon Presbyterian Church, and Clarendon Catholic Church. Arlington Boulevard became an important thoroughfare for the location of religious buildings due to their high visibility to passerbys. For example, between 1936 and 1954, the Faith Lutheran Church with its education building, and the Arlington Church of Christ (formerly the 2nd Church of Christ Scientist) at the corner of N. Irving Street, were constructed within two blocks of one another along Arlington Boulevard.

To meet the needs of the growing population in Arlington County, the Clarendon School was

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 168

constructed in 1910. An undeveloped two-acre lot of land at the intersection of Wilson Boulevard and North Monroe Street was purchased in July 1909 for the sum of \$1,800 from Edward A. and Martha I. Wilson of Indian Lake, New York. Charles M. Robinson of Richmond, Virginia, won the contract to design the school and M.W. Gayle of Newport News, Virginia, served as the builder.²⁴ During his career, Robinson (1867-1932) gained notoriety statewide as a school architect. Scholastic commissions included buildings for James Madison University, Radford University, the College of William and Mary, and Virginia State University. The architect was also responsible for the designs of numerous elementary and high school buildings throughout Virginia between 1907 and 1935, particularly in Richmond and Norfolk.²⁵

The Clarendon School, constructed in a Classical Revival style in 1910, served as the sole elementary school for the surrounding area for sixty-three years. It provided instruction to grades one through six. The name was changed to Matthew Maury School in 1924. In 1973, the Clarendon School ceased to function as a public education facility and, in 1977, the building was rehabilitated to serve as the Arlington Arts Center. The Clarendon School survives as the second oldest extant school building in Arlington County and was listed on the National Register of Historic Places in 1999.

As the community developed, civic groups began to organize and, in 1924, the Women's Club of Ashton Heights was formed. Ashton Jones donated a lot and helped the fledgling organization acquire a loan to build its clubhouse at 413 North Irving Street. Ashton Jones controlled seven lots on the east side of North Irving between North Pershing Drive and 5th Street North. After donating one lot to the women's club, he formed his addition to Lyon Park. Lyon Park, developed by Frank Lyon, was in the course of being subdivided during the same period as Ashton Heights. A neighborhood contractor was hired for \$4,700 to erect the building that was designed by Hazel L. Davies.²⁶ To help pay for the mortgage, the Women's Club held bake sales, dinners, and card parties and rented out the building to various groups. Especially popular during the early thirties were the dances held by many different fraternities and sororities of nearby universities.²⁷ In 1945, the final mortgage payment was made and the club devoted its time to community affairs. Over the years, the Women's Club organized numerous fundraising drives for neighborhood improvements and hosted educational and entertainment programs for

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 169

the community.²⁸

One of the most prominent features of Ashton Heights is the Columbia Gardens Cemetery. Located at the southern boundary of the district, it displays the 20th-century landscape design principles influenced by the rural cemetery movement of the late 19th century. With the rapid growth of urban centers late in the 19th century, landscape design and city planning began to slowly merge with the mid-century fashion for the “picturesque” work of designers such as Frederick Law Olmsted. The historic relationship of the cemetery and this principle of creating rural landscape design within urban centers is well documented in *Park and Cemetery*, one of the earliest professional journals in the field of landscape architecture. By the 1900s, parks and cemeteries began to take on more formal aspects of landscape planning, a school of thought that was made fashionable by the City Beautiful movement. With the reintroduction of classical formality early in the 20th century, cemetery landscapes tended to have axial aligned principal avenues that focused on more imposing resources such as churches.

The Columbia Gardens Cemetery is an example of the more rural cemetery design, however, with its winding roads and natural landscape features. The cemetery is maintained by the Alexandria Park Association, which was incorporated in 1914 in Huntington, West Virginia, the home of the principal founder Julius Broh. The president of the association was Colonel Robert Dye, the former superintendent of the Arlington National Cemetery. Having won approval from the Arlington County Board of Commission, the association platted the cemetery in 1917. The proposal indicated their intent to “make a place that will be attractive as a park and a credit to the county.”²⁹ The “park” initially encompassed nearly thirty-eight adjoining acres, with an option to purchase an additional thirty acres. In November 1917, the board of directors employed a landscape architect from Cleveland, Ohio, a Mr. Jenney, to prepare the design, specifications, and methods of procedure for operating a cemetery. The advertisement in *Hills 1955 Directory* for Columbia Gardens Cemetery claims it is a “shrine of perpetual beauty” with “perpetual care.”³⁰ One of the more significant interments is Francis Eugene Worley (1908-1974). He served as a member of the Texas State House of Representatives, 1935-1940; U.S. Representative from Texas, 1941-1950; and as Judge of U.S. Court of Customs and Patent Appeals, 1950-1959. Another politician buried in Columbia Gardens is Charles Noel Crosby

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 170

(1876-1951). He was a Pennsylvanian Democrat in the U.S. House of Representatives from 1933 to 1939. A mausoleum in honor of Admiral George Dewey (1837-1917), the famous American naval officer, is located near the entrance of the cemetery.

Development Between 1934 and 1950

In 1930, Ashton Jones gave a statement advocating the sewerage bond issue that was introduced to install a modern sewer system into Arlington County. This statement foresaw the importance of modern utilities for Arlingtonians. Concerned with the development of the county, he stated that a modern sewerage system would induce "far more people [to] move in, which will increase employment permanently." Ashton Jones foresaw the building boom in Arlington County with his final statement on the bond issue: "the sewerage and the school bond issues...coupled with the completion of the New Memorial Bridge, will mean the greatest building boom this county has seen since the days before the Great World War."³¹ He did not realize that in actuality the Second World War would bring about the largest building boom the county would ever see.

Subdivisions to Ashton Heights during this era included Langhorne (1931), Alice Indemauer property (1937), Mrs. Tyrell Property (1937), Kenmore (1938), Van Every (1939), and Crack (1949). Several individual builders were responsible for their own speculative building throughout Ashton Heights. Frederick E. Westenberger is one of several individual builders given restrictions from Ashton Jones. He served as developer for many of the brick dwellings constructed between 1933 and 1940 in Ashton Heights. Westenberger was a German immigrant who worked in Norfolk as a carpenter before moving to Arlington. Westenberger began building just one or two houses at a time, but eventually produced between ten to fifteen houses at once.³² Some of Westenberger's houses include 325, 415, 419, and 423 North Oakland Street; 435, 436, 507, and 601 North Monroe Street; and numerous houses in the 400 block of North Nelson Street. Westenberger was also a popular builder in the Lyon Village neighborhood, having built 23 houses for that community including his own residence. All of the bricks were made by hand on a wood press in Glasgow, Virginia.³³ Although the overall designs of the residences produced by Westenberger were similar, each dwelling was given an individual characteristic, such as a recessed window, fluted columns, a copper-roofed portico, or wood shingling. Kenton D.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 171

Hamaker, an associate architect with the Clarendon firm of Ernest Dorsey Stevens, in 1935 designed many of the architectural plans initiated by Westenberger.³⁴

Another set of builders in Ashton Heights were the Broyhill brothers; Marvin T. served as the developer, and Lincoln R. worked as the carpenter. Born in Wilkes County, North Carolina, Marvin T. Broyhill attended business school in Cincinnati, Ohio and Omaha Technical School in Nebraska. In 1912, he worked for the Southern Railroad Company as a telegraph operator and shipping clerk. In 1915, he formed the Virginia Real Estate Association, and eventually moved to Arlington in 1937. He located the M.T. Broyhill and Sons Corporation at 4600 Lee Highway. A number of houses in the Alice Indermauer tract in Ashton Heights were built by the M.T. Broyhill and Sons Corporation. Some of these houses include 514, 520, 524, 530, 538, and 544 North Monroe Street. Having constructed over 15,000 houses in Northern Virginia immediately following World War II, the Broyhill Corporation grew to be one of the largest real estate companies in the Washington area.

Walter J. England was another one of these individual speculative builders. He constructed a number of houses along North Jackson Street, including 204 and his own house at 206. England built smaller less expensive houses, one of which sold for only \$2,500 in the 1930s. Another such builder in Ashton Heights was Clarence Gosnell, who built a large number of duplexes in 1938 in the Kenmore subdivision along Oakland Street. Nelson Street was also developed by Gosnell along with O.T. Carr, Inc. in 1939. Builder Joseph L. Gaddy constructed many of the dwellings in Robert R. Dye's Third Addition to Ashton Heights. In 1939, Sixth Road was developed by contractor J.B. Tiffey.

The Kay-Alger Company, a Washington real estate firm, was a significant builder of a small area of Ashton Heights located above 1st Street North, below 2nd Road North, and bordered by Columbia Gardens Cemetery to the west, and Irving Street to the east. This company was selling its lots for twelve cents per square foot with immediate payment, and fourteen cents through monthly payments. Walter England built a few of the Kay-Algers lots, one going for an amount of \$1,310 at twelve cents per square foot. The Kay-Alger Company, located in the Bond Building in Washington, D.C., used innovative selling and advertising techniques to promote the

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 172

new suburbia in Arlington County. Washingtonians were given free auto rides from the Bond Building, leaving on the hour during the week, to the neighborhood for inspection trips. Their advertising for Ashton Heights included such adjectives as “picturesque,” “progressive,” and “natural beauty.”

A 1948 advertisement of a house for sale in Ashton Heights on North Nelson Street leads with “In Popular Ashton Heights.” The description of the house is as follows:

Beautiful all-brick residence with open fireplace in living room, den or bedroom on first floor, hardwood floors, 3 bedrooms on second and bath, with pull-down stairs to a finished attic. Shower in basement and also paneled recreation room. Oil hot-water heat, 2 electric refrigerators, Venetian blinds, 2-car det. Garage. 3- blocks of Buckingham Shopping Center, close to parochial and public schools, 1 block to bus transportation. Possession with title. Act quick.³⁵

The Great Depression suppressed the extensive building rate that had occurred in the Washington, D.C. area during the 1920s. The early thirties were a difficult time, economically for the entire nation that is why there were only sixteen houses built in Ashton Heights north of Pershing Road between 1931 and 1933.

Ashton Heights is a residential neighborhood with some commercial infringement, or rather support, at the northern edge along Wilson Boulevard. Most of the commercial buildings were primarily constructed during the second half of the 20th century. By 1938, only a few lots were zoned commercial in Ashton Heights, and one lot was zoned for industrial uses. The commercial corridor includes restaurants, gas stations, and numerous other retail establishments that service the Ashton Heights community and the automobile traffic passing to the north of the neighborhood.

Garden Apartments, Apartment Houses and Apartment Complexes in Arlington County: 1934-1954

The explosion of the population in the Washington, D.C. metropolitan area between 1934 and 1954

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 173

as a result of the federal government's New Deal programs, increasing need for wartime workers and return of World War II veterans, led to a crippling housing shortage throughout the area.³⁶ Arlington County, whose rural landscape would soon be an image from the past, became one of the fastest developing counties in the Washington, D.C. metropolitan area.³⁷ The extensive housing shortage in Washington, D.C. led to the construction of 176 new apartment buildings or complexes in Arlington County between 1934 and 1954 to house these new middle-class residents. During the late 1930s and particularly the war years of the forties, new construction was nearly entirely devoted to the construction of duplexes and multiple-family dwellings, the majority of which was located in the northwestern corner of Ashton Heights. Kenmore Development Company, J.B. Tiffey, Barkley Brothers, Gosnell and Paul Goff, and Crestwood Construction Company were some of the builders of this area. During the 1940s, at least 137 multiple-family units were constructed in Ashton Heights.³⁸

The number of Arlingtonians continued to grow, with the population reaching 26,615 residents in 1930. This number more than doubled ten years later with a total of 57,040 residents in 1940. Of those employed in 1940, more than 40% were involved with the government on a local, state, and federal basis. These workers, who made up the largest group of families and individuals in need of rental housing, spurred the government to become involved in housing developments. "Increased rentals for...apartment units..., coming in the wake of the largest federal payrolls since the World War (I), were the primary reason for the great revival of...building. Thousands of new employees of the New Deal agencies rapidly took up the slack in residential space, causing rentals to increase 25 percent and more."³⁹ The Federal Housing Administration (FHA), established in 1934, became the primary mortgage insurers for thousands of residential projects, both single-family and multiple dwellings, throughout the United States. The FHA's involvement in Arlington County directly impacted a number of the large apartment complexes that would be constructed in the county between 1934-1954. The county's location along the banks of the Potomac River across from Washington, D.C. attracted a number of developers with FHA-insured mortgages to construct these large-scale housing projects. Where the FHA was not directly involved, they influenced the designs and layouts of hundreds of the complexes and individual apartments being built in Arlington County. The dramatic increase in population during the 1930s and the limited availability of affordable rental housing for middle-class

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 174

government workers made the county a prime development area.

The beginning of World War II in Europe in 1939 turned the FHA's focus to defense housing. In Arlington County, the population jumped from approximately 57,000 in 1940 to 120,000 in 1944. The FHA Large Housing Division turned its attention to the development of more low-rent housing for the burgeoning defense requirements in the metropolitan area and throughout the United States. In order to encourage this type of housing by private developers, the FHA lowered its minimum construction, design and property requirements. Once the United States entered the war in December 1941, low-cost housing for wartime workers was essential, especially in the Washington, D.C. metropolitan area with the severe housing shortages. Changes that were adopted by the FHA to stimulate this development included the omission of service walks, a main exterior entrance and front stairs, the elimination of garages, and the construction of longer buildings.⁴⁰ These changes can be seen at the Kenmore Apartments at North Monroe, North Nelson and North Oakland Streets in Ashton Heights, built in 1940. This apartment complex comprises twenty-eight two-story buildings with off-street parking and individual entrances to each unit. The influence of the FHA suggestions is evident by the elimination of public halls and garage parking at the Kenmore Apartments. The buildings' modest Colonial Revival design and the elimination of expansive garden courts with individual landscaped areas at the rear adhere to the budget cutting items emphasized by the FHA's Large Scale Housing Division.

Ashton Heights is a residential neighborhood with some commercial buildings located at its northern edge along Wilson Boulevard. Most of them were primarily constructed during the second half of the 20th century. By 1938, only a few lots were zoned commercial in Ashton Heights, and one lot was zoned for industrial uses. The commercial corridor includes restaurants, gas stations, and numerous other retail establishments that serve the Ashton Heights community as well as the automobile traffic passing to the north of the neighborhood.

Development after 1950

In the 1950s, construction in the area began to decline, as nearly all subdivided lots had been improved. Only seventeen units, all single-family dwellings, were built during this decade. The

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 175

only apartment complex built since the 1940s, located on Sixth Road North with a total of eight units, was built by the Sharpe and Hamaker Company.⁴¹ There was even less construction during the 1960s and 1970s, with only five and four houses constructed, respectively. As for apartment units, the number jumped from 62 to 446 from the 1960s to the 1980s for the entire neighboring area.⁴² This increase is quite indicative of the building boom experienced by the area during the second half of the 20th century.

Although the area experienced a downward trend in the desirability of owning individual homes in the area between the 1960s and mid-1970s, property values have steadily increased and the attraction of the neighborhood has continued to grow throughout the 1980s and 1990s. The coming of the Metrorail in 1974 has also greatly impacted the neighborhood. Two Metrorail stations are located within two blocks of the neighborhood (at Virginia Square and Clarendon), making the area easily accessible to downtown Washington, D.C.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 176

TABLE 1. SUBDIVISIONS WITHIN ASHTON HEIGHTS

Subdivision	Date Platted/ Deed Book	Developers	Deed Restrictions
Strickler's Addition to Clarendon	1911, April 15 123/513	Harry M. Strickler	Unknown
Slack's Addition to Clarendon	1911, February 27 127/473	J.W. & M.L. Slacks, E.A. & M.L. Wilson	Unknown
Straights Addition to Clarendon	1911, July 1 129/ 353	George & Nette Straight	Unknown
Moyler's Addition to Clarendon	1918, October 30 159/152	John and Mary Z. Moyler	Unknown
Section 2, Wilson's Addition to Clarendon	1919, April 9 160/521	Edward A. & Martha L. Wilson	Unknown
J.W. Glennan's Addition to Clarendon	1919, July 25 162/543	John W. Glennan	Unknown
Ellen E. Fuss' Addition to Clarendon	1920, September 23 171/458	Ellen E. Fuss	<ul style="list-style-type: none"> ▪ Caucasians only ▪ No sale of alcohol ▪ No nuisance businesses
Ashton Heights	1921, September 23 177/381	Ashton C. & Margaret V. Jones	<ul style="list-style-type: none"> ▪ Caucasians only ▪ \$4,000 minimum ▪ Bldg Plan approval
Kay-Alger Company's Addition to Ashton Heights	1922, May 1 182/314	Kay-Alger Co., Inc. (Florence Means Kay & Ethel Orput Alger)	Unknown

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 177

Ball & Douglas Addition to South Ballston	1925, April 27 215/59	Frank L. & Marie S. Ball; Lawrence W. & Blanche C. Douglas	Unknown
M.W. Bowen Subdivision	1925, July 14 225/23	Mortimer W. & Sadie E. Bowen	Unknown
Robert R. Dye's 2 nd Addition to Ashton Heights	1929, December 19 306/251	Alexandria Park Association, Inc.	<ul style="list-style-type: none"> ▪ Caucasians only ▪ \$5,000
Crack's Addition to Ashton Heights	1932, November 1 300/358	Bessie I. & John E. Crack; Francis T. & Jessie L. Smith; Vernan T. Crack	<ul style="list-style-type: none"> ▪ Caucasians only ▪ \$4,000
Robert R. Dye's Addition to Ashton Heights	1933, August 1 342/403	Robert R. Dye; Julius & Ruth Broh	<ul style="list-style-type: none"> ▪ Caucasians only ▪ \$4,000 minimum
Langhorne Subdivision	1931, May 22 323/116	The District Corporation	<ul style="list-style-type: none"> ▪ Caucasians only
Section Two, Ashton Heights	1935, June 1 370/120	Ashton C. & Margaret V. Jones; Lizzie Rucker; N.A. & Ella B. Ress	Unknown
Alice Indemauer Property	1937, April 8 409/443	Alice Indermauer	<ul style="list-style-type: none"> ▪ Caucasians only ▪ \$4,500 minimum
Mrs. Tyrell Property	1937, April 10	Unknown	Unknown
Kenmore	1938, November 23 451/300	Washington Permanent Building Association	Unknown
Van Every's Addition to Ashton Heights	1939, March 21 459/382	Virginia M. Van Every; G.W. & V.P. Benzie	<ul style="list-style-type: none"> ▪ \$6,000 minimum ▪ Building approval

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 178

Crack's Second Addition to Ashton Heights	1949, October 13 898/520	John E. & Bessie L. Crack	Unknown
Wilson's Addition to Clarendon	Unknown	Unknown	Unknown
Robert T. Dye's 3 rd Addition to Ashton Heights	Unknown	Unknown	<ul style="list-style-type: none">▪ Caucasians only▪ \$4,500 minimum

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 179

ENDNOTES

¹ See Table 1 for a list of Ashton Heights developers, date of plat, and deed restriction.

² Nan Netherton and Ross Netherton, *Arlington County in Virginia: A Pictorial History*, (Norfolk/Virginia Beach, VA: The Donning Company Publishers, 1987), p. 138.

³ As quoted in Tony P. Wrenn, *Falls Church: History of a Virginia Village*, (Falls Church, VA: Historical Commission of Falls Church, 1972), p. 6.

⁴ Arlington County Bicentennial Commission, *Historic Arlington*, Rev. ed. (Arlington, VA: Arlington County Historical Commission, 1976), p. 3. Of those living in the town of Alexandria, 875 were slaves. Of the 978 living in the country, 297 were slaves.

⁵ Census numbers from 1820 District of Columbia Census, p. 219.

⁶ C.B. Rose, Jr., *Arlington County, Virginia: A History*, (Arlington County, VA: Arlington Historical Society, 1976), p. 75.

⁷ Rose, pp. 77, 105.

⁸ 1830 population total from District of Columbia Census, reel 35 and 1840 from District of Columbia Census, reel 932.

⁹ This area was destroyed by the construction of nine parkways and roads bordering the Potomac River from the Key Bridge to the George Mason Bridge; Rose, p. 69.

¹⁰ Peter Dickson, "A Short History of Ashton Heights," *Ashton Heights Civic Association Newsletter* (April 1991), pp. 3-4.

¹¹ *The Hunter Family of Virginia*, Compiled by Sidney Methiot Culbertson. Denver, CO, 1934, p. 41.

¹² Dorothea E. Abbott, "The Roots of Clarendon," *Arlington Historical Magazine* Vol. 8, No. 2 (October 1986), pp. 49-52.

¹³ Rose, p. 222.

¹⁴ Quoted in *Historic Resources In the Clarendon Commercial District*, p. 7.

¹⁵ "A Short History of Ashton Heights," pp. 3-4.

¹⁶ George H. Rucker, served as Clerk of the Court from 1899 to 1919.

¹⁷ McCarthy, p. 5.

¹⁸ *Arlington County Directory, 1974* (Hill Directory Company Publication), p. 59.

¹⁹ Michael McCarthy, "The Contribution of Real Estate Agents and Builders to the Development of Ashton Heights," Paper prepared for Historic Preservation: Principles and Methods, March 28, 1994. Archived at the Virginia Room of the Arlington County Library, p. 4

²⁰ *Polk's Ashton Heights Directory: 1927-1928*, (R.L. Polk & Co.), pp. 523-526.

²¹ "Clarendon United Methodist Celebrates 65th Anniversary," *Northern Virginia Sun*, May 29, 1971. p. 3 and 5.

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 8 Page 180

²² Anne Cadman, "Clarendon Is 73 Years Old," *Northern Virginia Sun*, January 26, 1974, p. 5.

²³ Cadman, p. 5.

²⁴ Arlington County School Board Minutes. Book 2.

²⁵ John E. Wells and Robert E. Dalton. *The Virginia Architects 1835-1955: A Biographical Dictionary*. (Richmond, VA: New South Architectural Press, 1997), pp. 377-378.

²⁶ "History of the Woman's Club of Ashton Heights, Arlington, Virginia, 1924-1976," Pamphlet on file at Arlington Central Library, Virginia Room, Vertical File "Ashton Heights."

²⁷ See Ashton Heights vertical files in the Virginia Room of the Arlington County Library.

²⁸ "History of the Woman's Club of Ashton Heights, Arlington, Virginia, 1924-1976."

²⁹ Rita R. Rothwarf, "Neighborhood History Preservation Study for the Ashton Heights Area of Arlington County, VA," (Archived at the Virginia Room, Arlington County Library, 1987), p. 4.

³⁰ *Hills Directory*, (Richmond: Hill Directory Co., Inc.), 1955, p. 41.

³¹ *Copy of Statement made by Ashton C. Jones favoring the Sewerage Bond Issue*. Courtesy the Washington Post, 1930.

³² Westenberger interview, 1994.

³³ Ehrenhalt, p. 2.

³⁴ By the late 1940s, Hamaker, who was active from 1935 to 1953, maintained his own practice in Arlington. In addition to his many designs in Lyon Village, Hamaker worked on the Westover Hills Shopping Center on North Washington Boulevard in 1940.

³⁵ Advertisement seen in the *Washington Post*, October 31, 1948.

³⁶ For additional information, refer to *Garden Apartments, Apartment Houses and Apartment Complexes in Arlington County, Virginia: 1934-1954*. Multiple Property Documentation Form, completed by E.H.T. Traceries for the Arlington County Department of Community Planning, Housing and Development, June 2002.

³⁷ James Goode, *Best Addresses*, (Washington, D.C.: Smithsonian Press 1988), p. 324.

³⁸ Laura M. Spina, "Ashton Heights: A Description of the Residential Changes Since 1940." (Paper written to fulfill the requirements of a course entitled Historic Preservation: Principles & Methods at George Washington University, March 30, 1994), p.3.

³⁹ "D.C. Building Activities Show Boom-Like Gains," *Evening Star*, December 28, 1935.

⁴⁰ "Garden Apartments," *The Architectural Forum*, Volume 72, Number 5, May 1940, p. 310.

⁴¹ Building permit 35915.

⁴² Arlington County Department of Community Planning, Housing and Development, *Development in the Metro Corridors*, Arlington, VA: Department of CPHD, 1990, p. 38.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 9 Page 181

Bibliography

Books and Other Published Materials

Arlington County Bicentennial Commission. *Historic Arlington*. Rev. ed. Arlington, VA: Arlington County Historical Commission, 1976.

Arlington County School Board, Ed. *The Arlington Story 1962*. Arlington, VA: The County School Board of Arlington, VA, 1962.

Arlington County Department of Community Planning, Housing and Development. *Development in the Metro Corridors*. Arlington, VA: Department of CPHD, 1990.

Carley, Rachel. *The Visual Dictionary of American Domestic Architecture*. New York, NY: Henry Holt and Company, 1994.

Chittenden, Cecil. *Arlington: A New Frontier*. New York, NY: The Hobson Book Press, 1946.

Goode, James M. *Best Addresses*. Washington, D.C.: Smithsonian Institution Press, 1988.

Houses by Mail: A Guide to Houses from Sears, Roebuck and Company. Introduction by Katherine Cole Stevenson and H. Ward Jandl. Washington, D.C.: The Preservation Press, 1986.

King, LeRoy O., Jr. *100 Years of Capital Traction: The Story of Streetcars in the Nations Capita*. Dallas, Texas: LeRoy O. King, Jr., 1972.

Lee, Dorothy Ellis. *A History of Arlington County, Virginia*. Richmond, VA: The Dietz Press, Inc., 1946.

Loth, Calder, editor. *The Virginia Landmarks Register, Fourth Edition*. Charlottesville, VA: The University Press of Virginia, 1999.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 9 Page 182

Mackey, Crandal, M.E. Church, and others. *A Brief History of Alexandria County, VA, Virginia: Its Wealth and Resources, Great and Growing Industries, Educational and Social Advantages, Future Outlook Promising.* Falls Church, VA: The Newell Printing Company, 1907.

McAlester, Virginia and Lee McAlester. *A Field Guide to American Houses.* New York, NY: Alfred A. Knopf, Inc., 1984.

McCarthy, Michael. "The Contribution of Real Estate Agents and Builders to the Development of Ashton Heights." Paper prepared for Historic Preservation: Principles and Methods, March 28, 1994. Archived at the Virginia Room of the Arlington County Library.

National Retail Institute, *The Book of Arlington County, Virginia.* Washington, D.C.: The National Retail Institute, 1928.

Netherton, Nan and Ross Netherton. *Arlington County in Virginia: A Pictorial History.* Norfolk/Virginia Beach, VA: The Donning Company Publishers, 1987.

Rose, C.B. Jr. *Arlington County, Virginia: A History.* Arlington County, VA: Arlington Historical Society, 1976.

Templeman, Eleanor Lee. *Arlington Heritage: Vignettes of a Virginia County.* New York, NY: Avenel Books, 1959.

Journal Articles

"An Annotated Guide to Selected Maps of Arlington County." *Arlington Historical Magazine*, Vol. 4, No. 2, (October 1970) pp. 56-65.

"Arlington County Building Active." *Evening Star*, (December 19, 1928), p. 15.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 9 Page 183

Cotton, J. Randall. "Return to Concrete Block Houses." In *Old House Journal* Vol. XXIII, No. 2, (March/April 1995), pp. 33-39.

"M.T. Broyhill, 78, Prominent Builder Dies in Arlington." *Northern Virginia Sun*, 24 November 1966.

"Plaque in Sears Marks Jack Jones' Birthplace." *Northern Virginia Sun*, 13 November 1959.

Ross, Nancy L. "'Club LT' Beware: Little Tavern Bought, To Spruce Up Image." *Washington Post*, February 13, 1981, p. E1.

"Son Succeeds A.C. Jones, 80, In 1st Federal." *Northern Virginia Sun*, 13 November 1959.

Stoneburner, Clifton G. "Early Roads in Arlington County." *Arlington Historical Magazine*, Vol. 4, No. 1, p. 19.

"Twentieth Century History of Arlington, 1900-1980: A Chronology." *Arlington Historical Magazine*, Vol. 9, No. 2, pp. 57-63.

Maps

Arlington Historical Society and Donald A. Wise, Researcher. *Land Ownership Map: 1669-1796*, 1976.

Arlington County, Virginia, Engineer Office. *Map of Arlington County, Showing Subdivisions*, 1925.

Bell, W. *Map of Alexandria County*, 18th century.

Franklin Survey Company. Franklin's indexed map of Arlington County, Virginia. Philadelphia, PA: Franklin Survey Company, 1943 and 1952.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 9 Page 184

G.M. Hopkins. *Atlas of Fifteen Miles Around Washington, D.C.*, 1878.

Howell and Taylor. *Map of Alexandria County, Showing Ownership*, 1900.

Lewis, Carberry. *Plat of Alexandria County, Virginia*, 1836.

Sanborn Fire Insurance Maps. Arlington, Virginia: 1936 and 1954.

United States Geological Survey. *USGS Quadrangle Map, Alexandria Quadrangle*, 1965 revised 1983.

United States Geological Survey. *USGS Quadrangle Map, Washington D.C.-West Quadrangle*, 1965 revised 1983.

United States War Department, Engineering Bureau. *Military Map of Virginia Showing Forts and Roads*, 1865.

Other Sources, Brochures

"Ashton Heights Neighborhood Conservation Plan," Arlington County Office of the County Board, April 1976.

Bellue, Megan K. "Ashton Heights: A Social Profile." Paper written to fulfill the requirements of a course entitled Historic Preservation: Principles & Methods at George Washington University, March 28, 1994.

Bobeczko, Laura, Theresa Burr, and Lisa Greenhouse. "Ashton Heights: The Growth of a Washington Suburb." A study paper for a course entitled Historic Preservation: Principles and Methods, for professor Richard Longstreth, March 28, 1994.

"History of the Woman's Club of Ashton Heights, Arlington, Virginia, 1924-1976." Pamphlet on file at Arlington Central Library, Virginia Room, Vertical File "Ashton Heights."

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 9 Page 185

Kumro, Rick. "The Evolution of the Suburb: An Analysis of Development in Arlington County, Virginia." A study paper for a University course entitled Study of the City under Professor Alexander Garvin, 1977.

McCarthy, Michael. "The Contribution of Real Estate Agents and Builders to the Development of Ashton Heights." Paper written to fulfill the requirements of a course entitled Historic Preservation: Principles & Methods at George Washington University, March 28, 1994.

Meyer, Brendon. "Ashton Heights Residential Development, 1931-1942." Paper written to fulfill the requirements of a course entitled Historic Preservation: Principles & Methods at George Washington University, March 28, 1994.

Polk's City Directory for Arlington County: 1927-1928. R.L. Polk & Co., Publishers

Rothwarf, Rita R. "Neighborhood History Preservation Study for the Ashton Heights Area of Arlington County, Virginia." Paper submitted in partial fulfillment of the requirements for Historic Preservation, HIST 693 for Dr. C. Ramirez, George Mason University, December 16, 1987.

Shafer, Mary Louise. "Arlington County, Virginia in Transition." Masters thesis, George Washington University, February 16, 1981.

Shearer, Anglea. "Selected Public and Private Institutions Concerning the Ashton Heights Community: Schools, Religious Institutions, Clubs/Civic Organizations." Paper submitted in for course entitled Principles and Methods of Historic Preservation 278, for Professor Richard Longstreth at George Mason University, March 28, 1994.

Smith, Don R. and Wayne Roberts. "Our Duty Then and Now and in the Future," an excerpt from *The Three Link Fraternity – Odd Fellowship in California*. Located on the Internet on December 14, 1999 <http://128.125.109.137/IOOF/Books/IOOFDuty.html>.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 9 Page 186

Snyderman, Lois and the Couture/Denig Partnership. "Historic Resources Survey: Early 18th-mid-20th Century School Buildings." Arlington County, VA: December 1991.

Spina, Laura M. "Ashton Heights: A Description of the Residential Changes Since 1940." Paper written to fulfill the requirements of a course entitled Historic Preservation: Principles & Methods at George Washington University, March 30, 1994.

Springston, Kathy Holt. "Sears Houses of Arlington," Unpublished Brochure, 1996.

U.S. Census Records

U.S. Bureau of the Census. The Census of 1820, District of Columbia. National Archives, page 219.

U.S. Bureau of the Census. The Census of 1830, District of Columbia. National Archives, reel 35.

U.S. Bureau of the Census. The Census of 1840, District of Columbia. National Archives, reel 932.

U.S. Bureau of the Census. The Census of 1870, Alexandria County, Virginia. National Archives, reel 1632.

U.S. Bureau of the Census. The Census of 1900, Alexandria County, Virginia. National Archives, reel 1698.

U.S. Bureau of the Census. The Census of 1930, Arlington County, Virginia. National Archives.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 10 Page 187

10. Geographical Data

- | | |
|--|--|
| 5) <u>1/8/</u> <u>3/1/7/3/3/3/</u> <u>4/3/0/5/3/2/7/</u> | 6) <u>1/8/</u> <u>3/1/7/4/2/4/</u> <u>4/3/0/5/3/2/5/</u> |
| Zone Easting Northing | Zone Easting Northing |
| 7) <u>1/8/</u> <u>3/1/7/4/3/1/</u> <u>4/3/0/5/4/3/9/</u> | |
| Zone Easting Northing | |

Verbal Boundary Description

Ashton Heights Historic District is located in central Arlington County, Virginia. It is located south of the Clarendon Commercial District, and west of the Lyon Park Historic District. The neighborhood is bounded by Arlington Boulevard to the south, North Irving Street to the east, roughly bounded by North Oxford and North Piedmont Streets to the west, and Wilson Boulevard to the north. The Ashton Heights Historic District occupies approximately 220 acres.

Boundary Justification

The boundaries of the Ashton Heights Historic District encompass early additions to Clarendon prior to Ashton Jones's platting of the neighborhood. The first section of Ashton Heights, platted in 1921, was bounded by North Irving Street, 5th Street North, 2nd Road North and Columbia Gardens Cemetery to the south, and North Nelson and North Monroe Streets to the west. The second section of Ashton Jones development occurred to the immediate west of the first section, bounded to the west by North Oxford Street. Adjacent blocks were improved as additions to Ashton Heights between 1922 and the 1950s. Each of these additions shows a similar development pattern to the original area by Ashton Jones, so, these properties were included in the historic district.

Arlington Boulevard serves as the southernmost boundary for the Historic District. Significant changes occurred in 1930 when Arlington Boulevard was opened along the border of Ashton Heights, creating a major automobile route to Washington, D.C. The additions that were made to Ashton Heights after the opening of Arlington Boulevard

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 10 **Page** 188

include Van Every's made in 1939 to the east of Columbia Gardens Cemetery and R.R. Dye's to the west of the cemetery.

The northernmost boundary is south of Wilson Boulevard, excluding all those commercial properties fronting this major transportation corridor. Established as a thoroughfare before the American Revolution, Wilson Boulevard is a longstanding boundary between Ashton Heights and the commercial centers to the north. The commercial buildings that serve the neighborhood are largely confined to this northern boundary, historically having provided the residents with access to goods and services. Yet, these commercial buildings have been excluded from the historic district because their development more fully reflects the evolution of Wilson Boulevard and commercial enterprises rather than residential development.

North Irving Street creates the eastern boundary, with Lyon Park to the east. Ashton Jones originally owned several lots on the east side of North Irving Street, when Lyon Park was being developed. In 1924, Ashton Jones donated one lot, 413 North Irving Street, to the Ashton Heights Women's Club. This building continues to serve as the women's club for the community, and is included within the eastern boundary for the historic district. Only two historic resources were demolished along North Irving Street to allow for the construction of late-20th-century resources. As these modern buildings are not consistent with the neighboring historic resources in form, ornament, or scale, they have been excluded from the district.

A portion of the westernmost boundary includes historic residences facing North Oakland Street, and six historic houses located along 2nd Street North west of North Oakland Street. Further north, the boundary keeps to the east of Buckingham Place including those dwellings facing west towards North Oxford Street. North of 5th Street, the boundary proceeds irregularly including historic dwellings along North Piedmont Street, and several multiple dwellings east of North Piedmont Street. Above 7th Street North, the western boundary juts back to include only those buildings facing N. Oakland Street. Since all modern buildings are not consistent with the neighboring historic resources in form, ornament, or scale, they have been excluded from the district. Buckingham Apartments, a

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON COUNTY, VA (000-7819)

Section number 10 Page 189

garden apartment complex, is included in the Ashton Heights neighborhood, however the complex is not within the historic district boundary. Buckingham Apartments was individually listed on the National Register of Historic Places as the Buckingham Historic District in 1999.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VIRGINIA (000-7819)

Section number Photographs Page 190

All photographs are of:

ASHTON HEIGHTS HISTORIC DISTRICT

Arlington County, Virginia

VDHR File Number: 000-7819

E.H.T. Tracerics, Inc., photographer

All negatives are stored with the Department of Historic Resources in Richmond:

DATE: July 2002
VIEW OF: 3520 North Pershing
Drive, looking southeast
NEG. NO.: 19987
PHOTO: 1 OF 16

DATE: July 2002
VIEW OF: 3606-3610 3rd Street
North, looking southwest
NEG. NO.: 19987
PHOTO: 2 OF 16

DATE: July 2002
VIEW OF: 225-231 North Jackson
Street, looking northeast
NEG. NO.: 19987
PHOTO: 3 OF 16

DATE: July 2002
VIEW OF: 502 North Jackson Street,
looking northwest
NEG. NO.: 19987
PHOTO: 4 OF 16

DATE: July 2002
VIEW OF: Ashton Heights Women's
Club, 413 North Irving Street, looking
east
NEG. NO.: 19987
PHOTO: 5 OF 16

DATE: July 2002
VIEW OF: 721-719 North Kenmore
Street, looking southeast
NEG. NO.: 19987
PHOTO: 6 OF 16

DATE: July 2002
VIEW OF: 521-517 North Kenmore
Street, looking southeast
NEG. NO.: 19987
PHOTO: 7 OF 16

DATE: July 2002
VIEW OF: 425-419 North Jackson
Street, looking southeast
NEG. NO.: 19986
PHOTO: 8 OF 16

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

ASHTON HEIGHTS HISTORIC DISTRICT, ARLINGTON, VIRGINIA (000-7819)

Section number Photographs **Page** 191

DATE: July 2002
VIEW OF: 133-125 North Oakland
Street, looking southeast
NEG. NO.: 19986
PHOTO: 9 OF 16

DATE: July 2002
VIEW OF: 3714-3718 7th Street
North, looking south
NEG. NO.: 19986
PHOTO: 14 OF 16

DATE: July 2002
VIEW OF: Columbia Gardens
Cemetery, looking northwest
NEG. NO.: 19986
PHOTO: 10 OF 16

DATE: July 2002
VIEW OF: 700-710 North Oakland
Street, looking north
NEG. NO.: 19986
PHOTO: 15 OF 16


DATE: July 2002
VIEW OF: Arlington Church of
Christ, 20 North Irving Street, looking
southwest
NEG. NO.: 19986
PHOTO: 11 OF 16

DATE: July 2002
VIEW OF: 3611 4th Street North &
407-411 North Nelson Street, looking
northeast
NEG. NO.: 19986
PHOTO: 16 OF 16

DATE: July 2002
VIEW OF: 210-214 North Irving
Street, looking northwest
NEG. NO.: 19986
PHOTO: 12 OF 16

DATE: July 2002
VIEW OF: 638-624 North Nelson
Street, looking southwest
NEG. NO.: 19986
PHOTO: 13 OF 16


ASHTON HEIGHTS HISTORIC DISTRICT (000-7819)
ARLINGTON COUNTY, VIRGINIA




UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

77°07'30" 16"E 1 280 000 FEET (MD) '18 '18 5' 20 21
38°52'30"

ASHTON HEIGHTS
HISTORIC DISTRICT
ARLINGTON
CCC-7819
18/318264/
4304782
18/317227/
1304357



000-7819
 ASHTON HEIGHTS
 HISTORIC DISTRICT
 ARLINGTON (VA.)
 118/318094/
 4305744
 118/317297
 4305068
 118/317333/
 4305329
 118/317424/
 4305325
 118/317431/
 4305431




380 000 FEET (MD.)
 38°52'30" 77°07'30" 16 HENRY B. SHIRLEY MEM. HY. 2.7 MI. 1770 000 FEET (MD.) SEVEN CORNERS 4.1 MI. FAIRFAX 14 MI. 5' (ALEXANDRIA) 5561 1 SE ALEXANDRIA (PO) 1.5 MI. MOUNT VERNON 14 MI. 2'30" ALEXANDRIA, VA. 3 MI. FREDERICKSBURG, VA. 53 MI. 2 420 000 FEET (VA.) INTERIOR: DOUG.

WANNAMAUER 5001 15W


Mapped, edited, and published by the Geological Survey and the National Ocean Service
 Control by USGS, NOS/NOAA, NCPS, and WSSC
 Compiled by photogrammetric methods from aerial photographs taken 1955. Field checked 1956. Revised 1965
 Bathymetry compiled by the National Ocean Service from tide-coordinated hydrographic surveys. This information is not intended for navigational purposes
 Mean low water (dotted) line and mean high water (heavy solid) line compiled by NOS from tide-coordinated aerial photographs. Apparent shoreline (outer edge of vegetation) shown by light solid line
 Polyconic projection. 10,000-foot grid ticks based on Maryland coordinate system, and Virginia coordinate system, north zone
 1000-meter Universal Transverse Mercator grid, zone 18
 1927 North American Datum
 To place on the predicted North American Datum 1983 move the projection lines 8 meters south and 26 meters west as shown by dashed corner ticks
 Red tint indicates areas in which only landmark buildings are shown
 There may be private inholdings within the boundaries of the National or State reservations shown on this map
 Revisions shown in purple and woodland compiled in cooperation with Commonwealth of Virginia agencies from aerial photographs taken 1981 and other sources. This information not field checked
 Map edited 1983
 Purple tint indicates extension of urban areas

NATIONAL OCEAN SERVICE
 HYDROGRAPHIC SURVEY INDEX




HYDROGRAPHIC SURVEY
 INFORMATION

Survey Number	Survey Date	Survey Scale	Survey Line spacing (Naut. Miles)
H-9478	1977	1:5,000	01-08
H-9488	1976	1:5,000	01-05



SCALE 1:24 000
 CONTOUR INTERVAL 10 FEET
 NATIONAL GEODETIC VERTICAL DATUM OF 1929
 BATHYMETRIC CONTOUR INTERVAL 1 METER WITH SUPPLEMENTARY 0.5 METER CONTOURS—DATUM IS MEAN LOW WATER
 THE RELATIONSHIP BETWEEN THE TWO DATUMS IS VARIABLE
 THE MEAN RANGE OF TIDE IS APPROXIMATELY 0.4 METER



BASE MAP COMPLIES WITH NATIONAL MAP ACCURACY STANDARDS
 BATHYMETRIC SURVEY DATA COMPLIES WITH INTERNATIONAL HYDROGRAPHIC ORGANIZATION (IHO) SPECIAL PUBLICATION 44 ACCURACY STANDARDS AND/OR STANDARDS USED AT THE DATE OF THE SURVEY
 FOR SALE BY U.S. GEOLOGICAL SURVEY
 DENVER, COLORADO 80225, OR RESTON, VIRGINIA 22092
 NATIONAL OCEAN SERVICE, ROCKVILLE, MARYLAND 20852
 AND VIRGINIA DIVISION OF MINERAL RESOURCES, CHARLOTTESVILLE, VIRGINIA 22903
 A FOLDER DESCRIBING TOPOGRAPHIC MAPS AND SYMBOLS IS AVAILABLE ON REQUEST

UTM GRID AND 1983 MAGNETIC NORTH DECLINATION AT CENTER OF SHEET

Heavy-duty.
 Medium-duty.
 Interstat
 WASHINC