

VLR-7/15/86 NRHP-9/26/86

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

See instructions in *How to Complete National Register Forms*  
Type all entries—complete applicable sections

1. Name

historic N/A

(DHL File No. 130-6)

and/or common South Boston Historic District

2. Location

street & number Industrial area along Railroad Avenue, Ferry and Factory streets; Commercial area along Main Street and Wilborn Avenue; Residential N/A not for publication

city, town South Boston area mainly along North Main Street, Washington Avenue, Peach Avenue, and Jeffress Street N/A vicinity of

state Virginia

code 51

county (city)

code 780

3. Classification

Category	Ownership	Status	Present Use
<input checked="" type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture
<input type="checkbox"/> building(s)	<input type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input checked="" type="checkbox"/> commercial
<input type="checkbox"/> structure	<input checked="" type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational
<input type="checkbox"/> site	<b>Public Acquisition</b>	<b>Accessible</b>	<input type="checkbox"/> entertainment
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input checked="" type="checkbox"/> government
	<input type="checkbox"/> being considered	<input checked="" type="checkbox"/> yes: unrestricted	<input checked="" type="checkbox"/> industrial
	N/A	<input type="checkbox"/> no	<input checked="" type="checkbox"/> transportation
			<input type="checkbox"/> other:

4. Owner of Property

name Multiple Owners

street & number N/A

city, town South Boston

N/A vicinity of

state Virginia

5. Location of Legal Description

courthouse, registry of deeds, etc. South Boston Municipal Building

street & number South Main and Ferry streets

city, town South Boston

state Virginia

6. Representation in Existing Surveys

Division of Historic Landmarks

title Survey (File No. 130-6)

has this property been determined eligible?  yes  no

date July 1985

federal  state  county  local

depository for survey records Division of Historic Landmarks, 221 Governor Street

town Richmond

state Virginia 23219





**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #2 Item number 7

Page 2

7. DESCRIPTION -- Architectural Analysis (continued)

South Boston's commercial district is characterized by compact, mostly two-story brick buildings usually possessing modernized storefronts but preserved upper-story facades highlighted with corbeled brick cornices, round-arched windows, and other decorative features. Most of the commercial buildings on South Main Street date from the 1880s and 1890s. Among the most prominent buildings of this period, and probably the oldest surviving example, is the E.L. Evans Building at 225-227 South Main Street. Built in 1888, as its central front plaque proudly declares, it is basically a Victorian Italianate brick structure defined by highly articulated brick parapets, panels, corbeled cornices, and heavy semi-circular Romanesque-like window heads. Fortunately, the original first-story storefront has been retained.

The Planters and Merchants Bank at 209 South Main Street is the most impressive late 19th-century commercial building in South Boston. It consists of a recessed, two-story central block flanked by one-story wings with semi-hexagonal facades. The central block is highlighted by a cast-iron false front featuring decorative panels, molded cornices, and a central pediment inscribed with the name of the building (P.&M. Bank) and its date of construction (1891). The first and second floors have large windows with brick arches and contrasting stone keystones and imposts, while the entire facade is enlivened with decorative brick, cast iron, and carved stone details.

Other Victorian Italianate commercial buildings include the Parkinson Block at 231 South Main Street, built in 1899 and sporting a bracketed cast-iron cornice and heavy window lintels; 235 South Main Street with its ornate brick facade; 213 South Main Street with its heavy cast-iron arched window hoods; and 425-427 South Main Street, a block of two stores, one with its original storefront, containing large upper-story fenestration with heavy lintels and an elaborate bracketed cast-iron cornice extending across the top of the building. A cast-iron segmental pediment with consoles is centrally positioned about the cornice of this building.

The entire west side of the 200 block of South Main Street consists of nine brick commercial structures with similar characteristics. Probably built in the late 1890s by the same unknown builder, the storefronts are divided by contrasting stone and brick pilasters and the buildings contain segmental-arched upper-story windows and corbeled brick cornices and parapets. A similar block of buildings is also seen in the 1000 block of Arch Street and at 519 and 521 North Main Street.

Neoclassical and Colonial Revival commercial buildings are also noted in the downtown area. Frequent fires and demolition of outdated structures allowed for the construction of some stylish early 20th-century buildings in South Boston including the brick buildings situated at three of the four corners of the intersection of North and South Main streets, Ferry Street, and Wilborn Avenue: The Municipal Building on the southwest corner of this principal intersection is a dignified two-story brick building with a rounded corner entrance framed by engaged Doric columns and surmounted by a full pediment. Several bays flanking the classical entrance are divided by Doric pilasters and feature windows with semi-circular transoms above. The second story is defined by fifteen-over-one double-sash windows with jack arches and keystones and a heavy modillion cornice. Built ca. 1910, the

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

<b>For NPS use only</b>
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #3 Item number 7

Page 3

7. DESCRIPTION -- Architectural Analysis (continued)

most unusual feature of the building is a tall circular arcaded brick belfry situated atop the building corner; the Colonial Revival three-story brick building on the southeast corner also features classical elements such as Doric pilasters, round-arched windows, and heavy modillion cornices; unfortunately, the building has recently undergone unsympathetic alterations. The finest example of Neoclassical commercial architecture in South Boston is the former United Virginia Bank at the northwest corner of Ferry Street and Wilborn Avenue. Built in 1918, it is an impressive temple-form stone building with engaged fluted Ionic columns flanking an entrance enriched by a classical frontispiece. Ionic pilasters divide the south side elevation into bays that originally contained large windows but which are now blocked. A stone water table, full entablature with a heavy modillion and dentil cornice, and a full triangular pediment with parapet above further identifies the Neoclassical spirit of this edifice.

Other Neoclassical or Colonial Revival buildings on South Main Street are the John Randolph Hotel, a four-story brick building built in 1928, and the Raylass Building at 310 South Main Street which is distinguished by a classically inspired cast-iron front.

A late 19th- and early 20th-century residential neighborhood lies immediately to the north and east of the downtown commercial area. North Main Street above Broad Street serves as a major spine from which minor perpendicular streets extend east and west. Few residences survive from the town's earliest beginnings in the mid-19th century; however, the small one-story brick dwelling located at 1319 Hodges Street is a simple vernacular structure that was probably built ca. 1840-1850. Traditionally believed to be the oldest house in the district, the building has Greek Revival details, but an unusual shotgun-type plan.

According to an 1884 map of South Boston, by that date several dwellings stood on North Main Street as far north as Fourth Street and several existed on Broad, Ferry, Jeffress, Third, and Washington streets as well. While an impressive group of late 19th- and early 20th-century residences is found in the 1000-12000 blocks of Washington Street, the three oldest houses on the street are the most outstanding. They are the Edgar H. Vaughan House, the E.L. Evans House, and the Noblin House located at 1014, 1204, and 1002 Washington Avenue, respectively. The Vaughan House is a fine example of a Victorian Italianate residence. Built in 1888, it is a frame structure exhibiting a bracketed cornice with fanciful sawnwork, arched window moldings and hoods, and a shallow hipped roof. Further down the street is the E.L. Evans House, a late 1880s Queen Anne-style house that is unusual for its elaborately detailed porches, wide central passage plan, and combination of different building materials including weatherboards, wood shingles, and pressed brick. One of the most flamboyant Queen Anne-style houses in South Boston is the Noblin House erected in 1895 by local builder/carpenter, Jerry Walker. The well-preserved frame dwelling features a round corner tower topped by a bellcast roof, a wraparound porch with decorative sawnwork, a bracketed cornice, and wooden shingles of various shapes and patterns. A central front gable is curiously decorated with a series of wooden bull's-eye blocks.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #4

Item number 7

Page 4

7. DESCRIPTION -- Architectural Analysis (continued)

North Main Street has always been a fashionable residential street in South Boston. Many of the town's most prominent citizens built their homes on this street beginning in the 1880s. The earliest houses tend to be Italianate or Gothic-influenced frame or brick two-story structures showing central front gables decorated with sawnwork, bracketed cornices, and long porches with turned posts and brackets. Three of the district's best examples of this type are noted at 616, 905, and 909 North Main Street and at 1330 Jeffress Street. By the late 1890s, large Queen Anne-style residences were being built along North Main especially in the 1300-1500 blocks. The R.W. Lawson House at 818, the R.S. Barbour House at 1304, the Robert H. Edmondson House at 1319, the Samuel F. Gilliland House at 1413, and the J.W. Elliott House at 1508 all share common characteristics of the style such as irregular building masses, multiple gables, corner turrets, bay windows, and wraparound porches. Some also show a Colonial Revival influence in such details as cornices, fenestration, and porch columns.

Besides its impressive array of houses representing fashionable styles of the period, the South Boston Historic District also contains vernacular houses of various types and patterns indigenous to the Southside Piedmont. The most common vernacular house type in the district is a single-story brick, or more likely, frame and weatherboarded structure invariably possessing a central front gable of varying proportions and a three-bay facade with corresponding porch extending across the front. Houses of this type are most numerous on Fenton, Second, Shepherd, and Traver streets and were built from the late 19th century into the early 1900s. Some feature decorative sawnwork in gables and on porches, but others are extremely simple with no decorative elements. The best examples include those houses at 1303, and 1400 Fenton Street, 1401 Hodges Street, 1315 Irish Street, 1318 and 1320 Shepherd Street, 1313 Wilkerson Street, 1224 Peach Avenue, 905 Traver Avenue, 820 Grove Avenue, 1119 Third Street, and 1102, 1104, and 1114 Second Street.

Variations on this house type are the one-story structures with paired symmetrically positioned front gables located at 1336 Shepherd and 1206 Sixth streets and the triple front gabled house, complete with elaborate bracketed cornices and decorative woodwork adorning bay windows, at 1223 Fenton Street. Two-story houses with central front gables are well represented in the district.

A curious vernacular house type consisting of a 1½-story frame section with an adjoining one-story wing and centrally positioned front gable is seen at 1336 Fenton Street and at 817 and 835 Traver Avenue.

Surprisingly, there are few Colonial Revival-style houses in the district, although several early 20th-century vernacular dwellings have classically inspired elements. The earliest Colonial Revival-style houses date from the 1910s and tend to be gable-or gambrel-roofed structures with columned porches, dormers, and entrances with transoms and sidelights such as are seen at 1228 Fenton Street, 900 Grove Avenue, 1010 Logan Avenue, and 1328 Shepherd Street. The more sophisticated Colonial Revival houses date from the 1920s and are two-story rectangular brick structures with symmetrically balanced facades, small porticos, a row of gabled dormers across the front, and fenestration topped by jack

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #5 Item number 7

Page 5

7. DESCRIPTION -- Architectural Analysis (continued)

arches or fanlights. The houses at 1002, 1100, and 1112 North Main Street and 1115 Washington Avenue fit this description.

Examples of the Bungalow, American Foursquare, Tudor Revival, and Spanish Colonial Revival styles are not well represented in the district; however, excellent examples of each style do exist. The houses at 1316 Hodges Street, 540 Logan Street, 903 Grove Avenue, 1612 North Main Street, 912 Randolph Avenue, 1219 and 1312 Peach Avenue and 1118 Second Street are all representative examples of the Bungalow style with their sweeping gable roofs, shed or gabled dormers, and wide porches supported by tapered square columns on brick piers. There are few American Foursquare houses in the district - 1302 and 1323 Peach Avenue, 1326 Barbours Street, and 529 Logan Street are the only true examples of the style - and only a small number of Tudor Revival or English Cottage-style houses, located at 1405 N. Main Street and 1100, 1103, 1105, 1109, and 1121 Washington Avenue. In addition, one example of the Spanish Colonial Revival style is the Tucker C. Watkins House at 1146 N. Main Street.

Institutional structures within the district include three historic churches and an early 20th-century hospital. First Presbyterian Church on North Main Street is a Gothic Revival-style brick structure with a steep cross gable slate roof, corner square bell tower, and pointed-arched stained-glass windows. The oldest church building surviving in South Boston today, it was built in 1887 and remains the most distinguished historical church in the city. Two black churches in the district are First Baptist Church on Ferry Street and Mt. Olive Baptist Church on North Main Street. Both churches were originally frame structures built ca. 1900 but were brick veneered in the 1960s. Each has square pyramidal-roofed bell towers and stained-glass windows. The Halcyon Hospital on Jeffress Street is a two-story frame building featuring a two-story front porch with an enclosed second level serving as a sleeping porch or solarium. A wide front gable decorated with sawnwork and turned posts adds charm to this 1909 building which served as a hospital until 1943.

Despite its large area and the diversity of its building types, the South Boston Historic District contains a remarkably cohesive and architecturally significant collection of industrial, commercial, and residential structures dating from the mid-19th century to the present. Few modern intrusions mar the architectural and historical integrity of the district.

DAE

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #6

Item number 7

Page 6

7. DESCRIPTION -- Inventory

ARCH STREET

900 BLOCK

- NA  
-435 #910: Service Cabs. Commercial. Modern. ca. 1940s. Concrete block; 1 story; 2 front bays; flat roof (not visible). Noncontributing.
- 130-6-1 915: Piedmont Barber Shop. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 1 story; 2 front asymmetrical bays; flat roof (parapet); decorative brickwork.

1000 BLOCK

- 2 1015: Barbara's Tax Service. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 1 story; 3 symmetrical bays; flat parapet roof (not visible); decorative brickwork, altered storefront.
- 3 1021: Newbill's Body Shop. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 1 story; 5 front asymmetrical bays; flat parapet roof (not visible); decorative brickwork, altered storefront.
- 4 1023: Jan's Hair Styling. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 1 story; 3 front symmetrical bays; flat parapet roof (not visible); decorative brickwork, altered storefront.
- 5 1025: Eddie's Shoe Shop. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 1 story; 2 front asymmetrical bays; flat parapet roof (not visible); decorative brickwork, original storefront retained.

BANCROFT STREET

100 BLOCK

- 6 105: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.
- 7 106: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #7 Item number 7

Page 7

7. DESCRIPTION -- Inventory

BANCROFT STREET

100 BLOCK (continued)

130-6-8

110: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, added balustrade.

-9 116: Detached house. Vernacular. ca. 1900. Wood frame (aluminum or vinyl siding); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with wrought-iron supports.

200 BLOCK

-10 202: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-11 204: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-12 205: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-13 208: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

BARBOUR STREET

1300 BLOCK

-14 1308: Detached house. Vernacular. ca. 1930s. Wood frame (aluminum siding); 1 story; 3 front asymmetrical bays; hipped roof (composition shingle); 1-story, 1-level, 1-bay side porch with square column clad in aluminum siding, simple balustrade.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #8

Item number 7

Page 8

7. DESCRIPTION -- Inventory

BARBOUR STREET

1300 BLOCK (continued)

130-6-15

1314: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay wraparound porch with Tuscan columns, simple balustrade; entrance with elliptical fanlight and sidelights.

-16

1315: Detached house. Vernacular. ca. 1930s. Wood frame (aluminum siding); 1 story; 5 front asymmetrical bays; gable roof (standing seam metal).

MC  
-436

\*1321: Detached house. Vernacular. ca. 1940s. Wood frame (weatherboard); 1½ stories; 3 front asymmetrical bays; gable roof (composition shingle); 1 front gable dormer; 1-story, 1-level, 3-bay porch with square wood columns, board balustrade. Noncontributing.

-17

1323: Detached house. Vernacular. ca. 1910s. Wood frame (weatherboard); 1½ stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1 front hipped dormer; 1-story, 1-level, 2-bay porch with tapered square wood columns, wide frieze.

-18

1326: Detached house. American Foursquare. ca. 1920. Wood frame (weatherboard); 2½ stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1 front hipped dormer; 1-story, 1-level, 2-bay porch with tapered square wood columns on brick piers.

-19

1327: Detached house. Vernacular. ca. 1910s. Wood frame (weatherboard); 1½ stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1 front hipped dormer; 1-story, 1-level, 2-bay porch with tapered square wood columns.

-20

1328: Detached house. Vernacular. ca. 1940s. Wood frame (weatherboard); 1 story; 4 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with slender wood posts, steeply pitched gable.

MC  
-437

\*1331: Detached house. Vernacular. ca. 1950s. Brick (stretcher bond); 1½ stories; 4 front asymmetrical bays; gable roof (composition shingle). Noncontributing.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #9

Item number 7

Page 9

7. DESCRIPTION — Inventory

BERMANN STREET

200 BLOCK

*-498 MC* \*204: Detached house. Modern. 1970s. Wood frame (weatherboard); 1 story; 4 asymmetrical bays; gable roof (shingle and composition). Noncontributing.

*130-6-21* 206: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, added balustrade.

*-22* 210: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, simple balustrade.

*-23* 214: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, simple balustrade.

*-24* 218: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, added balustrade.

CHARLES STREET

1100 BLOCK

*-25* 1104: Opthamology Associates. Commercial. Art Deco. 1930s. Brick (stretcher bond); 1 story; 5 symmetrical bays; flat/parapet roof (not visible); brick pilasters with stepped projections.

ELLYSON STREET

300 BLOCK

*-26* 300: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 asymmetrical bays; gable roof (shingle composition); 1-story, 1-level, 3-bay porch with turned posts; front ell with bay window, gable with decorative sawnwork.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

For NPS use only
received
date entered

Continuation sheet #10

Item number 7

Page 10

7. DESCRIPTION--Inventory

ELLYSON AVENUE

300 BLOCK (continued)

130-6-27

301: Detached house. Vernacular. 1890s. Wood frame (bricktex); 2 stories; 3 asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns, spindle frieze, bracketed cornice; central front gable with decorative sawnwork.

-28

305: Detached house. Vernacular. 1890s. Wood frame (aluminum siding); 2 stories; 3 asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered slender wood columns; bracketed cornice.

-29

306: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1½ stories; 3 symmetrical bays; gambrel roof (standing seam metal); 1 shed dormer; 1-story, 1-level, 3-bay porch with Tuscan columns.

400 BLOCK

-30

400: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1 story; 3 asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with wrought-iron supports on brick piers; central front hip-roof attic vent.

-31

403: Detached house. Modified Queen Anne. 1890s. Wood frame (aluminum siding); 2 stories; 3 asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 4-bay porch with wrought-iron supports; 2-story front ell with bay windows surmounted by gable with decorative sawnwork.

-32

406: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 2 asymmetrical bays; gable roof (shingle composition); 1-story, 1-level, 7-bay wraparound porch with turned posts, scroll brackets; decorative bargeboard, front gable clad in diagonal pattern wood strips.

-33

409: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 1 story; 4 asymmetrical bays; (standing seam metal); 1-story, 1-level, 4-bay porch with turned posts, turned balustrade.

-34

410: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 asymmetrical bays; gable roof (shingle composition); 1-story, 1-level, 4-bay wraparound porch with chamfered square columns; decorative bargeboard.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #11

Item number 7

Page 11

7. DESCRIPTION -- Inventory

ELLYSON AVENUE

400 BLOCK (continued)

130-6-35

412: Detached house. Vernacular. ca. 1910. Wood frame (aluminum siding); 1 story; 3 symmetrical bays; (standing seam metal); 1-story, 1-level, 3-bay porch with tapered wood columns on brick piers; central front hip-roofed attic vent.

-439  
NCS

\*417: Detached house. Vernacular. 1940s. Wood frame (weatherboard) 1½ stories; 4 asymmetrical bays; gable roof (shingle composition); 3 gable dormers with dentil cornice; paired square columns. Noncontributing.

FACTORY STREET

300 BLOCK

-36

322: Detached house. Vernacular. Late 19th century. Wood frame (weatherboard); 1½ stories; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, weatherboard railing.

-440  
NCS

\*324: Halifax County Farmers. Commercial. Vernacular. 1940s. Brick (6-course American bond); 1 story; 3 asymmetrical bays; flat parapet roof (not visible). Noncontributing.

-37

Warehouse. Commercial. Vernacular. 1890s. Brick (5-course American bond); 2 stories; 3 asymmetrical bays; flat parapet roof (not visible); stepped parapet.

-38

Hotpoint Warehouse. Warehouse. Vernacular. ca. 1920. Brick (stretcher bond); 1 story; 3 asymmetrical bays; gable parapet roof (not visible); decorative brick elements.

-39

So Bo Venture Center. Liggett-Meyer Tobacco Prizery. Warehouse. Vernacular. ca. 1920. Brick (5-course American bond); 1 story; 7 asymmetrical bays; flat parapet roof (not visible).

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

For NPS use only
received
date entered

Continuation sheet #12

Item number 7

Page 12

7. DESCRIPTION -- Inventory

FENTON STREET

1200 BLOCK

130-6-40

1216: Detached house. Vernacular. 1920s. Brick (stretcher bond); 2 stories; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 7-bay porch with tapered square wood columns on brick piers, simple balustrade.

-41

1218: Detached house. Vernacular. ca. 1920. Wood frame (weatherboard); 2 stories; 2 asymmetrical bays; gable roof (standing seam metal); 2-story, 2-level, 2-bay porch with square wood columns on brick piers, simple balustrade, central 2nd-story, single-bay porch.

-42

1219: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers.

-43

1223: Detached house. Carpenter Gothic. 1890s. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with extended porch with square wood columns on brick piers, original porch with turned posts, spindle frieze, decorative sawwork is behind extension; heavy bracketed cornice with dentils, triple gables in front, bay windows with bracketed cornices, decorative window cornices.

-44

1225: Detached house. Vernacular. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with wrought-iron supports; central front gable.

-45

1228: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1½ stories; 3 symmetrical bays; gambrel roof (standing seam metal); 1 shed dormer; 1-story, 1-level, 3-bay porch with Doric columns, wrought-iron balustrade.

-46

1229: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns; central front gable.

-47

1230: Vacant lot.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #13 Item number 7

7. DESCRIPTION -- Inventory

FENTON STREET

1300 BLOCK

*WBE*  
*441* \*Faulkner Memorial Masonic Hall. Masonic lodge. Modern. 1955. Brick (stretcher bond); 1 story; 2 asymmetrical bays; flat roof (not visible); 1-story, 1-level, 1-bay porch with square brick columns, brick railing. Noncontributing.

*130-6-48* 1303: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); no porch.

*409* 1333: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 5 asymmetrical bays; gable roof (standing seam metal) with porch removed; 2-story bay window surmounted by gable with brackets and decorative woodwork.

*50* 1336: Detached house. Vernacular. 1900. Wood frame (weatherboard); 1½ stories; 3 asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with slender wood columns.

1400 BLOCK

*51* 1400: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts.

*52* 1404: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal) with porch removed.

*53* 1408: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with slender wood columns, metal awning; central front gable.

FERRY STREET

200 BLOCK

*54* 209: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 4 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 6-bay wraparound porch with square wood columns, simple balustrade.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #14 Item number 7

Page 14

7. DESCRIPTION -- Inventory

FERRY STREET

200 BLOCK (continued)

130-6-55 227: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story with raised basement; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, screened; house situated on 2-bay garage below.

-56 First Baptist Church. Vernacular. ca. 1900. Brick (stretcher bond); 1 story with raised basement; 3 front asymmetrical bays; gable roof (pressed tin); probably originally a frame building--brick veneer added later.

300 BLOCK

-57 308: Kent's Funeral Home. Detached house (originally). Vernacular. ca. 1900. Wood frame (weatherboard and vertical siding); 2 stories; 2 front asymmetrical bays; gable roof (standing seam metal); porch removed and frame extension added.

NA 442 \*310: Christ Temple Church. Fraternal meeting hall (originally). Modern. ca. 1950s. Brick (stretcher bond) with concrete block; 1 story; 3 front symmetrical bays; flat roof (not visible). Noncontributing.

-58 311: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns, decorative brackets and cornice.

-59 315: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 1 front symmetrical bay; gable roof (composition shingle); enclosed porch.

-60 317: Detached house. Vernacular. late 19th c. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts on piers.

-61 329: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 2 stories; 2 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 2-bay porch with turned posts.

-62 340: J. P. Taylor Tobacco Prizery. Tobacco factory. Vernacular. ca. 1920s. Brick (stucco); 3 stories; multiple asymmetrical bays; flat parapet roof (not visible); brick and stucco bay differentiations, large casement windows.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #15

Item number 7

Page 15

130-6-63

343: Bouldin Beauty Shop. Commercial. Vernacular. ca. 1920s. Brick (stretcher bond); 1 story; 7 front asymmetrical bays; flat parapet roof (not visible); brick pilasters divide facade.

-64

345 - 349: Bell's Beauty Shop/Norman Williams, Dentist. Commercial. Vernacular. ca. 1920. Brick (5-course American bond); 2 stories; 5 front asymmetrical bays; flat parapet roof (not visible); original storefront retained, decorative tiles in brick.

106  
443

\*353 - 355: Edmondson Cleaners/Elite Barber Shop. Commercial. Vernacular. ca. 1940s. Brick (stretcher bond); 1 story; 4 front symmetrical bays; flat parapet roof (not visible). Noncontributing.

GROVE AVENUE

800 BLOCK

~~130-6-64~~  
130-6-430

804: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; hipped roof (pressed tin); 1-story, 1-level, 3-bay porch with paired Ionic columns, dentil cornice; central front gable.

130-6-65

809: Detached house. Colonial Revival. ca. 1920. Wood frame (stucco); 2½ stories; 3 front symmetrical bays; gable roof (pressed tin); 2 front gable dormers; 1-story, 1-level, 3-bay porch with stuccoed square columns, arched bays, dentil cornice, broken pediment over entrance bay.

-66

812: Detached house. Vernacular. ca. 1930s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (composition shingle); 1 front gable dormer; 1-story, 1-level, 2-bay porch with paired square wood columns, simple balustrade.

-67

815: Detached house. Bungalow. ca. 1920. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (standing seam metal); 1 front shed dormer; 1-story, 1-level, 3-bay porch with square wood columns, porte cochere.

-68

817: Detached house. Vernacular. ca. 1890s. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 13-bay wraparound porch with turned posts, simple balustrade, front entrance gable with decorative sawnwork; bracketed cornice.

-69

819: Detached house. Bungalow. ca. 1920s. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 4-bay wraparound porch with tapered square wood columns on brick piers.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #16

Item number 7

Page 16

7. DESCRIPTION -- Inventory

GROVE AVENUE

800 BLOCK (continued)

130-6-70 820: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with Tuscan columns; entrance with transom and sidelights, central front gable.

-71 827: Detached house. Vernacular. ca. 1920. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable (standing seam metal); 1-story, 1-level, 6-bay wraparound porch with tapered wood columns on brick piers.

900 BLOCK

-72 900: Detached house. Colonial Revival. ca. 1910s. Wood frame (weatherboard wood shingle); 1½ stories; 3 front symmetrical bays; gambrel roof (pressed tin); 2 front gambrel dormers; 1-story; 1-level, 3-bay porch with tapered square paneled columns, simple balustrade; several patterns of wood shingles on gables and dormers.

-73 903: Detached house. Bungalow. ca. 1920s. Wood frame (weatherboard); 1½ stories; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 5-bay wraparound porch with square brick columns supporting heavy wood braces, exposed rafter ends.

-74 910: Detached house. Vernacular. ca. 1910s. Wood frame (weatherboard and stucco); 2½ stories; 3 front asymmetrical bays; hipped roof (composition shingle); 1-story, 1-level, 7-bay wraparound porch with paired square columns on stuccoed piers, simple balustrade, porte cochere attached.

-75 913: Detached house. Vernacular. ca. 1910s. Wood frame (weatherboard); 2½ stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1 front gable dormer; 1-story, 1-level, 3-bay porch with square wood columns on brick piers.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #17

Item number 7

Page 17

7. DESCRIPTION -- Inventory

HODGES STREET

1300 BLOCK

130-6-76 1312: Detached house. Vernacular. 1890s. Wood frame (weatherboard/wood shingle); 1 story; 2 asymmetrical bays; gable/clipped end roof (standing seam metal); 1-story, 1-level, 2-bay porch with turned posts, scroll brackets; front ell with bay window surmounted by shingled gable with brackets.

NA 444 \*1313: Detached house. Vernacular. 1940s. Wood frame (weatherboard); 1½ stories; 4 asymmetrical bays; gable roof (shingle composition); 1-story, 1-level, 1-bay porch with slender wood column, screened porch to side. Noncontributing.

-77 1316: Detached house. Bungalow. 1920s. Brick (stretcher bond); 1½ stories; gable/clipped end roof (shingle composition); 1 shed dormer; 1-story, 1-level, 1-bay porch with tapered square brick columns on brick piers, brick railing.

-78 1319: Detached house. Vernacular/Greek Revival. 1840-1850. Brick (5-course American bond); 1 story; 2 asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with square wood columns; unusual plan, central brick chimney, 6/6 double sash windows with lintels.

-79 1322: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 1-bay porch with paired slender wood posts, gable roof; central front gable.

-80 1324: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 1 story; 3 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers, original porch removed; small central front gable.

445 NA \*1328: Detached house. Vernacular. 1940s. Wood frame (stucco); 1 story; 5 asymmetrical bays; gable roof (shingle composition). Noncontributing.

-81 1329: Detached house. Vernacular. 1930s. Brick (Flemish bond); 1 story; 3 asymmetrical bays; gable roof (shingle composition); 1 story, 1-level, 2-bay porch with tapered wood columns on brick piers.

446 NA \*1331: Detached house. Modern. 1960s. Brick (stretcher bond); 1 story; 4 asymmetrical bays; gable roof (shingle composition). Noncontributing.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #18

Item number 7

Page 18

7. DESCRIPTION -- Inventory

HODGES STREET

1400 BLOCK

130-6-82

1401: Detached house. Vernacular. 1880s. Brick (5-course American bond); 1 story; 3 symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 1-bay porch with square wood columns, bracketed cornice; bracketed cornice, central front gable.

-83

1403: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1 story; 3 symmetrical bays; hipped roof (shingle composition); 1-story, 1-level, 3-bay porch with square brick end columns, square wood columns on brick piers; central front hip-roofed attic vent.

-84

1409: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1 story; 3 symmetrical bays; hipped roof (pressed tin); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with square wood columns on brick piers.

-85

1412: Detached house. Wood frame (aluminum siding); 2 stories; 3 symmetrical bays; hipped roof (shingle composition); 1-story, 1-level, 6-bay porch with Tuscan columns, central front gable.

-86

1413: Detached house. Bungalow. 1920s. Wood frame (weatherboard); 1½ stories; 3 symmetrical bays; gable roof (shingle composition); 1 front shed dormer; 1-story, 1-level, 3-bay porch with square wood columns; entrance with transom and sidelights.

-87

1417: Detached house. Bungalow. 1920s. Brick (stretcher bond); 1 story, 3 asymmetrical bays; gable roof (shingle composition); 1-story, 1-level, 3-bay porch with square brick columns on brick piers.

-88

1419: Detached house. Vernacular. 1920s. Wood frame (aluminum siding); 1 story; 3 symmetrical bays; gable roof (shingle composition); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers.

IRISH STREET

1300 BLOCK

-89

1311: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1 story; 4 symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers; central front gable.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #19

Item number 7

Page 19

7. DESCRIPTION -- Inventory

IRISH STREET

1300 BLOCK (continued)

*MC 447* \*1314: Detached house. Vernacular. 1950s. Brick (stretcher bond); 1 story; 4 front asymmetrical bays; gable roof (shingle composition); 1-story, 1-level, 2-bay porch with square wood columns, screened in. Noncontributing.

*130-6-90* 1315: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 7-bay wraparound porch with Tuscan columns, turned balustrade; central front gable, entrance with transom and sidelights.

*-91* 1316: Detached house. Colonial Revival. 1920s. Brick (stretcher bond); 1 1/2 stories; 3 front asymmetrical bays; gambrel roof (shingle composition); 1 front shed dormer; 1-story, 1-level, 3-bay porch with Tuscan columns, dentil cornice; semi-circular fanlights over entrance.

*-92* 1319: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 2 stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 4-bay porch with Tuscan columns; central front gable.

*-93* 1320: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (shingle composition); 1-story, 1-level, 1-bay porch with clustered Tuscan columns, dentil cornice; bracketed cornice, central front gable with decorative sawnwork.


*-94* 1323: Detached house. Modified Queen Anne. ca. 1900. Wood frame (aluminum siding); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 9-bay wraparound porch with Tuscan columns; central front gable.

*MC 448* \*1325: Detached house. Modern. 1960s. Brick (stretcher bond) and stone (ashlar/rock-faced); 1 story; 5 front asymmetrical bays; hipped roof (shingle composition). Noncontributing.

*-95* 1328: Detached house. American Foursquare. 1910s. Wood frame (weatherboard); 2 1/2 stories; 3 front asymmetrical bays; hipped roof (pressed tin); 1 front hipped dormer; 1-story, 1-level, 7-bay wraparound porch with Tuscan columns.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**



SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #20

Item number 7

Page 20

7. DESCRIPTION -- Inventory

IRISH STREET

1300 BLOCK (continued)

130-6-96

1332: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with paired square wood columns, original porch removed; bracketed cornice, central front gable.

MC  
449

\*1338: Detached house. Vernacular. 1940s. Brick (stretcher bond); 1½ stories; 4 front asymmetrical bays; gable roof (shingle composition); 1 front gable dormer; 1-story, 1-level, 1-bay porch with paired chamfered columns. Noncontributing.

-97

1339: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (shingle composition); 1-story, 1-level, 3-bay porch with paneled square columns on brick piers.

1400 BLOCK

MC  
450

\*1404: Detached house. Vernacular. 1940s. Brick (stretcher bond); 1 story; 5 front symmetrical bays; gable roof (shingle composition). Noncontributing.

MC  
451

\*1406: Detached house. Cottage. 1940s. Brick (stretcher bond); 1 story; 4 front asymmetrical bays; gable roof (shingle composition). Noncontributing.

MC  
452

\*1408: Detached house. Colonial Revival. 1950s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (shingle composition); 2 front gable dormers. Noncontributing.

1500 BLOCK

MC  
453


\*1502: Detached house. Colonial Revival. 1950s. Brick (stretcher bond); 1½ stories; 3 front symmetrical bays; gable roof (shingle composition); 2 front gable dormers. Noncontributing.

-98

1504: Detached house. Queen Anne. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 7-bay porch with turned posts, turned balustrade, sawnwork.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form



SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #21

Item number 7

Page 21

7. DESCRIPTION -- Inventory

IRISH STREET

1600 BLOCK

*NA 454* \*1610: Detached house. Colonial Revival. 1960s. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; gable roof (shingle composition). Noncontributing.

*130-6-99* 1612: Detached house (duplex). Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 6 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square columns, arched bays, balustraded deck.

*NA 455* \*1617: Detached house. Vernacular. Brick (stretcher bond); 1½ stories; 5 front symmetrical bays; hipped roof (shingle composition); 1-story, 1-level, 3-bay porch with Tuscan columns, pedimented gable. Noncontributing.

JEFFERSON STREET

800 BLOCK

*130-6-100* 812: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with turned posts, sawn brackets, simple balustrade.

JEFFRESS STREET

1300 BLOCK

*-101* 1313: Detached house. Queen Anne. ca. 1900. Wood frame (weatherboard/wood shingle); 2½ stories; 3 front asymmetrical bays; hipped roof (slate); 1-story, 1-level, 8-bay wraparound porch with Tuscan columns, 2nd-story single-bay porch with short Ionic columns and arched wood bay; large corner tower with bellcast roof and wood shingled upper levels; wrought-iron fence.

*-102* 1317: Detached house. Queen Anne. ca. 1890s. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; gable roof (shingle composition); 2-story, 1-level, 7-bay porch with turned posts, turned balustrade, brackets, spindle frieze over entrance bay; pyramidal hipped roof over building corner, 2-story bay window surmounted by gable with brackets and spindles; wrought-iron and stone fence.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #22

Item number 7

Page 22

7. DESCRIPTION -- Inventory

JEFFRESS STREET

1300 BLOCK (continued)

- 130-6-103 1319-1321: Detached house (duplex); Vernacular. 1920s. Wood frame (weatherboard); 2½ stories; 4 front symmetrical bays; hipped/pyramidal roof (shingle composition); 1 front shed dormer; 2 porches - 1-story (each), 1-level (each), 1-bay (each) porch with tapered square wood columns on brick piers, exposed joists.
- 104 1328: Detached house. Victorian Italianate. 1890s. Brick (5-course American bond); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 11-bay porch with turned posts, spindle frieze, brackets, turned balustrade; bracketed cornice, segmental-arched windows.
- 105 1334: Halcyon Hospital. Detached house (currently). Hospital (originally). Vernacular. 1909. Wood frame (weatherboard); 2½ stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 2-level, 3-bay porch with Tuscan columns on 1st floor, enclosed 2nd floor; decorative woodwork in front gable.
- 106 1338: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2½ stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns; decorative bargeboard, entrance with transom and sidelights.
- 107 1345: Detached house. Vernacular. 1920s. Wood frame (weatherboard); 1 story with lower basement; 3 front symmetrical bays; gable roof (not visible); 1-story, 1-level, 1-bay porch with fluted Tuscan columns, gable roof; brick basement, entrance with sidelights.
- 108 1346: Detached house. Vernacular. 1920s. Wood frame (aluminum siding); 2 stories; 2 front asymmetrical bays; gable roof (shingle composition); 1-story, 1-level, 3-bay porch with Tuscan columns.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #23

Item number 7

Page 23

7. DESCRIPTION -- Inventory

JEFFRESS STREET

1300 BLOCK (continued)

130-6-109 1349: Detached house. Vernacular. 1910s. Wood frame (aluminum siding); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square wood columns, simple balustrade; wide central front gable.

-110 1350: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (shingle composition); 1-story, 1-level, 1-bay porch with slender square wood posts, gable roof, original porch removed; original windows replaced, alterations.

-111 1351: Detached house. American Foursquare. 1920s. Wood frame (weatherboard); 2½ stories; 3 front asymmetrical bays; hipped roof (slate); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with square wood columns, simple balustrade.

-112 1352: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 2 stories; 2 front asymmetrical bays; gable roof (standing seam metal); porch enclosed; bracketed cornice, replaced original windows, original porch removed.

-113 1358: Detached house. Queen Anne. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 8-bay wraparound porch with slender Ionic columns.

LOGAN STREET

500 BLOCK

-114 508: Detached house. Queen Anne. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 8-bay wraparound porch with Tuscan columns, bracketed modillion cornice with dentils.

-115 509: Detached house. Vernacular. 1930s. Wood frame (weatherboard); 1 story; 3 front bays; gable roof (shingle composition).

-116 516: Detached house. Queen Anne. 1890s. Wood frame (weatherboard); 2 stories; 3 front bays; gable roof (standing seam metal); 1-story, 1-level, 7-bay porch with turned posts, spindle frieze; bay window with gable and sawnwork, bracketed eaves.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #24

Item number 7

Page 24

7. DESCRIPTION -- Inventory

LOGAN STREET

500 BLOCK (continued)

130-6-117 517: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with turned posts, turned balustrade, scroll brackets, decorative sawnwork; central front gable with sawnwork.

-118 522: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1½ stories; 5 bays; gable roof (shingle composition); 1-story, 1-level, 5-bay porch with Tuscan columns; entrance with transom and sidelights.

-119 523-525: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (shingle composition); 1 front hipped dormer; 1-story, 1-level, 2-bay porch with square brick columns on brick piers, brick balustrade; wide overhanging eaves, entrance with sidelights.

NA 470 \*538: Apartment building. Colonial Revival. 1960s. Brick (stretcher bond); 2 stories; 7 front symmetrical bays; hipped roof (shingle composition); 2-story, 2-level, 3-bay porch with square paneled columns, decorative balustrade. Noncontributing.

-120 540: Detached house. Bungalow. 1920s. Brick (stretcher bond); 1½ stories; 3 front bays; gable roof (shingle composition); 2 front gable dormers; 1-story, 1-level, 3-bay porch with square brick columns; overhanging eaves with triangular knee braces.

1000 BLOCK


-121 1010: Detached house. Queen Anne. ca. 1910. Wood frame (weatherboard); 1½ stories; 2 front asymmetrical bays; gable roof (standing seam metal); 2 pedimented gable dormers; 1-story, 1-level, 5-bay porch with Ionic columns, simple balustrade, dentil cornice; entrance with transom and sidelights.

-122 1011: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (shingle composition); 1-story, 1-level, 5-bay porch with Tuscan columns.

-123 1014: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 2 stories; 5 front symmetrical bays; hipped roof (pressed tin); 1-story, 1-level, 5-bay porch with Ionic columns, gable over entrance bay; central front gable.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form



SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #25

Item number 7

Page 25

7. DESCRIPTION -- Inventory

LOGAN STREET

1000 BLOCK (continued)

130-6-124

1018: Detached house. Vernacular. 1880s. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 2-story, 2-level, 2-bay porch with chamfered posts, scroll brackets, decorative balustrade; unusual 2-story bay window surmounted by octagonal tower with hipped roof.

S. MAIN STREET

100 BLOCK

-125

107: Village Inn. Commercial. Vernacular. ca. 1900. Brick (aluminum siding); 3 stories; 4 front asymmetrical bays; flat parapet roof (not visible); altered facade.

-126

111: Commercial (vacant). Vernacular. ca. 1920s. Brick (stretcher bond); 1 story; 4 front asymmetrical bays; flat roof (not visible); altered storefront.

-127

115: Brooks Funeral Home. Commercial. Victorian Italianate. ca. 1890s. Brick (stretcher bond); 3 stories; 4 front asymmetrical bays; flat parapet roof (not visible); decorative brick cornice and parapet, brick window heads, altered storefront; modern gable-roofed brick chapel adjoining.

200 BLOCK

-128

205: Cunningham Beauty and Barber Shop. Commercial. Vernacular. 1891. Brick (stretcher bond); 1 story; 3 front symmetrical bays; flat parapet roof (not visible); metal cornice, chamfered building corner, altered storefront, decorative brick panels.

-129

208: Downtown Friendship Mission. Commercial. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); decorative brick cornice, altered storefront.

-130

209: Planters and Merchants Bank (originally). Ed's Used Furniture (currently). Commercial. 1891. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); elaborate brickwork and metal cornice with central pediment, original storefront.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #26

Item number 7

Page 26

7. DESCRIPTION -- Inventory

S. MAIN STREET

200 BLOCK (continued)

- 130-6-131 210: Budget Furniture Co. Commercial. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); decorative brick cornice, altered storefront.
- 132 211: South Boston Post Office (originally). Ed's Used Furniture (currently). Commercial. 1891. Brick (stretcher bond); 1 story; 3 front symmetrical bays; flat parapet roof (not visible); chamfered building corner, heavy metal cornice surmounted by broken pediment with urns and consoles.
- 133 213: Puryear's Florist. Commercial. Victorian Italianate. ca. 1890s. Brick (5-course American bond); 3 stories; 3 front asymmetrical bays; flat parapet roof (not visible); decorative and corbeled brickwork, heavy decorative window heads, altered storefront.
- 134 214-216: Commercial. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 7 front asymmetrical bays; flat parapet roof (not visible); original storefronts; decorative brick cornice; brick and stone pilasters.
- 135 217: Peddler Shop. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); brick quoins, decorative brickwork, round-arched windows, original storefront.
- 136 218: Crafts N'Tiques. Commercial. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); decorative brick cornice; segmental-arched 2nd story windows; original windows.
- 137 220: Irvin D. Sugg Law Office. Commercial. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 2 front bays; flat roof (not visible); decorative brick cornice; altered storefront.
- 138 222: Peerless Barber Shop. Commercial. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 2 front asymmetrical bays; flat parapet roof (not visible); decorative brick cornice, altered storefront.
- 139 224: Commercial. Vacant. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 2 front asymmetrical bays; flat parapet roof (not visible); Decorative brick cornice and pilasters, brick-arched drive-in entrance.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #27

Item number 7

Page 27

7. DESCRIPTION -- Inventory

S. MAIN STREET

200 BLOCK (continued)

130-6-140

225-227: E. L. Evans Building. Commercial. Victorian Italianate. 1888. Brick (stretcher bond); 2 stories; 7 symmetrical bays; flat/parapet roof (not visible); decorative brickwork, pilasters, and brick window arches, original storefronts retained.

141

226: Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories, 2 front asymmetrical bays; flat parapet roof (not visible); decorative and corbeled brickwork, altered storefront.

142

228: Patterson Building. Commercial. ca. 1900. Brick (stretcher bond); 3 stories; 2 front asymmetrical bays; flat parapet roof (not visible); segmental-arched windows, decorative brickwork, original storefront.

143

231: Parkinson Block. Haley's House of Carpets. Victorian Italianate. 1899. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); decorative metal cornice, decorative metal window hoods, altered storefront.

144

235: Carroll's Sporting Goods. Commercial. Victorian Italianate. ca. 1890s. Brick (stretcher bond); 2 stories; 2 front asymmetrical bays; flat parapet roof (not visible); decorative and corbeled brickwork, altered original storefront, round-arched 2nd-story windows.

300 BLOCK

145

300: Jerry's Thrift Shop. Commercial. Vernacular. ca. 1910. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); storefront and upper-story fenestration altered.

146

303: Tomz, Inc. Commercial. Vernacular. ca. 1930s. Brick (stretcher bond); 3 stories; 3 symmetrical bays; flat parapet roof (not visible); altered storefront, corbeled brickwork.

147

306: Main Street Market. Commercial. Vernacular. ca. 1910. Brick (stretcher bond); 2 stories; 2 front bays; flat parapet roof (not visible); altered storefront.

1451

\*309: Virginia Alcoholic Beverage Control Store. Commercial. Modern. ca. 1950s. Wood frame with stone veneer; 1 story; 3 front asymmetrical bays; flat parapet roof (not visible). Noncontributing.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #28

Item number 7

Page 28

7. DESCRIPTION -- Inventory


S. MAIN STREET

300 BLOCK (continued)

- 130-6-148 310: U. S. Factory Outlets. Raylass Building. Commercial. Neoclassical. ca. 1910. Wood frame (cast-iron); 2 stories; 3 front asymmetrical bays; flat parapet roof (not visible); cast-iron facade featuring modillion cornice, parapet with urns, pilasters, etc.
- WA 458 \*313: Perkins Drugs. Commercial. Vernacular. ca. 1940s. Brick sides with vertical siding at front; 1 story; 2 front asymmetrical bays; flat parapet roof (not visible). Noncontributing.
- 449 316-318: Western Auto. Commercial. Vernacular. ca. 1910. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); altered facade and storefront.
- 150 317: Super Dollar Discount Store. Commercial. Vernacular. ca. 1910. Brick (stretcher bond); 3 stories; 3 front asymmetrical bays; flat parapet roof (not visible); altered storefront, closed in windows on upper floors, minimal decorative brickwork.
- 151 322-324: Merit Shoes/Office Shop. Commercial. Vernacular. ca. 1920. Brick (stretcher bond); 3 stories; 7 front asymmetrical bays; flat parapet roof (not visible); altered storefronts.
- WA 459 \*323: Gilliland's Ladies' Apparel. Commercial. Modern. ca. 1940s. Wood frame (enameled metal); 1 story; 4 front asymmetrical bays; flat parapet roof (not visible). Noncontributing.
- 152 325: Randolph Motor Inn. Hotel. Colonial Revival. ca. 1920s. Brick (Flemish bond); 4 stories; 7 front symmetrical bays; flat parapet roof (not visible); stone cornice and string courses, balustrade encircling building.
- 153 328: Wilborn's Hardware Co. Commercial. Vernacular. ca. 1910. Brick (stretcher bond); 3 stories; 4 front asymmetrical bays; flat parapet roof (not visible); partially altered storefront and upper story facade.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form



SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #29

Item number 7

Page 29

7. DESCRIPTION -- Inventory

S. MAIN STREET

400 BLOCK

- 130-6-154 407: Commercial. Colonial Revival. ca. 1920. Brick (stretcher bond); 2 stories; 5 front asymmetrical bays; flat parapet roof (not visible); altered storefront, brick pilasters, paired fenestration, metal modillion cornice.
- MC 400 \*410: United Virginia Bank. Commercial. Modern. ca. 1970s. Brick (stretcher bond); 1 story; 1 front asymmetrical bay; flat roof (not visible). Noncontributing.
- 155 411: McCallum Ferrell Shoes. Commercial. Vernacular. ca. 1910. Brick (stretcher bond); 2 stories; 3 front asymmetrical bays; flat parapet roof (not visible); corbeled brickwork, altered storefront.
- MC 401 \*413: Faulkner and Lawson Drug Co. Commercial. Modern. ca. 1940s. Brick; 2 stories; 3 front asymmetrical bays; flat roof (not visible). Noncontributing.
- 156 415: City Style Shop. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories; 5 front asymmetrical bays; flat parapet roof (not visible); pressed metal cornice, corbeled brickwork, altered storefront.
- 157 416: Cato's. Commercial. Vernacular. ca. 1900. Brick (Flemish bond partially clad in aluminum siding); 2 stories; 2 front asymmetrical bays; flat parapet roof (not visible); altered facade.
- 158 419: J. C. Howlett Piano Co. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories; 2 front asymmetrical bays; flat parapet roof (not visible); decorative corbeled brickwork, altered storefront.
- 159 420: J. J. Newberry Co. Commercial. Vernacular. ca. 1920s. Brick (stretcher bond); 2 stories; 5 front symmetrical bays; flat parapet roof (not visible); original storefront retained, parapet with pantiles.
- 160 425-427: Glasscock Hardware Co. Commercial. Victorian Italianate. ca. 1890s. Brick (stretcher bond); 2 stories; 7 front asymmetrical bays; flat parapet roof (not visible); decorative cast-iron cornice with segmental pediment.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #30

Item number 7

Page 30

7. DESCRIPTION -- Inventory

S. MAIN STREET

400 BLOCK (continued)

130-6-161

429-431: Dr. William D. Owen, Jr./Joyce Apparel. Commercial and office. Vernacular. ca. 1910. Brick (stretcher bond); 2 stories; 5 front asymmetrical bays; flat roof (not visible); decorative corbeled brickwork, altered storefront.

-162

430: Municipal Building. Local government agencies. Neoclassical. ca. 1910s. Brick (5-course American bond with Flemish variant); 2 stories; 9 front asymmetrical bays; flat parapet roof (not visible); Neoclassical entrance and fenestration treatment, modillion cornice, 15/1 double sash 2nd-story windows, unusual open circular corner tower.

we  
-462

\*435: Scottie Discount Store. Commercial. Modern. ca. 1960s. Wood frame (aluminum siding); 1 story; 2 front asymmetrical bays; flat roof (not visible). Noncontributing.

-163

437: Lantor's. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories; 3 front asymmetrical bays; flat roof (not visible); decorative corbeled brickwork.

-164

441: A. R. Via Jewelers. Commercial. Colonial Revival. ca. 1910. Brick (stretcher bond); 3 stories; 3 front symmetrical bays; flat parapet roof (not visible); altered storefront and fenestration, modillion and dentil cornices.

N. MAIN STREET

500 BLOCK

-165


500: The Book Case. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories; 3 front asymmetrical bays; flat parapet roof (not visible); entire facade added to original ca. 1900 brick building.

-166

504: Home Appliance Co. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories; 3 front asymmetrical bays; flat parapet roof (not visible); entire facade appears to have been added to earlier brick building.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**



SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #31

Item number 7

Page 31

7. DESCRIPTION -- Inventory

N. MAIN STREET

500 BLOCK (continued)

130-6-167

508: Electric Service Co. Furniture and Appliances. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories; 2 front asymmetrical bays; flat parapet roof (not visible); entire facade appears to have been added to earlier building.

-168

512-516: Electric Service Co. Furniture and Appliances. Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 2 stories; 6 front symmetrical bays; flat parapet roof (not visible); entire facade appears to have been added to earlier brick building.

-169

513: Photo and Camera Shop. Commercial. Colonial Revival. ca. 1910. Brick (stretcher bond); 3 stories; 3 front symmetrical bays; flat parapet roof (not visible); altered storefront and fenestration, modillion and dentil cornice below parapet.

-170

515: Allen G. Roberts, Lawyer. Commercial (office); Vernacular. ca. 1910. Wood frame (bricktex); 2 stories; 2 front asymmetrical bays; flat roof (not visible); heavily altered facade.

-171

519: Ednes' Beauty Shop. Commercial. Vernacular. ca. 1910. Brick (stretcher bond); 2 stories; 3 front asymmetrical bays; flat parapet roof (not visible); altered storefront.

-172

520: Stevens Music and Appliance Co. Commercial. Vernacular. ca. 1930. Brick (stretcher bond); 1 story; 2 front asymmetrical bays; flat parapet roof (not visible); fluted stone pilasters, unadorned brick panel above storefront.

-173

521: Billiards. Commercial. Vernacular. ca. 1910; Brick (stretcher bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); altered storefront.

-174

524: Central Telephone Company. Commercial. Vernacular. ca. 1930; Brick (stretcher bond); 1 story; 2 front asymmetrical bays; flat parapet roof (not visible); fluted stone pilasters, unadorned brick panel above storefront.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #32

Item number 7

Page 32

7. DESCRIPTION -- Inventory

N. MAIN STREET

500 BLOCK (continued)

- 130-6-175 526: Finance One. Commercial. Vernacular. ca. 1930. Stone (dressed ashlar); 3 stories; 2 front asymmetrical bays; flat parapet roof (not visible); altered storefront, decorative stonework.
- 176 527: Reynolds Pastry Shop. Commercial. Vernacular. ca. 1910. Brick (5-course American bond); 2 stories; 2 front bays; flat parapet roof (not visible); altered 1st floor storefront.
- 177 528: The New Halifax Twin Movie Theatre. Theatre. Art Deco. ca. 1930. Brick with stone veneer (dressed ashlar); 3 stories; 2 front asymmetrical bays; flat parapet roof (not visible); decorative fluted stone panels, altered 1st floor.
- 178 536-540: Ridgeway Grocery Co./E. T. Francis Jeweler. Commercial. Art Deco. ca. 1930. Brick (stretcher bond); 2 stories; 5 front asymmetrical bays; flat parapet (not visible); stone-capped brick pilasters, altered storefronts.
- 179 539: Jerris Country Stitches. Commercial. Vernacular. ca. 1930s. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; brick veneered facade - added.
- 180 541: Mike's Radio and TV. Commercial. Vernacular. ca. 1930s. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; flat parapet roof (not visible); somewhat altered original storefront.
- ode 463 \*544: Central Telephone Co. Commercial. Colonial Revival. ca. 1970s. Brick (stretcher bond); 1 story; 3 front symmetrical bays; gable with pediment roof (composition shingle). Noncontributing.
- MA 464 \*548: Security Building. Commercial (offices). Modern. ca. 1960s. Brick (stretcher bond); 1 story; 1 front asymmetrical bay; flat roof (not visible). Noncontributing.
- 181 543-549: South Boston Insurance Agency, Inc./Creative Styling Salon. Commercial. Vernacular. ca. 1930s. Brick (stretcher bond), concrete block; 2 stories; 5 front asymmetrical bays; flat parapet roof (not visible); altered original facade.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #33 Item number 7

7. DESCRIPTION -- Inventory

N. MAIN STREET

500 BLOCK (continued)

130-7 U. S. Post Office. Post Office. Vernacular. ca. 1920. Brick (4-course American bond); 1 story; 5 symmetrical bays; flat parapet roof (not visible).

600 BLOCK

WC  
-465 \*600: Commercial (service station). Modern. ca. 1960s. Concrete block; 1 story; 4 front asymmetrical bays; shed roof (not visible). Noncontributing.

MC  
-466 \*Trinity Episcopal Church. Church. Colonial Revival. ca. 1964. Brick (Flemish bond); 1 story; 1 front, 4 side symmetrical bays; gable roof (slate); brick segmental pediment over door, round arched windows; modillion cornice. Noncontributing. Church annex, built in 1927 as original church building, connected to modern sanctuary.

MC  
-467 \*Michelin Tire Store. Commercial (service station). Modern. ca. 1960. Concrete block; 1 story; 4 front asymmetrical bays; shed roof (not visible); porte cochere supported by metal poles. Noncontributing.


130-6-182 616: Detached house. Vernacular. ca. 1880s. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; gable roof (metal, standing seam); 1-story, 1-level, 3-bay porch with paneled square columns, paneled frieze, dentil cornice, balustraded deck; paneled frieze, dentil cornice, central front gable.

-183 622: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1½ stories; 4 front asymmetrical bays; hipped pyramidal roof (composition shingle); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with square brick columns with corbeled capitals and bases.

-184 624: Detached house. Shingle Style. ca. 1890s. Wood frame (shingle, wood); 2 stories; 6 front asymmetrical bays; gable roof (standing seam metal); 2-story, 2-level, 6-bay wraparound porch with turned posts, spindle frieze, turned balustrade, screened upper-level 1-bay porch; decorative wood details in projecting front ell, bay windows, side porch.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**



SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #34

Item number 7

Page 34

7. DESCRIPTION -- Inventory

N. MAIN STREET

600 BLOCK (continued)

130-6-185

First Presbyterian Church. Church. Victorian Gothic. ca. 1887. Brick (stretcher bond); 1 story; 2 front asymmetrical bays; gable roof (slate); steeply pitched gable roof, pointed arched windows with tracery, corner bell tower with entrance sheltered by hood with brackets.

700 BLOCK

NO  
468

\*701: Main St. United Methodist Church. Church. Colonial Revival. ca. 1957. Brick (5-course American bond with Flemish variant); 1 story with raised basement; 1 front, 7 side symmetrical bays; gable roof with pediment (composition shingle); 2-story, 1-level, 3-bay frame porch with tetrastyle Tuscan portico; brick quoins, metal steeple, recessed arched side bays. Noncontributing. (Took place of 130-2 - destroyed church)

NO  
469

\*709: Residential. Colonial Revival. ca. 1950s. Brick (stretcher bond); 2 stories (low basement); 3 front symmetrical bays; gable roof (composition shingle); Doric frontispiece entrance, modillion cornice. Noncontributing.

800 BLOCK

130-6-186

801: Detached house. Colonial Revival. ca. 1910s. Wood frame (weatherboard); 1½ stories; 2 front asymmetrical bays; gambrel roof (composition shingle); 1-story, 1-level, 2-bay (frame and brick) porch with Tuscan column on brick pier, square brick columns on ends.

NO  
470

\*811: First Baptist Church. Church. Colonial Revival. ca. 1979. Brick (stretcher bond); 1 story; 3 front, 1 side symmetrical bay; octagonal roof (composition shingle); 2-story, 1-level, 3-bay porch with tetrastyle Doric portico, lunette in pediment; stained-glass windows, octagonal sanctuary. Noncontributing.

-187

818: Detached house. Queen Anne. ca. 1900. Brick (stretcher bond); 2 stories; 4 front asymmetrical bays; hipped roof (slate); 1-story, 1-level, 5-bay wraparound porch with Ionic columns.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #35

Item number 7

Page 35

7. DESCRIPTION -- Inventory

N. MAIN STREET

800 BLOCK (continued)

- 130-6-188 825: Detached house. Vernacular. ca. 1890s. Wood frame (weatherboard); 2 stories; 5 front symmetrical bays; flat roof (not visible); 1-story, 1-level, 7-bay (frame and brick) porch with Tuscan columns on brick piers; bracketed cornice, entrance with fanlight and sidelights.
- 189 829: Residential. Victorian Italianate. ca. 1890s. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 4-bay frame porch with decorative sawnwork; brackets with drop finials; transom with Gothic tracery, bracketed cornice.
- 190 833: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 2 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 2-bay frame porch with Tuscan columns; metal awning.
- MA  
-471 \*836: Detached house. Colonial Revival. ca. 1950s. Wood frame (weatherboard and vertical siding); 2 stories, 3 front symmetrical bays; gable roof (composition shingle). Noncontributing.
- 191 837: Detached house. Colonial Revival. ca. 1920s. Brick (stretcher bond); 1½ stories; 2 front asymmetrical bays; gambrel roof (composition shingle); 2 side shed dormers; 1-story, 1-level, 3-bay (frame and brick) porch with dentil cornice; Tuscan columns, balustraded deck with urn finials, brick floor; reorientation of front entrance to side, original front porch removed.
- 192 838: Detached house. Vernacular. ca. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (slate); 1-story, 1-level, 3-bay porch with Tuscan columns; central front gable, side bay windows.

900 BLOCK

- 193 905: Detached house. Queen Anne. ca. 1890s. Brick (painted); 2 stories; 3 front symmetrical bays; central front gable roof (standing seam metal); 1-story, 1-level, 6-bay wraparound porch with corner gazebo; bracketed cornice, stained-glass transom and sidelights, stone lintels over windows.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #36

Item number 7

Page 36

7. DESCRIPTION -- Inventory

N. MAIN STREET

900 BLOCK (continued)

130-6-194 908: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (slate); 1-story, 1-level, 9-bay wraparound porch with fluted Tuscan columns.

-195 909: Detached house. Victorian Italianate. ca. 1890s. Brick (painted); 2 stories; 3 front symmetrical bays; central front gable roof (standing seam metal); 1-story, 1-level, 5-bay frame porch with Tuscan columns; bracketed cornice, decorative frieze, segmental-arched windows.

-196 915: Detached house. Bungalow. ca. 1920s. Brick (stucco); 1½ stories; 5 front symmetrical bays; hipped roof (composition shingle); 2 side hipped dormers; 1-story, 1-level, 1-bay porch with paired square stuccoed columns.

1000 BLOCK

-197 1001: Detached house. Vernacular. ca. 1920s. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; hipped roof (composition shingle); 1-story, 1-level, 3-bay porch with tapered square wood columns, bracketed cornice, gable over entrance bay; bracketed cornice.

-198 1002: Detached house. Colonial Revival. ca. 1920s. Brick (stretcher bond); 2½ stories; 6 front symmetrical bays; gable roof (slate); 3 front gable dormers; 1-story, 1-level, 1-bay frame porch with fluted Doric columns; dentil cornice; iron balustraded deck; elliptical entrance with fanlight and side porte cochere; French doors with fanlights.

1100 BLOCK

-199 1100: Detached house. Colonial Revival. ca. 1920s. Brick (stretcher bond); 2½ stories; 6 front symmetrical bays; gable roof (slate); 3 front gable dormers; 1-story, 1-level, 1-bay frame porch with paired Tuscan columns, broken pediment; elliptical entrance with fanlight and sidelights, decorative window arches.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #37 Item number 7

Page 37

7. DESCRIPTION -- Inventory

N. MAIN STREET

1100 BLOCK (continued)

130-6-200

1103: Detached house. Colonial Revival. ca. 1920s. Brick (stretcher bond); 2 stories; 5 front symmetrical bays; gable roof (composition shingle); 3 front gable dormers; 1-story, 1-level, 1-bay porch with paired Tuscan columns; entrance with elliptical fanlight and sidelights.

201

1106: Detached house. Vernacular. ca. 1920. Wood frame (stucco); 1½ stories; 5 front asymmetrical bays; clipped end gable roof (slate); 2 front hipped dormers; 1-story, 1-level, 3-bay frame porch with square wood columns and scroll brackets; gabled entrance bay; transoms over entrance and 2 windows.

202

1112: Detached house. Colonial Revival. ca. 1920. Brick (stretcher bond); 2½ stories; 3 front symmetrical bays; hipped roof (slate); 2 front pedimented dormers; 1-story, 1-level, 1-bay frame porch with paneled square columns and fluted Doric columns; balustraded deck; stone lintels over openings, porte cochere; tripartite windows; entrance with transom and sidelights with decorative tracery.

412 ABC

\*1113: Detached house. Vernacular. ca. 1950s. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; gable roof (composition shingle). Noncontributing.

413 ABC

\*1118-1120: Detached house. Colonial Revival. ca. 1950s. Brick (stretcher bond); 2 stories; 4 front symmetrical bays; gable roof (composition shingle). Noncontributing.

414 ABC

\*1129: Health clinic. Modern. ca. 1960s. Brick (stretcher bond); 1 story; 1 front asymmetrical bay; flat roof (not visible). Noncontributing.

203

1130: Detached house. Vernacular. ca. 1890s. Wood frame (weatherboard); 2 stories; 4 front asymmetrical bays; gable roof (standing seam metal); 2-story, 2-level, 3-bay frame porch with turned posts, turned balustrade, added portico with shingled gable; entrance with sidelights, front ell with bay window.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #38

Item number 7

Page 38

7. DESCRIPTION -- Inventory

N. MAIN STREET

1100 BLOCK (continued)

130-6-204 1135: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 1-bay porch with original porch replaced by modern porch with coupled slender columns and pediment.

-205 1146: Tucker C. Watkins House (originally). Retirement home (currently). Spanish Colonial Revival. ca. 1920s. Wood frame (stucco); 2 stories; 15 front asymmetrical bays; hipped roof (pantile); 1-story, 1-level, 1-bay frame porch with paired fluted Doric columns, decorative frieze, iron balustraded deck; French doors with fanlights, entrance transom and sidelights, sun porch.

1200 BLOCK

-206 1201: Detached house. Colonial Revival. ca. 1920s. Wood frame (weatherboard); 1½ stories; 5 front symmetrical bays; gable roof (composition shingle); 1 front shed dormer; 1-story, 1-level, 3-bay porch with slender paired columns, simple balustrade.

-207 1209: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 4 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with wrought-iron supports and railing, original porch removed; transom over entrance, cornice with returns.

-208 1213: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 2-bay porch with tapered square wood columns, simple balustrade.

-209 1216: Detached house. Colonial Revival. ca. 1930s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (composition shingle); 3 front gable dormers; 1-story, 1-level, 1-bay frame porch with tripled slender columns, shallow gable roof.

-210 1217: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 1 story; 3 front asymmetrical bays; hipped pyramidal roof (standing seam metal); 1-story, 1-level, 3-bay porch with slender Tuscan columns, dentil cornice; central front gable, central brick chimney.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #39

Item number 7

Page 39

7. DESCRIPTION -- Inventory

N. MAIN STREET

1200 BLOCK (continued)

130-6-211

1221: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped pyramidal roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns, simple balustrade, dentil cornice; central front gable, central brick chimney.

475 MA

\*1222: Detached house. Colonial Revival. ca. 1940s. Brick (stretcher bond); 1½ stories; 4 front asymmetrical bays; gable roof (composition shingle); 2 front gable dormers. Noncontributing.

-212

1223: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns, simple balustrade, screened in; alterations and additions.

476 MA

\*1228: Apartment house. Vernacular. ca. 1950s. Wood frame (weatherboard); 2 stories (low basement); 3 front symmetrical bays; hipped roof (composition shingle). Noncontributing.

1300 BLOCK

-213

1303: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (slate); 1-story, 1-level, 1-bay porch with clustered square wood columns, wrought-iron railing, replaced original porch; alterations.

130-5

1304: R. S. Barbour House. Detached house. Queen Anne/Colonial Revival. ca. 1900. Wood frame (weatherboard); 2½ stories; 3 front bays; hipped roof (slate); 1 front gable dormer; 1-story, 1-level, 5-bay (frame and stone) porch with Ionic columns on stone piers, wide frieze and dentil cornice; entrance with transom and sidelights, modillion and dentil cornice, side porch, corner tower.

-214

1309: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 2 stories; 2 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 4-bay porch with slender Tuscan columns; 2-story bay window with decorative wood brackets.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #40

Item number 7

Page 40

7. DESCRIPTION -- Inventory

N. MAIN STREET

1300 BLOCK (continued)

130-6-215

1314: Detached house. Queen Anne. ca. 1900. Wood frame (pressed tin and weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (pressed tin); 1-story, 1-level; 2-bay porch with paired and tripled fluted Ionic columns; unusual pressed tin siding, bowed front ell; bracketed cornice.

MC 477

\*1315: Detached house. Colonial Revival. 1950s. Brick (stretcher bond); 1½ stories; 3 front symmetrical bays; gable roof (composition shingle); 3 front gable dormers. Noncontributing.

216

1318: Detached house. Vernacular. 1890s. Wood frame (aluminum siding); 1½ stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay frame porch with Tuscan columns; bracketed cornice; bracketed cornice with drop finials and decorative gable sawnwork.

217

1319: Robert H. Edmondson House. Detached house. Queen Anne. 1890s. Brick (stretcher bond); 2½ stories; 3 front asymmetrical bays; gable roof (slate); 1 front pedimented gable dormer; 1-story, 1-level, 4-bay porch with Ionic columns, turned balustrade; corbeled brick cornice, stone window lintels, entrance with leaded glass transom and sidelights, open porch turret above 2nd floor.

218

1322: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 4-bay frame porch with Tuscan columns; bracketed cornice with dropped finials; 2 front gables.

1400 BLOCK

MC 478

\*1401: Detached house. Vernacular. 1950s. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay side porch with shingled square columns, simple balustrade. Noncontributing.

MC 479

\*1403: Detached house. Vernacular. 1950s. Wood frame (weatherboard); 1 story; 4 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay side porch with square columns, simple balustrade, arched bays. Noncontributing.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #41

Item number 7

Page 41

7. DESCRIPTIONS -- Inventory

N. MAIN STREET

1400 BLOCK (continued)

130-219 1404: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (pressed tin); 2-story, 1-level, 3-bay frame porch with panelled square 2-story columns, flat roof; entrance with transom and sidelights.

220 1405: Detached house. Tudor Revival. 1920s. Brick (5-course American bond); 2 stories; 5 front asymmetrical bays; gable roof (slate); metal hood with brackets at entrance, casement windows, stone and brick chimney.

221 1408: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (pressed tin); 1-story, 1-level, 3-bay frame porch with columns with altered capitals, decorative frieze; entrance with transom and sidelights, decorative frieze.

222 1410: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay frame porch with Tuscan columns; central front gable, entrance with transom and sidelights.

223 1413: Samuel F. Gilliland House. Queen Anne/Colonial Revival. ca. 1900. Wood frame (weatherboard); 2½ stories; 3 front symmetrical bays; hipped roof (slate); 1 front gable dormer; 1-story, 1-level, 3-bay porch with Tuscan columns, dentil cornice, simple balustrade.

224 1414: Detached house. Vernacular. ca. 1910. Wood frame (asbestos shingle); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 2-bay frame porch with Tuscan columns, wrought-iron railing.

225 1420: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 5-bay frame porch with Tuscan columns bracketed cornice; bracketed cornice, central front gable, entrance with transom and sidelights.

226 1421: Detached house. Colonial Revival. ca. 1910. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (slate); 2-story, 2-level, 3-bay porch with central 2-story, 2-level pedimented portico with paired Ionic columns, flanking 1-story porch wings with Ionic columns and turned balustrade.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #42

Item number 7

Page 42

7. DESCRIPTION -- Inventory

N. MAIN STREET

1500 BLOCK

130-6-227

1500: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1 story; 4 front asymmetrical bays; hipped roof (slate); 1 front hipped dormer; 1-story, 1-level, 5-bay frame porch with Tuscan columns.

Me 480

\*1502-4: Detached house. Vernacular. ca. 1940s. Brick (stretcher bond); 2 stories; 4 front symmetrical bays; central front gable roof (composition shingle); 1-story, 1-level, 3-bay frame porch with tapered square columns. Noncontributing.

-228

1505: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (composition shingle); 1-story, 1-level, 1-bay porch with fluted Ionic columns, replaced original porch; alterations.

-229

1508: J. W. Elliott House. Detached house. Queen Anne. ca. 1900. Brick (5-course American bond); 2 stories; 5 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 6-bay frame wraparound porch with Tuscan columns, bracketed cornice with drop finials and spindle frieze; central front gable with decorative trim, corner tower with finial; wood lintels, decorative brick chimneys, bracketed cornice with egg and dart molding.

-230

1511: Detached house. Vernacular. ca. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns; central front gable.

1600 BLOCK

-231

1601: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 5 front symmetrical bays; gable roof (standing seam metal); 2-story, 1-level, 3-bay porch with 2-story square wood columns, brick floor, added porch; modern alterations.

-232

1602: Detached house. Modified Queen Anne. ca. 1910. Wood frame (weatherboard); 2½ stories; 3 front symmetrical bays; hipped roof (pressed tin); 1 front hipped dormer; 1-story, 1-level, 7-bay wraparound porch with paired Tuscan columns on rough-faced masonry piers.

**United States Department of the Interior  
National Park Service**

For NPS use only  
received  
date entered

**National Register of Historic Places  
Inventory—Nomination Form**

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #43

Item number 7

Page 43

7. DESCRIPTION -- Inventory

N. MAIN STREET

1600 BLOCK (continued)

130-6-233 1606: Detached house. Bungalow. 1920s. Wood frame (weatherboard); 2½ stories; 3 front symmetrical bays; hipped pyramidal roof (shingle composition); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with square wood columns.

-234 1607: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns; bracketed cornice, window hoods, transom over entrance.

481 MC \*1608: Detached house. Modern. 1960s. Brick (stretcher bond); 1 story; 3 front asymmetrical bays; gable roof (composition shingle). Noncontributing.

-235 1612: Detached house. Bungalow. 1920s. Wood frame (aluminum siding); 1 story; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 2-bay porch with tapered square wood columns on brick piers, simple balustrade.

-236 1615: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts, scroll brackets, spindle frieze; bracketed cornice.

-237 1616: Detached house. Bungalow. 1910s. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped pyramidal roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers.

482 MC PUBLIC PLAYGROUND


1700 BLOCK

-238 1702: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; clipped end gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts.

-239 1706: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1 story; 1 front symmetrical bay; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with square brick columns on piers.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form



SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #44

Item number 7

Page 44

7. DESCRIPTION -- Inventory

N. MAIN STREET

1700 BLOCK (continued)

1306-240

1708: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1½ stories; 3 front asymmetrical bays; hipped roof (composition shingle); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with slender Tuscan columns.

-241

1712: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with square brick columns on piers.

-242

1715: Detached house. Bungalow. ca. 1920. Wood frame (weatherboard); 1½ stories; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with tapered square columns on brick piers.

-243

1716: Mother Hubbard's Convenience Cupboard (currently). Commercial. Vernacular. ca. 1910. Wood frame (weatherboard) with brick (stretcher bond) addition; 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns, gable roof.

-244

1721: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with tapered square columns on brick piers, replaced original porch; two front gables.

-245

1724: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 2-bay porch with Tuscan columns.

Mc 483

\*1725: Detached house. Colonial Revival. 1940s. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; hipped roof (composition shingle). Noncontributing.

-246

1727: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood columns on piers; central front gable.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #45

Item number 7

Page 45

7. DESCRIPTION -- Inventory

N. MAIN STREET

1700 BLOCK (continued)

130-6-247 1728: Detached house. Vernacular. ca. 1920. Wood frame (weatherboard); 1 story; 2 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with paired square wood columns.

-248 1733: Detached house. Modified Queen Anne. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (pressed tin); 1-story, 1-level, 7-bay wraparound porch with tapered square wood columns on paneled piers, simple balustrade; 2-story bay windows with decorative woodwork under gable.

1800 BLOCK

-249 1804: Detached house. Vernacular. ca. 1920. Brick (stretcher bond); 2½ stories; 2 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay wraparound porch with tapered square wood columns on brick piers.

-250 1806: Detached house. Vernacular. ca. 1920s. Brick (Flemish bond); 2 stories; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with arched brick bays.

-251 1808: Mt. Olive Baptist Church. Church. ca. 1890s. Wood frame with brick veneer added; 1 story; 4 front asymmetrical bays; gable roof (composition shingle); remodeled 1962.

-252 1818: Funeral Home. Detached house. Vernacular. 1920s. Wood frame (aluminum siding); 2 stories; 2 front asymmetrical bays; hipped roof (pantile); 1-story, 1-level, 3-bay porch with tapered square columns on stone piers, simple balustrade, metal awning, porte cochere attached.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #46

Item number 7

Page 46

7. DESCRIPTION -- Inventory

McCANDLESS STREET

200 BLOCK

130-6-253

209: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, wood balustrade.

-254

213: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-255

215: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-256

219: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-257

221: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

MINERAL STREET

-258

Imperial Tobacco Company (originally). Sale Knitting Company (currently). Factory. Vernacular. 1890s. Brick (5-course American bond); 2 stories (raised basement); 4 front asymmetrical bays; flat parapet roof (not visible); decorative brick cornice, parapet, pilasters, etc.

MOORE STREET

1300 BLOCK

-259

1308: Detached house. Bungalow. 1910s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; hipped roof (composition shingle); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with square wood columns.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #47 Item number 7

Page 47

7. DESCRIPTION -- Inventory

MOORE STREET

1300 BLOCK (continued)

*NO 484* \*1311: Detached house. Vernacular. 1940s. Wood frame (aluminum siding); 1 story; 3 front symmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with wrought-iron supports, gable roof. Noncontributing.

*130-6-260* 1313: Detached house. Vernacular. Wood frame (weatherboard); 1 story, 2 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with turned posts, gable roof.

*NO 485* \*1314: Detached house. Vernacular. 1960s. Brick (stretcher bond); 1 story; 3 front bays; hipped roof (composition shingle); 1-story, 1-level, 3-bay porch with wrought-iron supports. Noncontributing.

*-261* 1317: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; hipped roof (standing seam metal); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with square paneled columns; transom over entrance.

*NO 486* \*1320: Detached house. Vernacular. 1960s. Wood frame (composition siding); 1 story; 4 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with slender wood posts. Noncontributing.

*-262* 1321: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; hipped roof (standing seam metal); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with square wood columns.

*-263* 1324: Detached house. Vernacular. 1920s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (standing seam metal); 1 front shed dormer; 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers.

*-264* 1325: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns, altered balustrade; double front gables with decorative sawnwork.

*-265* 1332: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #48

Item number 7

Page 48

7. DESCRIPTION -- Inventory

MOORE STREET

1400 BLOCK (continued)

437 ME \*1400: Detached house. Vernacular. 1940s. Wood frame (asbestos shingle); 1 story; 3 front asymmetrical bays; gable roof (composition shingle). Noncontributing.

438 ME \*1404: Detached house. Vernacular. 1950s. Wood frame (asbestos shingle); 1 story; 3 front symmetrical bays; gable roof (composition shingle). Noncontributing.

130-6-266 1408: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 1-bay porch with turned posts, gable roof, simple balustrade, original porch removed; bracketed cornice.

267 1420: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with Tuscan columns; central front gable.

PEACH AVENUE

1200 BLOCK

439 ME \*1203: Detached house. Colonial Revival. 1970s. Brick (stretcher bond); 1 story; 7 front symmetrical bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with square wood columns. Noncontributing.

490 ME \*1208: Detached house. Vernacular. 1950s. Brick (stretcher bond); 1 story; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 2-bay porch with square wood columns. Noncontributing.

491 ME \*1212: Detached house. Vernacular. 1950s. Brick (stretcher bond); 1½ stories; 3 front asymmetrical bays; gable roof (slate); 1-story, 1-level, 2-bay porch with square wood columns. Noncontributing.

492 ME \*1215: Detached house. Vernacular. 1950s. Brick (stretcher bond); 1 story; 5 front asymmetrical bays; gable roof (composition shingle). Noncontributing.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #49

Item number 7

Page 49

7. DESCRIPTION -- Inventory

PEACH AVENUE

1200 BLOCK (continued)

130-6-208

1219: Detached house. Bungalow. 1920s. Wood frame (weatherboard, wood shingle); 1½ stories; 3 front symmetrical bays; gable roof (standing seam metal); 1 front shed dormer; 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers; wood shingled gables.

-269

1220: Detached house. Bungalow. 1920s. Wood frame (weatherboard); 1½ stories; gable roof (pressed tin); 1 front gable dormer; 1-story, 1-level, 3-bay porch with square wood columns on brick piers, simple balustrade.

-270

1224: Detached house. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay frame porch with turned posts, scroll brackets; central front gable with decorative sawnwork.

-271

1225: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; gambrel roof (standing seam metal and pressed tin); 1-story, 1-level, 2-bay porch with slender wood columns.

1300 BLOCK

-493  
100

\*1301: Detached house. Vernacular. 1950s. Brick (stretcher bond); 1½ stories; 4 front asymmetrical bays; gable roof (composition shingle); 3 front gable dormers; 1-story, 1-level, 3-bay porch with square wood columns. Noncontributing.

-272

1302: Detached house. American Foursquare. 1920s. Wood frame (stucco); 2½ stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1 front hipped dormer; 1-story, 1-level, 1-bay porch with paired square stuccoed columns, shallow gable roof.

-273

1306: Detached house. Bungalow. ca. 1920. Wood frame (weatherboard); 1½ stories; 2 front bays; gable roof (composition shingle); 1 front shed dormer; 1-story, 1-level, 4-bay porch with tapered square wood columns on brick piers, simple balustrade.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #50

Item number 7

Page 50

7. DESCRIPTION -- Inventory

PEACH AVENUE

1300 BLOCK (continued)

130-6-274

1307: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers; entrance with transom and sidelights, central front gable with decorative sawnwork.

-275

1308: Detached house. Bungalow. 1930s. Brick (stretcher bond); 1 story; 3 front symmetrical bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers, brick railing.

-276

1312: Detached house. Bungalow. 1932. Wood frame (weatherboard, wood shingle); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers; shingled front gable.

-277

1313: Detached house. Bungalow. 1920s. Wood frame (aluminum siding); 1½ stories; 3 front symmetrical bays; gable roof (composition shingle); 1 front enclosed gable dormer; 1-story, 1-level, 3-bay porch with square brick columns, brick railing, metal awning.

-278

1314-1316: Detached house. Colonial Revival. 1910s. Wood frame (weatherboard); 1½ stories; 2 front symmetrical bays; gambrel roof (pressed tin); 1-story, 1-level, 3-bay porch with Tuscan columns, dentil cornice.

MAE  
494

\*1318: Detached house. Vernacular. 1940s. Wood frame (aluminum siding); 1½ stories; 3 front asymmetrical bays; gable roof (composition shingle); 1 front gable dormer. Noncontributing.

-279

1319: Detached house. Vernacular. ca. 1898. Wood frame (aluminum siding); 2 stories; 2 front asymmetrical bays; hipped roof (pressed tin); 1-story, 1-level, 4-bay frame porch with fluted Doric columns; entrance with transom and sidelights.

-280

1323: Detached house. American Foursquare; ca. 1920. Wood frame (wood shingle); 2½ stories; 2 front asymmetrical bays; hipped pyramidal roof (composition shingle); 1 front hipped dormer; 1-story, 1-level, 3-bay porch with shingled square columns on brick piers, shingled railing.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #51

Item number 7

Page 51

7. DESCRIPTION -- Inventory

PEACH AVENUE

1400 BLOCK (continued)

130-6-281 1403: Detached house. Modified Queen Anne. ca. 1900. Wood frame (asbestos shingle); 2 stories; 3 front asymmetrical bays; hipped roof (pressed tin); 1-story, 1-level, 4-bay porch with slender wood columns, dentil cornice, partially screened.

-282 1406: Detached house. Colonial Revival. 1920s. Wood frame (weatherboard); 1½ stories; 4 front asymmetrical bays; gambrel roof (composition shingle); 1 front shed dormer; 1-story, 1-level, 1-bay porch with paired slender wood columns, arch and gable roof.

-283 1407: Detached house. Vernacular. 1930s. Brick (stretcher bond); 1½ stories; gable roof (slate); 1 front gable dormer; round arched entrance, stone quoins in patterns near entrance, casement windows.

-284 1414: Detached house. Modified Queen Anne. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (slate); 1-story, 1-level, 8-bay wraparound porch with Tuscan columns.

-285 1416: Detached house. Vernacular. 1930s. Wood frame (weatherboard); 1 story; 4 front asymmetrical bays; hipped roof (composition shingle).

-286 1420: Detached house. Vernacular. 1930s. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (shingle composition); 1-story, 1-level, 1-bay side porch with square brick columns, screened.

MC 445 \*1421: Detached house. Vernacular. 1950s. Brick (stretcher bond); 1 story; 4 front asymmetrical bays; gable roof (composition shingle). Noncontributing.

MC 446 \*1423: Detached house; Vernacular. 1950s. Brick (stretcher bond); 1½ stories; 3 front symmetrical bays; gable roof (composition shingle); 2 front gable dormers. Noncontributing.

RAGLAND STREET

-287 Tobacco warehouse. Vernacular. 1890s. Brick (5-course American bond); 1 story; 8 front asymmetrical bays; gable parapet roof (not visible).

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #52

Item number 7

Page 52

7. DESCRIPTION -- Inventory

RAILROAD AVENUE

130-288

Century Cotton Mill (originally). Halifax Cotton Mill (currently). Textile Mill. Italianate. ca. 1897. Brick (5-course American bond); 2 stories; 25 front symmetrical bays; gable parapet roof (not visible); central front tower with tall arched windows, round openings and crenellation. 1927 additions.

-289

Commercial. Vernacular. 1930s. Concrete block; 1 story; 3 front symmetrical bays; gable parapet roof (not visible).

-290

30: Central Atlantic States Service Corp. (originally). City Coal and Crating Co. (currently). Commercial. Vernacular. ca. 1900. Brick (stretcher bond); 1 story; 4 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with simple wood posts.

-291

South Boston Waterworks. (Abandoned). Vernacular. ca. 1910. Brick (5-course American bond); 3 stories; 5 front asymmetrical bays; flat parapet roof (not visible); corbeled brickwork, tall brick smokestack, brick pilasters.

-292

500: Halifax Construction Co., Inc. (originally). U. S. Oil Plant (currently). Oil storage facility. Vernacular. ca. 1900. Wood frame (board and batten); 1 story; 4 front asymmetrical bays; gable roof (standing seam metal); two frame, 1-story outbuildings on property, ca. 1930.

-293

Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers; 1-story ca. 1930 garage.

-294

Norfolk and Western Depot. Depot. Vernacular. ca. 1889. Brick (5-course American bond with Flemish variant); 1 story; 8 front asymmetrical bays; hipped roof (standing seam metal); typical late 19th-century brick depot; fenestration altered.

-295

Bruce Family Warehouse. Warehouse. Vernacular. late 19th c. Brick (5-course American bond); 1 story; 1 front symmetrical bay; hipped roof (standing seam metal); overhanging eaves with exposed rafter ends.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #53

Item number 7

Page 53

7. DESCRIPTION -- Inventory

RANDOLPH AVENUE

800 BLOCK

*296* 823: Detached house. Vernacular. ca. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts, spindle brackets.

900 BLOCK

*297* 901: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered wood columns on brick piers; central front gable.

*298* 907: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns on brick piers; central front gable.

*299* 912: Detached house. Bungalow. 1920s. Wood frame (weatherboard); 1½ stories; 3 front asymmetrical bays; gable roof (composition shingle); 1 front shed dormer; 1-story, 1-level, 3-bay porch with square wood columns on brick piers.

*300* 913: Detached house. Vernacular. ca. 1910. Wood frame (aluminum siding); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with clustered slender columns, pedimented gable roof, original porch removed.

SECOND STREET

1100 BLOCK

*301* 1102: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts, spindle brackets, cutout pattern balustrade; central front gable.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #54

Item number 7

Page 54

7. DESCRIPTION -- Inventory

SECOND STREET

1100 BLOCK

- 302 1104: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with Doric columns, dentil cornice; central front gable.
- 303 1110: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood posts.
- 304 1114: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns; central front gable.
- 305 1118: Detached house. Bungalow. 1920s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (standing seam metal); 1 front gable dormer; 1-story, 1-level, 3-bay porch with tapered wood columns on brick piers.
- 306 1121: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped pyramidal roof (standing seam metal); 1-story, 1-level, 3-bay porch with wrought-iron supports which replaced original columns.

SEYMOUR DRIVE

- 307 Blue Ribbon Creamery. McDannald Construction. Commercial. Vernacular. ca. 1920. Brick (5-course American bond); 1½ stories; 5 front asymmetrical bays; parapet gable roof (not visible)
- 308 American Tobacco Company Warehouse. Lennox Warehouse. Warehouse. Vernacular. 1890s. Brick (4-course American bond); 1 story; multiple front bays; parapet gable roof (not visible)
- 309 American Tobacco Co. Prizery. R. J. Reynolds Tobacco Co. Warehouse. Vernacular. 1890s. Brick (5-course American bond); 2 stories; 18 front asymmetrical bays; gable parapet roof (composition shingle); segmental-arched openings.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #55

Item number 7

Page 55

7. DESCRIPTION -- Inventory

SEYMOUR DRIVE

-310 R. J. Reynolds Tobacco Prizery (originally). R. J. Reynolds Tobacco Co. (currently). Warehouse. Vernacular. 1890s. Brick (5-course American bond); 3 stories; 7 front asymmetrical bays; gable roof (not visible); four-story brick tower, segmental-arched windows.

-311 Export Leaf Tobacco Co. Liggett-Meyer Tobacco Warehouse. Warehouse. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 4 front asymmetrical bays; flat roof (not visible); segmental-arched openings, large brick 1950s addition.

SHEPHERD STREET

1300 BLOCK

-312 1311: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gambrel roof (standing seam metal); 1 front shed dormer; 1-story, 1-level, 3-bay porch with tapered square columns on brick piers.

me  
497 \*1312: Detached house. Modern. 1960s. Wood frame (aluminum siding); 1 story; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with wrought-iron supports. Noncontributing.

-313 1313: Detached house. Vernacular. ca. 1900. Wood frame (asbestos shingle); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns; 4-light transom over entrance.

-314 1314: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with slender wood columns; central front gable, central brick chimney.

-315 1317: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 7-bay wraparound porch with Tuscan columns; projecting front ell with 2-story bay window.

-316 1318: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns; central front gable.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #56

Item number 7

Page 56

7. DESCRIPTION -- Inventory

SHEPHERD STREET

1300 BLOCK

130-6-317

1320: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns; central front gable.

-318

1321: Detached house. Vernacular. 1910s. Wood frame (weatherboard); 1½ stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay side porch with tapered square columns on brick piers.

-319

1324: Detached house. Vernacular. 1910s. Wood frame (aluminum siding); 1½ stories; 3 front asymmetrical bays; clipped end gable roof (standing seam metal); 1-story, 1-level, 2-bay porch with supports clad in aluminum siding; wide central gable, tripled windows.

-320

1325: Detached house. Modified Queen Anne. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 7-bay wraparound porch with slender wood columns; corner turret with bellcast metal roof, 2-story bay window surmounted by gable with decorative sawnwork.

-321

1328: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (pressed tin); 1 front gable dormer; 1-story, 1-level, 5-bay porch with Tuscan columns, simple balustrade; entrance with transom and sidelights.

-322

1329: Detached house. Vernacular. ca. 1900. Wood frame (asbestos shingle); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square columns on brick piers; central front gable.

-323

1332: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with turned posts, decorative wood balustrade; central front gable.

-324

1333: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts, scroll brackets; central front gable.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #57

Item number 7

Page 57

7. DESCRIPTION -- Inventory

SHEPHERD STREET

1300 BLOCK (continued)

130-6-325 1336: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts, modern balustrade; double front gables.

498 \*1337: Detached house. Modern. 1960s. Brick (stretcher bond); 1 story; 3 front symmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with wrought-iron supports, gable roof. Noncontributing.

-326 1340: Detached house. Vernacular. ca. 1920. Brick (stretcher bond); 2 stories; 3 front symmetrical bays; hipped roof (composition shingle); 1-story, 1-level, 3-bay porch with square brick columns, brick balustrade.

499 \*1341: Detached house. Modern. 1970s. Wood frame (vertical siding); 1 story; 2 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 6-bay porch with square wood posts, crisscross balustrade. Noncontributing.

-327 1344: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 4 front bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts, turned balustrade, scroll brackets; 2-story bay window surmounted by gable with decorative sawnwork.

500 \*1347: Detached house. Modern. 1940s. Concrete block; 1 story; 2 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with square wood columns, gable roof. Noncontributing.

SHORT STREET

400 BLOCK

130-6-328 437: G. B. King and Son Sheet Metal Work. Commercial. Vernacular. ca. 1910. Brick (5-course American bond); 1 story; 4 front asymmetrical bays; flat parapet roof (not visible); metal cornice extends across facade.

-329 443: Carrington's Cabinet Shop. Commercial. Vernacular. ca. 1910. Brick (5-course American bond); 1 story; 3 front asymmetrical bays; flat parapet roof (not visible); metal cornice extends across facade, little altered storefront.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #58

Item number 7

Page 58

7. DESCRIPTION -- Inventory

SHORT STREET

400 BLOCK (continued)

130-6-330 447: Hedderly's Printing Co. Commercial. Vernacular. ca. 1910. Brick (5-course American bond); 1 story; 4 front asymmetrical bays; flat parapet roof (not visible); metal cornice extends across facade, little altered storefront.

-331 449: Artistic Beauty Salon. Commercial. Vernacular. ca. 1910. Brick (vertical siding added); 1 story; 3 front symmetrical bays; flat parapet roof (not visible); considerably altered facade on earlier building.

-332 451: Connie Lowery Income Tax Service. Commercial. Vernacular. ca. 1910. Brick (vertical siding added); 1 story; 3 front bays; flat parapet roof (not visible); considerably altered facade on earlier building.

SIXTH STREET

1200 BLOCK

-333 1202: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (pressed tin); 1-story, 1-level, 3-bay porch with Tuscan columns, low balustrade; bracketed cornice, central front gable entrance with fanlight and sidelights.

-334 1204: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 4 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with square wood columns, arched bays; bracketed cornice with returns.

-335 1206: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (composition shingle); 1-story, 1-level, 6-bay wraparound porch with turned posts, spindle brackets, turned balustrade; double front gables with decorative sawnwork, 1-story section at rear.

all -501 \*1211: Detached house. Vernacular. 1940s. Wood frame (weatherboard); 1½ stories; 2 front bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with Tuscan column, scroll brackets, turned balustrade. Noncontributing.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #59

Item number 7

Page 59

7. DESCRIPTION -- Inventory

SUMMIT DRIVE

100 BLOCK

130-6-336 140: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-337 144: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with wrought-iron supports.

200 BLOCK

-338 202: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood posts.

-339 205: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, added balustrade.

-340 206: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood posts.

-341 210: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 1 story; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with wrought-iron supports and railing.

-342 211: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story, 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-343 212: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood posts.

-344 215: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #60

Item number 7

Page 60

7. DESCRIPTION -- Inventory

SUMMITT DRIVE

200 BLOCK (continued)

130-6-345 218: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with wrought-iron supports.

-346 219: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood posts.

-347 226: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with square posts.

-348 227: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level; 2-bay porch with square wood posts.

300 BLOCK

-349 300: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped pyramidal roof (standing seam metal); 1-story, 1-level, 2-bay porch with turned posts, screened.

-350 306: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-351 310: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, stick balustrade.

-352 315: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-353 316: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood posts, simple balustrade.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #61 Item number 7

Page 61

7. DESCRIPTION -- Inventory

SUMMIT DRIVE

300 BLOCK (continued)

130-6-354 319: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 2 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-355 322: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-356 328: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

-357 329: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts.

400 BLOCK

-358 412: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with turned posts.

-359 418: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with turned posts.

-360 424: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with square wood posts.

-361 430: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with turned posts, partially screened.

-362 432: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with square wood posts.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #62

Item number 7

Page 62

7. DESCRIPTION -- Inventory

SUMMIT DRIVE

500 BLOCK

130-6-363 500: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with square wood posts.

-364 502: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 5-bay porch with turned posts, simple balustrade.

-365 506: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story, 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, lattice balustrade.

THIRD STREET

500 BLOCK

130-18 508: Detached house. Queen Anne. ca. 1900. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; gambrel roof with hips and gables (standing seam metal); 2 gable side dormers; 1-story, 1-level, 10-bay wraparound porch; semi-hexagonal projecting bays, entrance with transom and sidelights.

130-6-366 507: Detached house. Vernacular. 1920s. Wood frame (asbestos shingle); 1 story; 3 front bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with square wood columns; cinderblock basement.

130-19 509: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns, simple balustrade; bracketed cornice, central gabled front projection.

130-20 520: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns and simple balustrade.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #63

Item number 7

Page 63

7. DESCRIPTION -- Inventory

THIRD STREET

500 BLOCK (continued)

*WA*  
*-502* \*522: Detached house. Vernacular. 1950s. Vernacular. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (composition shingle); 2 front gable dormers; 1-story, 1-level, 1-bay porch with tripled square wood columns, gable roof. Noncontributing.

*130-6-367* 526: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 2 stories, 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with paired wood columns, shed roof, original porch removed.

1000 BLOCK

*WA*  
*-503* \*1002: Detached house. Modern. 1960s. Brick (stretcher bond); 1 story; 5 front asymmetrical bays; gable roof (composition shingle). Noncontributing.

*130-6-368* 1003: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard) with brick (stretcher bond) addition; 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); modern brick addition, hood over entrance.

*WA*  
*-504* \*1005: Detached house. Modern. 1960s. Wood frame (aluminum siding); 1 story; 4 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with wrought-iron supports. Noncontributing.

*-369* 1010: Detached house. Vernacular. 1870s. Wood frame (weatherboard); 2 stories; 2 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns, simple balustrade; bracketed cornice.

*-370* 1016: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts, scroll brackets, simple balustrade.

1100 BLOCK

*-371* 1100: Detached house. Vernacular. ca. 1920. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gable roof (composition shingle); 1 front gable dormer; 1-story, 1-level, 1-bay side porch with tapered wood columns.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #64

Item number 7

Page 64

7. DESCRIPTION -- Inventory

THIRD STREET

1100 BLOCK (continued)

130-6-372 1113: Detached house. Vernacular. ca. 1910. Wood frame (aluminum siding); 2½ stories; 2 front asymmetrical bays; gable roof (standing seam metal); 1 front hipped dormer; 1-story, 1-level, 2-bay porch with Tuscan columns.

-373 1117: Detached house. Vernacular. ca. 1920. Wood frame (aluminum siding); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood posts, simple balustrade, metal awning.

-374 1119: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered wood columns on brick piers, original porch altered; central front gable.

1200 BLOCK

-375 1203: Detached house. Vernacular. 1920s. Wood frame (weatherboard); 1½ stories; 4 front asymmetrical bays; gable roof (composition shingle); 1 front shed dormer; 1-story, 1-level, 3-bay porch with square wood columns.

-376 1205: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with Tuscan columns; front gable with decorative sawnwork.

-377 1211: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood columns; front gable with decorative sawnwork.

THOMAS STREET

300 BLOCK

-378 305: C. W. Walters Tobacco Warehouse. Warehouse. Vernacular. ca. 1900. Brick (6-course American bond) with corrugated metal covering much of facade; 1 story; 2 front bays; parapet shed roof (standing seam metal)

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #65

Item number 7

Page 65

7. DESCRIPTION — Inventory

THOMAS STREET

300 BLOCK (continued)

130-6-379 309: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with slender square wood posts, simple balustrade; central brick flue.

905 NE \*310: Garage and repair shop. Modern. 1950s. Concrete block; 1 story; 2 front asymmetrical bays; parapet flat roof (not visible). Noncontributing.

380 313: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with tapered wood columns on brick piers.

TRAVER AVENUE

800 BLOCK

381 817: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1½ stories; 2 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 2-bay porch with turned posts.

382 820: Detached house. Vernacular. 1880s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns, balustraded deck; bracketed cornice.

383 823: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 4 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 5-bay porch with square wood posts; central front gable in original section, 2-story frame side extension.

384 827: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with turned posts; central front gable.

385 831: Detached house. Vernacular. 1930s. Wood frame (aluminum siding); 1½ stories; 2 front asymmetrical bays; gable roof (composition shingle); 1 front gable dormer; 1-story, 1-level, 2-bay porch with wrought-iron supports.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #66

Item number 7

Page 66

7. DESCRIPTION -- Inventory

TRAVER AVENUE

800 BLOCK (continued)

130-6-386

832: Detached house. Vernacular. 1890s. Wood frame (aluminum siding); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns, arched bays.

-387

835: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 1½ stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 1-bay porch with square wood columns on brick piers, original porch removed.

-388

837: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (composition shingle); 2-stories, 1-level, 3-bay porch with 2-story square wood columns, original porch removed.

900 BLOCK

-389

901: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with square wood columns; bracketed cornice.

-390

905: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns on brick piers; central front gable with decorative sawnwork.

-391

907: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with tapered square columns on brick piers.

-392

911: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; hipped roof (pressed tin); 1-story, 1-level, 3-bay porch with square wood columns on brick piers.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #67

Item number 7

Page 67

7. DESCRIPTION -- Inventory

WASHINGTON AVENUE

1000 BLOCK

130-6-393

1001: Detached house. Colonial Revival. 1930s. Brick (stretcher bond); 1½ stories; 3 front symmetrical bays; gable roof (composition shingle); 3 front gable dormers; 1-story, 1-level, 1-bay porch with wrought-iron supports; entrance with fanlight and sidelights, decorative wood cornice.

-394

1002: Noblin House. Detached house. Queen Anne. 1895. Wood frame (weatherboard with wood shingle); 2½ stories; 5 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 13-bay wraparound porch with turned posts, turned balustrade, spindle frieze, 2nd-story single-bay porch; corner 3-level tower with domed roof, bracketed cornice, front gable with decorative woodwork and Palladian window.

-395

1014: Edgar H. Vaughan House. Detached house. Victorian Italianate. 1888. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 2-bay porch with paired square wood columns on brick piers, simple balustrade; heavy bracketed cornice with decorative frieze, segmental-arched central 2nd-story windows, decorative window heads, wide transom over entrance.

1100 BLOCK

-396

1100: Detached house. Tudor Revival. 1920s. Brick (English bond); 1½ stories; 3 front asymmetrical bays; hipped roof (slate); 2 front hipped projecting wall dormers; 1-story, 1-level, 1-bay porch with wood posts with brackets, large similar side porch.

-397

1102: Detached house. Vernacular. ca. 1900. Wood frame (aluminum siding); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 8-bay wraparound porch with Tuscan columns, simple balustrade; central front gable entrance with transom and sidelights.

-398

1103: Detached house. Cottage. 1920s. Brick (stretcher bond); 1½ stories; 3 front asymmetrical bays; gable roof (flat tile); 1-story, 1-level, 1-bay porch with arched brick bay.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #68

Item number 7

Page 68

7. DESCRIPTION -- Inventory

WASHINGTON AVENUE

1100 BLOCK (continued)

- 130-6-399 1105: Detached house. Cottage. 1920s. Brick (irregular); 1½ stories; 6 front bays; gable roof (slate); house burned and remodeled, casement windows, stone and brick exterior end chimney at front.
- 400 1107: Detached house. Bungalow. 1920s. Wood frame (stucco); 1½ stories; 3 front asymmetrical bays; gable roof (standing seam metal); 1 front shed dormer; 1-story, 1-level, 1-bay porch with square stuccoed columns, stuccoed railing, gable roof; tripled double sash windows.
- 401 1108: Detached house. Colonial Revival. 1930s. Brick (stretcher bond); 1½ stories; 4 front asymmetrical bays; gable roof (composition shingle); 2 front gable dormers); 1-story, 1-level, 4-bay porch with wrought-iron supports and decoration; interior end brick chimneys.
- 402 1109: Detached house. Cottage. 1930s. Brick (stretcher bond); 1½ stories; 3 front asymmetrical bays; gable roof (slate); 1 front shed dormer; steeply-pitched gable projection with round-arched entrance, casement windows.
- 403 1115: Detached house. Colonial Revival. 1930s. Brick (stretcher bond); 2 stories; 6 front asymmetrical bays; gable roof (slate); 1-story, 1-level, 1-bay porch with paired Tuscan columns, segmental-arched roof; entrance with elliptical fanlight and sidelights.
- 404 1116: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 4 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 4-bay porch with tapered square wood columns on brick piers, turned balustrade; bracketed cornice, shingled gables, bay window projections.
- 405 1119: Detached house. Colonial Revival. 1920s. Brick (stetcher bond); 2 stories; 3 front symmetrical bays; hipped roof (tile); 1-story, 1-level, 3-bay porch with tapered square paneled columns, simple balustrade; entrance with transom and sidelights, flat arches with keystones over principal windows.
- 406 1121: Detached house. Cottage. 1930s. Brick (stretcher bond); 1½ stories; 4 front asymmetrical bays; gable roof (slate); 1-story, 1-level, 1-bay porch with brick arched support with flared shed roof.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #69

Item number 7

Page 69

7. DESCRIPTION -- Inventory

WASHINGTON AVENUE

1200 BLOCK

130-6-407

1204: E. L. Evans House. Detached house. Queen Anne. 1880s. Wood frame (weatherboard-sides and rear) with brick (stretcher bond)-1st floor front and (wood shingle-2nd floor front); 2½ stories; 5 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 11-bay porch with turned posts, brackets, spindle frieze with cutout pattern woodwork above, geometric pattern stick balustrade, central gable with bull's-eye cornerblocks, rounded bays, corner tower, heavy bracketed cornice, significant decorative woodwork.

408

1205: Detached house. Vernacular. 1920s. Brick (stretcher bond); 2 stories; 6 front asymmetrical bays; hipped roof (flat tile); 1-story, 1-level, 3-bay porch with tapered square wood columns on brick piers, brick railing; broad overhanging eaves, entrance with sidelights.

409

1211: Detached house. Modified Queen Anne. ca. 1900. Wood frame (weatherboard); 2½ stories; 2 front asymmetrical bays; hipped roof (composition shingle); 1 front gable dormer; 1-story, 1-level, 8-bay wraparound porch with paired Tuscan columns on stone piers, gable over entrance bay; wide entrance with transom and sidelights.

410

1214: Detached house. Victorian Italianate. 1890s. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with Tuscan columns, turned balustrade; bracketed cornice with dentils, paired narrow windows with decorative heads.

1300 BLOCK

411

1300: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front asymmetrical bays; gable roof (standing seam metal); 2-story, 2-level, 3-bay porch with turned posts, decorative wood balustrade on 2nd floor, slender columns and simple balustrade on 1st floor.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #70

Item number 7

Page 70

7. DESCRIPTION -- Inventory

WILBORN AVENUE

500 BLOCK

1306-412 502: United Virginia Bank (originally). Fry, Jordan & Wilson, Inc. (currently). Commercial. Neoclassical. 1918. Dressed ashlar stone. 1 story; 1 front symmetrical bay; pedimented gable roof with parapet (not visible); fluted engaged Ionic columns, full entablature, full pedimented gable, Ionic pilasters

NR 504 \*504: Leggett Department Store. Commercial. Modern. 1960s. Brick (6-course American bond); 2 stories; multiple front asymmetrical bays; parapet flat roof (not visible). Noncontributing.

-413 523: The Professional Building. Commercial (offices). Vernacular. ca. 1910. Brick (stretcher bond); 2 stories; 5 front symmetrical bays; parapet flat roof (not visible); decorative yellow and red brickwork, altered storefront and upper fenestration.

-414 527: Hall's Variety Shop/Donald S. Barger CPA. Commercial. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; parapet flat roof (not visible); decorative brick cornice, altered storefront.

-415 530: Star Laundry. Commercial. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 3 front asymmetrical bays; parapet flat roof (not visible); decorative brickwork, altered storefront.

-416 532: Fred S. Black, Attorney at Law. Commercial (office). Vernacular. 1920s. Brick (stretcher bond); 1 story; 4 front asymmetrical bays; false mansard roof (composition shingle); probably originally served as service station, considerably altered facade.

600 BLOCK

-417 605-611: Country Kitchen/Granny's Collectibles. Commercial. Vernacular. ca. 1920. Brick (stretcher bond); 1 story; 8 front asymmetrical bays; parapet flat roof (not visible); decorative brick, tile and stucco details, altered storefronts, Mission-like parapet.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA

Continuation sheet #71

Item number 7

Page 71

7. DESCRIPTION -- Inventory

WILBORN AVENUE

700 BLOCK

130-6-418 701: Planters Warehouse. Warehouse. Vernacular. ca. 1900. Brick (5-course American bond); 2 stories; 14 front asymmetrical bays; parapet gable roof (not visible); recessed brick panels, decorative brickwork, stepped parapet, banked site, tall segmental-arched windows.

WILKERSON STREET

1300 BLOCK

419 1313: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 1 story; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts, spindle brackets; central front gable with decorative bargeboard.

420 1314: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with square wood columns; bracketed cornice with returns.

421 1315: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gambrel roof (standing seam metal); 1 front shed dormer; 1-story, 1-level, 5-bay porch with Tuscan columns; entrance with sidelights.

422 1319: Detached house. Vernacular. ca. 1910. Wood frame (weatherboard); 1½ stories; 3 front symmetrical bays; gambrel roof (standing seam metal); 1 front shed dormer; 1-story, 1-level, 5-bay porch with Tuscan columns.

423 1320: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (pressed tin); 1-story, 1-level, 3-bay porch with slender wood columns, dentil cornice; entrance with transom and sidelights.

424 1323: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only  
received  
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, VA  
Continuation sheet #72

Item number 7

Page 72

7. DESCRIPTION -- Inventory

WILKERSON STREET

1300 BLOCK (continued)

130-6-425

1324: Detached house. Vernacular. ca. 1900. Wood frame (weatherboard); 2 stories; 2 front asymmetrical bays; hipped roof (standing seam metal); 1-story, 1-level, 3-bay porch with slender wood columns, dentil cornice; entrance with transom and sidelights.

-426

1325: Detached house. Vernacular. 1890s. Wood frame (weatherboard); 2 stories; 3 front symmetrical bays; gable roof (standing seam metal); 1-story, 1-level, 3-bay porch with turned posts.

NA  
507

\*1329: Detached house. Vernacular. 1950s. Wood frame (aluminum siding); 1 story; 3 front asymmetrical bays; gable roof (composition shingle); 1-story, 1-level, 3-bay porch with wrought-iron supports. Noncontributing.

YANCEY STREET

500 BLOCK

-427

509: Detached house. Vernacular. 1920s. Wood frame (aluminum siding); 2 stories; 3 bays; gable roof (composition shingle); 1-story, 1-level, 1-bay porch with paired square columns and a gable roof.

-428

515: Carrington Memorial Library. Library. Colonial Revival. 1935. Brick (Flemish bond); 1 story; 3 front symmetrical bays; gable roof (slate); parapet gable ends with interior end chimneys, bracketed modillion cornice.

-429

523: Detached house. Cottage. 1930s. Brick (stretcher bond); 1½ stories; 3 asymmetrical bays; gable roof (composition shingle); 1 gable dormer.

130-6-431

529 Logan St.  
detached house, 1920s Am. 4 square.

130-6-0508 311 RAGLAND

# 8. Significance

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/ humanitarian
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> theater
<input checked="" type="checkbox"/> 1800-1899	<input checked="" type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> transportation
<input checked="" type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input checked="" type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input checked="" type="checkbox"/> other (specify)
		<input type="checkbox"/> invention		

**Specific dates** Mid-19th Century to 1930s  
**Builder/Architect** Various

**Statement of Significance (in one paragraph)**

## STATEMENT OF SIGNIFICANCE

The South Boston Historic District is representative of the City of South Boston's industrial, commercial, and residential development from the 19th century to the 1930s. From its modest beginnings as a depot on the Richmond and Danville Railroad in 1854, the city prospered from the 1870s to become in the early 20th century the second largest bright leaf tobacco market in the United States. Preserved in the district are a wealth of tobacco warehouses, factories and prizeries as well as related commercial and residential buildings associated with South Boston's golden age of tobacco trading. In addition to its historical importance, the district is significant for its late Victorian commercial and residential architecture and for its interesting variety of late 19th- and 20th-century vernacular dwellings.

## HISTORICAL BACKGROUND

South Boston traces its origins to a community established at Boyd's Ferry in Halifax County in 1796. The town did not develop as expected, however, due to occasional floods which inundated the low grounds on which it was situated.

Two major events -- the completion of the Richmond and Danville Railroad in 1854, and the construction of a covered bridge in 1858 precipitated the development of present-day South Boston. Prior to the completion of the railroad, the area contained only a few scattered residences. The arrival of the railroad in Halifax County opened the county's rich agricultural lands to the promise of eastern markets. In 1855, Captain E.B. Jeffress and the builder Josiah Dabbs constructed a brick storehouse and began a general merchandise business at "South Boston Depot" as the town became known. The following year, Captain Jeffress erected a hotel which became popular with travelers.

The Civil War halted the growth of the South Boston community. In 1870, W.B. Ellison of Milton, N.C. built the town's first tobacco warehouse and began buying leaf from growers. A second warehouse was built in 1871 by W.L. Wade who also conducted sales by public auction. Shortly thereafter, the construction of a number of other tobacco warehouses established the town as a tobacco trading center.

By 1884 the town's population had grown to 187, warranting its incorporation by the General Assembly on February 19, 1884 with the first mayor elected the following week. Prior to incorporation, the name of the settlement was changed from "South Boston Depot" to "South Boston."

The evaluation of South Boston's physical development by 1889 can be gleaned from a Sanborn Insurance Company map of the town, dated July of that year. The principal streets, Main, Broad, Factory and Ferry all had buildings that served the tobacco

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #73 Item number 8

Page /

8. SIGNIFICANCE -- Historical Background (continued)

industry. On Main Street were located the Edmondson Leaf Tobacco Warehouse, the Star Warehouse, the Shepherd & Edmondson Warehouse and the J.W. Easley Leaf Tobacco Warehouse. The warehouses were used for tobacco sales; therefore it is not surprising to find the town's largest hotels, the South Boston Hotel and White's Hotel, located on the same street as the warehouses. Tobacco prizeeries were found on Factory, Ferry, and Broad streets, with the largest, the Edmondson Tobacco Company prizeery located on Broad Street.

The prominence of the tobacco industry in South Boston stemmed from a number of factors. First and foremost was the town's strategic location within Halifax County, which, prior to the Civil War, had ranked near the top of the tobacco growing counties in Virginia. In addition to the growing of tobacco, the county was also the home of the Slate Seed Company, for many years the largest producer of tobacco seed in the world. The company was founded in 1867 by Major Robert L. Ragland at his Halifax Farm and by 1916 was supplying 90% of the world's tobacco seed. With the growth of the Danville tobacco market after the Civil War, South Boston's position on the Richmond and Danville Railroad linked the town with Virginia's busiest market. By 1907, South Boston had become the second largest bright leaf tobacco market in the United States with over 13 million pounds sold. The tonnage of tobacco continued to rise and the town retained its number two ranking until the Great Depression.

Fortunately, a number of buildings associated with South Boston's thriving late 19th-century tobacco industry survive. The earliest building is the Bruce family tobacco warehouse. The brick, hipped roof structure is located on the Norfolk-Southern Railroad tracks and was built during the third quarter of the 19th century by the Bruce family of Berry Hill plantation. The warehouse was associated with the Richmond-Danville Railroad and was used to store the tobacco harvested at Berry Hill before it was transported to market. It is now owned by the railroad which uses it for storage.

A number of tobacco factories survive from South Boston's boom tobacco period. The factories are located in the southern end of the district near the railroad tracks. These include the former R.J. Reynolds factory, the former Liggett-Meyers factory and the Imperial tobacco factory. The buildings are one- and two-story structures constructed in brick and distinguished by corbeling. The buildings date to the late 19th century with additions made throughout the early 20th century.

While South Boston's early development was tied to tobacco, it was not the town's only industry. The Halifax Cotton Mill was founded in 1897 as the Century Cotton Mill. The mill first manufactured cotton yarns and within four years had undergone expansion. In 1914 the mill was purchased by local businessmen and the mill's name was changed to

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #74 Item number 8

Page 2

8. SIGNIFICANCE -- Historical Background (continued)

Halifax Cotton Mill. The industry continued to prosper and between 1924-27 added a weave room, bleachery, sewing room, warehouse and offices. The largest industrial plant in South Boston of its period, the factory is distinguished by a tower which originally served as the main entrance to the 1897 building. The mill continues to operate and is a principal factor in the damask table cloth field.

The Halifax Cotton Mill provided company housing for its workers in an area located in the southwest section of the town. The company's small, one-story dwellings were built to the rear of the factory on Summit Drive, McCanless, Bancroft, and Bermann streets. Many of the early 20th-century houses have been turned over to the workers and have been personalized through later additions and modifications.

With the tobacco boom there followed a rapid development in the town's commercial district. The 1889 Sanborn Insurance Company map indicates a number of small commercial buildings that included a bank, groceries, jewelers, a drug store, barber shop and bakers. Main street still boasts the town's heaviest concentration of commercial buildings, the earliest dating to the late 1880s and 1890s.

When it was built in 1888, the E.L. Evans Building was undoubtedly the most stylish storefront in South Boston. The two-story brick edifice is distinguished by an ornamental pressed brick cornice, the center plaque bearing the name, "E.L. Evans" and the date "1888." Presently abandoned, the structure retains its architectural detailing and integrity. Built within a few doors south of the Evans Building is the Planters and Merchants Bank of 1891. It stands as one of the most opulent structures in the commercial area and clearly reflects the prosperity of the tobacco planters and merchants who established it. Like the earlier Evans Building it has a pressed brick cornice and arched openings. It presently serves as an antique shop. Constructed adjacent to the Evans Building, the Parkinson Block was built in 1899. While its first-story facade has been altered, the structure retains its second-story lintels and cast-iron cornice. Its two-story height is typical of the turn-of-the-century commercial structures found on South Boston's Main and Arch streets and Wilborn Avenue, the core of the business district. A notable exception to the scale is 441 South Main Street, a three-story building. It is distinguished not so much by its cornice or elaborate brickwork, but rather its arched openings. The somewhat irregular corner site contributes greatly to its distinctive appearance.

For the most part the town's later 20th-century commercial buildings have retained the two-story scale established by the late 19th-century structures. In fact, many of the 20th-century buildings have corbeled brick facades, reminiscent of the older 19th-century stores. Unfortunately, insensitive changes have been made to several first-story facades.

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #75 Item number 8

Page 3

8. SIGNIFICANCE -- Historical Background (continued)

The chief landmark of the commercial district is the South Boston Municipal Building located at the corner of Main and Ferry streets. The imposing "U"-shaped building, erected in ca. 1910 epitomizes the town's rapid turn-of-the-century development. The main entrance is executed in the Neoclassical style, then the preferred style for civic architecture. An unusual feature is the circular belfry, which has lost its bell. Across the street from the municipal building is another Neoclassical building, the former United Virginia Bank Building of 1918. The bank with its temple form stands as the town's best example of 20th-century classicism.

Immediately adjacent to the late 19th- and early 20th-century commercial area is an architecturally interesting residential neighborhood which arose in the same period. Its houses represent a variety of building styles, reflecting varying economic levels of South Boston society.

What is traditionally believed to be the oldest house in South Boston and the district is the dwelling at 1319 Hodges Street. Built ca. 1840-1850, the one-story brick structure is South Boston's best example of vernacular Greek Revival. While other earlier dwellings may still survive incorporated within later structures, 1319 Hodges remains the only free-standing house in the district dating from the period of settlement.

A number of residences which were indicated on the Sanborn Insurance Company map as standing in 1889 remain in the district. Especially notable is a cohesive collection of late Victorian dwellings on Washington Avenue. The houses include late Italianate-style and Queen Anne-style residences. In this regard, the best example of a wood frame Italianate house is found at 1014 Washington Street. Its arched window hoods and bracketed cornice clearly distinguish it from similar houses of the same period within the district. Likewise, the E.L. Evans House at 1204 Washington Street is a fine representative example of the Queen Anne Style at its best. Built during the late 1880s, the imposing residence features elaborately detailed porches, pressed-brick ornamentation and an exceptional interior. The hooded pressed-brick fireplace in the main entrance hall, together with the interior woodwork, ranks this dwelling among the best of the Queen Anne style in Virginia. On the same block, 1002 Washington Street also stands as a classic Queen Anne residence. It has a fanciful first-story porch, corner tower and stained-glass windows. Fortunately, the house has been sensitively restored.

North Main Street has always been considered a fashionable address in South Boston. Much longer than Washington Avenue, it has an assortment of late 19th- and early 20th-century residences. 1319 North Main Street is a stylistically eclectic residence that shows the influence of the French Romanesque on the domestic architecture of South Boston. Its stone lintels, pyramidal-roofed tower and corbeled chimneys contribute to the architectural sophistication of this turn-of-the-century dwelling. Unfortunately, as is the case with much of the architecture of South Boston, the architect is not known. The Queen

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #76

Item number 8

Page 4

8. SIGNIFICANCE -- Historical Background (continued)

Anne style is also well represented on North Main Street. Varied examples may be found at 1304 N. Main, 1314 and 1413 North Main. The residences date to the turn of the century and were constructed on a very grand scale reflecting the town's prosperity at that time. North Main also boasts significant and varied examples of the Colonial Revival. The former Tucker C. Watkins House at 1146 North Main along with the residences at 1002 North Main and 1421 North Main are among the most important examples in the district. All were built before the Great Depression and reflect the town's prominent role in Virginia's tobacco and textile industries.

The historic district also includes numerous examples of the Bungalow style, American Foursquare and builders' vernacular. South Boston's mixture of very stylish residences with less ornate examples was noted by Wirt Johnson Carrington in A History of Halifax County, published in 1924:

"The streets are bordered with beautiful homes, large and small, old and new; some with extensive grounds ornamented with shrubs and flowers, others with greensward and forest trees, decorative plots of beauty everywhere, each vying with the other in attractiveness; and in the midst of it all activity and life, evidences of a growing town."

Fortunately for South Boston, growth has meant the preservation of the town's older buildings, resulting in the present historic district, one of the largest and architecturally interesting in Southside Virginia.

RCC

# 9. Major Bibliographical References (See Continuation Sheet #77)

Arnold, B. W. History of the Tobacco Industry in Virginia From 1860 to 1894.  
 Baltimore: The Johns Hopkins Press, 1897.

Carrington, Wirt J. A History of Halifax County. Baltimore: Regional  
 Publishing Co., 1969.

# 10. Geographical Data

Acreeage of nominated property approx. 262

Quadrangle name South Boston, VA

Quadrangle scale 1:24000

UTM References (See Continuation Sheet #81)

A 

1	7
---	---

6	8	7	6	2	0
---	---	---	---	---	---

4	0	6	4	7	1	0
---	---	---	---	---	---	---

  
 Zone Easting Northing

B 

1	7
---	---

6	8	7	9	5	0
---	---	---	---	---	---

4	0	6	4	4	0	0
---	---	---	---	---	---	---

  
 Zone Easting Northing

C 

1	7
---	---

6	8	8	1	5	0
---	---	---	---	---	---

4	0	6	3	7	6	0
---	---	---	---	---	---	---

D 

1	7
---	---

6	8	8	1	3	0
---	---	---	---	---	---

4	0	6	3	5	2	0
---	---	---	---	---	---	---

E 

1	7
---	---

6	8	7	9	4	0
---	---	---	---	---	---

4	0	6	3	1	4	0
---	---	---	---	---	---	---

F 

1	7
---	---

6	8	7	5	4	0
---	---	---	---	---	---

4	0	6	3	2	2	0
---	---	---	---	---	---	---

G 

1	7
---	---

6	8	7	5	8	0
---	---	---	---	---	---

4	0	6	2	8	6	0
---	---	---	---	---	---	---

H 

1	7
---	---

6	8	7	3	1	0
---	---	---	---	---	---

4	0	6	2	7	3	0
---	---	---	---	---	---	---

## Verbal boundary description and justification

VBD Refers to Map 1 of 2 (See Continuation Sheets #78)

## List all states and counties for properties overlapping state or county boundaries

state	N/A	code	county	N/A	code
-------	-----	------	--------	-----	------

state	N/A	code	county	N/A	code
-------	-----	------	--------	-----	------

# 11. Form Prepared By

name/title Division of Historic Landmarks Staff

organization Division of Historic Landmarks

date June 1986

street & number 221 Governor Street

telephone (804) 786-3143

city or town Richmond,

state Virginia 23219


# 12. State Historic Preservation Officer Certification

The evaluated significance of this property within the state is:

national  state  local

As the designated State Historic Preservation Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service.

State Historic Preservation Officer signature



H. Bryan Mitchell, Director

title Division of Historic Landmarks

date August 7, 1986

For NPS use only

I hereby certify that this property is included in the National Register

Keeper of the National Register

Attest:

Chief of Registration

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #77 Item number 9

Page 1

9. MAJOR BIBLIOGRAPHICAL REFERENCES

Cook, Kenneth, ed. South Boston, Virginia. Historical Sketches. South Boston:  
South Boston Steering Committee, 1984.

French, M. Map of South Boston, 1885.  
Virginia State Library Map Archives

Sanborn Insurance Company Maps of South Boston.  
Virginia State Library Map Archives, 1889; 1929.

Tilley, Nannie M. The Bright-Tobacco Industry, 1860-1929. Chapel Hill:  
University of North Carolina

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #78 Item number 10

Page 1

10. GEOGRAPHICAL DATA - Boundary Description

Beginning at a point (A) located at the SW corner of the intersection of Summit Drive and Edmunds Street; thence following the S side of Summit Drive to the SE corner of the lot at 506 Summit Drive; thence following the rear property lines of the lots on the S side of Summit Drive and the S property lines of the lots of 205 and 208 Bancroft Street to a point (B) at the NE corner of the lot at 140 Summit Drive; thence following the S side of Summit Drive to a point (C) opposite the NW corner of the intersection of Summit Drive and Railroad Avenue, thence following rear, S, and E property lines of the lots on the S side of Railroad Avenue to the point (D) at the terminus of Bruce Street; thence following the S side of Bruce Street to a point (E) opposite the NW corner of the intersection of Bruce and Factory streets; thence following the W side of Factory Street to the SW corner of the intersection of Factory Street and Seymour Drive; thence following the S side of Seymour Drive to the SW corner of the intersection of Seymour Drive and South Main Street; thence following the W side of South Main Street to a point (F) opposite the SW corner of the lot at 107 South Main Street; thence crossing said street and following the S property line of said lot to the SE corner of said lot; thence following the rear property lines of the lots on the E side of the 100-300 blocks of South Main Street (including the lots at 1015-1025 Arch Street) to a point on the S side of Charles Street; thence following S side of street to a point (G) opposite the SE corner of the lot at 1104 Charles Street; thence crossing said street and following the E and rear property lines of said lot to a point on the E side of Short Street; thence following E side of street to the SW corner of the lot at 437 Short Street; thence following the S side of said lot and the rear property lines of the lots on the E side of Short Street to a point (H) opposite the SW corner of the South Boston Post Office lot; thence crossing Broad Street and following the rear property lines of the post office lot and the Trinity Episcopal Church lot to a point opposite the SE corner of said church lot on the E side of Yancey Street; thence following said side of street and W side of the lot at 1219 Fenton Street to the SW corner of said lot; thence following the rear property lines of the lots on the S side of Fenton Street and the rear property lines of the lots at 300 and 306 Ellyson Avenue to the SW corner of the lot at 300 Ellyson Avenue; thence following the S property lines of the lots at 300 and 301 Ellyson Avenue to the SE corner of the lot at 301 Ellyson Avenue; thence following the rear property lines of the lots on the E side of Ellyson Avenue and the E side of the lot at 1408 Fenton Street to the NE corner of said lot; thence following the rear property lines of the lots on the N side of Jeffress Street to a point (I) on the W side of Fuller Avenue; thence following said side of Fuller Avenue to a point opposite the SW corner of the lot at 820 Traver Avenue; thence crossing Fuller Avenue and following the S property lines of the lot at 820 Traver Avenue and crossing Traver Avenue to the NW corner of the lot at 817 Traver Avenue; thence following the W and S property lines of said lot to the SE corner of said lot; thence following the rear property lines of the lots at 804 and 812 Grove Avenue to the SW corner of the lot at 804 Grove Avenue; thence following the S property lines of the lots at 804 and 809 Grove Avenue to the SE corner of the lot at 809 Grove Avenue; thence following the rear property lines of the lots on the E side of Grove Avenue N of the lot at 809 Grove Avenue and crossing Lovelace Street to a point (J) on the N side of said street; thence following the N side of Lovelace Street to the NE corner of the intersection of Lovelace Street and Grove Avenue; thence following the E side of Grove Avenue to the SE corner of the intersection of Grove Avenue and Irish Street; thence

United States Department of the Interior  
National Park Service

For NPS use only

received

date entered

National Register of Historic Places  
Inventory—Nomination Form

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #79 Item number 10

Page 2

10. GEOGRAPHICAL DATA - Boundary Description (continued)

following the S side of Irish Street to a point (K) opposite the SE corner of the lot at 1612 Irish Street; thence crossing Irish Street and following the E property line of the lot at 1612 Irish Street to the NE corner of said lot; thence following the rear property lines of the lots on the N side of the 1300-1600 blocks of Irish Street to the NW corner of the lot at 1113 North Main Street; thence following the east side of North Main Street and crossing Bernard Street to the SW corner of the lot at 1129 North Main Street; thence following the rear property lines of the lots on the S side of the 1300-1400 blocks of Hodges Street to the SE corner of the lot at 1419 Hodges Street; thence following the E property line of said lot, crossing Hodges Street and following the E and rear property lines of the lot at 1412 Hodges Street to the NW corner of said lot; thence following the rear property lines of the lots on the E side of Peach Avenue and crossing Moore Street to a point (L) on the N side of Moore Street; thence following the N side of said street to the SE corner of the lot at 1420 Moore Street; thence following the E and rear property lines of said lot and the rear property lines of the lots at 1408, 1404, 1400, and 1332 Moore Street to the SE corner of the lot at 1607 North Main Street; thence following the rear property lines of the lots on the E side of North Main Street N of the lot at 1607 North Main Street to the NE corner of the lot at 1733 North Main Street; thence following the N property line of said lot and crossing North Main Street to a point (M) on the W side of said street; thence following the W side of said street to the NE corner of the lot at 1818 North Main Street; thence following N property line of said lot to the NW corner of said lot; thence following the rear property lines of the lots on the W side of North Main Street S of the lot at 1818 North Main Street to the SW corner of the lot at 1216 North Main Street; thence following the rear property lines of the lots at 1204 and 1202 Sixth Street and crossing Washington Avenue to a point (N) on the W side of Washington Avenue; thence following said side of street to the NE corner of the lot at 1300 Washington Avenue; thence following the N and W property lines of said lot and crossing Sixth Street to a point (O) on the S side of said street; thence following the N property line of the lot at 1214 Washington Avenue to the NW corner of said lot; thence following the rear property lines of the lots on the W side of Washington Avenue to the SW corner of the lot at 1014 Washington Avenue; thence crossing Randolph Avenue and following the rear property lines of the lots at 1016, 1010, 1002, 526, 522, 520, and 508 Third Street to the NW corner of the lot at 508 Third Street; thence following the W property lines of the lots at 508 and 509 Third Street to a point (P) on the rear property line of the lot at 538 Logan Street; thence following the rear property lines of the lots on the N side of Logan Street W of the lot at 538 Logan Street to the NW corner of the lot at 508 Logan Street; thence following the W property line of said lot, crossing Logan Street, and following the W property line of the lot at 509 Logan Street to the SW corner of said lot; thence following the rear property lines of the lots on the S side of Logan Street to a point (Q) on the W side of Jefferson Street; thence crossing Jefferson Street, following the S property line of the lot at 812 Jefferson Street, and crossing Broad Street to the SE corner of the lot at 1011 Logan Street; thence following the E property line of said lot to the NE corner of said lot; thence following the S side of Logan Street

**United States Department of the Interior  
National Park Service**

**National Register of Historic Places  
Inventory—Nomination Form**

For NPS use only
received
date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia

Continuation sheet #80

Item number 10

Page 3

10. GEOGRAPHICAL DATA - Boundary Description (continued)

to the SW corner of the intersection of Logan Street and Randolph Avenue; thence following the W side of Randolph Avenue to a point (R) opposite the SW corner of the lot at 823 Randolph Avenue; thence crossing Randolph Avenue and following the S property line of said lot to the SE corner of said lot; thence following the rear property lines of the lots at 823 and 901 Randolph Avenue, and the rear property lines of the lots in the 1100 and 1200 blocks (S side) of Third Street to the SW corner of the lot at 908 North Main Street; thence following the rear property lines of the lots of 838, 836, 818 North Main Street and the First Presbyterian Church lot to a point (S) on the N side of Second Street; thence following the N side of Second Street and crossing Washington Avenue to the SE corner of the lot at 1118 Second Street; thence following the E property line of said lot to the NE corner of said lot; thence following the rear property lines of the lots at 1118, 1114, 1110, 1104, and 1102 Second Street to the NW corner of the lot at 1102 Second Street; thence following the W property line of the lot at 1102 Second Street and crossing said street to a point (T) on the S side of Second Street; thence following the S side of Second Street to a point (U) at the NW corner of the lot at 1121 Second Street; thence following the W property line of the lot at 1121 Second Street and the rear property lines of the lots at 624, 622, 616, and 600 North Main Street; thence crossing Broad Street and following the rear property lines of the lots at 548 and 544 North Main Street to the E side of an alley between ~~512~~ <sup>and</sup> ~~540~~ <sup>512</sup> North Main Street; thence following the E side of said alley and the ~~E~~ <sup>and</sup> property lines of the lot at 701 Wilborn Avenue to a point (V) on the S side of First Street; thence following the S side of First Street and crossing Wilborn Avenue; thence following the W side of Wilborn Avenue to the NE corner of the lot at 532 Wilborn Avenue; thence following the N and rear property lines of said lot to the SW corner of said lot; thence following the rear property lines of the lots on the N side of the 300 and 200 blocks of Ferry Street to the SE corner of the lot containing a brick warehouse on the S side of Ragland Street; thence following the E and N property lines of said lot to the terminus of Ragland Street; thence following the railroad right-of-way NW to the terminus of Mineral Street; thence following the S, E, and N property lines of the lot containing the Sale Knitting Company to the railroad right-of-way; thence following the said right-of-way to a point (W) opposite the NE corner of the improved lots on the N side of Railroad Avenue; thence following the easternmost property line of the lots on the N side of Railroad Avenue to a point (X) on the N side of Railroad Avenue; thence following said side of Railroad Avenue to the N corner of the intersection of Railroad Avenue and Edmunds Street; thence crossing Railroad Avenue and following the S side of Edmunds Street to the point of origin.

Boundary Justification

The South Boston Historic District generally contains the largest concentration of historic buildings in the city dating from the mid-19th century to the 1930s. The industrial area located in the southwestern region of the district contains the entire Halifax Cotton Mill/company town complex, excludes a wooded area between the railroad warehouse area and the company town, and includes all the historic buildings associated with the tobacco industry on both sides of the railroad and along Ferry Street, Factory Street, and Seymour Drive.

United States Department of the Interior  
National Park Service

National Register of Historic Places  
Inventory—Nomination Form

For NPS use only

received

date entered

SOUTH BOSTON HISTORIC DISTRICT, South Boston, Virginia  
Continuation sheet #81 Item number 10

Page 4

10. GEOGRAPHICAL DATA - Boundary Justification (continued)

Nearly all of the downtown commercial area of South Boston was included in the district along North and South Main streets and Wilborn Avenue. Areas to the south and east of the 100 block of South Main Street as well as on both sides of Broad Street were excluded from the district because of the large number of vacant lots, parking lots, and noncontributing buildings in these areas. The area north of the 700 block of Wilborn Avenue was also excluded due to a large number of noncontributing buildings.

The residential area of the district extends primarily along North Main Street and as far north as the 800 block. North of the district's northernmost boundary is an area with fewer concentrations of historic buildings and a large number of vacant lots. The residential area east of the district boundaries on Moore, Hodges, Irish, and Fenton streets as well as the residential area west of North Main, Washington, and Third streets contain mostly noncontributing buildings. A small residential area south of Third and Logan streets was excluded from the district because it contains mostly buildings dating from the 1950s. The residential area northwest of Ferry Street was excluded from the district. It also contains a large number of noncontributing buildings, vacant lots, and several dilapidated structures of compromised integrity.


UTMS (continued)


I-17/687160/4062670  
K-17/686880/4062710  
M-17/686340/4062850  
O-17/686880/4063130  
Q-17/687220/4063680  
S-17/687500/4064080

J-17/686990/4062930  
L-17/686630/4062700  
N-17/686370/4063280  
P-17/687180/4063180  
R-17/687440/4063950  
T-17/687450/4064750

SOUTH BOSTON HISTORIC DISTRICT  
South Boston (city), VA

SKETCH MAP                      Map 1 of 2  
Source: City of South Boston  
Date: 1978  
Scale: 1" = 300'






**BUILDING CONDITIONS**

- SOUND
- WITH DEFICIENCIES
- SUBSTANDARD
- NONCONTRIBUTING ELEMENTS
- DISTRICT BOUNDARIES

A X





1204  
1116  
1108  
1102  
1100  
1014  
1100 1002

1146  
1130  
1118  
1112  
1106  
1100  
1002

1208  
1319  
1329  
1331  
1401  
1403  
1419  
1417  
1413  
1409  
1403  
1404  
1406  
1408  
1502  
504

1612  
1610  
1612  
1610


913  
1113  
1117  
1119  
907  
901  
823  
1102  
1104  
1110  
1114  
1118

1001  
915  
909  
905  
1001  
1311  
1319  
1315  
1323  
1325  
1320  
1328  
1339  
1332  
1338  
1324  
1320  
1318  
1323  
1314  
1312  
1321  
1325  
1329  
1333  
1337  
1341  
1347  
1340  
1336  
1330  
1326  
1322  
1318  
1314  
1310  
1306  
1302  
1298  
1294  
1290  
1286  
1282  
1278  
1274  
1270  
1266  
1262  
1258  
1254  
1250  
1246  
1242  
1238  
1234  
1230  
1226  
1222  
1218  
1214  
1210  
1206  
1202  
1198  
1194  
1190  
1186  
1182  
1178  
1174  
1170  
1166  
1162  
1158  
1154  
1150  
1146  
1142  
1138  
1134  
1130  
1126  
1122  
1118  
1114  
1110  
1106  
1102  
1098  
1094  
1090  
1086  
1082  
1078  
1074  
1070  
1066  
1062  
1058  
1054  
1050  
1046  
1042  
1038  
1034  
1030  
1026  
1022  
1018  
1014  
1010  
1006  
1002  
998  
994  
990  
986  
982  
978  
974  
970  
966  
962  
958  
954  
950  
946  
942  
938  
934  
930  
926  
922  
918  
914  
910  
906  
902  
898  
894  
890  
886  
882  
878  
874  
870  
866  
862  
858  
854  
850  
846  
842  
838  
834  
830  
826  
822  
818  
814  
810  
806  
802  
798  
794  
790  
786  
782  
778  
774  
770  
766  
762  
758  
754  
750  
746  
742  
738  
734  
730  
726  
722  
718  
714  
710  
706  
702  
698  
694  
690  
686  
682  
678  
674  
670  
666  
662  
658  
654  
650  
646  
642  
638  
634  
630  
626  
622  
618  
614  
610  
606  
602  
598  
594  
590  
586  
582  
578  
574  
570  
566  
562  
558  
554  
550  
546  
542  
538  
534  
530  
526  
522  
518  
514  
510  
506  
502  
498  
494  
490  
486  
482  
478  
474  
470  
466  
462  
458  
454  
450  
446  
442  
438  
434  
430  
426  
422  
418  
414  
410  
406  
402  
398  
394  
390  
386  
382  
378  
374  
370  
366  
362  
358  
354  
350  
346  
342  
338  
334  
330  
326  
322  
318  
314  
310  
306  
302  
298  
294  
290  
286  
282  
278  
274  
270  
266  
262  
258  
254  
250  
246  
242  
238  
234  
230  
226  
222  
218  
214  
210  
206  
202  
198  
194  
190  
186  
182  
178  
174  
170  
166  
162  
158  
154  
150  
146  
142  
138  
134  
130  
126  
122  
118  
114  
110  
106  
102  
98  
94  
90  
86  
82  
78  
74  
70  
66  
62  
58  
54  
50  
46  
42  
38  
34  
30  
26  
22  
18  
14  
10  
6  
2

911  
907  
905  
901  
837  
835  
831  
827  
823  
817  
910  
900  
820  
812  
804  
913 K  
903 J  
827  
819  
817  
815  
809

624  
622  
616  
600  
548  
539  
449-51  
447  
443  
437  
435  
429  
427  
1104  
323  
317  
313  
309  
1023  
1025  
231  
225  
217  
213  
209-11  
205  
115  
87

838  
836  
834  
832  
829  
825  
811  
807  
803  
801  
709  
707  
705  
703  
701  
523  
515  
509  
1216  
1218  
1228  
1219  
1223  
1225  
1227  
1229  
1231  
1233  
1235  
1237  
1239  
1241  
1243  
1245  
1247  
1249  
1251  
1253  
1255  
1257  
1259  
1261  
1263  
1265  
1267  
1269  
1271  
1273  
1275  
1277  
1279  
1281  
1283  
1285  
1287  
1289  
1291  
1293  
1295  
1297  
1299  
1301  
1303  
1305  
1307  
1309  
1311  
1313  
1315  
1317  
1319  
1321  
1323  
1325  
1327  
1329  
1331  
1333  
1335  
1337  
1339  
1341  
1343  
1345  
1347  
1349  
1351  
1353  
1355  
1357  
1359  
1361  
1363  
1365  
1367  
1369  
1371  
1373  
1375  
1377  
1379  
1381  
1383  
1385  
1387  
1389  
1391  
1393  
1395  
1397  
1399  
1401  
1403  
1405  
1407  
1409  
1411  
1413  
1415  
1417  
1419  
1421  
1423  
1425  
1427  
1429  
1431  
1433  
1435  
1437  
1439  
1441  
1443  
1445  
1447  
1449  
1451  
1453  
1455  
1457  
1459  
1461  
1463  
1465  
1467  
1469  
1471  
1473  
1475  
1477  
1479  
1481  
1483  
1485  
1487  
1489  
1491  
1493  
1495  
1497  
1499  
1501  
1503  
1505  
1507  
1509  
1511  
1513  
1515  
1517  
1519  
1521  
1523  
1525  
1527  
1529  
1531  
1533  
1535  
1537  
1539  
1541  
1543  
1545  
1547  
1549  
1551  
1553  
1555  
1557  
1559  
1561  
1563  
1565  
1567  
1569  
1571  
1573  
1575  
1577  
1579  
1581  
1583  
1585  
1587  
1589  
1591  
1593  
1595  
1597  
1599  
1601  
1603  
1605  
1607  
1609  
1611  
1613  
1615  
1617  
1619  
1621  
1623  
1625  
1627  
1629  
1631  
1633  
1635  
1637  
1639  
1641  
1643  
1645  
1647  
1649  
1651  
1653  
1655  
1657  
1659  
1661  
1663  
1665  
1667  
1669  
1671  
1673  
1675  
1677  
1679  
1681  
1683  
1685  
1687  
1689  
1691  
1693  
1695  
1697  
1699  
1701  
1703  
1705  
1707  
1709  
1711  
1713  
1715  
1717  
1719  
1721  
1723  
1725  
1727  
1729  
1731  
1733  
1735  
1737  
1739  
1741  
1743  
1745  
1747  
1749  
1751  
1753  
1755  
1757  
1759  
1761  
1763  
1765  
1767  
1769  
1771  
1773  
1775  
1777  
1779  
1781  
1783  
1785  
1787  
1789  
1791  
1793  
1795  
1797  
1799  
1801  
1803  
1805  
1807  
1809  
1811  
1813  
1815  
1817  
1819  
1821  
1823  
1825  
1827  
1829  
1831  
1833  
1835  
1837  
1839  
1841  
1843  
1845  
1847  
1849  
1851  
1853  
1855  
1857  
1859  
1861  
1863  
1865  
1867  
1869  
1871  
1873  
1875  
1877  
1879  
1881  
1883  
1885  
1887  
1889  
1891  
1893  
1895  
1897  
1899  
1901  
1903  
1905  
1907  
1909  
1911  
1913  
1915  
1917  
1919  
1921  
1923  
1925  
1927  
1929  
1931  
1933  
1935  
1937  
1939  
1941  
1943  
1945  
1947  
1949  
1951  
1953  
1955  
1957  
1959  
1961  
1963  
1965  
1967  
1969  
1971  
1973  
1975  
1977  
1979  
1981  
1983  
1985  
1987  
1989  
1991  
1993  
1995  
1997  
1999  
2001  
2003  
2005  
2007  
2009  
2011  
2013  
2015  
2017  
2019  
2021  
2023  
2025  
2027  
2029  
2031  
2033  
2035  
2037  
2039  
2041  
2043  
2045  
2047  
2049  
2051  
2053  
2055  
2057  
2059  
2061  
2063  
2065  
2067  
2069  
2071  
2073  
2075  
2077  
2079  
2081  
2083  
2085  
2087  
2089  
2091  
2093  
2095  
2097  
2099  
2101  
2103  
2105  
2107  
2109  
2111  
2113  
2115  
2117  
2119  
2121  
2123  
2125  
2127  
2129  
2131  
2133  
2135  
2137  
2139  
2141  
2143  
2145  
2147  
2149  
2151  
2153  
2155  
2157  
2159  
2161  
2163  
2165  
2167  
2169  
2171  
2173  
2175  
2177  
2179  
2181  
2183  
2185  
2187  
2189  
2191  
2193  
2195  
2197  
2199  
2201  
2203  
2205  
2207  
2209  
2211  
2213  
2215  
2217  
2219  
2221  
2223  
2225  
2227  
2229  
2231  
2233  
2235  
2237  
2239  
2241  
2243  
2245  
2247  
2249  
2251  
2253  
2255  
2257  
2259  
2261  
2263  
2265  
2267  
2269  
2271  
2273  
2275  
2277  
2279  
2281  
2283  
2285  
2287  
2289  
2291  
2293  
2295  
2297  
2299  
2301  
2303  
2305  
2307  
2309  
2311  
2313  
2315  
2317  
2319  
2321  
2323  
2325  
2327  
2329  
2331  
2333  
2335  
2337  
2339  
2341  
2343  
2345  
2347  
2349  
2351  
2353  
2355  
2357  
2359  
2361  
2363  
2365  
2367  
2369  
2371  
2373  
2375  
2377  
2379  
2381  
2383  
2385  
2387  
2389  
2391  
2393  
2395  
2397  
2399  
2401  
2403  
2405  
2407  
2409  
2411  
2413  
2415  
2417  
2419  
2421  
2423  
2425  
2427  
2429  
2431  
2433  
2435  
2437  
2439  
2441  
2443  
2445  
2447  
2449  
2451  
2453  
2455  
2457  
2459  
2461  
2463  
2465  
2467  
2469  
2471  
2473  
2475  
2477  
2479  
2481  
2483  
2485  
2487  
2489  
2491  
2493  
2495  
2497  
2499  
2501  
2503  
2505  
2507  
2509  
2511  
2513  
2515  
2517  
2519  
2521  
2523  
2525  
2527  
2529  
2531  
2533  
2535  
2537  
2539  
2541  
2543  
2545  
2547  
2549  
2551  
2553  
2555  
2557  
2559  
2561  
2563  
2565  
2567  
2569  
2571  
2573  
2575  
2577  
2579  
2581  
2583  
2585  
2587  
2589  
2591  
2593  
2595  
2597  
2599  
2601  
2603  
2605  
2607  
2609  
2611  
2613  
2615  
2617  
2619  
2621  
2623  
2625  
2627  
2629  
2631  
2633  
2635  
2637  
2639  
2641  
2643  
2645  
2647  
2649  
2651  
2653  
2655  
2657  
2659  
2661  
2663  
2665  
2667  
2669  
2671  
2673  
2675  
2677  
2679  
2681  
2683  
2685  
2687  
2689  
2691  
2693  
2695  
2697  
2699  
2701  
2703  
2705  
2707  
2709  
2711  
2713  
2715  
2717  
2719  
2721  
2723  
2725  
2727  
2729  
2731  
2733  
2735  
2737  
2739  
2741  
2743  
2745  
2747  
2749  
2751  
2753  
2755  
2757  
2759  
2761  
2763  
2765  
2767  
2769  
2771  
2773  
2775  
2777  
2779  
2781  
2783  
2785  
2787  
2789  
2791  
2793  
2795  
2797  
2799  
2801  
2803  
2805  
2807  
2809  
2811  
2813  
2815  
2817  
2819  
2821  
2823  
2825  
2827  
2829  
2831  
2833  
2835  
2837  
2839  
2841  
2843  
2845  
2847  
2849  
2851  
2853  
2855  
2857  
2859  
2861  
2863  
2865  
2867  
2869  
2871  
2873  
2875  
2877  
2879  
2881  
2883  
2885  
2887  
2889  
2891  
2893  
2895  
2897  
2899  
2901  
2903  
2905  
2907  
2909  
2911  
2913  
2915  
2917  
2919  
2921  
2923  
2925  
2927  
2929  
2931  
2933  
2935  
2937  
2939  
2941  
2943  
2945  
2947  
2949  
2951  
2953  
2955  
2957  
2959  
2961  
2963  
2965  
2967  
2969  
2971  
2973  
2975  
2977  
2979  
2981  
2983  
2985  
2987  
2989  
2991  
2993  
2995  
2997  
2999  
3001  
3003  
3005  
3007  
3009  
3011  
3013  
3015  
3017  
3019  
3021  
3023  
3025  
3027  
3029  
3031  
3033  
3035  
3037  
3039  
3041  
3043  
3045  
3047  
3049  
3051  
3053  
3055  
3057  
3059  
3061  
3063  
3065  
3067  
3069  
3071  
3073  
3075  
3077  
3079  
3081  
3083  
3085  
3087  
3089  
3091  
3093  
3095  
3097  
3099  
3101  
3103  
3105  
3107  
3109  
3111  
3113  
3115  
3117  
3119  
3121  
3123  
3125  
3127  
3129  
3131  
3133  
3135  
3137  
3139  
3141  
3143  
3145  
3147  
3149  
3151  
3153  
3155  
3157  
3159  
3161  
3163  
3165  
3167  
3169  
3171  
3173  
3175  
3177  
3179  
3181  
3183  
3185  
3187  
3189  
3191  
3193  
3195  
3197  
3199  
3201  
3203  
3205  
3207  
3209  
3211  
3213  
3215  
3217  
3219  
3221  
3223  
3225  
3227  
3229  
3231  
3233  
3235  
3237  
3239  
3241  
3243  
3245  
3247  
3249  
3251  
3253  
3255  
3257  
3259  
3261  
3263  
3265  
3267  
3269  
3271  
3273  
3275  
3277  
3279  
3281  
3283  
3285  
3287  
3289  
3291  
3293  
3295  
3297  
3299  
3301  
3303  
3305  
3307  
3309  
3311  
3313  
3315  
3317  
3319  
3321  
3323  
3325  
3327  
3329  
3331  
3333  
3335  
3337  
3339  
3341  
3343  
3345  
3347  
3349  
3351  
3353  
3355  
3357  
3359  
3361  
3363  
3365  
3367  
3369  
3371  
3373  
3375  
3377  
3379  
3381  
3383  
3385  
3387  
3389  
3391  
3393  
3395  
3397  
3399  
3401  
3403  
3405  
3407  
3409  
3411  
3413  
3415  
3417  
3419  
3421  
3423  
3425  
3427  
3429  
3431  
3433  
3435  
3437  
3439  
3441  
3443  
3445  
3447  
3449  
3451  
3453  
3455  
3457  
3459  
3461  
3463  
3465  
3467  
3469  
3471  
3473  
3475  
3477  
3479  
3481  
3483  
3485  
3487  
3489  
3491  
3493  
3495  
3497  
3499  
3501  
3503  
3505  
3507  
3509  
3511  
3513  
3515  
3517  
3519  
3521  
3523  
3525  
3527  
3529  
3531  
3533  
3535  
3537  
3539  
3541  
3543  
3545  
3547  
3549  
3551  
3553  
3555  
3557  
3559  
3561  
3563  
3565  
3567  
3569  
3571  
3573  
3575  
3577  
3579  
3581  
3583  
3585  
3587  
3589  
3591  
3593  
3595  
3597  
3599  
3601  
3603  
3605  
3607  
3609  
3611  
3613  
3615  
3617  
3619  
3621  
3623  
3625  
3627  
3629  
3631  
3633  
3635  
3637  
3639  
3641  
3643  
3645  
3647  
3649  
3651  
3653  
3655  
3657  
3659  
3661  
3663  
3665  
3667  
3669  
3671  
3673  
3675  
3677  
3679  
3681  
3683  
3685  
3687  
3689  
3691  
3693  
3695  
3697  
3699  
3701  
3703  
3705  
3707  
3709  
3711  
3713  
3715  
3717  
3719  
3721  
3723  
3725  
3727  
3729  
3731  
3733  
3735  
3737  
3739  
3741  
3743  
3745  
3747  
3749  
3751  
3753  
3755  
3757  
3759  
3761  
3763  
3765  
3767  
3769  
3771  
3773  
3775  
3777  
3779  
3781  
3783  
3785  
3787  
3789  
3791  
3793  
3795  
3797  
3799  
3801  
3803  
3805  
3807  
3809  
3811  
3813  
3815  
3817  
3819  
3821  
3823  
3825  
3827  
3829  
3831  
3833  
3835  
3837  
3839  
3841  
3843  
3845  
3847  
3849  
3851  
3853  
3855  
3857  
3859  
3861  
3863  
3865  
3867  
3869  
3871  
3873  
3875  
3877  
3879  
3881  
3883  
3885  
3887  
3889  
3891  
3893  
3895  
3897  
3899  
3901  
3903  
3905  
3907  
3909  
3911  
3913  
3915  
3917  
3919  
3921  
3923  
3925  
3927  
3929  
3931  
3933  
3935  
3937  
3939  
3941  
3943  
3945  
3947  
3949  
3951  
3953  
3955  
3957  
3959  
3961  
3963  
3965  
3967  
3969  
3971  
3973  
3975  
3977  
3979  
3981  
3983  
3985  
3987  
3989  
3991  
3993  
3995  
3997  
3999  
4001  
4003  
4005  
4007  
4009  
4011  
4013  
4015  
4017  
4019  
4021  
4023  
4025  
4027  
4029  
4031  
4033  
4035  
4037  
4039  
4041  
4043  
4045  
4047  
4049  
4051  
4053  
4055  
4057  
4059  
4061  
4063  
4065  
4067  
4069  
4071  
4073  
4075  
4077  
4079  
4081  
4083  
4085  
4087  
4089  
4091  
4093  
4095  
4097  
4099  
4101  
4103  
4105  
4107  
4109  
4111  
4113  
4115  
4117  
4119  
4121  
4123  
4125  
4127  
4129  
4131  
4133  
4135  
4137  
4139  
4141  
4143  
4145  
4147  
4149  
4151  
4153  
4155  
4157  
4159  
4161  
4163  
4165  
4167  
4169  
4171  
4173  
4175  
4177  
4179  
4181  
4183  
4185  
4187  
4189  
4191  
4193  
4195  
4197  
4199  
4201  
4203  
4205  
4207  
4209  
4211  
4213  
4215  
4217  
4219  
4221  
4223  
4225  
4227  
4229  
4231  
4233  
4235  
4237  
4239  
4241  
4243  
4245  
4247  
4249  
4251  
4253  
4255  
4257  
4259  
4261  
4263  
4265  
4267  
4269  
4271  
4273  
4275  
4277  
4279  
4281  
4283  
4285  
4287  
4289  
4291  
4293  
4295  
4297  
4299  
4301  
4303  
4305  
4307  
4309  
4311  
4313  
4315  
4317  
4319  
4321  
4323  
4325  
4327  
4329  
4331  
4333  
4335  
4337  
4339  
4341  
4343  
4345  
4347  
4349  
4351  
4353  
4355  
4357  
4359  
4361  
4363  
43



1808    
 1806    
 1804    
 HILL ST   
 1728    
 1724    
 1716    
 1712    
 1708    
 1706    
 1702    
 PUBLIC PLAYGROUND

COLLEGE ST.   
 1616    
 1612    
 1608    
 1606    
 1602    
 1615    
 1607    
 1601    
 1511    
 1505    
 1311    
 1313    
 1317    
 1321    
 1325    
 1400    
 1404    
 1408    
 1420

1508    
 1502    
 1500    
 1420    
 1414    
 1410    
 1408    
 1404    
 MOORE ST.   
 1420    
 1416    
 1414    
 1406    
 1423    
 1421    
 1407    
 1403    
 1401

EDMUNDS ST.   
 1322    
 1318    
 1314    
 1304    
 1228    
 1222    
 1202    
 1204    
 1216    
 1206    
 BARBOUR ST.   
 1318    
 1314    
 1312    
 1308    
 1306    
 1302    
 1319    
 1315    
 1311    
 1309    
 1327    
 1323    
 1320    
 1314    
 1312    
 1308    
 1304    
 1302

WILKERSON ST.   
 1225    
 1219    
 1215    
 1203    
 1224    
 1220    
 1212    
 1208    
 1223    
 1221    
 1217    
 1213    
 1209    
 1201

SIXTH ST.   
 1214    
 1204    
 1116    
 1108    
 1102    
 1100    
 1014    
 1100    
 1211    
 1205    
 1121    
 1119    
 1115    
 1109    
 1107    
 1105    
 1103    
 1001    
 1146    
 1130    
 1118    
 1112    
 1106    
 1100    
 1002

BERNARD ST.   
 1113    
 1103    
 1001    
 915    
 909    
 905    
 1135    
 1131    
 1129    
 1319    
 1329    
 1331    
 1401    
 1403    
 1409    
 1413    
 1417    
 1419

IRISH ST.   
 911    
 907    
 905    
 901    
 837    
 835    
 831    
 827    
 822    
 1328    
 1324    
 1320    
 1318    
 1314    
 1312    
 1308    
 1304    
 1302    
 1325    
 1329    
 1333    
 1337    
 1341    
 1347

SHEPHERD ST.   
 837    
 833    
 829    
 825    
 1311    
 1313    
 1317    
 1321    
 1325    
 1329    
 1333    
 1337    
 1341    
 1347

1733    
 1727    
 1725    
 1721    
 1715

1420    
 1416    
 1414    
 1406    
 1423    
 1421    
 1407    
 1403    
 1420    
 1416    
 1414    
 1406    
 1423    
 1421    
 1407    
 1403


1318    
 1314    
 1312    
 1308    
 1306    
 1302    
 1319    
 1315    
 1311    
 1309    
 1327    
 1323    
 1320    
 1314    
 1312    
 1308    
 1304    
 1302

1225    
 1219    
 1215    
 1203    
 1224    
 1220    
 1212    
 1208

1408    
 1406    
 1404    
 1502    
 504

1612    
 1610    
 1502    
 504    
 1408    
 1406    
 1404    
 1502    
 504    
 1612    
 1610

HILL AV.   
 SOUTH AV.   
 913    
 903    
 827    
 919    
 817    
 815    
 910    
 900    
 820    
 812    
 800    
 911    
 907    
 905    
 901    
 837    
 835    
 831    
 827    
 822    
 1311    
 1313    
 1317    
 1321    
 1325    
 1329    
 1333    
 1337    
 1341    
 1347



USGS 7.5' quadrangle (scale:1:24000)  
 South Boston, VA 1969 (PR 1981)

SOUTH BOSTON HISTORIC DISTRICT,  
 South Boston (city), VA Map 2 of 2

- UTM References:
- |                     |                     |
|---------------------|---------------------|
| A-17/687620/4064710 | B-17/687950/4064400 |
| C-17688150/4063760  | D-17/688130/4063520 |
| E-17/687940/4063140 | F-17/687540/4063220 |
| G-17/687580/4062860 | H-17/687310/4062730 |
| I-17/687160/4062670 | J-17/686990/4062930 |
| K-17/686880/4062710 | L-17/686630/4062700 |
| M-17/686340/4062850 | N-17/686370/4063280 |
| O-17/686880/4063130 | P-17/687180/4063180 |
| Q-17/687220/4063680 | R-17/687440/4063950 |
| S-17/687500/4064080 | T-17/687450/4064750 |

SOUTH BOSTON CITY  
 HALIFAX CO  
 RIVER

JOHN H. KERR

RESERVOIR

4064  
 4063  
 (OMEGA)  
 3257 III NE LARKSVILLE 19 M