

VLR-9/10/03 NRHP-1/16/04

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
REGISTRATION FORM

This form is for use in nominating or requesting determinations for individual properties or districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "X" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and areas of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900a). Use a typewriter, word processor, or computer, to complete all items.

1. Name of Property

Historic name: WEST END HISTORIC DISTRICT

Other names/site number: (VDHR File Number 133-5040)

2. Location

Street & Number: Roughly bounded by Causey Avenue, the Seaboard Coast Lines Railroad tracks, Pender Street, Wellons Street, Linden Avenue, the Norfolk and Western Railroad tracks, and Causey Avenue

City or town: Suffolk [N/A] Not for Publication [N/A] Vicinity

State: Virginia Code: VA County: Suffolk (Independent City) Code: 800 Zip Code: 23439

3. State/Federal Agency Certification

As the designated authority under the National Historic Preservation Act, as amended, I hereby certify that this [X] nomination [] request for determination of eligibility meets the documentation standards for registering properties in the National Register of Historic Places and meets the procedural and professional requirements set forth in 36 CFR Part 60. In my opinion, the property [X] meets [] does not meet the National Register criteria. I recommend that this property be considered significant [] nationally [] statewide [X] locally. ([] See continuation sheet for additional comments.)

Signature of certifying official/Title

Date

Virginia Department of Historic Resources

State or Federal agency and bureau

In my opinion, the property [] meets [] does not meet the National Register criteria. ([] See continuation sheet for additional comments.)

Signature of certifying official/Title

Date

State or Federal agency and bureau

4. National Park Service Certification

I hereby certify that this property is

[] entered in the National Register

() see continuation sheet

[] determined eligible for the National Register

() see continuation sheet

[] determined not eligible for the National Register

[] removed from the National Register

[] other, (explain):

Signature of the Keeper

Date of Action

United States Department of the Interior
National Park Service

WEST END HISTORIC DISTRICT

SUFFOLK, VA

Name of Property

County and State

5. Classification

Ownership of Property	Category of Property	No. Resources within Property		
		Contributing	Noncontributing	
☒ Private	☐ Building(s)			
☐ Public-Local	☒ District	<u>193</u>	<u>42</u>	Buildings
☐ Public-State	☐ Site	<u>0</u>	<u>0</u>	Sites
☐ Public-Federal	☐ Structure	<u>93</u>	<u>69</u>	Structures
	☐ Object	<u>0</u>	<u>0</u>	Objects
		<u>286</u>	<u>111</u>	Total

Name of related multiple property listing
N/A

Number of contributing Resources previously listed in the National Register 0

6. Function or Use

Historic Functions (enter categories from instructions)	Current Functions (enter categories from instructions)
<u>DOMESTIC/single dwelling</u>	<u>DOMESTIC/single dwelling</u>
<u>DOMESTIC/secondary structure</u>	<u>DOMESTIC/secondary structure</u>
<u>COMMERCIAL/specialty store</u>	<u>COMMERCIAL/specialty store</u>
<u>COMMERCIAL/financial institution</u>	<u>COMMERCIAL/financial institution</u>
<u>RELIGION/religious facility</u>	<u>RELIGION/religious facility</u>
<u></u>	<u>FUNERARY/mortuary</u>
<u></u>	<u>VACANT/not in use</u>
<u></u>	<u>COMMERCE/TRADE/business</u>

7. Description

Architectural Classification (enter categories from instructions)

LATE VICTORIAN/Queen Anne

LATE VICTORIAN/Italianate

LATE 19th & 20th CENTURY REVIVALS/Colonial Revival

LATE 19th & 20th CENTURY REVIVALS/Tudor Revival

LATE 19th & 20th CENTURY REVIVALS/Classical Revival

LATE 19th & 20th CENTURY REVIVALS/ Late Gothic Revival

LATE 19th & 20th CENTURY AMERICAN MOVEMENT/Bungalow/Craftsman

Materials (enter categories from instructions)

Foundation: BRICK; CONCRETE

Walls: WOOD: Weatherboard, Shingle; BRICK; METAL: Aluminum; STUCCO; ASBESTOS;
CONCRETE; SYNTHETICS: Vinyl

Roof: METAL: Tin; ASPHALT; SLATE

Narrative Description

Describe the historic and current condition of the property on one or more continuation sheets
[X] See continuation sheet

United States Department of the Interior
National Park Service

WEST END HISTORIC DISTRICT

SUFFOLK, VA

Name of Property

County and State

8. Statement of Significance

Applicable National Register Criteria

(Mark x in one or more boxes for the criteria
qualifying the property for National Register listing.)

☒ **A** Property is associated with events that have
made a significant contribution to the broad patterns
of our history.

☐ **B** Property is associated with the lives of
persons significant in our past.

☒ **C** Property embodies the distinctive characteristics
of a type, period, or method of construction or represents
the work of a master, or possesses high artistic values, or
represents a significant and distinguishable entity whose
components lack individual distinction.

☐ **D** Property has yielded, or is likely to yield,
information important in prehistory or history.

Criteria Considerations

(Mark x in all the boxes that apply.)

☐ **A** owned by a religious institution or
used for religious purposes.

☐ **B** removed from its original location.

☐ **C** a birthplace or grave.

☐ **D** a cemetery.

☐ **E** a reconstructed building, object, or structure.

☐ **F** a commemorative property.

☐ **G** less than 50 years of age or achieved
significance within the past 50 years.

Narrative Statement of Significance

(Explain the significance of the property on one or more continuation sheets.)

☒ See continuation sheet

Areas of Significance

(Enter categories from instructions)

ARCHITECTURE

COMMUNITY PLANNING
AND DEVELOPMENT

Period of Significance

1865-1939

Significant Dates

1865

Significant Person

(Complete if Criterion B is marked above.)

N/A

Cultural Affiliation

N/A

Architect/Builder

Name of Property

County and State

9. Major Bibliographic References☒ See continuation sheet

Previous documentation on file (NPS):

☐ preliminary determination of
individual listing (36 CFR 67)☐ previously listed in the NR☐ previously determined eligible
by the National Register☐ designated a National Historic
Landmark☐ recorded by Historic American
Buildings Survey #.☐ recorded by Historic American
Engineering Record #_____

Primary location of additional data:

☒ State SHPO office☐ Other State agency☐ Federal agency☒ Local government☐ University☐ OtherSpecify repository:
_____**10. Geographical Data**Acreage of property 73.76 acres

UTM References

1) 11/8/ 3/5/7/8/8/5/ 4/0/6/6/2/7/4/
Zone Easting Northing2) 11/8/ 3/5/8/0/1/0/ 4/0/6/5/7/9/0/
Zone Easting Northing3) 11/8/ 3/5/7/7/1/3/ 4/0/6/5/3/5/5/
Zone Easting Northing4) 11/8/ 3/5/7/4/3/9/ 4/0/6/5/3/0/2/
Zone Easting Northing☒ See continuation sheet

Verbal Boundary Description

☒ See continuation sheet

Boundary Justification

☒ See continuation sheet**11. Form Prepared By**Name/title Jana E. Riggle and Laura V. Trieschmann, Architectural HistoriansOrganization EHT Traceries, Inc. Date April 2003Street & Number 1121 5th Street, NW Telephone (202) 393-1199City or Town Washington State D.C. Zip code 20001

**United States Department of the Interior
National Park Service**

WEST END HISTORIC DISTRICT

SUFFOLK, VA

Name of Property

County and State

Additional Documentation

Submit the following items with the completed form:

Continuation Sheets

Maps

A **USGS map** (7.5 or 15 minute series) indicating the property's location.

A **Sketch map** for historic districts and properties having large acreage or numerous resources.

Photographs

Representative **black and white photographs** of the property.

Additional items

(Check with the SHPO or FPO for any additional items)

Property Owner

(Complete this item at the request of the SHPO or FPO.)

name See attached list of property owners.
street & number _____ telephone _____
city or town _____ state _____ zip code _____

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 *et seq.*)

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of the Management and Budget, Paperwork Reductions Projects (1024-0018), Washington, DC 20503.

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 1

7. Description

SUMMARY DESCRIPTION

Set approximately four blocks west of the Suffolk Historic District, the West End is a residential neighborhood located within the City of Suffolk. The West End neighborhood is roughly bounded by the Seaboard Coast Line Railroad to the north, the Norfolk & Western Railroad (N & W) to the south, Linden Avenue, Wellons Street and Pender Street to the east, and Brewer Street and Causey Avenue on the west. The streets are laid out in a perpendicular grid pattern fronted by long rectangular housing lots. Linden Avenue is unique in that it is the widest street within the West End neighborhood and the only street divided by a landscaped median. The wood-frame and masonry dwellings are set back from the roads with sidewalks and landscaped yards buffering them from the public right-of-ways. Nearly all of the lots have driveways and freestanding garages.

The majority of the buildings in this neighborhood date from the last decade of the 19th century through the first four decades of the 20th century, and display the fashionable architectural styles of the period in which they were constructed. There are a few examples dating from the third quarter of the 19th century that proceed the area's major period of development. The dominant forms and styles, albeit vernacular, include Italianate, Queen Anne, Colonial Revival, Classical Revival, Tudor Revival, Bungalow/Craftsman, and American foursquare. Single-family dwellings dominated the area initially with a few multiple-family dwellings beginning to appear in the second quarter of the 20th century. The West End neighborhood is also home to several churches and some early- and late-20th-century commercial development.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 2

DETAILED DESCRIPTION

Early Development (1860 – 1899)

Dating from circa 1860, the earliest surviving dwelling within the West End neighborhood is located at 504 West Washington Street. Set near the road on a level grassy lot the dwelling is partially hidden from view by mature trees and shrubs. Built in the Greek Revival style, the original central block of the building is two-and-a-half stories in height and three bays wide with an imposing full-width front gabled portico. The stuccoed façade features a central entry set in a pedimented surround with a 15-light transom and sidelights, and large double-hung wood sash windows. Detailing on the portico includes dentil molding and a half-round window with a keystone arch. In the 1930s, one-story wings were added to the east and west sides of the dwelling. The original outbuildings, including a kitchen, servants quarters, and a well house, have been attached to the dwelling by a series of hyphens.

The Italianate style, defined by an overall emphasis on verticality, is illustrated on about thirteen examples within the district, all of which date to the last quarter of the 19th century. The West End contains suburban vernacular versions of the Italianate style which display only select embellishments such as eave brackets. The houses located at 520 and 528 West Washington Street (both dating to circa 1880) appear similar and may have been constructed by the same builder. These two houses are square in plan, two stories in height, and three bays wide with a side entry. Both have double-pile plans with full-width hipped-roof porches across the façades and exhibit applied eave brackets. Square wood columns ornamented with lace-like or scroll-shaped brackets support the porches. The façade windows have double-hung vertical 2/2 sash. Further examples of the Italianate style can be seen at 116 Pender Avenue (circa 1870), 616 West Washington Street (circa 1870), and 530 West Washington Street (circa 1880).

Dating from the last quarter of the 19th century, the dwellings located at 105-107 Linden Avenue are representative of early forms of the Colonial Revival style. Both structures are single pile with side gable roofs, cornice returns, weatherboard siding, and 6/6 double-hung sash windows. The house at 107 Linden Avenue (circa 1880) is three bays wide with a central passage and two interior end brick chimneys, whereas the dwelling at 105 Linden Avenue (circa 1880) is two bays wide with a hall/parlor plan, and one interior end brick chimney.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 3

The Queen Anne style, favored throughout the nation for everything from rowhouses to sprawling seaside retreats, is one of the more prolific architectural expressions in the West End neighborhood. Typical examples of this style nationwide were resplendent in patterned shingles, spindles, brackets, and curlicue cutouts; many boasted ample verandahs, turrets, and sleeping porches. During the latter part of the 19th century, the Queen Anne style found an exuberant expression in wood, and frequently incorporated columns and decorative motifs borrowed from our own colonial architecture. Yet, the traditional architectural detailing of the Queen Anne style was easily reinterpreted with only select embellishments applied. The intricate form commonly associated with the Queen Anne style was often the only identifiable element of the fashion. This vernacular interpretation of the style was distinctly prominent in the West End neighborhood. These buildings, dating primarily from the 1890s up to 1915, are significant examples of the fast growing residential development of the neighborhood. There are several resplendent high-style examples in addition to the more vernacular forms noted in West End, particularly along Linden Avenue at 124, 120, and 117 Linden Avenue, all of which date to circa 1895. Modest examples of the Queen Anne style can also be found on neighboring streets at 116 South Broad Street (circa 1895), 125 St. James Avenue (circa 1900), and 201 Bosley Avenue (circa 1895), to name a few.

20th Century Development (1900 – 1939)

After the turn of the 20th century, traditional domestic forms were often interpreted for economy and convenience. The resulting bungalow mimicked the plan and massing traditionally associated with the fashionable Queen Anne style; yet, the bungalow form was invariably one to one-and-a-half stories in height. Overwhelmingly known as a style rather than a form, the bungalow is covered by a low-pitched, intersecting gable roof that encompassed the often wrapping porch. The irregular plan allowed for additional window openings and direct access to the porch from various secondary rooms. The modest arrangement of the wood-frame buildings made them one of the most popular low- to middle-income domestic forms in growing suburban communities across the United States. The bungalow, very often melding with the Craftsman-style, is seen predominantly on Brewer Avenue with several examples on St. James Avenue and Linden Avenue, all of which retain their integrity. Stylistic elements displayed include raised brick foundations, battered wood posts on masonry piers, full-width front gable porches, exposed rafter tails, eave brackets, and double-hung windows with multi-light upper sash above a one-light lower

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 4

sash. Early 20th century examples include 111 Linden Avenue (circa 1905), 134 Brewer Avenue (circa 1910), and 127 Brewer Avenue (circa 1910). The majority of the bungalows in West End date to the 1920s and include 711 West Washington Street (circa 1920), 116 Brewer Avenue (circa 1920), 302 South Broad Street (circa 1925), and 106 St. James Avenue (circa 1925).

Another of the popular building forms of the early 20th century was the American foursquare, commonly ornamented with Colonial Revival- and Craftsman-style detailing. The two-story, four-room-per-floor house plan without a hall is a much-used concept that refers to the hall/parlor plan of the 18th century. Numerous illustrations of the American foursquare exhibiting architectural detailing fashionable in the early part of the 20th century have been documented in the West End, particularly in the eastern portion of the neighborhood. The buildings have the characteristically distinguished two-story height, hipped or pyramidal roof with pronounced eaves and dormers that light an extra half-story, large front porch, and the lack of applied exterior ornament. The overall shape of the buildings is a cube and the main entry openings are located off-center. Examples dating to circa 1910 are located at 308 South Broad Street, 213 Linden Avenue, and 205 Bosley Avenue. Built circa 1925, 311 South Broad Street features Craftsman-style details. The dwelling features overhanging eaves, exposed rafter tails and a porch with battered wood posts on masonry piers.

The Colonial Revival style proved to be a significant contribution throughout the West End neighborhood in the first half of the 20th century. The Colonial Revival-style buildings found in this district range from the large high-style dwellings to the more restrained vernacular houses. Characteristic features of the style include a rectangular form, projecting porticos, cornice returns, open pediments, Tuscan columns, and either wood-frame or brick construction. High-style examples in the West End typically are five bays wide with three front gable dormers and two interior-end chimneys. Several examples include an ornate entablature with a triglyph and metope frieze. High-style examples can be seen at 212 South Broad Street (circa 1925) and 706 Gittings Street (1929). The modest vernacular illustrations of this style are three bays wide with side gable roofs and a projecting portico, or have a T-shaped footprint with a wrap-around one-story porch. Some of these houses have infused Queen Anne and Craftsman details. Examples of the more vernacular form of Colonial Revival can be seen at 316 Causey Avenue (circa 1925), 120 St. James Avenue (circa 1930), and 309 Linden Avenue (circa 1930).

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 5

Another of the early-20th-century styles is the Classical Revival, represented in the neighborhood by the dwelling located at 104 South Broad Street. Built in 1907, this two-and-a-half-story, stretcher-bond brick house is three bays wide featuring a full-width two-story Classical Revival porch with a center forward extension supported by fluted Corinthian columns and pilasters with a balustrade roofline. The house exhibits three-bay-wide projecting cross gables on the side elevations with full denticulated pediments and center semi-circular windows. An ornate heavy wood cornice wraps around the hipped-roof dwelling. A balcony is set above the central entry on the façade and the entry is comprised of a two-leaf glass-and-paneled door with an elliptical transom and patterned multi-light tracery sidelights. The windows and entry openings have flat arch lintels with keystones and the original windows on the side and rear elevations are double-hung with a nine-light upper sash over a one-light lower sash. The inset rectangular panels between the stories and window bays are decorated with inset brick and stone designs.

Built in the late 1920s the dwelling at 122 Brewer Avenue is the only Tudor Revival-style dwelling within West End. As with many of the other styles represented in the neighborhood, this building is a modest example of the style delineating itself only through the footprint and roof shape. The dwelling is a large two-story masonry structure with steeply pitched gables, a T-shaped footprint with dominant projecting front gables, inset gable-front wall dormers, and double-hung windows with eight-light sash.

During the late 1920s and early 1930s, a few multiple dwellings in the form of duplexes and twin dwellings, began to appear in the West End neighborhood. The duplexes, located at 606 Virginia Avenue (circa 1924), 314 Bosley Avenue (circa 1925), and 305 Linden Avenue (circa 1935) are rectangular wood-frame buildings, two stories in height, with hipped roofs and two-story porches. These dwellings lack ornamental details but exhibit central and side entrances and paired sets of double-hung wood sash windows. The West End neighborhood contains two twin dwellings, 400-400 ½ and 402-402 ½ South Broad Street, both constructed circa 1935. These Colonial Revival-style twin dwellings are two stories in height and four bays wide with symmetrical facades, side gable roofs, interior-end brick chimneys and front gabled porticos.

Most of the residential properties contain one or more outbuildings such as garages or sheds. The majority of the surviving outbuildings were built during the first quarter of the 20th century. In general these buildings are one story in height, two to three bays wide and exhibit a square or rectangular

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 6

footprint, wood-frame construction clad in weatherboards, with shed, gable, or pyramidal roofs sheathed in asphalt shingles or standing seam metal. Decorative details include wide eaves and exposed rafter tails.

Examples can be seen throughout the neighborhood including the properties at 102 Brewer Avenue (circa 1930), 210 South Broad Street (circa 1920), and 107 Wellons Street (1910-1925). Outbuildings dating to the second half of the 20th century display the same form as their predecessors but feature more modern materials such as concrete block, aluminum siding, and vinyl siding.

Religious and Commercial Resources in West End

In addition to the domestic buildings throughout West End, there are also religious and commercial buildings. Historically commercial development within the West End neighborhood concentrated in the area between Virginia Avenue and the Norfolk & Western Railroad and involved industries reliant on the railroads for the shipment of their products. According to the Sanborn Maps from 1920 and 1926, there was a hardware and lumber store, a casket company and a mattress company. The structure which housed the Suffolk Mattress Company in 1920, survives today at 401 Linden Avenue (circa 1915). The one-story, six-bay brick building is now vacant. The building does not feature any stylistic elements except for a stepped parapet which hides the flat roof. A brick addition was constructed in the northeast corner of the building during the second half of the 20th century. North of Virginia Avenue, the West End neighborhood was historically predominantly residential, but there remains at least one example of a combination store/dwelling from the early 20th century. This structure is located at 700 West Washington Street (circa 1900) towards the western edge of the district. Typical of the commercial/residential building types is the gable front with a recessed center entrance flanked by store windows, a long rectangular plan, and a side entrance to the second-story apartment. During the last twenty years of the 20th century West Washington Street has been transformed into a commercial street serving the residents of the West End neighborhood as well as the residents of downtown Suffolk. A number of residential buildings along West Washington Street, which is the main western thoroughfare from the Downtown Historic District, have been rehabilitated during the last fifty years to serve as commercial buildings. This includes 528 West Washington Street (circa 1880) and 711 West Washington Street (circa 1920). Both of these buildings were constructed as single family dwellings and have since been converted into offices.

There are several religious structures located in West End. One of the most impressive, the Oxford

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 7

Methodist Episcopal Church, now the Oxford United Methodist Church, is located at 601 West Washington Street. Constructed in 1922, in the Gothic Revival style, the brick building has a Greek cross plan. It features crenellated corner towers topped with pinnacles, large lancet windows with cast concrete hood molds and surrounds, shallow wall buttresses, and a parapet gable roof. The church at 501 West Washington Street, built in 1938, houses the West End Baptist Church. Built in the Colonial Revival-style, the church has a symmetrical façade, central entrance, double-hung wood sash windows and a central steeple covered with copper and topped with a finial. Not all the churches within the West End neighborhood exhibit such high-style detailing. The building at 509 Smith Street, built in 1908, housed the Oxford Methodist Episcopal Church for fourteen years. The rock-faced concrete block building has a brick façade which features a central entry and double-hung wood sash windows. In 1922 it was converted to an apartment building.

Development After 1939

By 1939 the West End neighborhood was nearly complete with only a handful of residential buildings erected on empty lots after 1940. These buildings, generally located along the western and southern boundaries, consist of duplexes and single-family dwellings. The duplexes, dating to the late 1940s, have a rectangular form and are two stories in height and three bays wide. Lacking ornamental detailing, the duplexes are wood-frame construction and clad with either vinyl siding or a brick veneer and capped with a hipped roof. Two-story front porches with square wood posts and half-hipped roofs serve both the first- and second-story residents. A few single-family dwellings were also added along the western and southern borders during the late 1950s. These vernacular brick dwellings are generally one story in height with a L-shape form and cross gable roofs. In-fill housing consisting of one-story vernacular single dwellings and two-story rectangular Colonial Revival-style apartment blocks in West End continued to be built through the last quarter of the 20th century, resulting in only a small number of new buildings.

The West End neighborhood has also experienced a limited amount of commercial development during the last half of the 20th century. This development is contained along the western blocks of West Washington Street and is composed of two commercial buildings, three offices, and one bank. Both the commercial buildings, located at 519 and 608 West Washington Street, were constructed during the third quarter of the 20th century. The building at 519 West Washington Street is representative of the

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 8

Commercial style and is clad with a brick veneer and features fixed metal plate glass windows and a side-gable roof. During the last twenty years of the 20th century, the three office buildings (607, 705, and 709 West Washington Street) and the bank at 611 West Washington Street were built. The office buildings reflect a more modern interpretation of the Colonial Revival style and exhibit features such as brick veneers, recessed central entries, double-hung vinyl sash multiple-light windows with rowlock sills and gauged lintels, and gable roofs. The bank, which currently serves as the Word of Faith Worship Center, and the commercial building at 608 West Washington Street are vernacular and display materials popular in commercial construction during the second half of the 20th century, such as concrete foundations, brick veneers, metal window sashes, and flat roofs.

West End Historic District Inventory

Bosley Avenue

101 Bosley Avenue
133-5040-0144
Single Dwelling 1950-1965 Other 1.0
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Veneer, Brick
Window(s): Sash, double-hung Wood 6/1
Window(s): Sash, double-hung Wood 6/6
Door(s): Single Leaf Metal Paneled
Roof: Gable: Side Asphalt Shingle
Portico: 1-story, 1-bay Asphalt Shingle
Individual Resource Status: **Single Dwelling**

Non-contributing

109 Bosley Avenue
133-5040-0145
Single Dwelling 1930 ca Colonial Revival 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Masonry Brick Stretcher Bond
Window(s): Sash, double-hung Wood 6/6
Door(s): Single Leaf Wood Paneled
Roof: Gable: Side Slate Tiles
Chimney: Interior end Brick Corbeled Cap
Chimney: Central interior Brick Corbeled Cap
Chimney: Exterior Brick Corbeled Cap

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 9

Portico: 1-story, 1-bay Wood Tuscan Columns

Dormer: Gable Wood Weatherboard

Individual Resource Status: Single Dwelling

Individual Resource Status: Garage

Contributing

Non-contributing

112 Bosley Avenue

133-5040-0143

Single Dwelling 1925-1940 Colonial Revival 2.5

Foundation: Solid Brick 6-course Amer.Bond

Structural System: Masonry Brick 6-course Amer.Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Portico: 1-story, 1-bay Wood Columns, Doric

Roof: Gable: Side Slate Tiles

Chimney: Interior end Brick Stretcher Bond

Chimney: Central interior Brick Stretcher Bond

Dormer: Gable Wood Shingle

Individual Resource Status: Single Dwelling

Contributing

201 Bosley Avenue

133-5040-0151

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick American Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood 1-light

Door(s): Single Leaf Wood 1-light

Roof: Hipped Metal Shingle

Chimney: Interior Brick Corbeled Cap

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Porte Cochere: 1-story, 1-bay Wood Tuscan Columns

Individual Resource Status: Single Dwelling

Individual Resource Status: Garage

Contributing

Contributing

204 Bosley Avenue 133-5040-0188

Primary Resource Information: Multiple dwelling, Stories 2.50, Style: Other, ca 1930

This vernacular-style duplex is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features three one-leaf wood paneled door with lights, double-hung wood sash 6/6-light windows, and 4- and 6-light wood casement windows. All the openings are set in square-

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 10

edged aluminum clad surrounds. The dwelling has wide eaves and a front gable roof which is covered with asphalt shingles. One exterior-side corbeled brick chimney is positioned on the south elevation and one interior brick chimney is visible above the roof line. A two-story, two-bay screened porch with aluminum clad Tuscan columns is attached to the west (front) elevation. A one-story, one-bay porch with a shed roof supported by a square wood post shades the main entrance.

Individual Resource Status: Multiple dwelling

Contributing

Individual Resource Status: Garage

Contributing

205 Bosley Avenue 133-5040-0187

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1910

This Colonial Revival-style dwelling has an American 4-square form and is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards. The facade features an off-center entry with a 1-light transom and double-hung wood sash 1/1-light windows set in square-edged wood surrounds. The windows are arranged singly, in pairs and in sets of three. The dwelling has wide eaves, a wood fascia, an aluminum clad soffit and a hipped roof covered with asphalt shingles. One hipped dormer, clad in weatherboards and containing a double-hung aluminum sash 1/1-light window, rises from the roof. Two interior brick chimneys are visible over the roof line. A one-story, three-bay porch with a half-hipped roof supported by battered and fluted wood posts, is attached to the east (front) elevation.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Shed

Contributing

206 Bosley Avenue 133-5040-0189

Primary Resource Information: Multiple dwelling, Stories 2.00, Style: Other, ca 1945

This vernacular-style dwelling is two stories in height and four bays wide. It has a solid stretcher-bond brick foundation supporting a masonry structural system with brick laid in a 7-course Flemish bond. The facade features three one-leaf wood paneled doors, one of which is located in a projecting front gabled entry vestibule, and double-hung wood sash 6/6-light windows with rowlock sills and solid course lintels. The dwelling has a molded wood cornice and a hipped roof which is covered with asphalt shingles. One interior brick chimney with a corbeled cap is visible over the roof line. A two-story, one-bay screened porch with a solid brick balustrade and brick posts, is attached to the west (front) elevation.

Individual Resource Status: Multiple dwelling

Non-Contributing

Individual Resource Status: Garage

Non-Contributing

207 Bosley Avenue 133-5040-0186

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1925

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a masonry structural system with brick laid in a 6-course Flemish bond. The facade features a central entry flanked by double-hung wood sash 2/2- and 1/1-light windows with rowlock sills and fixed louvered shutters. The dwelling has a wood cornice, wide eaves, and a hipped roof which is covered with pressed metal shingles. One hipped dormer, clad in wood shingles and containing a 2-light fixed wood sash window, rises from the roof. Two interior brick chimneys with corbeled caps are visible over the roof line. A one-story, one-bay porch, which extends to cover the drive, has battered wood posts on stone capped brick piers. A one-story addition with a hipped roof and an interior-end brick chimney, extends from the north elevation.

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 11

Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Contributing

208 Bosley Avenue 133-5040-0190

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1935**

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a central entry flanked by double-hung wood sash 6/6-light windows set in square-edged aluminum surrounds. The dwelling has a boxed aluminum cornice and a side gable roof which is covered with asphalt shingles. One central interior brick chimney with a corbeled cap is visible over the roof line. A one-story, one-bay front gabled portico with wood Tuscan columns shades the entrance. A one-story wing with a side gable roof exists on the south elevation and a one-story gabled carport is attached to the north elevations. A one-story porch has been added to the east elevation.

Individual Resource Status: **Single Dwelling**

Contributing

209 Bosley Avenue 133-5040-0185

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Bungalow/Craftsman, ca 1918**

This Craftsman-style dwelling has a bungalow form and is one story in height and four bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards. The facade features a replacement one-leaf wood paneled door flanked by 6-light casements and double-hung wood sash 1/1-light windows, wood cornerboards, and wood louvered vents. All the openings are set into square-edged wood surrounds. The dwelling has wide eaves, wood brackets, and a front gable roof which is covered with asphalt shingles. One central-interior brick chimney is visible above the roof line. A one-story, three-bay rebuilt porch with a front gable roof supported by turned wood posts is attached to the southeast elevation. A one-story addition with a half-hipped roof and one interior brick chimney exists on the southwest elevation. A wood deck, connecting the above-ground pool to the house, is attached to the northwest elevation of the dwelling.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

210 Bosley Avenue 133-5040-0191

Primary Resource Information: **Multiple Dwelling, Stories 2.00, Style: Colonial Revival, ca 1945**

This Colonial Revival-style dwelling is two stories in height and four bays wide. It has a solid stretcher-bond brick foundation supporting a masonry structural system with brick laid in a 7-course Flemish bond. The entrances, one serving each story, feature one-leaf wood paneled doors with a wood surround, dado panels, and 8-light sidelights. Double-hung wood sash 6/6-light windows with wood lug sills flank the entrances. The building has an aluminum clad cornice, wide eaves, and a hipped roof which is covered with asphalt shingles. One interior brick chimney is visible over the roof line. A two-story, two-bay porch with a half-hipped roof and battered wood posts, is attached to the west (front) elevation.

Individual Resource Status: **Multiple dwelling**

Non-Contributing

Individual Resource Status: **Garage**

Non-Contributing

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 12

212 Bosley Avenue 133-5040-0192

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Other, ca 1918**

This vernacular style dwelling is two-and-a-half stories in height and four bays wide. It has a solid brick foundation supporting a masonry structural system with rubbed brick laid in a Flemish bond. The symmetrical facade features a side entry with a 1-light transom and double-hung wood sash 6/6-light windows set in arched openings with splayed brick lintels and wood lug sills. The dwelling has overhanging eaves, exposed rafters, and a hipped roof covered with asphalt shingles. The facade also features one gabled dormer, clad in asphalt shingles and containing two double-hung wood sash 6/6-light windows, rises from the roof. One interior brick chimney laid in a Flemish bond, is visible above the roof line. A one-story, three-bay partially screened wrap porch with brick posts, is attached to the west and south elevations. A one-story carport with a half-hipped roof supported by brick posts exists on the north elevation. A one-story brick addition with a half-hipped roof and a one-story wood-frame addition clad in aluminum siding is attached to the east elevation. A wooden ramp leads to the front porch.

Individual Resource Status: **Single Dwelling** **Contributing**

Individual Resource Status: **Garage**

Contributing

213 Bosley Avenue 133-5040-0184

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Queen Anne, ca 1915**

This dwelling has a Queen Anne-style and is two-and-a-half stories in height and four bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The off-center entry set is set in an aluminum clad surround with a 12-light transom. A secondary entry, also set in an aluminum clad surround, provides access from the rear section of the house to the wrap porch. The facade features double-hung wood sash 2/2-, 12/1-, and 40/1-light windows, all set in molded aluminum clad surrounds. The dwelling has wide eaves and a hipped roof which is covered with sheets of standing seam metal. One asymmetrically placed gable dormer, clad in aluminum siding and containing a wood sash lancet window, rises from the roof. A one-story, two-bay porch with fluted wood posts is attached to the east and south elevations.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-Contributing

301 Bosley Avenue 133-5040-0183

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Bungalow/Craftsman, ca 1915**

This Craftsman-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in wood shingles. The facade features an off-center entry set in a molded wood surround with dado panels, 1-light sidelights and a 1-light transom, and double-hung wood sash 1/1-light windows with wood lug sills. The dwelling has a wood cornice, wood fascia board and a side gable roof covered with asphalt shingles. One shed dormer, clad in wood shingles and containing two double-hung wood sash 1/1-light windows, rises from the roof. One central-interior brick chimney with a corbeled cap is visible over the roof line. A one-story, three-bay porch with battered wood posts on brick piers, is attached to the east (front) elevation. Two and one-story additions as well as a one-story garage, exist on the west elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 13

304 Bosley Avenue 133-5040-0194

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1925**

This Colonial Revival-style dwelling has an American four-square form and is two-and-a-half stories in height and two bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a 6-course Flemish bond and a soldier-course water-table. The facade features an off-center entry and replacement double-hung vinyl sash 1/1-light windows arranged in pairs and sets of three, all with concrete lug sills. The dwelling has a vinyl clad boxed cornice, wide eaves, and a hipped roof which is covered with asphalt shingles. One hipped dormer clad in vinyl siding and containing two double-hung wood sash 1/1-light windows rises from the roof. Two interior-end brick chimneys are visible over the roof line. A one-story, two-bay porch with a half-hipped roof supported by battered wood posts on brick piers, is attached to the west (front) elevation. A one-story wood-frame addition with a gable roof and a wood deck exist on the east elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

305 Bosley Avenue 133-5040-0182

Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Colonial Revival, ca 1945**

This Colonial Revival-style dwelling is one-and-a-half stories in height and four bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features an off-center entry flanked by double-hung wood sash 6/6-light windows with wood lug sills and fixed louvered shutters. The dwelling has an aluminum clad cornice and a side gable roof covered with asphalt shingles. A cross gable is centered above the two central bays. The gable peak is clad in aluminum siding and contains one double-hung wood sash 6/6-light window. Two gabled dormers, clad in aluminum siding and containing double-hung wood sash 6/6-light windows flank the central cross gable. One exterior-end brick shouldered chimney with a corbeled cap is positioned on the south elevation. A one-story one-bay front gabled portico with wood Tuscan posts shades the entrance. One-story screened porches with gable roofs are attached to the north and south elevations.

Individual Resource Status: **Single Dwelling**

Non-Contributing

306 Bosley Avenue 133-5040-0195

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1995**

This Colonial Revival-style dwelling is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards. The facade features a recessed central entry flanked by double-hung vinyl sash 1/1-light windows with fixed louvered shutters. The dwelling has wide eaves and a cross gable roof which is covered with asphalt shingles. An awning shades the entrance.

Individual Resource Status: **Single Dwelling**

Non-Contributing

Individual Resource Status: **Shed**

Non-Contributing

308 Bosley Avenue 133-5040-0196

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1925**

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features a central entry, paired sets of double-hung wood sash 6/6-light windows, and a louvered vent covered by a storm window. The dwelling has projecting gables and overhanging eaves

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 14

with triangle knee brackets, and a front gable roof which is covered with sheets of standing seam metal. One interior-side brick chimney is visible above the roof line. A one-story, one-bay front gabled portico with square wood posts shades the entrance. A one-story addition with a shed roof exists on the east (rear) elevation.

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Shed**

Contributing

Non-Contributing

309 Bosley Avenue 133-5040-0181

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Other, ca 1922**

This dwelling has an American four-square form with Colonial Revival and Craftsman-style detailing. The dwelling is two-and-a-half stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a 7-course Flemish bond. The facade features a side entry set in a thin molded wood surround with a 1-light transom, a secondary entry, also with a molded wood surround and a 1-light transom, provides access from the rear section of the house onto the porch. Double-hung wood sash 6/1- and 4/1-light windows with square-edged wood sills, pierce the facade. The first story features one tripartite window. The dwelling has an aluminum clad cornice, wide eaves and a hipped roof which is clad with asphalt shingles. One hipped dormer, clad in asphalt shingles and containing two fixed wood sash 6-light windows, rises from the roof. The original block of the house contains two interior-side brick chimneys. A one-story, three-bay wrap porch with battered wood posts on brick piers is attached to the east (front) and south elevations. A two-story wood-frame addition clad in aluminum siding and topped with a gable roof exists on the west elevation. This addition contains one interior end brick chimney. A later one-story wood-frame addition with a shed roof extends from the two-story addition.

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Garage**

Contributing

Contributing

310 Bosley Avenue 133-5040-0197

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Bungalow/Craftsman, ca 1925**

This Craftsman-style dwelling has an American four-square form and is two-and-a-half stories in height and two bays wide. It has a solid brick foundation supporting a wood-frame structural system clad in weatherboards. The facade features a side entry set in a wood surround with 2-light side-lights and paired double-hung wood sash 6/1-light windows with wood surrounds. The dwelling has overhanging eaves, exposed rafters, and a hipped roof covered with asphalt shingles. One hipped dormer, clad in weatherboards and containing two 6-light wood sash windows, rises from the roof. Two interior brick chimneys are visible over the roof line. A one-story, three-bay porch with a half-hipped roof supported by battered wood post on brick piers is attached to the west (front) elevation and extends south to form a porte cochere.

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Garage**

Contributing

Contributing

312 Bosley Avenue 133-5040-0198

Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Colonial Revival, ca 1950**

This Colonial Revival-style dwelling has a Cape Cod form and is one-and-a-half stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features a central entry flanked by double-hung wood sash 8/8-light windows with rowlock sills. The dwelling has a molded wood cornice, fascia

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 15

board, and a side gable roof which is covered with asphalt shingles. One central-interior brick chimney with a corbeled cap is visible over the roof line. A one-story, one-bay screened porch with a front gable roof supported by wood posts is attached to the west (front) elevation. The peak of the gable is clad in weatherboards.

Individual Resource Status: **Single Dwelling**

Non-Contributing

Individual Resource Status: **Garage**

Non-Contributing

314 Bosley Avenue 133-5040-0199

Primary Resource Information: **Multiple dwelling, Stories 2.00, Style: Other, ca 1925**

This vernacular-style dwelling is two stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The principle elevation, facing northwest towards Bosley Avenue, features an off-center entry and double-hung wood sash 2/2-light windows set in vinyl clad surrounds. The dwelling has projecting eaves and a hipped roof which is covered with asphalt shingles. Two interior brick chimneys with corbeled caps are visible over the roof line. A two-story, one-bay screened porch with a half-hipped roof supported by square wood posts on brick piers is attached to the northeast (front) elevation.

Individual Resource Status: **Multiple dwelling**

Contributing

Individual Resource Status: **Garage**

Non-Contributing

315 Bosley Avenue 133-5040-0180

Primary Resource Information: **Multiple dwelling, Stories 2.00, Style: Other, ca 1945**

This vernacular-style duplex is two stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a 7-course Flemish bond. The facade features a one-story, one-bay front gabled entry vestibule, double-hung wood sash 6/6-light windows with concrete lug sills, a wood fascia board, a boxed cornice and a vinyl clad soffit. The building has wide eaves and a hipped roof which is covered with asphalt shingles. One central-interior brick chimney with a corbeled cap is visible above the roof line. A two-story, one-bay screened porch with brick piers supporting the half-hipped roof is attached to the southeast (front) elevation. Cloth awnings provide further shade for the porch. A two-story addition with a shed roof exists on the northwest (rear) elevation.

Individual Resource Status: **Multiple dwelling**

Non-Contributing

Individual Resource Status: **Garage**

Non-Contributing

401 Bosley Avenue 133-5040-0179

Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Bungalow/Craftsman, ca 1925**

This Craftsman-style dwelling is one-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in asbestos shingles. The facade features two entries, one with a 1-light transom, and one double-hung wood sash 4/1-light window set in a square-edged molded wood surround. The dwelling has a side gable roof which is covered with asphalt shingles. One shed dormer, clad in asbestos shingles and containing a set of four double-hung wood sash 1/1-light windows, pierces the roof. One interior-end brick chimney with a corbeled cap is visible over the roofline. A one-story, two-bay wrap-around inset porch with square wood posts on brick piers, exists on the east (front) and north elevations.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 16

403 Bosley Avenue 133-5040-0178

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1945**

This Colonial Revival-style dwelling has a Cape Cod form and is one story in height and three bays wide. The dwelling has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features a central entry flanked by double-hung wood sash 2/2- 4/4-, and 8/8-light windows set in aluminum surrounds. The dwelling has side gable roof covered with asphalt shingles. One interior-end brick chimney with a corbeled cap is visible over the roof line. A one-story, one-bay front gabled portico with fluted metal columns shades the entrance. A one-story addition with a gable roof exists on the northeast elevation.

Individual Resource Status: **Single Dwelling**

Non-Contributing

Individual Resource Status: **Garage**

Non-Contributing

404 Bosley Avenue 133-5040-0210

Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Colonial Revival, ca 1950**

This Colonial Revival-style dwelling has a Cape Cod form and is one-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a central entry flanked by double-hung wood sash 6/6-light windows set in square-edged surrounds. The dwelling has a side gable roof which is covered with asphalt shingles. Three gabled dormers, clad in aluminum siding and containing double-hung wood sash 6/6-light windows, rise from the roof. A one-story, one-bay porch with an awning supported by metal posts, is attached to the west (front) elevation.

Individual Resource Status: **Single Dwelling**

Non-Contributing

405 Bosley Avenue 133-5040-0211

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1950**

This vernacular-style dwelling is one story in height and three bays wide. It has a solid brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a central entry flanked by paired sets of double-hung wood sash 1/1-light windows. The dwelling has wide eaves and a side gable roof which is covered with asphalt shingles. A one-story addition with a gable roof extends from the west (rear) elevation.

Individual Resource Status: **Single Dwelling**

Non-Contributing

407 Bosley Avenue 133-5040-0176

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1922**

This Colonial Revival-style dwelling has an American four-square form and is two-and-a-half stories in height and two bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a side entry, a double-hung wood sash 4/4-light window and replacement double-hung vinyl sash 6/6-light windows. The dwelling has wide eaves and a hipped roof which is covered with sheets of standing seam metal. One hipped dormer, clad in aluminum siding and containing a replacement double-hung vinyl sash 6/6-light window rising from the roof. Two interior brick chimneys, one with a corbeled cap, are visible over the roof line. A one-story, three-bay porch with a half-hipped roof supported by square wood posts, is attached to the east (front) elevation. A one-story addition with a shed roof exists on the west elevation.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 17

Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Non-Contributing

409 Bosley Avenue 133-5040-0175

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Other, ca 1925**

This vernacular-style dwelling has Colonial Revival and Craftsman style detailing applied to its American 4-square form. It is two-and-a-half stories in height and two bays wide. The dwelling has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in asbestos shingles. The facade features double-hung wood sash 2/2-light windows set in square-edged wood surrounds, a wide wood fascia board, a molded cornice with a closed tympanum. The front gable roof is covered with sheets of standing seam metal. One central-interior brick chimney with a corbeled cap is visible over the roof line. A one-story, two-bay screened porch with a half-hipped roof supported by battered wood posts on brick piers is attached to the east (front) elevation. A one-story addition with a flat roof exists on the west elevation.

Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

Contributing
Contributing

415 Bosley Avenue 133-5040-0173

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1930**

This vernacular-style dwelling is one story in height and three bays wide. Its original brick pier foundation has been in-filled and it now appears as a solid brick foundation. The dwelling has a wood-frame structural system clad in aluminum siding and a front gable roof which is covered with sheets of standing seam metal. The facade features a central entrance flanked by double-hung wood sash 6/6-light windows set in square-edged surrounds, an aluminum clad cornice with returns, and wide eaves. One central interior brick chimney with a corbeled cap is visible over the roof line. A one-story, one-bay screened porch with a half-hipped roof supported by square wood posts exists on the east (front) elevation.

Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

Contributing
Contributing

417 Bosley Avenue 133-5040-0172

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Bungalow/Craftsman, ca 1928**

This Craftsman-style dwelling has a bungalow form and is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a one-leaf wood paneled door with lights and double-hung wood sash 3/1-light windows. The dwelling has overhanging eaves, exposed rafters and a side gable roof which is covered with sheets of standing seam metal. One interior metal stove-pipe is visible over the roof line. A one-story, one-bay screened porch with square wood posts supporting a front gable roof, exists on the east (front) elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Brewer Avenue

**101 Brewer Avenue
133-5040-0022**

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 18

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood 1-light

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Columns, Ionic

Individual Resource Status: **Single Dwelling**

Contributing

102 Brewer Avenue

133-5040-0056

Multiple dwelling 1935 ca Colonial Revival 2.0

Foundation: Solid Brick 7-course Flem.Bond

Structural System: Masonry Brick 7-course Flem.Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 2-story, 1-bay Brick Piers

Portico: 1-story, 1-bay Brick Stretcher Bond

Individual Resource Status: **Multiple Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

103 Brewer Avenue

133-5040-0023

Single Dwelling 1930 ca Bungalow/Craftsman 1.5

Foundation: Solid Brick 7-course Amer.Bond

Structural System: Masonry Brick 7-course Amer.Bond

Window(s): Sash, double-hung Wood 30/1

Window(s): Sash, double-hung Wood 21/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Side Asphalt Shingle

Chimney: Exterior end Brick Stretcher Bond

Porch: 1-story, 3-bay Brick Craftsman

Dormer: Gable Wood Shingle

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 19

104 Brewer Avenue

133-5040-0055

Single Dwelling 1895 ca Classical Revival 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled w/ lights

Door(s): Single Leaf Wood Oval light

Roof: Hipped Metal Standing Seam

Porch: Wrap-around Wood Columns

Portico: 2-story, 1-bay Wood Columns, Ionic

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Garage**

Contributing

Contributing

105 Brewer Avenue

133-5040-0024

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Window(s): Sash, double-hung Wood 9/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 4-bay Wood Columns, Ionic

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Garage**

Contributing

Contributing

106 Brewer Avenue

133-5040-0054

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 6/1

Window(s): Sash, double-hung Wood 6/2

Door(s): Single Leaf Wood Multi-light

Door(s): Single Leaf Wood Paneled

Roof: Gable: Cross Metal Pressed

Chimney: Exterior end Brick Stretcher Bond Historic

Chimney: Interior end Metal Stretcher Bond

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 20

Porch: 1-story, 4-bay Wood Columns

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Contributing

107 Brewer Avenue

133-5040-0025

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-Contributing

108 Brewer Avenue

133-5040-0053

Single Dwelling 1930 ca Bungalow/Craftsman .5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Multi-light

Roof: Gable: Side Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Chimney: Interior end Metal Capped

Porch: 1-story, 3-bay Wood Craftsman

Dormer: Gable Vinyl Siding

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Non-Contributing

109 Brewer Avenue

133-5040-0026

Single Dwelling 1925 ca Bungalow/Craftsman 1.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood 1-light

Roof: Hipped Asphalt Shingle

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 21

Chimney: Exterior end Brick Stretcher Bond
Chimney: Central interior Brick Corbeled Cap
Chimney: Central interior Brick Reconstructed
Porch: 1-story, 3-bay Wood Craftsman
Dormer: Hipped Vinyl Siding
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

Contributing
Contributing

110 Brewer Avenue

133-5040-0052

Single Dwelling 1900 ca Queen Anne 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Vinyl Siding
Window(s): Sash, double-hung Wood 1/1
Door(s): Single Leaf Wood Oval light
Door(s): Single Leaf Wood Multi-light
Roof: Hipped Metal Shingle
Chimney: Interior end Brick Corbeled Cap
Porch: Wrap-around Wood Columns
Dormer: Gable Vinyl Siding
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Non-Contributing

111 Brewer Avenue

133-5040-0027

Single Dwelling 1900 ca Queen Anne 2.5
Foundation: Solid Brick 7-course Amer.Bond
Structural System: Masonry Brick 7-course Amer.Bond
Window(s): Sash, double-hung Wood 1/1
Door(s): Single Leaf Wood Oval light
Roof: Hipped Asphalt Shingle
Chimney: Interior end Brick Reconstructed
Porch: Wrap-around Wood Posts, Turned
Dormer: Gable Wood Shingle
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Contributing

113 Brewer Avenue

133-5040-0028

Single Dwelling 1930 ca Bungalow/Craftsman 2.5

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 22

Foundation: Solid Brick 6-course Flem.Bond
Structural System: Masonry Brick 6-course Flem.Bond
Window(s): Sash, double-hung Wood 6/6
Door(s): Single Leaf Wood Paneled
Roof: Hipped Asbestos Shingle
Chimney: Interior end Brick Reconstructed
Chimney: Exterior end Brick Shouldered
Porch: 1-story, 1-bay Wood Craftsman
Dormer: Hipped Asbestos Shingle
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

**Contributing
Non-Contributing**

115 Brewer Avenue

133-5040-0029

Single Dwelling 1900 ca Queen Anne 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard
Window(s): Sash, double-hung Wood 1/1
Window(s): Not Visible Wood Boarded
Door(s): Single Leaf Wood Oval light
Roof: Hipped Asphalt Shingle
Chimney: Interior end Brick Stretcher Bond
Porch: Wrap-around Wood Tuscan Columns
Dormer: Gable Wood Weatherboard
Individual Resource Status: **Single Dwelling**

Contributing

116 Brewer Avenue

133-5040-0051

Single Dwelling 1925 ca Bungalow/Craftsman 1.5
Foundation: Solid Brick 3-course Amer.Bond
Structural System: Frame Wood Shingle
Window(s): Sash, double-hung Wood 8/8
Window(s): Sash, double-hung Wood 16/1
Window(s): Casement Wood 6-light
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Gable: Side Asphalt Shingle
Chimney: Exterior end Brick Shouldered
Chimney: Central interior Brick Stretcher Bond
Porch: 1-story, 3-bay Wood Craftsman
Dormer: Shed Wood Shingle

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 23

Individual Resource Status: Single Dwelling

Contributing

117 Brewer Avenue

133-5040-0030

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Oval light

Roof: Hipped Metal Standing Seam

Chimney: Interior end Brick Stretcher Bond

Porch: 2-story, 4-bay Wood Tuscan Columns

Dormer: Gable Wood Weatherboard

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

119 Brewer Avenue

133-5040-0031

Single Dwelling 1925 ca Bungalow/Craftsman 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Hipped Asbestos Shingle

Chimney: Interior end Brick Stretcher Bond

Chimney: Exterior end Brick Stretcher Bond

Porch: 1-story, 1-bay Wood Craftsman

Dormer: Gable Wood Weatherboard

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Tenant House

Contributing

Individual Resource Status: Garage

Contributing

121 Brewer Avenue

133-5040-0032

Single Dwelling 1895 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood Multi-light

Door(s): Single Leaf Wood Not visible

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 24

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Chimney: Exterior end Brick Shouldered

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Columns

Dormer: Hipped Wood Weatherboard

Individual Resource Status: Single Dwelling

Contributing

122 Brewer Avenue

133-5040-0050

Single Dwelling 1925 ca Tudor Revival 2.5

Foundation: Solid Brick 7-course Flem.Bond

Structural System: Masonry Brick 7-course Flem.Bond

Window(s): Sash, double-hung Wood 8/8

Window(s): Sash, double-hung Wood 6/6

Window(s): Casement Wood 3-light

Door(s): Single Leaf Wood Paneled

Roof: Gable: Front Slate Tiles

Chimney: Central interior Brick Corbeled Cap

Dormer: Gable Wood Vertical Board

Individual Resource Status: Single Dwelling

Contributing

123 Brewer Avenue

133-5040-0033

Single Dwelling 1915 ca Bungalow/Craftsman .5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 8/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Side Metal Standing Seam

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 1-bay Wood Craftsman

Dormer: Shed Wood Shingle

Individual Resource Status: Single Dwelling

Contributing

125 Brewer Avenue

133-5040-0034

Single Dwelling 1915 ca Bungalow/Craftsman 1.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Shingle

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 25

Window(s): Sash, double-hung Wood 5/1
Window(s): Casement Wood 2-light
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Gable: Side Metal Standing Seam
Chimney: Interior end Brick Corbeled Cap
Porch: 1-story, 3-bay Wood Post
Dormer: Shed Wood Shingle
Individual Resource Status: **Single Dwelling**

Contributing

127 Brewer Avenue

133-5040-0035

Single Dwelling 1910 ca Bungalow/Craftsman 2.5

Foundation: Solid Brick Stucco
Structural System: Frame Wood Stucco
Window(s): Sash, double-hung Wood 1/1
Window(s): Casement Wood Diamond
Window(s): Sash, double-hung Wood 8/1
Window(s): Sash, double-hung Wood 8/4
Window(s): Casement Wood 6-light
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Gable: Front Asphalt Shingle
Chimney: Exterior end Brick Stucco
Portico: 1-story, 1-bay Wood Brackets
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

Contributing

Contributing

128 Brewer Avenue

133-5040-0049

Single Dwelling 1915 ca Colonial Revival 2.5

Foundation: Solid Brick Flemish Bond
Structural System: Masonry Brick Flemish Bond
Window(s): Sash, double-hung Wood 1/1
Door(s): Single Leaf Wood Paneled
Roof: Gable: Cross Slate Tiles
Chimney: Interior end Brick Capped
Portico: 1-story, 1-bay Wood Tuscan Columns
Dormer: Gable Wood Siding
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 26

129 Brewer Avenue

133-5040-0036

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 2/1

Window(s): Sash, double-hung Wood 5/1

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood Diamond

Window(s): Fixed Wood Multi-light

Door(s): Single Leaf Wood Paneled

Roof: Gable: Cross Metal Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 1-bay Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Garage**

Contributing

Contributing

130 Brewer Avenue

133-5040-0048

Single Dwelling 1915 ca Colonial Revival 2.5

Foundation: Solid Concrete Parged

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Window(s): Casement Wood 12-light

Door(s): Single Leaf Wood 1-light

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Chimney: Central interior Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Dormer: Gable Wood Weatherboard

Individual Resource Status: **Single Dwelling**

Contributing

131 Brewer Avenue

133-5040-0037

Multiple Dwelling 1950-1965 Colonial Revival 2.0

Foundation: Solid None Listed Not Visible

Structural System: Frame Wood Veneer, Brick

Window(s): Sash, Double-hung Wood 6/6

Door(s): Single Leaf Wood Not Visible

Roof: Hipped Asphalt Shingle

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 27

Chimney: Central Interior Brick Corbeled Cap
Portico: 1-Story, 1 Bay Metal Post
Individual Resource Status: **Multiple Dwelling**

Non-contributing

133 – 133 ½ Brewer Avenue

133-5040-0038

Multiple Dwelling 1950-1965 Colonial Revival 2.0

Foundation: Solid None Listed Not Visible
Structural System: Frame Wood Veneer, Brick
Window(s): Sash, Double-hung Wood 6/6
Door(s): Single Leaf Wood Paneled
Roof: Hipped Asphalt Shingle
Chimney: Central Interior Brick Corbeled Cap
Portico: 1-story, 1-bay Wood Post
Individual Resource Status: **Multiple Dwelling**
Individual Resource Status: **Shed**

**Non-contributing
Non-contributing**

134 Brewer Avenue

133-5040-0047

Single Dwelling 1910 ca Bungalow/Craftsman .5

Foundation: Solid Brick Stretcher Bond
Structural System: Masonry Brick Stretcher Bond
Window(s): Sash, double-hung Wood 24/1
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Gable: Side Metal Standing Seam
Chimney: Exterior end Brick Stretcher Bond
Chimney: Central interior Brick Stretcher Bond
Porch: 1-story-3-bay Concrete Craftsman
Dormer: Gable Wood Shingle
Individual Resource Status: **Single Dwelling**

Contributing

135 Brewer Avenue

133-5040-0039

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard
Window(s): Sash, double-hung Wood 1/1
Door(s): Single Leaf Wood 1-light
Roof: Hipped Metal Shingle
Chimney: Interior end Brick Corbeled Cap

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 28

Chimney: Interior end Brick Stretcher Bond
Porch: 1-story, 3-bay Wood Tuscan Columns
Dormer: Gable Wood Weatherboard
Individual Resource Status: **Single Dwelling**

Contributing

136 Brewer Avenue
133-5040-0046
Single Dwelling 1950-1965 Other 2.0
Foundation: Solid Concrete Block
Structural System: Frame Wood Sliding, Vinyl
Window(s): Sash, Double-hung Wood 1/1
Door(s): Single Leaf Wood Paneled
Roof: Gable: Side Asphalt Shingle
Individual Resource Status: **Single Dwelling**

Non-contributing

137 Brewer Avenue
133-5040-0040
Single Dwelling 1935 ca Colonial Revival 2.0
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Aluminum
Window(s): Sash, double-hung Wood 6/6
Door(s): Single Leaf Wood Paneled
Roof: Gable: Side Asphalt Shingle
Chimney: Exterior end Brick Shouldered
Chimney: Interior end Brick Stretcher Bond
Porch: 1-story, 3-bay Wood Tuscan Columns
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing

Non-contributing

138 Brewer Avenue
133-5040-0045
Single Dwelling 1930 ca Colonial Revival 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Masonry Brick Stretcher Bond
Window(s): Sash, double-hung Wood 6/1
Door(s): Single Leaf Wood Flush
Roof: Hipped Asphalt Shingle
Chimney: Exterior end Brick Corbeled Cap
Portico: 1-story, 1-bay Wood Columns
Porte Cochere: 1-story Wood Tuscan Columns

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 29

Dormer: Hipped Wood Weatherboard
Individual Resource Status: **Single Dwelling**

Contributing

**139 Brewer Avenue
133-5040-0041**

Single Dwelling 1935 ca Colonial Revival 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Shingle

Window(s): Sash, double-hung Wood 8/8

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Chimney: Interior end Brick Stretcher Bond

Portico: 1-story, 1-bay Wood Columns, Ionic

Dormer: Shed Wood Shingle

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

**140 Brewer Avenue
133-5040-0044**

Single Dwelling 1915 ca Bungalow/Craftsman 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Multi-light

Roof: Gable: Side Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Porch: 1-story-3-bay Wood Columns

Dormer: Shed Wood Weatherboard

Individual Resource Status: **Single Dwelling**

Contributing

**142 Brewer Avenue
133-5040-0043**

Single Dwelling 1945 ca Classical Revival 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable: Side Asphalt Shingle

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 30

Chimney: Interior end Brick Corbeled Cap
Portico: 1-story, 1-bay Wood Columns, Square
Individual Resource Status: **Single Dwelling**

Non-Contributing

143 Brewer Avenue

133-5040-0042

Single Dwelling 1915 ca Bungalow/Craftsman 2.0

Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard
Window(s): Sash, double-hung Wood 6/6
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Gable: Front Asphalt Shingle
Chimney: Interior end Brick Corbeled Cap
Porch: 1-story, 3-bay Wood Posts, Square
Individual Resource Status: **Single Dwelling**

Contributing

Causey Avenue

102 Causey Avenue

133-5040-0161

Single Dwelling 1925 ca Bungalow/Craftsman .0

Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Vinyl
Window(s): Sash, double-hung Wood 6/6
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Gable: Front Asphalt Shingle
Chimney: Central interior Brick Corbeled Cap
Porch: 1-story, 1-bay Wood Posts, Square
Individual Resource Status: **Single Dwelling**

Contributing

316 Causey Avenue 133-5040-0171

Primary Resource Information: **Single Dwelling, Stories 2.5, Style: Colonial Revival, ca 1925**

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a masonry structural system with brick laid in a 6-course Flemish bond. The symmetrical façade features a central entrance set in a molded wood surround with dado panels and 10-light side-lights. Double-hung wood sash 6/6-light windows with wood lug sills flank the entrance and are repeated in the second story. The dwelling has a molded wood cornice, wide eaves, and a side gable roof which is covered with asphalt shingles. Two gabled dormers, clad in asbestos shingles and containing double-hung wood sash 6/6-light windows, rise from the roof. One exterior-end brick chimney is positioned on the south elevation and a second interior chimney stands in the northeast corner of the house. The one-story, one-bay portico features paired wood

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 31

Tuscan columns supporting a front gable roof with a molded cornice with returns. A one-story wood-frame addition with a shed roof exists on the south elevation and there is a one-story addition with a half-hipped roof on the east elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

Gittings Street

706 Gittings Street

133-5040-0160

Single Dwelling 1929 Colonial Revival 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/9

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof:: Gable: Side Asphalt Shingle

Chimney: Interior end Brick Stretcher Bond

Portico: 1-story, 1-bay Wood Tuscan Columns

Dormer: Gable Wood Weatherboard

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

Linden Avenue

103 Linden Avenue

133-5040-0105

Single Dwelling 1895 ca Italianate 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Metal Standing Seam

Chimney: Central interior Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 32

105 Linden Avenue

133-5040-0106

Single Dwelling 1885 ca Colonial Revival 2.0

Foundation: Piers w/ infill Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf None Listed Not visible

Roof: Gable: Side Metal Standing Seam

Chimney: Interior end Brick Corbeled Cap

Chimney: Central interior Brick Capped

Porch: 1-story, 2-bay Wood Tuscan Columns

Individual Resource Status: Single Dwelling

Contributing

107 Linden Avenue

133-5040-0107

Single Dwelling 1885 ca Vernacular 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable: Side Metal Standing Seam

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Posts, Tuscan

Individual Resource Status: Single Dwelling

Individual Resource Status: Shed

Individual Resource Status: Garage

Contributing

Contributing

Non-contributing

108 Linden Avenue

133-5040-0102

Single Dwelling 1915 ca Colonial Revival 2.5

Foundation: Solid Concrete Block, Rock-faced

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood 1-light

Door(s): Single Leaf Wood 1-light

Roof: Pyramidal Asphalt Shingle

Chimney: Central interior Brick Parged

Porch: 1-story, 3-bay Concrete Columns, Tuscan

Individual Resource Status: Single Dwelling

Individual Resource Status: Shed

Contributing

Non-contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 33

109 Linden Avenue

133-5040-0108

Single Dwelling 1900 ca Colonial Revival 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Front Metal Standing Seam

Chimney: Central interior Brick Corbeled Cap

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

111 Linden Avenue

133-5040-0109

Single Dwelling 1895 ca Bungalow/Craftsman 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Metal Standing Seam

Chimney: Central interior Brick Stucco

Porch: 2-story, 1-bay Wood Craftsman

Individual Resource Status: **Single Dwelling**

Contributing

112 Linden Avenue

133-5040-0101

Single Dwelling 1905 ca Queen Anne 2.5

Foundation: Solid Concrete Parged

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 2/2

Window(s): Fixed Wood 1-light

Door(s): Double leaf Wood Paneled w/ lights

Roof: Gable: Cross Metal Standing Seam

Chimney: Central interior Brick Corbeled Cap

Chimney: Interior end Concrete Parged

Porch: Wrap-around Wood Columns, Ionic

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 34

Individual Resource Status: Shed

Non-contributing

113 Linden Avenue

133-5040-0110

Church 1905 ca Vernacular 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Multi-light

Door(s): Single Leaf Wood Oval light

Roof: Gable: Front Metal Standing Seam

Chimney: Interior end Brick Corbeled Cap

Portico: Gable Wood Brackets

Individual Resource Status: Church

Contributing

Individual Resource Status: Shed

Contributing

114 Linden Avenue

133-5040-0100

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Vinyl 1/1

Door(s): Single Leaf Wood Paneled

Roof: Pyramidal Concrete Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 3-bay Brick Corbeled Cap

Individual Resource Status: Single Dwelling

Contributing

115 Linden Avenue

133-5040-0111

Single Dwelling 1950 ca Colonial Revival 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Individual Resource Status: Single Dwelling

Non-contributing

Individual Resource Status: Shed

Non-contributing

Individual Resource Status: Shed

Non-contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 35

116 Linden Avenue

133-5040-0099

Single Dwelling 1925 ca Bungalow/Craftsman .5

Foundation: Solid Concrete Block

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 12/1

Door(s): Single Leaf Wood Multi-light

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 2-bay Wood Craftsman

Dormer: Hipped Wood Siding, Vinyl

Individual Resource Status: **Single Dwelling**

Contributing

117 Linden Avenue

133-5040-0112

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick 7-course Amer.Bond

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, clerestory Wood 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Metal Standing Seam

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 3-bay Brick Piers

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-contributing

119 Linden Avenue

133-5040-0113

Single Dwelling 1900 ca Colonial Revival – Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled

Roof: Hipped Metal Shingle

Chimney: Interior end Brick Corbeled Cap

Chimney: Exterior end Concrete Block

Porch: 1-story, 3-bay Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 36

120 Linden Avenue

133-5040-0098

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Piers Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Concrete Tiles

Chimney: Interior end Brick Stucco

Porch: 1-story, 4-bay Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

121 Linden Avenue

133-5040-0114

Single Dwelling 1905 ca Colonial Revival – Queen Anne 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood Multi-light/1

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Front Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Columns, Ionic

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

122 Linden Avenue

133-5040-0097

Single Dwelling 1900 ca Queen Anne 2.5

Foundation: Solid Concrete Parged

Structural System: Frame Wood Siding, Aluminum

Window(s): Fixed Wood 1-light

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Concrete Tiles

Chimney: Interior end Brick Parged

Porch: Wrap-around Wood Columns, Ionic

Individual Resource Status: **Single Dwelling**

Contributing

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 37

Individual Resource Status: Shed

Non-contributing

123 Linden Avenue
133-5040-0115

Single Dwelling 1900 ca Colonial Revival 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Columns, Ionic

Dormer: Hipped Vinyl Siding

Individual Resource Status: Single Dwelling

Contributing

124 Linden Avenue
133-5040-0096

Single Dwelling 1900 ca Colonial Revival - Italianate 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood Multi-light

Door(s): Single Leaf Wood Multi-light

Roof: Gable: Cross Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: Wrap-around Wood Columns, Ionic

Portico: Gable: Front Wood Columns, Ionic

Dormer: Gable Wood Weatherboard

Individual Resource Status: Single Dwelling

Contributing

125 Linden Avenue
133-5040-0116

Single Dwelling 1905 ca Colonial Revival 2.5

Foundation: Solid Concrete Block, Rock-faced

Structural System: Masonry Concrete Block, Rock-faced

Window(s): Sash, double-hung Wood 1/1

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Cross Asphalt Shingle

Chimney: Interior Brick Corbeled Cap

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 38

Porch: Wrap-around Concrete Piers w/ posts

Individual Resource Status: Single Dwelling

Individual Resource Status: Shed

Contributing

Non-contributing

201 Linden Avenue 133-5040-0132

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Queen Anne, ca 1910

This Queen Anne style dwelling is two-and-a-half stories in height and three bays wide. It has a solid rock-faced concrete block foundation supporting a wood-frame structural system re-clad in vinyl siding. The facade features a side entry with dado panels, 1-light side-lights and a 3-light transom, sets of three double-hung wood sash 1/1-light windows with 3-light elliptical transoms, single double-hung wood sash 1/1-light windows, and in the closed front gable, a tripartite window with a half-round diamond-paned transom. The dwelling has wide eaves, an aluminum soffit, and a flat on hip roof which is covered with asphalt shingles. An iron balustrade encloses the flat peak of the roof. One interior brick chimney with a corbeled cap is visible over the roof line. A one-story, five-bay wrap-around porch with wood composite columns is attached to the east (front), north and south elevations. A two-story addition and a sun-porch exist on the west elevation.

Individual Resource Status: Single Dwelling

Individual Resource Status: Garage

Individual Resource Status: Shed

Contributing

Contributing

Non-Contributing

202 Linden Avenue 133-5040-0063

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Queen Anne, ca 1910

This Queen Anne style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards which are currently being replaced with vinyl siding. The facade features an off-center entry, double-hung wood sash 2/2- and 1/1-light windows and 1-light fixed wood sash windows. The dwelling has a canted bay on the second story and a closed front gable peak with a tripartite window, wide eaves, a vinyl-clad soffit, and a hipped roof which is covered with standing seam metal sheets. One interior brick chimney with a corbeled cap is visible. The one-story, four-bay porch with wood composite columns is attached to the west (front) elevation. One- and two-story additions exist on the east elevation.

Individual Resource Status: Single Dwelling

Individual Resource Status: Shed

Individual Resource Status: Pool/Swimming Pool

Contributing

Non-Contributing

Non-Contributing

205 Linden Avenue 133-5040-0133

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1925

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond and decorated with a soldier-course water-table. The facade features a central entry with dado panels, leaded side-lights and a leaded elliptical transom, and double-hung wood sash 6/6-light windows with rowlock sills and wood louvered shutters. The dwelling has overhanging eaves, scroll-sawn brackets, and a hipped roof which is covered with slate shingles. A hipped dormer clad in weatherboards and containing two double-hung wood sash 3/3-light windows. One exterior-end shouldered brick chimney is positioned on the north elevation. A one-story, one-bay front

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 39

gabled portico with a molded wood cornice with returns, an arched opening and fluted columns is attached to the east (front) elevation. The one-story wing with a half-hipped roof attached to the south elevation features a central entry flanked by 8-light wood casement windows.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

206 Linden Avenue 133-5040-0233

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Queen Anne, ca 1905

This Queen Anne-style dwelling is two-and-a-half stories in height and three bays wide. It has a wood-frame structural system clad in weatherboards and a hipped roof which is covered with asphalt shingles. The facade features a two-story canted bay, an off-center entry with a 1-light transom, two 1-light fixed wood sash windows and double-hung wood sash 1/2- and 2/2-light windows, one of which has a half-round 1-light transom. All the windows are set in molded wood surrounds and have wood lug sills. The dwelling has wide eaves, an aluminum clad soffit, one closed front gable and a hipped roof which is covered with asphalt shingles. One interior brick chimney with a corbeled cap is visible. The one-story wrap porch features wood Tuscan columns. A gabled addition exists on the west (rear) elevation.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Outbuilding

Contributing

208 Linden Avenue 133-5040-0221

Primary Resource Information: Multiple dwelling, Stories 2.00, Style: Colonial Revival, ca 1950

This Colonial Revival-style twin dwelling is two stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher bond. The facade features two central entrances and double-hung vinyl sash 8/8-light windows with rowlock sills. The dwelling has a wood fascia and wood cornice, and a side gable roof which is covered with asphalt shingles. A one-story, one-bay front gabled portico with square wood posts is attached to the west (front) elevations. The front gable peak is clad with weatherboards.

Individual Resource Status: Multiple dwelling

Non-Contributing

209 Linden Avenue 133-5040-0135

Primary Resource Information: Multiple dwelling, Stories 2.00, Style: Other, ca 1940

This vernacular-style dwelling is two stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a masonry structural system with brick laid in a 6-course Flemish bond. The facade features a one-story, one-bay projecting front gable entry vestibule with buttressed side walls, rowlock lintel, and molded cornice, two other entrances, and double-hung wood sash 6/6-light windows with rowlock sills. The dwelling has wide eaves and a hipped roof which is covered with asphalt shingles. One interior brick chimney with a corbeled cap is visible over the roof line. A two-story, one-bay partially enclosed and screened porch with a half-hipped roof and brick posts, is attached to the east (front) elevation.

Individual Resource Status: Multiple dwelling

Non-Contributing

Individual Resource Status: Garage

Non-Contributing

210 Linden Avenue 133-5040-0222

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 40

Primary Resource Information: Multiple dwelling, Stories 2.00, Style: Colonial Revival, ca 1950

This Colonial Revival-style twin dwelling is two stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher bond. The facade features two central entrances and double-hung vinyl sash 8/8-light windows with rowlock sills. The dwelling has a wood fascia and wood cornice, and a side gable roof which is covered with asphalt shingles. A one-story, one-bay front gabled portico with square wood posts is attached to the west (front) elevations. The front gable peak is clad with weatherboards.

Individual Resource Status: Multiple dwelling

Non-Contributing

211 Linden Avenue 133-5040-0142

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1905

This Colonial Revival-style dwelling is two-and-a-half stories in height and four bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in lapped weatherboards. The facade features an off-center entry, double-hung wood sash 2/2-light windows set in wood surrounds with projecting sills. The dwelling has wood cornerboards with capitals, wood fascia, molded wood cornice, wide eaves, and a hipped roof which is covered with asphalt shingles. The closed front gable contains a tripartite window with a double-hung wood sash 1/1-light window flanked by 1-light fixed wood sash windows. Two interior end corbeled brick chimneys and one metal stove-pipe are visible above the roof line. The one-story, five-bay screened and partially enclosed wrap porch has wood Ionic columns. A series of one- and two-story additions exist on the west elevation.

Individual Resource Status: Single Dwelling

Contributing

212 Linden Avenue 133-5040-0060

Primary Resource Information: Single Dwelling, Stories 2.00, Style: Queen Anne, ca 1905

This Queen Anne style dwelling is two stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards. The facade features a two-bay wide projecting front gable with an off-center entry with a 1-light transom, and double-hung wood sash 1/1- and 2/2-light windows. The recessed bay also features double-hung wood sash windows. All the windows are set in molded wood surrounds. The dwelling has a molded wood cornice with returns, a wood fascia, wide eaves, a wood soffit, and a cross gable roof which is covered with standing seam metal. One interior-end brick chimney, and one interior brick chimney with a corbeled cap are visible. The one-story, three-bay wrap porch features wood Tuscan columns.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

213 Linden Avenue 133-5040-0141

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1915

This Colonial Revival-style dwelling has an American four-square form and is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in lapped weatherboards. The facade features an off-center entry with a 1-light transom, and double-hung wood sash 1/1-light windows set in wood surrounds. The dwelling has wide eaves, a vinyl-clad soffit, and a hipped roof which is covered with metal standing seam sheets. A hipped dormer clad in weatherboards and containing two double-hung wood sash 1/1-light windows rises from the roof. One interior parged chimney is visible over the roof line. A one-story, two-bay porch with a half-hipped roof, molded entablature, and square battered

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 41

posts, is attached to the east (front) elevation. A one-story addition with a gable roof exists on the west elevation.
Individual Resource Status: **Single Dwelling** **Contributing**
Individual Resource Status: **Shed** **Contributing**

214 Linden Avenue 133-5040-0234

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Queen Anne, ca 1900**

This Queen Anne style dwelling is two-and-a-half stories in height and three bays wide. It has a brick pier foundation supporting a wood-frame structural system clad in new vinyl siding. The facade features a two-story canted bay, an off-center entry, double-hung wood sash 1/1-light windows set in flush wood surrounds, and in the closed front gable peak there is a tripartite window with 1-light fixed wood sash windows flanking a double-hung window. The dwelling has wide eaves and a hipped roof which is covered with asphalt shingles. The one-story 4-bay wrap porch features square wood posts. A wood deck has been added to the west (rear) elevation.

Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Non-Contributing

215 Linden Avenue 133-5040-0140

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Bungalow/Craftsman, ca 1918**

This Craftsman-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards on the first story and wood shingles in the upper stories. The facade features a central entry, sets of three double-hung wood sash 9/1-light windows, double-hung wood sash 6/6-light windows, and one double-hung wood sash 3/3-light window in the gable peak. All the windows are set in wood surrounds with beaded lintels and projecting sills. The dwelling has overhanging eaves, exposed rafters, knee braces, and a front gable roof which is covered with asphalt shingles. One central interior brick chimney with a metal cap is visible over the roof line. The one-story, two-bay porch which extends to form a porte cochere, has square wood battered posts on brick piers.

Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Contributing

216 Linden Avenue 133-5040-0223

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1905**

This Colonial Revival-style dwelling is two stories in height and three bays wide. It has a brick pier foundation which has been infilled with cinder-blocks, supporting a wood-frame structural system clad in vinyl siding. The facade features a projecting front gable two-bays wide with an off-center entry and double-hung wood sash 1/1-light windows with molded wood surrounds which are repeated in the recessed bay. The dwelling has wide eaves, an aluminum clad soffit, an aluminum-clad molded cornice with returns and a cross gable roof which is covered with standing seam metal. One interior brick chimney with a corbeled cap is visible. The one-story, four-bay wrap porch features wood Tuscan columns.

Individual Resource Status: **Single Dwelling**

Contributing

300 Linden Avenue 133-5040-0224

Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Bungalow/Craftsman, ca 1920**

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 42

This Craftsman-style dwelling has a bungalow form and is one-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features an off-center entry flanked by paired and single double-hung wood sash 9/1-light windows set in square-edged wood surrounds. The dwelling has overhanging eaves, an aluminum clad soffit, and a side gable roof which is covered with asphalt shingles. One shed dormer, clad in aluminum siding and containing a set of paired double-hung wood sash 9/1-light windows, rises from the roof. The one-story, three-bay inset porch has been screened and partially enclosed with aluminum siding. The porch feature wood battered posts on brick piers.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

Individual Resource Status: **Shed**

Undetermined

301 Linden Avenue 133-5040-0139

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Queen Anne, ca 1915**

This Queen Anne style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features one projecting front gabled bay, an off-center entry with 3-light side-lights and a fan-light transom, replacement double-hung vinyl sash 6/6-light windows with wood lug sills, and one double-hung wood sash 1/1-light window in the front gable peak. The dwelling has a hipped roof covered with asphalt shingles and ornamented with metal acroteria. Two interior-end brick chimneys with corbeled caps are visible over the roof line. A one-story, four-bay porch with wood Tuscan columns is attached to the east (front), north, and south elevations. A one-story addition exists on the west elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-Contributing

303 Linden Avenue 133-5040-0138

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1910**

This Colonial Revival style dwelling has an American four-square form and is two stories in height and two bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features an off-center entry with a 1-light transom and double-hung wood sash 2/2- and 1/1-light windows set in wood surrounds with lug sills. The dwelling has wide eaves and a hipped roof which is covered with sheets of standing seam metal. One central-interior metal round stove-pipe is visible over the roof line. A one-story, three-bay wrap porch with wood Tuscan columns is attached to the east (front) and north elevations. Two one-story additions exist on the west elevation.

Individual Resource Status: **Single Dwelling**

Contributing

304 Linden Avenue 133-5040-0225

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1925**

This Colonial Revival-style dwelling is two stories in height and three bays wide. It has a brick pier foundation infilled with cinder-blocks supporting a wood-frame structural system clad in German weatherboard. The facade features an off-center entry with a 1-light transom, and replacement double-hung vinyl sash 1/1-light windows set in flush wood surrounds with lug sills. The dwelling

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 43

has overhanging eaves, and a hipped roof which is covered with standing seam metal sheets. One interior-side brick chimney and one partially dismantled exterior-side brick chimney are visible. The one-story, three-bay wrap porch features wood battered posts on brick piers. A one-story addition with a gable roof and one chimney exists on the west (rear) elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Contributing

Individual Resource Status: **Gazebo**

Non-Contributing

305 Linden Avenue 133-5040-0137

Primary Resource Information: **Multiple dwelling, Stories 2.00, Style: Other, ca 1935**

This vernacular-style duplex is two stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in wood German weatherboards. The facade features a side entry and paired sets of double-hung wood sash 6/6-light windows set in beaded wood surrounds. A pedimented hood with wood brackets shades the entrance. The dwelling has a molded wood cornice, wide eaves, and a hipped roof which is covered with sheets of standing seam metal. Two interior brick chimneys with corbeled caps are visible. A two-story, one-bay screened porch with a half-hipped roof and square wood posts is attached to the east (front) elevation.

Individual Resource Status: **Multiple dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

306 Linden Avenue 133-5040-0014

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1930**

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a side entry and double-hung wood sash 6/6-light windows set in aluminum clad surrounds. An arched pediment supported by brackets shades the entrance. The dwelling has wide eaves, an aluminum clad soffit and a side gable roof which is covered with standing seam metal sheets. One exterior-end corbeled brick chimney with a corbeled cap is located on the north elevation. A one-story addition with a shed roof exists on the east (rear) elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

307 Linden Avenue 133-5040-0235

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1910**

This Colonial Revival-style dwelling has an American four-square form and is two stories in height and two bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a side entry and double-hung wood sash 2/2- and 1/1-light windows set in wood surrounds. The dwelling has wide eaves and a hipped roof which is covered with sheets of standing seam metal. One interior end brick chimney with a corbeled cap is visible. A one-story, two-bay porch with a half-hipped roof and wood Tuscan columns is attached to the east elevation. A one-story addition with a half-hipped roof exists on the west elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 44

Individual Resource Status: Shed

Non-Contributing

308 Linden Avenue 133-5040-0226

Primary Resource Information: Single Dwelling, Stories 2.00, Style: Other, ca 1928

This vernacular-style dwelling contains Craftsman and Colonial Revival style details. The dwelling is two stories in height and three bays wide. It has a wood-frame structural system clad in aluminum siding and a hipped roof which is covered with standing seam metal. The facade features an off-center entry and double-hung wood sash 1/1-light windows set in aluminum clad surrounds. The windows in the upper story are shaded by metal awnings. The dwelling has wide eaves and an aluminum clad soffit. One central interior brick chimney with a corbeled cap is visible over the roof line. A one-story, three-bay porch wrap porch with a half-hipped roof, metal awnings, and wood battered posts on brick piers, is attached to the east (front) and south elevations. A portion of the porch on the south elevation has been enclosed.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

309 Linden Avenue 133-5040-0150

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1930

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features a central entry flanked by double-hung wood sash 6/6-light windows set in aluminum clad surrounds and repeated in the upper story. The dwelling has wide eaves and a side gable roof covered with sheets of standing seam metal. One central-interior brick chimney with a corbeled cap is visible above the roof line. A one-story, one-bay front gabled portico with a molded wood cornice and wood Tuscan columns.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Non-Contributing

310 Linden Avenue 133-5040-0227

Primary Resource Information: Single Dwelling, Stories 1.00, Style: Other, ca 1955

This vernacular-style dwelling is one story in height and four bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher bond. The facade features two entrances and double-hung wood sash 6/6-light windows and one fixed wood sash 24-light window, all of which have rowlock sills. The building has wide eaves, a wood soffit, and a hipped roof which is covered with asphalt shingles. Two one-story, one-bay inset porches with metal posts exist on the west elevation.

Individual Resource Status: Single Dwelling

Non-Contributing

311 Linden Avenue 133-5040-0228

Primary Resource Information: Single Dwelling, Stories 1.00, Style: Other, ca 1945

This vernacular-style dwelling is one story in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher bond. The facade features a central entry flanked by sets of double-hung wood sash 4/4-light windows with wood sills and a wood louvered vent in the upper story. A front gabled porch with brick piers and a

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 45

soldier-course arched opening shades the entrance. The dwelling has a hipped roof covered with asphalt shingles. One central interior brick chimney is visible over the roof line. A one-story, one-bay porch with a flat roof with a wooden balustrade and metal posts is attached to the east (front) elevation.

Individual Resource Status: Single Dwelling

Non-Contributing

Individual Resource Status: Garage

Non-Contributing

312 Linden Avenue 133-5040-0229

Primary Resource Information: Single Dwelling, Stories 2.00, Style: Other, ca 1910

This vernacular-style dwelling is two stories in height and two bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in asbestos shingles. The facade features a projecting bay, an off-center entry and double-hung wood sash 2/2-light windows set in molded wood surrounds. The dwelling has a wood cornice, wide eaves, and a hipped roof which is covered with asphalt shingles. One interior-side brick chimney is visible. The one-story, three-bay screened porch features square wood posts and a metal awning.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

313 Linden Avenue 133-5040-0230

Primary Resource Information: Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1955

This Colonial Revival-style dwelling has a Cape Cod form and is one story in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features a central entry flanked by double-hung wood sash 8/8-light windows with rowlock sills. The dwelling has a molded wood cornice and a side gable roof which is covered with asphalt shingles. One central interior brick chimney is visible over the roof line. A one-story, one-bay front gabled porch with a metal post. The gable is covered with vertical boards.

Individual Resource Status: Single Dwelling

Non-Contributing

314 Linden Avenue 133-5040-0231

Primary Resource Information: Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1910

This Colonial Revival-style dwelling has an American four-square form and is two stories in height and two bays wide. It has a wood-frame structural system clad in aluminum siding and a hipped roof covered with standing seam metal. The facade features a side entry with a 1-light transom, double-hung wood sash 1/1- and 2/2- light windows, and wide eaves. One interior-end brick chimney with a corbeled cap is visible. The one-story, two-bay porch has a half-hipped roof supported by metal posts. A one-story addition exists on the east (rear) elevation.

Individual Resource Status: Single Dwelling

Contributing

315 Linden Avenue 133-5040-0232

Primary Resource Information: Single Dwelling, Stories 1.50, Style: Other, ca 1955

This vernacular-style dwelling is one-and-a-half stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features a central entry flanked by double-hung vinyl sash 1/1-light windows with rowlock sills, and a 6-light fan-light in the vinyl siding clad gable. The dwelling has a cross gable

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 46

roof which is covered with asphalt shingles. One central interior brick chimney is visible over the roof line. A one-story, two-bay porch with a shed roof supported by metal posts is attached to the east (front) elevation.

Individual Resource Status: Single Dwelling

Non-Contributing

Individual Resource Status: Garage

Non-Contributing

401 Linden Avenue 133-5040-0149

Primary Resource Information: Commerce/Trade, Stories 1.00, Style: Other, ca 1915

This building is one story in height and ten bays wide. It has a solid stretcher-bond brick foundation supporting a masonry structure with brick laid in a 7-course Flemish bond. The original seven bays of the building features boarded-up windows with square-edged wood lintels and sills, a one-leaf wood paneled roll-up door and has a stepped parapet and a flat roof. A brick three-bay addition with one double-hung wood sash 9/9-light window with a rowlock sill, two one-leaf wood paneled doors, and a mansard roof. Two interior brick chimneys are visible over the roof line.

Individual Resource Status: Commerce/Trade

Contributing

Maryland Avenue

605 Maryland Avenue 133-5040-0193

Primary Resource Information: Single Dwelling, Stories 1.00, Style: Other, ca 1955

This vernacular-style twin dwelling is one story in height and six bays wide. It has a solid stretcher-bond brick foundation supporting a masonry structural system with brick laid in a stretcher bond. The facade features a side entry, and double-hung wood sash 2/2-light windows with rowlock sills. The building has a vinyl clad boxed cornice, wide eaves, and a cross gable roof which is covered with asphalt shingles.

Individual Resource Status: Multiple dwelling

Non-Contributing

Individual Resource Status: Shed

Non-Contributing

North Broad Street

103 North Broad Street

133-5040-0012

Single Dwelling 1900 ca Vernacular 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Brick-tex Siding

Walls: Frame Wood Siding, Vinyl

Window(s): Not Visible None Listed Not visible

Door(s): Single Leaf None Listed Not visible

Roof: Gable: Cross Metal Standing Seam

Chimney: Interior end Brick Stretcher Bond

Chimney: Exterior end Brick Cap, Metal

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 47

Porch: 1-story, 2-bay Wood Post

Individual Resource Status: Single Dwelling

Contributing

Pender Street

113 Pender Street

133-5040-0058

Single Dwelling 1875 ca Italianate 2.0

Foundation: Piers Brick Stretcher Bond

Structural System: Frame Wood Shingle, Asbestos

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable: Side Metal Standing Seam

Chimney: Exterior end Brick Stretcher Bond

Porch: 1-story, 3-bay Wood Columns, Ionic

Individual Resource Status: Single Dwelling

Individual Resource Status: Garage

Contributing

Contributing

116 Pender Street

133-5040-0062

Single Dwelling 1875 ca Italianate 2.0

Foundation: Piers Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Metal Standing Seam

Chimney: Interior end Brick Parged

Porch: Wrap-around Wood Craftsman

Individual Resource Status: Single Dwelling

Individual Resource Status: Shed

Contributing

Contributing

117 Pender Street

133-5040-0059

Multiple dwelling 1925 ca Bungalow/Craftsman 2.0

Foundation: Solid Brick Flemish Bond

Structural System: Masonry Brick Flemish Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Metal Standing Seam

Chimney: Interior end Brick Corbeled Cap

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 48

Porch: 2-story, 3-bay Wood Post

Individual Resource Status: Multiple Dwelling

Individual Resource Status: Garage

Contributing

Contributing

122 Pender Street

133-5040-0061

Single Dwelling 1895 ca Italianate 2.0

Foundation: Solid Brick 3-course Amer.Bond Historic

Structural System: Masonry Brick 3-course Flem.Bond

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Exterior end Brick Corbeled Cap

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 1-bay Wood Enclosed

Individual Resource Status: Single Dwelling

Individual Resource Status: Garage

Contributing

Contributing

St. James Avenue

105 St. James Avenue

133-5040-0085

Church 1938 Colonial Revival 1.0

Foundation: Solid Brick Flemish Bond

Structural System: Masonry Brick Flemish Bond

Window(s): Octagonal Wood 16-light

Window(s): Sash, double-hung Wood 16/16

Window(s): Fixed Wood 16-light

Door(s): Double leaf Wood 3-panel

Roof: Gable: Front Wood Shingle

Chimney: Exterior end Brick Corbeled Cap

Individual Resource Status: Church

Contributing

106 St. James Avenue

133-5040-0083

Single Dwelling 1930 ca Bungalow/Craftsman 1.5

Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood 6-panel

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 49

Roof: Hipped Asphalt Shingle

Chimney: Exterior end Brick Stretcher Bond

Porch: 1-story, 2-bay Brick Post

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

107 St. James Avenue

133-5040-0086

Single Dwelling 1900 ca Colonial Revival 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled

Roof: Gable: Side Metal Standing Seam

Chimney: Exterior end Brick Corbeled Cap

Chimney: Interior end Brick Corbeled Cap

Portico: Gable Wood Post

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

108 St. James Avenue

133-5040-0082

Multiple dwelling 1935 ca Colonial Revival 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Brick Veneer, Brick

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Concrete Tiles

Chimney: Central interior Brick Stretcher Bond

Porch: Hipped Brick Piers

Individual Resource Status: Multiple Dwelling

Contributing

Individual Resource Status: Garage

Contributing

Individual Resource Status: Garage

Contributing

109 St. James Avenue

133-5040-0087

Single Dwelling 1900 ca Italianate 2.0

Foundation: Solid Brick Stretcher Bond

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 50

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Vinyl 6/6

Door(s): Single Leaf Wood 6-panel

Roof: Hipped Asphalt Shingle

Chimney: Interior end Brick Stretcher Bond

Porch: 1-story, 3-bay Wood Posts, Turned

Individual Resource Status: **Single Dwelling**

Contributing

110 St. James Avenue

133-5040-0081

Single Dwelling 1920-1935 Bungalow/Craftsman 1.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Front Asphalt Shingle

Chimney: Exterior end Brick Stretcher Bond

Porch: Gable Brick Piers

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

111 St. James Avenue

133-5040-0088

Single Dwelling 1895 ca Queen Anne 2.5

Foundation: Piers w/ infill Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood Oval light

Window(s): Fixed Wood 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Cross Metal Standing Seam

Chimney: Interior end Brick Stretcher Bond

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-contributing

112 St. James Avenue

133-5040-0080

Multiple dwelling 1940 ca Colonial Revival 2.0

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 51

Foundation: Solid Brick Stretcher Bond
Structural System: Masonry Brick Stretcher Bond
Window(s): Sash, double-hung Wood 6/6
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Hipped Concrete Shingle
Chimney: Central interior Brick Corbeled Cap
Porch: 2-story Brick Piers
Individual Resource Status: **Multiple Dwelling**
Individual Resource Status: **Garage**

Non-contributing
Non-contributing

113 St. James Avenue

133-5040-0089

Single Dwelling 1900 ca Queen Anne 2.0
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Vinyl
Window(s): Sash, double-hung Wood 1/1
Window(s): Fixed Wood 1-light
Door(s): Single Leaf Wood Paneled w/ lights
Roof: Hipped Asphalt Shingle
Chimney: Interior end Brick Corbeled Cap
Porch: Wrap-around Wood Tuscan Columns
Individual Resource Status: **Single Dwelling**

Contributing

115 St. James Avenue

133-5040-0090

Single Dwelling Queen Anne 1900ca 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard
Roof: Gable: Cross Asphalt Shingle
Chimney: Central interior Brick Corbeled Cap
Door(s): Single Leaf Wood Paneled w/ lights
Window(s): Sash, double-hung Wood 2/2
Porch: Wrap-around Wood Tuscan Columns
Individual Resource Status: **Single Dwelling**

Contributing

116 St. James Avenue

133-5040-0079

Single Dwelling Colonial Revival 1910ca 2.0
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Aluminum

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 52

Roof: Hipped Metal Standing Seam
Chimney: Interior end Brick Corbeled Cap
Door(s): Single Leaf Wood Oval light
Door(s): Single Leaf Wood 1-light
Window(s): Sash, double-hung Wood 2/2
Porch: Wrap-around Wood Tuscan Columns
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Contributing

117 St. James Avenue

133-5040-0091

Single Dwelling Other 1980ca 1.0
Foundation: Solid Concrete Block, Cinder
Structural System: Frame Wood Siding, Vinyl
Roof: Gable: Side Asphalt Shingle
Door(s): Single Leaf Wood Paneled
Window(s): Sash, double-hung Vinyl 1/1
Portico: 1-story, 1-bay Wood Post
Individual Resource Status: **Single Dwelling**

Non-Contributing

118 St. James Avenue

133-5040-0078

Single Dwelling Colonial Revival 1925ca 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Masonry Brick Stretcher Bond
Roof: Hipped Asphalt Shingle
Chimney: Central interior Brick Stretcher Bond
Dormer: Hipped Asphalt Shingle
Door(s): Single Leaf Wood Multi-light
Window(s): Sash, double-hung Wood 1/1
Window(s): Sash, double-hung Wood 24/1
Porch: 1-story, 3-bay Wood Posts, Tuscan
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Contributing

119 St. James Avenue

133-5040-0092

Multiple dwelling Queen Anne 1905 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Vinyl

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 53

Roof: Hipped Metal Standing Seam
Chimney: Interior end Brick Corbeled Cap
Door(s): Single Leaf Wood Flush
Door(s): Single Leaf Wood Paneled w/ lights
Porch: 2-story, 3-bay Wood Post
Window(s): Fixed Wood 1-light
Window(s): Sash, double-hung Wood 1/1
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Contributing

120 St. James Avenue

133-5040-0077

Single Dwelling Colonial Revival 1935ca 1.5
Foundation: Solid Brick Flemish Bond
Structural System: Masonry Brick Flemish Bond
Roof: Gable: Side Asphalt Shingle
Chimney: Exterior end Brick Corbeled Cap
Dormer: Shed Asphalt Shingle
Portico: Gable Wood Tuscan Columns
Door(s): Single Leaf Wood 6-panel
Window(s): Sash, double-hung Wood 6/6
Window(s): Sash, double-hung Wood 4/4
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Contributing

121 St. James Avenue

133-5040-0093

Single Dwelling Colonial Revival 1900ca 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Aluminum
Roof: Pyramidal Asphalt Shingle
Door(s): Single Leaf Wood Multi-light
Window(s): Fixed Wood 1-light
Window(s): Sash, double-hung Wood 25/1
Porch: 1-story, 1-bay Wood Post
Porch: 1-story, 3-bay Wood Post
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

Contributing
Contributing

123 St. James Avenue

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 54

133-5040-0094

Single Dwelling Classical Revival 1905ca 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Roof: Pyramidal Metal Shingle

Chimney: Interior end Brick Stretcher Bond

Dormer: Hipped Wood Weatherboard

Door(s): Single Leaf Wood 15-light

Window(s): Sash, double-hung Wood 4/1

Window(s): Sash, double-hung Wood 9/1

Porch: 1-story, 3-bay Wood Post

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Shed**

Individual Resource Status: **Shed**

Contributing

Non-contributing

Non-contributing

124 St. James Avenue

133-5040-0076

Single Dwelling Colonial Revival 1905 2.0

Foundation: Solid Brick Stretcher Bond

Roof: Pyramidal Asphalt Shingle

Structural System: Frame Wood Siding, Vinyl

Door(s): Single Leaf Metal 1-light

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Wood 1/1

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

125 St. James Avenue

133-5040-0095

Single Dwelling Queen Anne 1905ca 2.5

Foundation: Solid Brick Stretcher Bond

Roof: Gable: Cross Metal Shingle

Structural System: Frame Wood Siding, Vinyl

Chimney: Interior end Brick Stretcher Bond

Chimney: Central interior Brick Stretcher Bond

Door(s): Single Leaf Wood Multi-light

Door(s): Single Leaf Wood Paneled w/ lights

Window(s): Sash, double-hung Wood 1/1

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 55

Window(s): Fixed Wood Multi-light
Window(s): Sash, double-hung Wood 25/1
Porch: Wrap-around Wood Post
Individual Resource Status: Single Dwelling
Individual Resource Status: Shed

**Contributing
Non-contributing**

Smith Street

509 Smith Street 133-5040-0212

Primary Resource Information: Church, Stories 2.00, Style: Colonial Revival,

This Colonial Revival-style church has been converted into an apartment building. The structure is two stories in height and three bays wide. It has a solid rock-faced concrete block foundation and a masonry structural system built with rock-faced concrete-blocks and a brick stretcher-bond facade. The facade features a central recessed entry with a 2-light transom, double-hung wood sash 2/2 windows, and double-hung vinyl sash 6/6-light windows. All the windows have rowlock sills and splayed brick lintels. The building has wide eaves, a wood soffit, and a hipped roof which is covered with sheets of standing seam metal. One interior-end brick chimney with a corbeled cap is visible.

Individual Resource Status: Church

Contributing

709 Smith Street

133-5040-0153

Single Dwelling Colonial Revival 1935ca 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Roof: Gable: Side Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Chimney: Exterior Wood Stretcher Bond

Dormer: Gable Wood Weatherboard

Door(s): Single Leaf Wood Paneled

Window(s): Sash, double-hung Wood 6/6

Window(s): Sash, double-hung Wood 8/8

Portico: 1-story, 1-bay Wood Tuscan Columns

Individual Resource Status: Single Dwelling

Individual Resource Status: Shed

Individual Resource Status: Garage

Individual Resource Status: Garage

**Contributing
Contributing
Contributing
Non-contributing**

711 Smith Street

133-5040-0155

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 56

Single Dwelling Colonial Revival 1935ca 2.5
Structural System: Masonry Brick Stretcher Bond
Foundation: Solid Brick Stretcher Bond
Roof: Gable: Side Asphalt Shingle
Chimney: Central interior Brick Corbeled Cap
Chimney: Exterior Brick Stretcher Bond
Door(s): Double leaf Wood 20-light
Door(s): Single Leaf Wood Paneled
Window(s): Sash, double-hung Wood 6/6
Dormer: Gable Wood Weatherboard
Portico: 1-story, 1-bay Asphalt Shingle
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

Contributing
Non-contributing

South Broad Street

100 South Broad Street
133-5040-0126

Single Dwelling Colonial Revival 1900ca 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard
Roof: Hipped Metal Standing Seam
Chimney: Interior Brick Corbeled Cap
Chimney: Interior Brick Reconstructed
Dormer: Gable: Front Wood Weatherboard
Door(s): Single Leaf Wood Paneled w/ lights
Window(s): Sash, double-hung Wood 16/2
Window(s): Sash, double-hung Wood 16/1
Window(s): Sash, double-hung Wood Multi-light/2
Window(s): Sash, double-hung Wood Multi-light/1
Porch: Wrap-around Wood Columns, Ionic
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Non-contributing

102 South Broad Street
133-5040-0125

Single Dwelling Queen Anne 1900ca 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 57

Roof: Hipped Metal Shingle

Chimney: Interior Brick Corbeled Cap

Door(s): Single Leaf Wood Paneled

Window(s): Sash, double-hung Vinyl 1/1

Window(s): Sash, double-hung Wood Multi-light/1

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

104 South Broad Street

133-5040-0124

Single Dwelling Colonial Revival 1907 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Roof: Hipped Asphalt Shingle

Chimney: Interior Brick Corbeled Cap

Chimney: Central interior Brick Corbeled Cap

Door(s): Single Leaf Wood Paneled w/ lights

Window(s): Fixed Lead Multi-light

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood 1-light

Porch: 2-story, 3-bay Wood Column, Corinthian

Dormer: Gable Wood Weatherboard

Porte Cochere: 1-story, 2-bay Wood Column, Corinthian

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

107 South Broad Street

133-5040-0131

Single Dwelling Colonial Revival 1907 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Roof: Gable: Cross Metal Standing Seam

Chimney: Interior end Brick Reconstructed

Chimney: Central interior Brick Corbeled Cap

Door(s): Single Leaf Wood Paneled w/ lights

Porch: Wrap-around Wood Tuscan Columns

Window(s): Sash, double-hung Wood 2/2

Window(s): Fixed Wood 1-light

Individual Resource Status: **Single Dwelling**

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 58

Individual Resource Status: **Shed**

Non-contributing

108 South Broad Street

133-5040-0123

Single Dwelling Queen Anne 1895 2.5

Foundation: Solid None Listed Not visible

Structural System: Frame Wood Weatherboard

Roof: Hipped Concrete Tiles

Chimney: Interior end Brick Parged

Chimney: Central interior Brick Parged

Door(s): Single Leaf Wood Paneled

Door(s): Single Leaf Wood Paneled w/ lights

Window(s): Sash, double-hung Wood Multi-light/1

Window(s): Sash, double-hung Wood 3/3

Window(s): Fixed Wood Multi-light

Window(s): Fixed Wood 4-light

Porch: 1-story, 4-bay Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Non-contributing

112 South Broad Street

133-5040-0122

Single Dwelling Colonial Revival 1920ca 2.5

Foundation: Solid None Listed Stucco

Roof: Hipped Asphalt Shingle

Chimney: Central interior Brick Cap, Rowlock

Chimney: Exterior side Brick Shouldered

Structural System: Frame Wood Stucco

Door(s): Single Leaf Wood Paneled w/ lights

Window(s): Sash, double-hung Wood 9/1

Window(s): Sash, double-hung Wood 6/1

Porch: Wrap-around Concrete Piers

Porte Cochere: 1-story, 1-bay Concrete Piers

Dormer: Hipped Concrete Stucco

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

114 South Broad Street

133-5040-0121

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 59

Single Dwelling Colonial Revival 1900ca 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard
Roof: Hipped Asphalt Shingle
Chimney: Central interior Brick Parged
Door(s): Single Leaf Wood Paneled w/ lights
Window(s): Sash, double-hung Wood 1/1
Porch: Wrap-around Wood Columns, Ionic
Individual Resource Status: **Single Dwelling**

Contributing

116 South Broad Street

133-5040-0120

Single Dwelling Queen Anne 1900ca 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Vinyl
Roof: Gable: Cross Asphalt Shingle
Chimney: Interior end Brick Corbeled Cap
Door(s): Single Leaf Wood Paneled w/ lights
Window(s): Sash, double-hung Wood 2/2
Window(s): Fixed Wood 1-light
Window(s): Sash, double-hung Vinyl 1/1
Window(s): Fixed Vinyl 1-light
Window(s): Sash, double-hung Wood 6/6
Porch: Wrap-around Wood Columns, Ionic
Porch: 1-story, 1-bay Wood Screened
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing

Non-contributing

117 South Broad Street

133-5040-0134

Single Dwelling Colonial Revival 1904-1907 2.5
Chimney: Interior end Brick Flemish Bond
Foundation: Solid Brick Not visible
Roof: Gable: Side Slate Tiles
Structural System: Frame Wood Weatherboard
Chimney: Exterior Brick Flemish Bond
Window(s): Sash, double-hung Wood 9/9
Window(s): Sash, double-hung Wood 6/9

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 60

Door(s): Single Leaf Wood Paneled
Dormer: Gable Wood Weatherboard
Portico: 1-story, 1-bay Wood Tuscan Columns
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

**Contributing
Contributing**

118 South Broad Street

133-5040-0119

Single Dwelling Bungalow/Craftsman 1920-1935 1.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard
Roof: Gable: Side Asphalt Shingle
Chimney: Central interior Brick Stretcher Bond
Door(s): Single Leaf Wood Paneled w/ lights
Window(s): Sash, double-hung Wood 6/1
Porch: 1-story-3-bay Wood Craftsman
Dormer: Shed Wood Weatherboard
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

**Contributing
Non-contributing**

120 South Broad Street

133-5040-0118

Single Dwelling Colonial Revival 1895ca 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Aluminum
Roof: Gable and Hipped Metal Standing Seam
Chimney: Interior Brick Corbeled Cap
Door(s): Single Leaf Wood Paneled w/ lights
Window(s): Sash, double-hung Wood 2/2
Window(s): Sash, double-hung Wood 1/1
Porch: Wrap-around Wood Columns, Tuscan
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Shed**

**Contributing
Non-contributing**

122 South Broad Street

133-5040-0117

Single Dwelling Colonial Revival 1895ca 2.5
Foundation: Solid Brick Stretcher Bond Queen Anne
Structural System: Frame Wood Siding, Aluminum
Door(s): Single Leaf Wood Paneled w/ lights

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 61

Window(s): Sash, double-hung Wood Multi-light/1

Window(s): Sash, double-hung Wood 1/1

Window(s): Sash, double-hung Vinyl 1/1

Porch: Wrap-around Wood Columns, Ionic

Roof: Gable and Hipped Metal Shingle

Chimney: Central interior Brick Stretcher Bond

Chimney: Interior Brick Corbeled Cap

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Shed**

Individual Resource Status: **Shed**

Contributing

Non-contributing

Non-contributing

200 South Broad Street 133-5040-0168

Primary Resource Information: **Church, Stories 1.00, Style: Other, ca 1910**

This vernacular-style church is one story in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features a recessed central entry with a 2-leaf pressed vertical board door set in a stone surround with buttresses flanked by stained and leaded lancet windows, also in stone surrounds. Above the entrance are three stained and leaded lancet windows. The building has a front gable roof which is covered with slate shingles. One interior brick chimney is visible over the roof line. A two-story addition exists on the east elevation.

Individual Resource Status: **Church**

Contributing

202 South Broad Street 133-5040-0169

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Queen Anne, ca 1905**

This Queen Anne style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features an off-center entry set in a wood surround with dado panels and 1-light side-lights and double-hung wood sash 2/2-light windows set in aluminum clad square-edged surrounds. The projecting closed front gabled bay contains a lancet louvered vent. The entrance bay is topped by a pyramidal roof while the remainder of the dwelling has wide eaves, an aluminum clad soffit, and a cross gable roof which is covered with asphalt shingles. One interior brick chimney is visible over the roof line. A one-story, one-bay porch with wood fluted posts, is attached to the west (front) elevation.

Individual Resource Status: **Single Dwelling**

Contributing

203 South Broad Street

133-5040-0136

Colonial Revival 1905ca Single Dwelling 2.5

Foundation: Solid Brick Stretcher Bond

Roof: Hipped Slate Tiles

Structural System: Frame Wood Weatherboard

Chimney: Interior Brick Corbeled Cap

Door(s): Single Leaf Wood Paneled w/ lights

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 62

Door(s): Single Leaf Wood Paneled
Window(s): Sash, double-hung Wood 12/1
Dormer: Gable Wood Weatherboard
Portico: 2-story, 1-bay Wood Columns, Ionic
Individual Resource Status: Single Dwelling
Individual Resource Status: Garage

Contributing
Non-contributing

204 South Broad Street 133-5040-0170

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1910

This Colonial Revival-style dwelling has an American four-square form and is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features an off-center entry flanked by double-hung wood sash 1/1-light windows set in aluminum clad surrounds which are repeated in the upper stories. The dwelling has wide eaves and a flat-on-hipped roof which is covered with metal pressed shingles. One hipped dormer clad in aluminum siding and containing two double-hung wood sash 1/1-light windows, rises from the roof. One interior-side brick chimney with a corbeled cap is visible over the roof line. A one-story, four-bay porch with wood Tuscan columns extends over the driveway to form a porte cochere. A two-story addition, attached to the east elevation, doubled the size of the dwelling.

Individual Resource Status: Single Dwelling
Individual Resource Status: Garage

Contributing
Contributing

207 South Broad Street 133-5040-0167

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Queen Anne, ca 1900

This Queen Anne style dwelling is two-and-a-half stories in height and four bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features an off-center entry with 2-light side-lights and a fan-light transom flanked by replacement double-hung vinyl sash 1/1-light windows and one diamond-light stained glass window. The second story has a canted bay topped by a front gable roof with a closed tympanum and contains a double-hung vinyl sash 1/1-light window surrounded by half-round fixed 1-light windows. The dwelling has wide eaves and a hipped roof which is covered with pressed metal shingles. Three interior brick chimneys are visible over the roof line. A one-story, six-bay wrap porch with wood Ionic columns is attached to the east (front) north and south elevations. The porch features a dentiled entablature and a front gable at the porch entry.

Individual Resource Status: Single Dwelling
Individual Resource Status: Garage

Contributing
Non-Contributing

206 South Broad Street 133-5040-0174

Primary Resource Information: Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1905

This Colonial Revival-style dwelling is two-and-a-half stories in height and four bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards. The facade features two off-center entrances with 1-light transoms and double-hung wood sash 2/2-light windows and 1-light wood sash fixed windows set in square-edged wood surrounds. The dwelling has a molded wood cornice with returns, overhanging eaves, and a cross gable roof which is covered with

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 63

pressed metal shingles. Two interior brick chimneys, one with a corbeled cap and one with a concrete cap, are visible over the roof line. A one-story, four bay porch with wood Tuscan columns is attached to the west (front) elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

208 South Broad Street 133-5040-0177

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1900**

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards. The asymmetrical facade features an off-center entry with a 1-light transom flanked by double-hung wood sash 2/2-light windows set in square-edged wood surrounds. The second story has a projecting canted bay topped with a front gable roof. The gable peak contains one 1-light fixed wood sash window. The dwelling has a wood cornice, wide eaves, and a hipped roof which is covered with sheets of standing seam metal. One interior-end brick chimney with a corbeled cap is visible. A one-story, five-bay wrap porch with replacement metal posts is attached to the west (front) and south elevations. A one-story addition exists on the east elevation.

Individual Resource Status: **Single Dwelling**

Contributing

210 South Broad Street 133-5040-0156

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Queen Anne, ca 1900**

This Queen Anne-style dwelling is two stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards. The facade features a two-story projecting bay, two one-leaf wood paneled doors with lights and double-hung wood sash 2/2- and 1/1-light windows. All the openings are set in square-edged wood surrounds. The dwelling has a molded wood cornice, wide eaves, a wood soffit, and a complex roof covered with asphalt shingles. One interior brick chimney is visible over the roof line. A one-story, three-bay porch with wood Tuscan columns supporting a half-hipped roof covered with sheets of standing-seam metal, is attached to the west (front) elevation. The dwelling appears to have been constructed as a single-family dwelling and later converted to a duplex.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Contributing

211 South Broad Street 133-5040-0166

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1925**

This Colonial Revival-style dwelling has Craftsman style detailing and is two-and-a-half stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features a central entry set in a wood surround with multiple light sidelights and transom flanked by double-hung wood sash 6/6-light windows which are repeated in the upper story. The windows have hinged wooden louvered shutters. The dwelling has wide eaves and a side gable roof which is covered with asphalt shingles. Two shed dormers, clad in asbestos shingles and containing double-hung wood sash 3/3-light windows, rise from the roof. One exterior-end brick chimney is positioned on the southwest elevation. A one-story, one-bay porch with a shed roof supported by wood posts, wood brackets, and lattice. A one-story, one-bay screened side-porch with a

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 64

shed roof is attached to the southwest elevation. A one-story addition with a flat roof exists on the northeast elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

212 South Broad Street 133-5040-0157

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1925**

This Colonial Revival-style dwelling is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in beaded aluminum siding. The facade features a central entry set in a wood surround with dado panels, 1-light side-lights and an 8-light transom flanked by double-hung wood sash 4/4- and 12/1-light windows set in square-edged surrounds with wood sills. The dwelling has wide eaves, applied dentils, and a side gable roof which is covered with asphalt shingles. Three gabled dormers clad in aluminum siding and containing double-hung wood sash 12/1-light windows, rise from the roof. One exterior-end shouldered brick chimney with a corbeled cap is positioned on the southwest elevation. A one-story, one-bay front gabled portico with a molded cornice and supported by wood Tuscan columns is attached to the northwest (front) elevation. A one-story, one-bay porte cochere with a half-hipped roof and wood Tuscan columns extends from the southwest elevation. A one-story, one-bay screened porch with a half-hipped roof exists on the northeast elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

217 South Broad Street 133-5040-0165

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Queen Anne, ca 1900**

This Queen Anne style dwelling is two stories in height and five bays wide. It has a solid brick foundation supporting a wood-frame structural system clad in weatherboards. The asymmetrical facade features an off-center entry with a 1-light transom, double-hung wood sash 2/2- and 1/1-light windows set in wood surrounds, and a canted bay with turret at the east corner. The dwelling has wood cornerboards, a wood dentiled cornice, and a hipped roof which is covered with sheets of metal standing seam. Three interior brick chimneys, two of which have corbeled caps, are visible over the roof line. A one-story, four-bay wrap porch with turned wood posts is attached to the northeast, southeast, and southwest elevations.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Non-Contributing

300 South Broad Street 133-5040-0158

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1910**

This Colonial Revival-style dwelling has an American 4-square form and is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features an off-center entry set in a wood surround with a 1-light transom and double-hung wood sash 2/2-, 1/1- and 14/1- light windows set in square-edged surrounds with lug sills. The dwelling has wide eaves, an aluminum clad cornice and a hipped roof which is covered with pressed metal shingles. One asymmetrically placed gabled dormer with one fixed wood sash 1-light window. Two interior deteriorating brick chimneys with corbeled caps are visible over the roof line. A one-story, three-bay wrap porch with wood composite columns is attached to the northwest (front) and northeast elevations.

Individual Resource Status: **Single Dwelling**

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 65

Individual Resource Status: **Garage**

Contributing

301 South Broad Street 133-5040-0164

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1910**

This Colonial Revival-style dwelling is two stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in wide lapped weatherboards. The facade features a central entry with side-lights and a transom, and double-hung wood sash 2/2- and 6/6-light windows. The dwelling has a wood molded cornice and a side gable roof which is covered with sheets of standing seam metal. A central gable, featuring fish-scale shingles and a diamond vent, rises from the roof. Three interior-end brick chimneys with corbeled caps are visible. A one-story, six-bay porch with a half-hipped roof, central gable peak, and wood Tuscan columns, is attached to the east (front) elevation. A one-story addition exists on the west elevation, and a porch has been enclosed on the north elevation.

Individual Resource Status: **Single Dwelling**

Contributing

302 South Broad Street 133-5040-0159

Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Bungalow/Craftsman, ca 1925**

This Craftsman-style dwelling has a bungalow form and is one-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features an off-center entry flanked by double-hung wood sash 6/1- and 9/1-light windows. The dwelling has wide eaves, cut-away brackets, exposed rafters, and a side gable roof which is covered with asphalt shingles. One shed dormer, clad in weatherboards and containing two double-hung wood sash 6/1-light windows, rises from the roof. One interior-end brick chimney with a corbeled cap is visible over the roof line. A one-story, three-bay inset porch with wood battered posts on brick piers exists on the west (front) elevation. A one-story screened porch with a shed roof is attached to the east elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

304 South Broad Street 133-5040-0152

Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Bungalow/Craftsman, ca 1925**

This Craftsman-style dwelling has a bungalow form and is one-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a masonry structural system with brick laid in a 6-course Flemish bond. The facade features an off-center entry flanked by double-hung wood sash 6/1-light windows with rowlock sills. The dwelling has overhanging eaves, an aluminum clad soffit and a side gable roof which is covered with asphalt shingles. One gabled dormer, clad in aluminum siding and containing three double-hung wood sash 6/1-light windows, rises from the roof. One exterior-end tapered brick chimney is positioned on the northeast elevation. A one-story, three-bay inset porch with brick and metal posts exists on the northeast (front) elevation. A one-story addition with a shed roof is on the southwest elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

305 South Broad Street 133-5040-0163

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Colonial Revival, ca 1915**

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 66

This Colonial Revival-style dwelling has an American four-square form and is two-and-a-half stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features an off-center entry and double-hung wood sash 6/1-light windows set in flush wood surrounds. The dwelling has projecting eaves and a flat on hip roof which is covered with asphalt shingles. One gabled dormer, clad in vinyl siding and containing a set of paired double-hung vinyl sash 1/1-light windows, rises from the roof. Two interior brick chimneys with corbeled caps are visible above the roof. A one-story, three-bay screened porch with wood battered posts on brick piers, is attached to the east (front) and south elevations. The roof of the porch extends from the south elevation to form a one-bay porte cochere. The one-story addition has a shed roof and two brick chimneys.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

308 South Broad Street 133-5040-0154

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1910**

This Colonial Revival-style dwelling has an American four-square form and is two stories in height and two bays wide. It originally had a brick pier foundation which has subsequently been infilled to form a solid foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a side entry with a 1-light transom and double-hung wood sash 2/2- and 1/1-light windows set in molded square surrounds. The dwelling has wide eaves and a hipped roof which is covered with asphalt shingles. Two interior-end brick chimneys with corbeled caps are visible over the roof line. A one-story, two-bay porch with a half-hipped roof supported by wood Tuscan columns is attached to the west (front) elevation. Two one-story additions and a wood deck exist on the east elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

309 South Broad Street 133-5040-0205

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Queen Anne, ca 1915**

This Queen Anne-style dwelling is two stories in height and four bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features a side entry, double-hung wood sash 1/1-light windows with rowlock sills and soldier course lintels, and a soldier-course cornice. The dwelling has wide eaves and a hipped roof which is covered with sheets of standing seam metal. A central front gable with one fixed window, rises from the roof. Two interior brick chimneys with corbeled caps are visible. A one-story, three-bay wrap porch with a half hipped roof supported by squared wood posts is attached to the southeast (front) elevation. A second story partially enclosed screened porch with square wood posts and a half-hipped roof has been built onto the top of the one-story porch. One two-story wood-frame addition and three one-story wood-frame additions exist on the northwest elevation.

Individual Resource Status: **Single Dwelling**

Contributing

310 South Broad Street 133-5040-0213

Primary Resource Information: **Single Dwelling, Stories 1.50, Style: Other, ca 1950**

This vernacular-style dwelling is one-and-a-half stories in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features a projecting front gabled bay, an off-center

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 67

entry, double-hung wood sash 3/1-light windows, one fixed wood sash 1-light window, all of which have rowlock sills, and a doveote in the front gable peak. The dwelling has a cross gable roof covered with asphalt shingles. One exterior-end brick shouldered chimney with a corbeled cap is positioned on the north elevation. A one-story, two-bay porch with a shed roof supported by metal posts is attached to the west (front) elevation.

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Shed**

Non-Contributing

Non-Contributing

311 South Broad Street 133-5040-0201

Primary Resource Information: **Single Dwelling, Stories 2.50, Style: Bungalow/Craftsman, ca 1925**

This Craftsman-style dwelling has an American four-square form and is two-and-a-half stories in height and two-bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a 6-course American bond. The facade features a side entry with a soldier-course lintel, and double-hung wood sash 1/1-light windows. Metal awnings shade the windows. The dwelling has overhanging eaves, exposed rafters, and a hipped roof which is covered with asphalt shingles. One hipped dormer, clad in weatherboards and containing two 2-light wood sash windows, rises from the roof. One interior-end stuccoed brick chimney is visible. A one-story, three-bay porch with wood battered posts on brick piers, is attached to the east (front) and south elevations. A one-story addition with a shed roof exists on the west elevation.

Individual Resource Status: **Single Dwelling Contributing**

Individual Resource Status: **Garage**

Non-Contributing

314 South Broad Street 133-5040-0214

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1950**

This vernacular-style dwelling is one story in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features an off-center entry, double-hung wood sash 8/8-, 6/6-, and 4/4-light windows with rowlock sills, a canted bay, and a soldier-course cornice. The dwelling has a flush wood fascia, and a side gable roof which is covered with asphalt shingles. One interior brick chimney with a corbeled cap is visible over the roof line. A one-story, one-bay front gabled portico with aluminum siding in the peak and supported by metal posts, is attached to the northwest (front) elevation.

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Shed**

Non-Contributing

Non-Contributing

313 South Broad Street 133-5040-0209

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1925**

This Colonial Revival-style dwelling is two stories in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in weatherboards. The facade features a central entry and double-hung wood sash 6/6-light windows set in wood surrounds with lug sills and beaded lintels. The dwelling has a wood fascia, molded wood cornice, and a side gable roof which is covered with asphalt shingles. One interior-end brick chimney with a corbeled cap is visible. A one-story, one-bay front gabled portico with square wood posts is attached to the east (front) elevation. One-story additions with shed roofs have been added to the west elevation.

Individual Resource Status: **Single Dwelling**

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 68

Individual Resource Status: **Shed**

Non-Contributing

400 South Broad Street 133-5040-0146

Primary Resource Information: **Multiple dwelling, Stories 2.00, Style: Colonial Revival, ca 1935**

This Colonial Revival twin dwelling is two stories in height and four bays wide, with two bays assigned to each property. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features two side entrances and double-hung wood sash 6/6-light windows set in square-edged aluminum surrounds. The building has an aluminum clad cornice and a side gable roof which is covered with sheets of standing seam metal. Two interior-end and two interior brick chimneys, all with corbeled caps, are visible over the roof line. Both dwellings have a one-story, one-bay front gabled portico supported by square wood posts. A one-story addition with a shed roof exists on the east (rear) elevations.

Individual Resource Status: **Multiple dwelling**

Contributing

402 South Broad Street 133-5040-0147

Primary Resource Information: **Single Dwelling, Stories 2.00, Style: Colonial Revival, ca 1935**

This Colonial Revival twin dwelling is two stories in height and four bays wide, with two bays assigned to each property. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features two side entrances and double-hung wood sash 6/6-light windows set in square-edged aluminum surrounds. The building has an aluminum clad cornice and a side gable roof which is covered with sheets of standing seam metal. Two interior-end and two interior brick chimneys, all with corbeled caps, are visible over the roof line. Both dwellings have a one-story, one-bay front gabled portico supported by square wood posts. A one-story addition with a shed roof exists on the east (rear) elevations.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-Contributing

404 South Broad Street 133-5040-0215

Primary Resource Information: **Multiple dwelling, Stories 1.00, Style: Other, ca 1990**

The property contains two identical pre-fabricated dwellings laid end-to-end. The dwellings are one story in height and two bays wide. They both have solid stretcher-bond brick foundation supporting frame structural systems clad in vinyl siding. Both facades contain a side entry shaded by a one-story, one-bay porch with a front gable roof supported by square wood posts. The western dwelling has one double-hung vinyl sash 6/6-light window. Both houses have wide eaves and a vinyl clad soffit, boxed cornice, and a front gable roof which is covered with asphalt shingles.

Individual Resource Status: **Multiple dwelling**

Non-Contributing

407 South Broad Street 133-5040-0208

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1930**

This vernacular-style dwelling is one story in height and three bays wide. It has a solid concrete block foundation supporting a wood-frame structural system clad in weatherboards. The facade features a central entry flanked by double-hung wood sash 6/1-light windows set in square-edged wood surrounds. The dwelling has overhanging eaves, exposed rafters, a wood soffit and cornice, and a cross gable roof which is covered with asphalt shingles. One central interior brick chimney with a corbeled cap is visible. A one-story, one-bay front gabled porch with paired wood posts, is attached to the east (front) elevation. One exterior-end concrete block

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 69

chimney has been added to the north elevation.

Individual Resource Status: **Single Dwelling**

Contributing

408 South Broad Street 133-5040-0148

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Bungalow/Craftsman, ca 1930**

This Craftsman-style dwelling has a bungalow form and is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl German siding. The facade features an off-center entrance with a 1-light transom flanked by double-hung wood sash 2/2-light windows set in square-edged vinyl surrounds. The dwelling has overhanging eaves and a hipped roof covered with asphalt shingles. One interior brick chimney with a corbeled cap is visible over the roof line. A one-story, four-bay wrap porch with wood Tuscan columns is attached to the west (front) and north elevations.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Non-Contributing

Virginia Avenue

524 Virginia Avenue 133-5040-0216

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1955**

This Colonial Revival-style dwelling has a Cape Cod form and is one story in height and three bays wide. It has a solid brick foundation supporting a masonry structural system with brick laid in a stretcher-bond. The facade features an off-center entry flanked by double-hung wood sash 2/2-light windows with rowlock sills. The windows are arranged singly, in pairs and in sets of threes. The dwelling has a molded wood cornice, a wood fascia board, wide eaves, and a side gable roof which is covered with asphalt shingles. One interior brick chimney with a corbeled cap is visible over the roof line. A metal awning shades the entrance.

Individual Resource Status: **Single Dwelling**

Non-Contributing

525 Virginia Avenue 133-5040-0217

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1955**

This vernacular-style dwelling is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl German siding. The facade features a central entry flanked by double-hung vinyl sash 1/1-light windows set in square-edged surrounds. The dwelling has a boxed aluminum cornice and a front gable roof which is covered with asphalt shingles. One central-interior brick chimney with corbeled cap is visible over the roof line. A one-story, two-bay porch with a front gable roof and aluminum clad square posts, is attached to the north (front) elevation.

Individual Resource Status: **Single Dwelling**

Non-Contributing

526 Virginia Avenue 133-5040-0218

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1955**

This Colonial Revival-style dwelling has a Cape Cod form and is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in asbestos shingles. The facade features a central entry with a wood surround decorated with fluted pilasters, flanked by paired sets of double-hung wood sash 2/2-light windows set in molded

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 70

aluminum clad surrounds. The dwelling has wide eaves, an aluminum clad soffit, and a side gable roof which is covered with asphalt shingles. One central-interior brick chimney is visible over the roof line. A metal awning shades the entrance. A one-story, one-bay screened porch with a gable roof extends from the west elevation.

Individual Resource Status: **Single Dwelling**

Non-Contributing

Individual Resource Status: **Shed**

Non-Contributing

527 Virginia Avenue 133-5040-0219

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1945**

This vernacular-style dwelling is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a central entry flanked by double-hung vinyl sash 1/1-light windows set in aluminum surrounds. The dwelling has an aluminum clad boxed cornice and a front gable roof which is covered with asphalt shingles. One interior brick chimney with a corbeled cap is visible over the roof line. A one-story, one-bay front gabled portico with metal posts is attached to the north (front) elevation.

Individual Resource Status: **Single Dwelling**

Non-Contributing

Individual Resource Status: **Garage**

Non-Contributing

601 Virginia Avenue 133-5040-0207

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1945**

This Colonial Revival-style dwelling has a Cape Cod form and is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features a central entry flanked by paired sets of double-hung wood sash 6/6-light windows. The dwelling has a side gable roof which is covered with asphalt shingles. One exterior-end corbeled brick chimney is positioned on the east elevation and a second is located on the south elevation. A one-story, one-bay front gabled portico with turned wood posts is attached to the north (front) elevation. A second side porch exists on the east elevation. A one-story addition is attached to the south elevation.

Individual Resource Status: **Single Dwelling**

Non-Contributing

Individual Resource Status: **Shed**

Non-Contributing

603 Virginia Avenue 133-5040-0206

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Other, ca 1930**

This vernacular-style dwelling is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features a central entry flanked by double-hung wood sash 6/1-light windows set in square-edged wood surrounds. The building has projecting gables, wide eaves, exposed rafters, knee-braces, an aluminum clad soffit, and a front gable roof which is covered with asphalt shingles. One central interior brick chimney with a corbeled cap is visible. A one-story, one-bay porch with a half-hipped roof, exposed rafters, and square wood posts, is attached to the north (front) elevation.

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 71

606 Virginia Avenue 133-5040-0204

Primary Resource Information: Multiple dwelling, Stories 2.00, Style: Other, ca 1924

This vernacular-style dwelling is two stories in height and four bays wide. It has a solid brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features a side entry shaded by a shed roof supported on brackets, a central entry, and double-hung wood sash 2/2-light windows. The building has projecting eaves and a hipped roof which is covered in sheets of standing seam metal. Two interior brick chimneys, one of which is stuccoed and one of which has a corbeled cap, are visible. A one-story, two-bay partially screened porch with a half-hipped roof supported by battered wood posts on brick piers, is attached to the southwest (front) elevation. A two-story addition with a shed roof exists on the northeast elevation.

Individual Resource Status: Multiple dwelling

Contributing

607 Virginia Avenue 133-5040-0220

Primary Resource Information: Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1960

This Colonial Revival style dwelling has a Cape Cod form and is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features a central entry flanked by paired sets of double-hung wood sash 6/6-light windows. The dwelling has wide eaves and a cross gable roof which is covered with asphalt shingles.

Individual Resource Status: Single Dwelling

Non-Contributing

609 Virginia Avenue 133-5040-0203

Primary Resource Information: Single Dwelling, Stories 1.00, Style: Other, ca 1935

This vernacular-style dwelling is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in vinyl siding. The facade features a central entry flanked by double-hung wood sash 6/6-light windows. The dwelling has overhanging eaves, a projecting gable with wood knee brackets and a front gable roof which is covered with asphalt shingles. One central-interior brick chimney with a corbeled cap is visible over the roof line. A one-story, one-bay porch with a front gable roof supported by square wood posts is attached to the north (front) elevation.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

611 Virginia Avenue 133-5040-0202

Primary Resource Information: Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1935

This Colonial Revival-style dwelling is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a central entry flanked by replacement double-hung vinyl sash 1/1-light windows set in aluminum clad square-edged surrounds. The dwelling has wide eaves and a cross gable roof which is covered with asphalt shingles. A one-story, one-bay front gabled porch with metal posts is attached to the north (front) elevation.

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 72

613 Virginia Avenue 133-5040-0200

Primary Resource Information: **Single Dwelling, Stories 1.00, Style: Colonial Revival, ca 1935**

This Colonial Revival-style dwelling has a Cape Cod form and is one story in height and three bays wide. It has a solid stretcher-bond brick foundation supporting a wood-frame structural system clad in aluminum siding. The facade features a central entry flanked by double-hung wood sash 8/8-light windows set in square-edged aluminum clad surrounds. An arched pent roof supported by scrolled brackets shades the entrance.

Individual Resource Status: **Single Dwelling**

Contributing

Wellons Street

107 Wellons Street

133-5040-0064

Single Dwelling 1945-1960 Other 1.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Veneer, Brick

Window(s): Sash, Double-hung Wood 8/8

Door(s): Single Leaf Wood Paneled

Door(s): Roll-up Wood Paneled

Roof: Gable: Side Asphalt Shingle

Chimney: Central Interior Brick Cap, Rowlock

Porch: 1-story, 1-bay Wood Post

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Shed**

Non-contributing

Contributing

113 Wellons Street

133-5040-0066

Single Dwelling 1900-1915 Other 2.0

Foundation: Piers Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Side Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Chimney: Exterior end Concrete Block

Portico: Gable Wood Post

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Shed**

Contributing

Non-contributing

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 73

115 Wellons Street

133-5040-0067

Single Dwelling 1895-1910 Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 2/2

Window(s): Fixed Wood 1-light

Door(s): Single Leaf Wood Oval light

Roof: Gable: Front Asphalt Shingle

Chimney: Interior Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

117 Wellons Street

133-5040-0068

Single Dwelling 1895-1910 Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled

Roof: Hipped Metal Shingle

Chimney: Interior Brick Stretcher Bond

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

119 Wellons Street

133-5040-0069

Single Dwelling 1895-1910 Italianate 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 4/4

Door(s): Single Leaf Metal Paneled

Roof: Gable: Cross Metal Standing Seam

Chimney: Central interior Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

121 Wellons Street

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 74

133-5040-0070

Single Dwelling 1885-1900 Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood 12-light

Roof: Gable: Cross Metal Standing Seam

Chimney: Central interior Metal Capped

Porch: 1-story, 4-bay Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

123 Wellons Street

133-5040-0071

Single Dwelling 1920-1935 Colonial Revival .5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood 6-light, 2-panel

Roof: Gable: Side Asphalt Shingle

Chimney: Central interior Brick Capped

Porch: 1-story, 3-bay Wood Tuscan Columns

Dormer: Gable Wood Plywood

Individual Resource Status: **Single Dwelling**

Contributing

125 Wellons Street

133-5040-0072

Single Dwelling 1895-1910 Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 6/2

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Cross Metal Standing Seam

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: **Single Dwelling**

Contributing

127 Wellons Street

133-5040-0073

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 75

Single Dwelling 1900-1915 Colonial Revival 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood 15-light

Roof: Gable: Cross Metal Standing Seam

Chimney: Central interior Brick Stretcher Bond

Porch: 1-story-3-bay Concrete Post

Individual Resource Status: Single Dwelling

Individual Resource Status: Garage

Contributing

Contributing

129 Wellons Street

133-5040-0074

Single Dwelling 1900-1915 Colonial Revival 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Shingle, Asbestos

Window(s): Not Visible None Listed Not visible

Window(s): Not Visible None Listed Not visible

Door(s): Single Leaf None Listed Not visible

Roof: Hipped Metal Standing Seam

Chimney: Central interior Brick Corbeled Cap

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Columns, Ionic

Individual Resource Status: Single Dwelling

Contributing

131 Wellons Street

133-5040-0075

Commercial Building 1950-1965 Other 1.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Veneer, Brick

Window(s): Fixed Wood Plate Glass

Door(s): Single Leaf Metal Plate Glass

Roof: Flat w/parapet None Listed Not Visible

Individual Resource Status: Commercial Building

Non-contributing

West Washington Street

457 West Washington Street

133-5040-0084

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 76

Single Dwelling ca. 1890 Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Wood 1/1

Window(s): Fixed Wood 1-light

Door(s): Double leaf Wood Paneled w/ lights

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable and Hipped Metal Shingle

Chimney: Interior end Brick Corbeled Cap

Chimney: Central interior Brick Corbeled Cap

Porch: Wrap-around Wood Tuscan Columns

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

500 West Washington Street

133-5040-0057

Single Dwelling 1910-1925 Bungalow/Craftsman .5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 12/12

Door(s): Single Leaf Wood Paneled

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Asphalt Shingle

Chimney: Interior Brick Cap, Rowlock

Chimney: Exterior side Brick Stretcher Bond

Porch: Wrap-around Wood Craftsman

Dormer: Hipped Aluminum Siding

Individual Resource Status: Single Dwelling

Contributing

Individual Resource Status: Garage

Contributing

504 West Washington Street

133-5040-0162

Single Dwelling ca. 1865 Greek Revival 2.5

Foundation: Not Visible None Listed Not visible

Structural System: Frame Wood Weatherboard

Walls: Frame Wood Stucco

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 77

Window(s): Sash, double-hung Wood 12/12
Window(s): Sash, double-hung Wood 8/8
Window(s): Sash, double-hung Wood 12/8
Window(s): Fixed Wood Multi-light
Door(s): Single Leaf Wood Paneled
Roof: Gable: Front Asphalt Shingle
Chimney: Exterior end Brick Corbeled Cap
Chimney: Interior end Brick Corbeled Cap
Portico: 2-story, 3-bay Wood Columns
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Kitchen**
Individual Resource Status: **Servant Quarters**
Individual Resource Status: **Well House**

Contributing
Contributing
Contributing
Contributing

509 West Washington Street
133-5040-0103

133-5005

Funeral Home 1915-1930 Colonial Revival 2.0
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Siding, Aluminum
Window(s): Sash, double-hung Wood 1/1
Window(s): Fixed Wood 8-light
Window(s): Sash, double-hung Wood Awnings
Door(s): Single Leaf Wood Paneled
Roof: Hipped Asphalt Shingle
Chimney: Interior end Brick Stretcher Bond
Porch: 2-story, 1-bay Wood Columns, Ionic
Individual Resource Status: **Funeral Home**
Individual Resource Status: **Single Dwelling**
Individual Resource Status: **Garage**

Contributing
Contributing
Contributing

512 West Washington Street
133-5040-0021

Single Dwelling 1890-1905 Queen Anne 2.5
Foundation: Solid Brick Stretcher Bond
Structural System: Frame Wood Weatherboard
Window(s): Sash, double-hung Wood 1/1
Door(s): Single Leaf Wood 1-light
Roof: Hipped Metal Shingle

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 78

Chimney: Central interior Brick Corbeled Cap

Porch: Wrap-around Wood Columns, Ionic

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

514 West Washington Street

133-5040-0020

Single Dwelling 1885-1900 Queen Anne 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Oval light

Door(s): Single Leaf Wood Paneled

Roof: Gable: Cross Metal Shingle

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Columns

Dormer: Gable Wood Weatherboard

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

518 West Washington Street

133-5040-0019

Single Dwelling 1880-1890 Italianate 2.0

Foundation: Piers w/ infill Brick Stretcher Bond

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Hipped Metal Standing Seam

Chimney: Interior Brick Corbeled Cap

Porch: Wrap-around Wood Columns

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Garage**

Contributing

519 West Washington Street

133-5040-0104

Commercial Building 1960 Commercial Style 1.0

Foundation: Solid Concrete Poured

Structural System: Frame None Listed Veneer, Brick

Window(s): Fixed Metal Plate Glass

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 79

Door(s): Single Leaf Metal Plate Glass

Roof: Gable: Side None Listed Not visible

Individual Resource Status: Commercial Building

Non-contributing

520 West Washington Street

133-5040-0018

Single Dwelling 1880-1895 Italianate 2.0

Foundation: Piers w/ infill Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled

Roof: Hipped Metal Standing Seam

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story-3-bay Wood Chamfered Posts

Individual Resource Status: Single Dwelling

Contributing

521 West Washington Street

133-5040-0129

Single Dwelling 1880-1895 Colonial Revival 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Wood 2/2

Door(s): Single Leaf Wood Paneled

Roof: Hipped Asphalt Shingle

Chimney: Central interior Brick Stretcher Bond

Chimney: Central interior Brick Corbeled Cap

Portico: 1-story, 1-bay Vinyl Post

Individual Resource Status: Single Dwelling

Contributing

523 West Washington Street

133-5040-0128

Single Dwelling 1890-1905 Colonial Revival 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 2/2

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Metal Paneled

Roof: Hipped: Cross Metal Standing Seam

Chimney: Central interior Brick Stretcher Bond

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 80

Chimney: Exterior Brick Stretcher Bond

Chimney: Interior Brick Stretcher Bond

Individual Resource Status: **Single Dwelling**

Contributing

526 West Washington Street

133-5040-0017

Single Dwelling 1880-1895 Italianate 2.0

Foundation: Piers w/ infill Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 2/2

Door(s): Double leaf Wood Paneled w/ lights

Roof: Hipped Metal Standing Seam

Chimney: Interior Brick Capped

Chimney: Interior end Brick Corbeled Cap

Porch: Wrap-around Wood Posts, Square

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Contributing

Individual Resource Status: **Garage**

Contributing

527 West Washington Street

133-5040-0127

Single Dwelling 1880-1895 Italianate 2.5

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, German

Window(s): Sash, double-hung Wood 2/2

Window(s): Fixed Wood Multi-light

Window(s): Sash, double-hung Wood 1/1

Door(s): Single Leaf Wood Paneled

Roof: Gable: Side Metal Standing Seam

Chimney: Central interior Brick Corbeled Cap

Chimney: Central interior Brick Reconstructed

Portico: 1-story, 1-bay Wood Posts, Square

Individual Resource Status: **Single Dwelling**

Contributing

528 West Washington Street

133-5040-0016

Single Dwelling 1880-1895 Italianate 2.0

Foundation: Piers w/ infill Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 2/2

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 81

Door(s): Single Leaf Wood Paneled
Roof: Hipped Asphalt Shingle
Chimney: Central interior Brick Corbeled Cap
Porch: 1-story, 3-bay Wood Chamfered Posts
Individual Resource Status: **Single Dwelling**

Contributing

**530 West Washington Street
133-5040-0015**

Commercial Building 1880-1895 Italianate 2.0
Foundation: Solid Brick Stretcher Bond
Structural System: Masonry Brick 7-course Amer.Bond
Window(s): Fixed Metal 1-light
Window(s): Fixed Wood 1-light
Window(s): Sash, double-hung Wood 1/1
Door(s): Single Leaf Wood 1-light
Door(s): Single Leaf Wood Paneled
Roof: Flat w/parapet Asphalt Not visible
Chimney: Exterior end Brick Stretcher Bond
Chimney: Interior end Brick Stretcher Bond
Individual Resource Status: **Commercial Building**

Contributing

**601 West Washington Street
133-5040-0130**

Church 1922 Gothic Revival 2.0
Foundation: Solid Brick Not visible
Structural System: Masonry Brick 9-course Flemish
Window(s): Fixed Wood Stained Glass
Door(s): Double leaf Wood Paneled
Roof: Gable: Cross Asphalt Shingle
Chimney: Exterior end Brick Stretcher Bond
Chimney: Interior Brick Stretcher Bond
Individual Resource Status: **Church**

Contributing

**607 West Washington Street
133-5040-0011**

Office Building 1980 Colonial Revival 1.0
Foundation: Solid None Listed Not visible
Structural System: Frame Wood Veneer, Brick
Window(s): Sash, Double-hung Vinyl 6/9
Door(s): Single Leaf Wood Paneled with lights

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 82

Roof: Gable: Side Asphalt Shingle
Chimney: Interior end Brick Corbeled Cap
Individual Resource Status: Office

Non-contributing

**608 West Washington Street
133-5040-0013**

Commercial Building 1945-1955 Other 1.0

Foundation: Solid None Listed Not Visible

Structural System: Masonry Brick Stretcher Bond

Window(s): Fixed Vinyl 12-light

Door(s): Single Leaf Wood Paneled

Roof: Flat with parapet None Listed Not Visible

Individual Resource Status: Commercial Building

Non-contributing

**611 West Washington Street
133-5040-0010**

Bank 1980-1995 Modern Movement 1.0

Foundation: Solid Concrete Not visible

Structural System: Frame Wood Veneer, Brick

Window(s): Fixed Metal 6-light

Door(s): Single Leaf Metal 1-light

Roof: Flat Metal Standing Seam

Individual Resource Status: Bank

Non-contributing

**616 West Washington Street
133-5040-0006**

Single Dwelling 1865-1880 Italianate 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Weatherboard

Window(s): Sash, double-hung Wood 1/1

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable: Cross Metal Standing Seam

Chimney: Central interior Brick Corbeled Cap

Chimney: Interior end Brick Corbeled Cap

Porch: 1-story, 3-bay Wood Post

Individual Resource Status: Single Dwelling

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 83

620 West Washington Street

133-5040-0005

Single Dwelling 1910-1920 Colonial Revival 2.5

Foundation: Solid Brick English Bond

Structural System: Masonry Brick English Bond

Window(s): Sash, double-hung Vinyl 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable: Side Slate Tiles

Chimney: Interior end Brick Cap, Rowlock

Portico: 1-story, 1-bay Wood Tuscan Columns

Dormer: Gable Wood Weatherboard

Individual Resource Status: **Single Dwelling**

Individual Resource Status: **Garage**

Individual Resource Status: **Carport**

Contributing

Contributing

Non-contributing

626 West Washington Street

133-5040-0004

Single Dwelling 1896 Colonial Revival 2.0

Foundation: Solid Stone Parged

Structural System: Frame Wood Siding, Aluminum

Window(s): Sash, double-hung Wood 6/6

Window(s): Sash, double-hung Vinyl 1/1

Door(s): Single Leaf Wood Paneled

Roof: Gable: Side Metal Standing Seam

Chimney: Interior end Brick Parged

Portico: 1-story, 1-bay Wood Posts, Square

Individual Resource Status: **Single Dwelling**

Contributing

630 West Washington Street

133-5040-0003

Multiple dwelling 1915-1930 Other 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Masonry Brick Stretcher Bond

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Door(s): Single Leaf Wood 15-light

Roof: Hipped Asbestos Shingle

Chimney: Interior end Brick Stretcher Bond

Porch: 2-story, 1-bay Brick Piers

Individual Resource Status: **Multiple Dwelling**

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 **Page** 84

Individual Resource Status: **Shed**

Non-contributing

700 West Washington Street

133-5040-0002

Mixed:Commerce/Domestic 1900-1915 Other 2.0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Fixed Wood 4-light

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled

Roof: Gable: Front Metal Standing Seam

Chimney: Interior Brick Reconstructed

Porch: 2-story, 3-bay Vinyl Posts, Square

Individual Resource Status: **Mixed: Commerical/Domestic**

Contributing

705 West Washington Street

133-5040-0009

Office Building 1980-1995 Colonial Revival 1.0

Foundation: Solid Concrete Block

Structural System: Frame Wood Veneer, Brick

Window(s): Sash, Double-hung Vinyl 8/8

Door(s): Single Leaf Wood 15-light

Roof: Gable: Side Asphalt Shingle

Individual Resource Status: **Office Building**

Non-contributing

708 West Washington Street

133-5040-0001

Single Dwelling 1910-1925 Colonial Revival 2.5

Foundation: Solid None Listed Not visible

Structural System: Masonry Brick 7-course Flem.Bond

Window(s): Sash, double-hung Wood 6/1

Window(s): Fixed Wood 5-light

Window(s): Fixed Vinyl 10-light

Door(s): Single Leaf Wood 15-light

Roof: Hipped Asphalt Shingle

Chimney: Exterior side Brick Stretcher Bond

Porch: 1-story, 3-bay Wood Tuscan Columns

Dormer: Hipped Wood Weatherboard

Individual Resource Status: **Single Dwelling**

Contributing

Individual Resource Status: **Shed**

Contributing

United States Department of the Interior
National Park Service

NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 7 Page 85

Individual Resource Status: Shed

Contributing

709 West Washington Street

133-5040-0008

Office Building 1980-1995 Colonial Revival .0

Foundation: Solid None Listed Not visible

Structural System: Frame Wood Veneer, Brick

Window(s): Casement Vinyl 1-light

Door(s): Single Leaf Wood Paneled

Roof: Mansard Asphalt Shingles

Individual Resource Status: Office Building

Non-contributing

711 West Washington Street

133-5040-0007

Single Dwelling 1920-1935 Bungalow/Craftsman .0

Foundation: Solid Brick Stretcher Bond

Structural System: Frame Wood Siding, Vinyl

Window(s): Sash, double-hung Wood 6/6

Door(s): Single Leaf Wood Paneled w/ lights

Roof: Gable: Front Asphalt Shingle

Chimney: Central interior Brick Corbeled Cap

Porch: 1-story, 1-bay Wood Posts, Square

Individual Resource Status: Single Dwelling

Contributing

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 Page 86

STATEMENT OF SIGNIFICANCE

The West End neighborhood in the City of Suffolk, Virginia, is significant as a residential community that grew to support the city's commercial downtown and surrounding industrial areas. The West End is a late-19th- and early-20th-century residential neighborhood improved by large-scale high-style dwellings and modest vernacular housing, as the market demanded. The various levels of economic status are illustrated in the built fabric constructed to serve not only the middle- and upper-class residents of the City of Suffolk, but also the blue-collar industrial workers. The middle- to upper-class housing is generally of an earlier construction date and located within one to two blocks of West Washington Street, whereas the sections northwest of West Washington Street and south of Smith Avenue are of a later date and contain smaller modest dwellings.

The neighborhood consists of a grid-shaped pattern bounded on the north and south by separate railroad lines that run east and west through the City of Suffolk. The housing blocks in West End are both rectangular- and square-shaped, laid out on a grid, denoting a systematic street plan completed in several stages by the end of the first decade of the 20th century. Linden Avenue, Wellons Street, and Pender Street mark the eastern boundaries, while the western boundary is marked by Brewer Avenue, Causey Avenue, South Broad Street and Bosley Avenue. The north and south boundaries are delineated by the railroad tracks of the Seaboard Coast Line Railroad, originally called the Seaboard Air Line Railroad, and the Norfolk & Western Railroad, respectively.

Eligible under criteria A and C of the National Register of Historic Places, the West End Historic District has a period of significance extending from 1865 to 1939, and reflects the themes of architecture and community planning and development. The neighborhood consists of 234 properties with 397 resources including 199 single dwellings, 20 multiple dwellings, 5 churches, 5 commercial buildings, 1 mixed domestic and commercial building, 1 bank, 3 office buildings, 1 funeral home, and 162 secondary resources such as garages and sheds. In all, there are 286 contributing resources and 111 non-contributing resources within the West End.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 Page 87

Criterion A: That are associated with events that have made a significant contribution to the broad patterns of our history.

West End meets Criterion A of the National Register of Historic Places as a community which developed to support the growing upper-, middle-, and working-class populations during the last half of the 19th century and first four decades of the 20th century. The development and expansion of various local industries during this time period necessitated the westward expansion of the City of Suffolk and the creation of the West End neighborhood. Pre-20th-century development within West End supported the middle- to upper-class population that was steadily moving away from the downtown area and occurred along, or within close proximity to West Washington Street. Further south and north of West Washington Street lots were improved during the 20th century to house the lower-income employees of the factories and local businesses. West Washington Street, which provides easy access to and from the manufacturing industries and the downtown business district, as well as West End's proximity to the industrial and business centers, made it an ideal location for business owners and employees alike.

Criteria C: That embody the distinctive characteristics of a type, period, or method of construction or that represent the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction.

The residential neighborhood of West End meets Criterion C of the National Register of Historic Places for its substantial concentration of domestic architecture of the late 19th and early 20th century. Dwellings within the neighborhood represent the Greek Revival, Italianate, Queen Anne, Colonial Revival, Classical Revival, and Craftsman styles that were popular during the period. The earliest houses are generally imposing in scale and massing and represent high-style examples of these fashionable styles. As the population of Suffolk grew, residential construction in West End increased and house sizes and styles began to change in response to a new clientele. Many of these later modest dwellings exhibit American foursquare or bungalow forms with Queen Anne- or Colonial Revival-style detailing.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 Page 88

HISTORICAL BACKGROUND

City of Suffolk

The City of Suffolk, established in 1742, is ideally located along the waterways of Lake Kilby, Lake Meade, the Nansemond River and Shingle Creek. The original town consisted of fifty acres of land based at the location of John Constant's tobacco warehouse. The access to major waterways proved essential to the commercial success of the town. By 1748, ferries connected Suffolk to the neighboring towns of Norfolk and Southampton, and by the eve of the Revolutionary War (1775-1781) Suffolk was a prospering commercial center relying on trade in lumber, tar, turpentine, staves, shingles and other by-products that could be extracted from nearby Dismal Swamp. During the Revolutionary War, the British destroyed the prospering commercial center in Suffolk, which was soon rebuilt. The majority of the earliest buildings in this area, known as "Old Town," are Federal-period wood-frame dwellings with a commercial enclave that was centered along Main Street. A fire destroyed most of Suffolk in 1837, prompting a second period of rebuilding that moved beyond Old Town to an area known as "Up Town." The main trade in Suffolk during the 19th century continued to focus on the lumber industry, while the more rural county trade was dedicated to the production of grains and other agricultural products. Between 1819 and 1822, steamboat lines between Suffolk, Norfolk, and Smithfield were opened and continued to operate until the turn of the 20th century. In 1835, Suffolk received the first of its six railways, the Seaboard Air Line, connecting Suffolk to Portsmouth and Wealdon, North Carolina.¹ With the advent of the railways, Suffolk's prominence as a manufacturing and exporting town was established.

Suffolk's railroads and steamships made it an attractive prize during the Civil War (1861-1865). In May 1862, the town of Suffolk was surrendered to Union forces which held the town until the summer of 1863.² On April 11, 1863, 20,000 Confederate troops under Lieutenant General James Longstreet attacked the town in an attempt to re-capture Suffolk and re-establish the railways. The failed siege ended on May 4, 1863, when Longstreet withdrew his troops in an attempt to aid Robert E. Lee in Chancellorsville.³ During the Union occupation, troop encampments were set up in the fields to the east,

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 **Page** 89

south and west of the town, including the area which would subsequently become the West End neighborhood.⁴

Suffolk experienced a steady growth in population during the Reconstruction period. Real estate development increased beyond Old Town and Up Town to the east and west of Main Street, with four new streets created to meet the growing residential demands of immigrating upper-class citizens. This second addition to Suffolk's central core was known as "New Town" and included some of the town's most elaborate and large-scale residences.

The Evolution of West End

With the end of the Civil War, the citizens of Suffolk began to rebuild their town, farms and industries. The town of Suffolk as well as Nansemond County recovered quickly and between 1870 and 1880, the county's population increased by 33% from 9,000 to 15,903.⁵ To accommodate the growing population Suffolk's town limits were expanded in 1879.⁶ The earliest structure within the West End neighborhood was constructed soon after the conclusion of the Civil War. Located on the north side of West Washington Street (known at the time as Kilby Street) between Brewer Avenue and Pender Street, the dwelling stands on a square lot with numerous service buildings which have subsequently been attached to the main dwelling by the construction of numerous hyphens. Between 1870 and 1890, a scattering of dwellings were erected within West End. These high-style dwellings reflect Italianate and Queen Anne styles and appear to have been constructed for the upper-class citizens of Suffolk who wished to live on the outskirts of town.

By 1890, Suffolk had fully recovered from the devastating economic effects of the Civil War, and had begun to show signs of a new age of prosperity. In 1891, the town's first electrical plant was constructed and in 1895, telephone service was begun. By 1898, several streets of the West End neighborhood had been platted. Linden Avenue, St. James Avenue, and Wellons Streets were laid out consecutively in a north-south direction parallel to Broad Street, which is a significant thoroughfare for this area as it provides access northward across the rail lines to the Nansemond River. Other than Kilby Street (now Washington Street), Smith Street is the only other east-west route in the neighborhood by 1898, terminating at its intersection with Broad Street. Town limits

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 Page 90

noted on the 1898 map stretch to the west side of Linden Street, but they do not include Broad Street.⁷

By 1903, West End had grown to include approximately fifty buildings, the majority of which were clustered along West Washington Street with a few dwellings positioned on Wellons Street, St. James Avenue, Linden Avenue, South Broad Street, and Brewer Avenue. These buildings represent Italianate, Queen Anne, and Colonial Revival styles. The two-story dwellings, which display rectangular and L-shape footprints, were set near to the streets with freestanding service buildings located to the rear of the rectangular lots. The first inhabitants of these dwellings were generally employed as merchants, lumber dealers, and treasurers.⁸

In 1900, Suffolk was the terminus for six railroad lines transporting people and freight daily to and from Suffolk. Tied to the growth of the railroads was the development of over one hundred industries within the Suffolk area. These industries included but were not limited to: peanut factories, lumber mills, iron foundries, woodworking establishments, and knitting mills.⁹ The manufacturing census for 1900, shows Nansemond County supported 115 establishments with a total capital of \$555,071.¹⁰ The growth of the industries drew a large number of workers to Nansemond County and the town of Suffolk. In 1900, there was a total of 23,078 people in Nansemond County, an increase of 69% within twenty years.¹¹ According to a 1907 map of Suffolk, the town's population totaled 8,000 people.¹² With the large-scale growth of industry, the town of Suffolk was declared an incorporated city by the courts in 1910.¹³

One of the more well-known industries to develop in Suffolk after the Civil War was the peanut industry. Farmer's Alliance was the first peanut factory in Suffolk but it failed in 1893. The second factory, Suffolk Peanut Company, run by John King and John Pinner, was much more successful and lured other peanut investors to Suffolk. Between 1900 and 1939, numerous additional peanut processing and distributing firms appeared in Suffolk including The Columbian Peanut Company (1904), The Planter's Nut and Chocolate Company (1913) and Old Dominion Peanut Corporation (1933).¹⁴ By 1915 the peanut industry had surpassed the prosperous lumbering industry. A 1915 pamphlet claims the expected total lumber output would exceed two million dollars while the gross income of the eight peanut factories in Suffolk was expected to equal more than eight million dollars.¹⁵

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 Page 91

Tied to the growth of Suffolk, significant changes occurred in West End. Between 1903 and 1908, the town limits of Suffolk were expanded to the south to include the area adjacent to the Norfolk & Western Railroad and to the west to include portions of the blocks on the west side of Causey Avenue and Pitchkettle Road. Suffolk also grew to the north of West Washington Street including Pitchkettle Road, Bute Street, First Street, Second Street and Third Street. This area to the north, supported by locally funded amenities, became a neighborhood of worker housing, many of which were square-shaped structures balanced by a few L-shaped dwellings. The majority of the buildings were wood-frame, one-story dwellings set close to the street. By 1908, a new grid street plan was laid out south of West Washington Street and west of Broad Street creating Causey Avenue, Bosley Avenue, Virginia Avenue, Maryland Avenue, and Gittings Street. The 1908 *Sanborn Fire Insurance* map shows West Washington Street to be the main residential corridor with the flanking blocks developing quickly.¹⁶

With a population of over 12,000 in 1914, Suffolk continued to expand in all directions around the city's center core, which was developing as a business district. The West End steadily was becoming a self-sufficient neighborhood with health, education, and religious institutions attending to the needs of its residents. Lakeview Hospital (demolished circa 1950) was constructed at the corner of Smith Street and Bosley Avenue to serve the growing community. Similarly, the Oxford Methodist Church was erected on Smith Avenue in 1908, and St. Mary's Roman Catholic Church improved the corner of Broad Street and Smith Street. The Randolph Public School was built between 1908 and 1914, at the corner of St. James Avenue and Smith Street.

Along with these public buildings, single-family dwellings continued to be built within West End between 1910 and 1926. Most of the dwellings dating to this period display vernacular interpretations of the Queen Anne, Colonial Revival and Craftsman styles and are located to the south of Smith Street with some in-fill housing north of Smith Street and on Brewer Avenue. These dwellings are smaller in scale and were constructed for foremen, shipping clerks, teachers, stenographers, bank tellers, and laborers. The effects of industry development is evident in the 1930 census as many of West End's dwellings were inhabited by employees of the peanut factories, lumber mills, and railroads. The owners, general managers, superintendents, agents, buyers, and chemists of the factories inhabited the older high-style dwellings located within a block or two of West

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 Page 92

Washington Street, while the salesmen, stenographers, and clerks of the factories lived in the newer smaller dwellings south of Smith Street.¹⁷ Development did not extend south to the railroads. According to the 1920 and 1926 *Sanborn Fire Insurance* maps, there were companies located along the Norfolk and Western Railway, including a casket company, a hardware and lumber company, and a mattress company.¹⁸

Between 1926 and 1939, the need for modest, inexpensive housing prompted an increase in development to the west of Broad Street and extended the residential development of West End south to the Norfolk and Western Railway. All but the mattress company was demolished and between 1926 and 1939 single-family dwellings, and twin dwellings were erected south of Virginia Avenue. These rectangular wood-frame buildings are one to two stories in height and display elements of the Colonial Revival and Craftsman styles.

Development After 1939

By 1939, the development of the West End neighborhood was nearly complete. With the onset of World War II and the wartime economy, the City of Suffolk experienced another rise in population. As there were only a handful of unimproved lots within the West End neighborhood by 1940, new development occurred along and to the west of Causey Avenue. However, a handful of single-family dwelling and multiple dwellings were constructed on vacant lots after 1939. The few post-1939 multiple-family dwellings are two stories in height, have a rectangular massing and are constructed of brick. These buildings, reflecting the growing population during and immediately after the war, are located along the western boundaries of the district. The majority of single family dwellings constructed within the West End neighborhood after 1939 are one-story brick buildings with L-shaped footprints. These dwellings dating to the late 1950s, are distributed between the historic dwellings along Virginia and Linden Avenues. Commercial buildings and offices have more recently improved lots along the western blocks of West Washington Street and are the direct result of West Washington Street's status as a major transportation route to and from downtown Suffolk. These buildings serve the residents of West End as well as those living to the east in downtown Suffolk and those in the post-WWII developments to the west of West End.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 Page 93

Although the development of West End was completed by 1939, Suffolk has continued to grow throughout the 20th century and has become the Commonwealth of Virginia's largest city in geographic size, encompassing 430 square miles. With this growth, the population has climbed from 47,621 in 1980 to 67,195 in 2002.¹⁹ A portion of this growth can be attributed to the transportation systems that link Suffolk and the entire Hampton Roads region to the rest of the country and international ports by highway, air, rail, and shipping ports. The city has also become a prime location for large corporations, some of which have become major regional employers, including Planters' Peanuts, QVC, Inc., United States Joint Forces Command (USJFCOM), Lipton, Inc., Sara Lee Coffee and Tea Company, and the Birdsong Peanuts Corporation. In addition to its economic growth, the City of Suffolk brought in more than \$32.7 million dollars in tourism in 2000, by attracting visitors to the area's historic, cultural and architectural resources.²⁰

Endnotes

¹ Kermit Hobbs and William A. Paquette, *Suffolk: A Pictorial History* (Norfolk: The Downing Company, 1987), 21-25.

² O. Kermit Hobbs, *Storm Over Suffolk The Years 1861-1865* (Suffolk: Suffolk Nansemond Historical Society, 1979), 3, 22.

³ O. Kermit Hobbs, *Storm Over Suffolk The Years 1861-1865* (Suffolk: Suffolk Nansemond Historical Society, 1979), 20.

⁴ Capt. E.A. Curtis, "Map of Suffolk and Vicinity"; in The Suffolk-Nansemond Historical Society, *The Quiet Regiment* (Suffolk: The Suffolk-Nansemond Historical Society, 1990), 20-21.

⁵ Report on the Social Census, Record Group 287, National Archives at College Park, Department of the Interior, Census Office, (Washington, D.C.: Government Printing Office, 1840-1880).

⁶ Report on the Social Census, Record Group 287, National Archives at College Park, Department of the Interior, Census Office, (Washington, D.C.: Government Printing Office, 1840-1870).

⁷ Sanborn Fire Insurance Company, 1898.

⁸ United States Census Records, "Suffolk Town, Enumeration District 30," National Archives, Washington, D.C., 1900.

⁹ Kermit Hobbs and William A. Paquette, *Suffolk: A Pictorial History* (Norfolk: The Downing Company, 1987), 72.

¹⁰ Report on the Social Census, Record Group 287, National Archives at College Park, Department of the Interior, Census Office, (Washington, D.C.: Government Printing Office, 1900).

¹¹ Report on the Social Census, Record Group 287, National Archives at College Park, Department of the Interior, Census Office, (Washington, D.C.: Government Printing Office, 1900).

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 8 Page 94

¹² Report on the Social Census, Record Group 287, National Archives at College Park, Department of the Interior, Census Office, (Washington, D.C.: Government Printing Office, 1840-1870).

¹³ Kermit Hobbs and William A. Paquette, *Suffolk: A Pictorial History* (Norfolk: The Downing Company, 1987), 117.

¹⁴ Kermit Hobbs and William A. Paquette, *Suffolk: A Pictorial History* (Norfolk: The Downing Company, 1987), 100.

¹⁵ "Suffolk, Nansemond County, Virginia – In a Nutshell" (Lynchburg: J.P. Bell Company, Inc., 1915), 11.

¹⁶ Sanborn Fire Insurance Company, 1908.

¹⁷ United States Census Records, "City of Suffolk, Enumeration District Number 119-5," National Archives, Washington, D.C., 1930.

¹⁸ Sanborn Fire Insurance Company, 1920, 1926.

¹⁹ "Demographics – City of Suffolk." Located on the Internet at www.suffolk.va.us/cmty/demog.html on February 25, 2002.

²⁰ "Suffolk City Travel Economic Impact Profile." Located on the Internet at www.vatc.org/research/files/51800 on February 25, 2002.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 9 Page 95

BIBLIOGRAPHY

Books and Other Published Materials

Burton, Ann H., ed. *History of Suffolk and Nansemond County, Virginia*. Suffolk: Phelps Ideas, 1970.

Carley, Rachel. *The Visual Dictionary of American Domestic Architecture*. New York, NY: Henry Holt and Company, 1994.

The City of Suffolk, Virginia: Pen and Picture Sketches, Year 1915. Richmond: Central Publishing Co., Inc., 1915.

Hobbs, Kermit, and William A. Paquette. *Suffolk: A Pictorial History*. Norfolk: The Downing Company, 1987.

Houses by Mail: A Guide to Houses from Sears, Roebuck and Company. Introduction by Katherine Cole Stevenson and H. Ward Jandl. Washington, D.C.: The Preservation Press, 1986.

Loth, Calder, editor. *The Virginia Landmarks Register, Fourth Edition*. Charlottesville, VA: The University Press of Virginia, 1999.

Lowe, Elgin, M., Sr. *Suffolkians: Two Plus Cultures: Facing Realities from 1900-1970*. Suffolk, VA: By the author, 1970.

McAlester, Virginia and Lee McAlester. *A Field Guide to American Houses*. New York, NY: Alfred A. Knopf, Inc., 1984.

Norfleet, Fillmore. *Suffolk in Virginia: 1795-1840: A Record of Lots, Lives, and Likenesses*. Richmond: Whittet & Shepperson, 1974.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 9 Page 96

Pollock, Edward. *Sketch Book of Suffolk, Virginia: Its People and Its Trade*. Portsmouth, VA: Fiske & Purdie, 1886.

Journals

Maguire, Carole C. Suffolk Journal, vols. 1-2, privately printed, 1987 (vol. 1), 1988 (vol. 2).

Internet Sources

“Demographics – City of Suffolk.” Located on the Internet at
www.suffolk.va.us/cmtty/demog.html, 2002

“Suffolk City Travel Economic Impact Profile.” Located on the Internet at
www.vatc.org/research/files/51800., 2002

Maps

Curtis, E.A. “Map of Suffolk and Vicinity” in *The Quiet Regiment*. Suffolk: The Suffolk-Nansemond Historical Society, 1990.

Fowler, T.M. *Birds eye view of Suffolk, Nansemond Co., Virginia. 1907*. Drawn by T. M. Fowler. Morrisville, PA: Fowler & Kelly, c. 1907.

Sanborn Fire Insurance Maps. Suffolk, Virginia: 1898, 1903, 1908, 1914, 1921, and 1926-1949.

United States Geological Survey. USGS Quadrangle Map, Suffolk Quadrangle, 1919, revised 1997.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 9 Page 97

Other Sources, Brochures

Hobbs, Kermit O. *Storm Over Suffolk The Years 1861-1865*. Suffolk: Suffolk Nansemond Historical Society, 1979.

MacClenny, W.E. "A History of Suffolk, VA." Published by the Suffolk News Herald, Jan. 1930. Reprinted by the Nansemond River Power Squadron, 1986.

Maxwell, Shirley, James C. Massey, and Geoffrey B. Henry. "Suffolk Historic District (Increased Boundary)." National Register of Historic Places Inventory-Nomination Form, 1999.

"Suffolk, Nansemond County, Virginia – In a Nutshell." Lynchburg: J.P. Bell Company, Inc., 1915.

Wagner, Marc Christian and Richard Laub. "Suffolk Historic District." National Register of Historic Places Inventory-Nomination Form, 1987.

U.S. Census Records

U.S. Bureau of the Census. The Census of 1790, Nansemond County, Virginia. National Archives, reel 3.

U.S. Bureau of the Census. The Census of 1820, Nansemond County, Virginia. National Archives, reel 139.

U.S. Bureau of the Census. The Census of 1830, Nansemond County, Virginia. National Archives, reel 193.

U.S. Bureau of the Census. The Census of 1840, Nansemond County, Virginia. National Archives, reel 569.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 9 Page 98

U.S. Bureau of the Census. The Census of 1850, Nansemond County, Virginia. National Archives, reel 962.

U.S. Bureau of the Census. The Census of 1860, Nansemond County, Virginia. National Archives, reel 1394.

U.S. Bureau of the Census. The Census of 1870, Nansemond County, Virginia. National Archives, reel 1664.

U.S. Bureau of the Census. The Census of 1880, Nansemond County, Virginia. National Archives, reel 1379.

U.S. Bureau of the Census. The Census of 1900, Nansemond County, Virginia. National Archives, reel 1719, page 44.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 10 Page 99

10. Geographical Data

5) 1/8/ 3/5/7/4/7/7/ 4/0/6/6/0/1/7/
Zone Easting Northing

Verbal Boundary Description

West End Historic District, located within the limits of the City of Suffolk, Virginia, is approximately four blocks west of the Suffolk Historic District. The Seaboard Coast Line Railroad creates the northernmost boundary of the West End Historic District and the Norfolk and Western Railroad defines the southern border. The eastern boundary of the district includes those properties on Pender Street and on the west side of Wellons Street, as well as properties fronting both the east and west sides of Linden Avenue. The western boundary, impacted the greatest by non-contributing and non-historic properties excluded from the historic district, includes resources fronting the east and west sides of Bosley Avenue, South Broad Street, and Brewer Avenue. A few properties on Causey Avenue, the westernmost border, are included in the district. The West End neighborhood occupies approximately 73 acres.

**United States Department of the Interior
National Park Service**

**NATIONAL REGISTER OF HISTORIC PLACES
Continuation Sheet**

WEST END HISTORIC DISTRICT, SUFFOLK, VA (VDHR 133-5040)

Section number 10 Page 100

Boundary Justification

The boundaries of the West End Historic District were determined by 1) the boundaries of the Suffolk Local Historic Conservation Overlay District and 2) the survey work completed in 2001 and 2002 in this neighborhood of the City of Suffolk. The properties within the local historic overlay district were surveyed in 2001. The survey outside the local historic overlay district, assigned by the City of Suffolk Planning Department in 2002, included all properties within the area bounded by Smith Street to the north; the properties fronting both sides of Linden Avenue to the east; The Norfolk and Western Railroad to the south; and Causey Avenue to the west. The properties included the West End Historic District, as a result of both these survey phases, document the nineteenth-century development along West Washington Street and illustrate the expansion of the neighborhood to the north along Brewer Avenue and to the south along Wellons Street, Linden Avenue, and South Broad Street at the turn of the twentieth century. Further, it includes the last phase of sustained development between Smith Street and the Norfolk and Western Railroad during the first forty years of the twentieth century.

West End Historic District
(133-5040-)
City of Suffolk, Virginia

Legend

-  Building Rooflines
-  Railroad Tracks
-  District Boundary Line




Disclaimer: THE CITY OF SUFFOLK MAKES NO WARRANTY, REPRESENTATION OR GUARANTEE OF ANY KIND REGARDING EITHER THE QUALITY OR QUANTITY OF THE INFORMATION OR THE ACCURACY OF THE INFORMATION. THE CITY OF SUFFOLK, VIRGINIA, DISCLAIMS ALL REPRESENTATIONS OR WARRANTIES, EXPRESS OR IMPLIED, INCLUDING WITHOUT LIMITATION, THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE.

The City of Suffolk assumes no liability for any errors, omissions, or inaccuracies in the information contained herein or for any use of the information for any purpose other than that for which it was intended. The City of Suffolk assumes no liability for any use of the information for any purpose other than that for which it was intended.

Printed and Zoning Information has been reviewed to provide a graphic representation of the West End Historic District. The boundaries of any historic district have been established to provide a more readily visible and consistent boundary line for the purpose of historic preservation and planning.


Aerial Photography acquired from 1998. A limited view of the City was taken in March of 2001. The most accurate photography available was used to update the historic information.

1:3,600
1 inch equals 300 feet



City of Suffolk GIS
gis.city.suffolk.va.us
January 23, 2003

Suffolk
VIRGINIA
It's a good thing to be in Suffolk.





U.S. DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY



WEST END
HISTORIC DISTRICT
CITY OF SUFFOLK,
VIRGINIA

(VDHR 133-5040)

UTM REFERENCES

1) 18/357885/
4066274

2) 18/358010/
4065790

3) 18/357713/
4065355

4) 18/357439/
4065302

5) 18/357477/
4066017

SUFFOLK QUAD